PROJECT MANUAL

South King Fire & Rescue Facility Improvements

Station 63

December 1, 2016

33414 21st Avenue SW
Federal Way, WA 98003

By:

Rice Fergus Miller Inc
275 5th Street, Suite 100
Bremerton, Washington 98337

TABLE OF CONTENTS

NUMBER TITLE PAGES

Overleaf 1
Table of Contents 4

DIVISION 0 – PROCUREMENT AND CONTRACTING REQUIREMENTS
001113 Advertisement for Bids 4
002113 Instructions to Bidders 1
003100 Information Available to Bidders 1
Attachment: Prevailing Wage Rates 1
Attachment: Benefits Code Key 1
Attachment: Limited Hazardous Materials Survey Report 1
004110 Bid Form 3
004113 Agreement Form – Stipulated Sum 3
007200 General Conditions of the Contract 40
007300 Supplemental Conditions 16

DIVISION 1 - GENERAL REQUIREMENTS
011000 Summary 4
011110 Summary of Hazardous Materials Work 27
012500 Substitution Procedures 4
012600 Contract Modification Procedures 3
012900 Payment Procedures 5
013100 Project Management and Coordination 6
013200 Construction Progress Documentation 4
013300 Submittal Procedures 4
014000 Quality Requirements 9
015000 Temporary Facilities and Controls 3
016000 Product Requirements 5
017300 Execution 8
017419 Construction Waste Management and Disposal 5
017700 Closeout Procedures 3
017823 Operation and Maintenance Data 4
017839 Project Record Documents 4

DIVISION 2 – EXISTING CONDITONS
024119 Selective Demolition 6
028200 Asbestos Remediation 4
028300 Lead-Containing Paint Disturbance 4
028400 Arsenic Remediation 4
028500 Hg Light Tube and Thermostat Remediation 7

DIVISION 3 – CONCRETE:
033000 Cast-In-Place Concrete 7
033713 Shotcrete 12

DIVISION 4 – MASONRY: Not Used

DIVISION 5 – METALS:
051200 Structural Steel Framing 12
055000 Metal Fabrications 5
055213 Pipe and Tube Railings 6

DIVISION 6 – WOOD PLASTICS, AND COMPOSITES
061000 Rough Carpentry 6
062012 Interior Finish Carpentry 4
066400 Plastic Paneling 3

DIVISION 7 - THERMAL AND MOISTURE PROTECTION:
071900 Water Repellents 2
072100 Thermal Insulation 4
072500 Weather Barriers 3
074646 Fiber-Cement Siding 4
075419 Thermoplastic Membrane Roofing 18
076200 Sheet Metal Flashing and Trim 4
079200 Joint Sealants 6

DIVISION 8 – OPENINGS:
081113 Hollow Metal Doors and Frames 10
081416 Flush Wood Doors 5
085113 Aluminum Windows 7
087100 Door Hardware 9
088000 Glazing 8
089200 Louvered Equipment Enclosures 3

DIVISION 9 – FINISHES
092900 Gypsum Board 5
096513 Resilient Base and Accessories 4
096513 Resilient Sheet Flooring 6
096810 Tile Carpeting 5
099113 Exterior Painting 7
099123 Interior Painting 9

DIVISION 10 – SPECIALTIES:
102600 Wall and Door Protection 2
102800 Toilet, Bath, and Laundry Accessories 5

DIVISION 11 – EQUIPMENT: Not Used

DIVISION 12 – FURNISHINGS:
123623.13 Plastic-Laminate-Clad Countertops 4

DIVISION 13 – SPECIAL CONSTRUCTION: Not Used

DIVISION 14 - CONVEYING SYSTEMS: Not Used

DIVISION 21 – FIRE SURPRESSION:
210000 Fire Suppression General Conditions 9
210500 Common Work Results for Fire Suppression 9
211313 Wet-Pipe Sprinkler Systems 3

DIVISION 22 – PLUMBING:
220000 Plumbing General Conditions 11
220500 Common Work Results for Plumbing 13
220700 Plumbing Insulation 4
221100 Facility Water Distribution 5
221300 Facility Sanitary Sewerage 6
221400 Facility Strom Drainage 3
221500 General Service Compressed Air Systems 4
222300 Natural Gas Systems 3
224000 Plumbing Fixtures 4
224223 Commercial Showers, Receptors, and Basins 5

DIVISION 23 – HVAC:
230000 HVAC General Conditions 14
230500 Common Work Results for HVAC 14
230593 Testing, Adjusting, and Balancing 6
230700 HVAC Insulation 7
230800 Project Commissioning 7
230900 Instrumentation and Control for HVAC 6
232300 Refrigerant Piping 4
233100 HVAC Ducts and Casings 6
233300 Air Duct Accessories 7
233400 HVAC Fans 2
233700 Air Outlets and Inlets 3
234000 Filters 2
237200 Energy Recovery Units 4
238143 Air-Cooled, Variable Refrigerant Flow, Multi-Unit Heat Pump 10
238200 Terminal Heating Units 2

DIVISION 26 - ELECTRICAL
260000 Electrical General Conditions 13
260005 Electrical – Existing Systems 2
260010 Excavation and Backfill for Electrical Underground Utilities 5
260519 Wires and Cables 3
260526 Grounding and Bonding 2
260532 Outlet and Pull Boxes 4
260533 Raceway 4
260534 Metal Clad Cable (Type MC) and Fittings 4
262416 Panelboards 3
262419 Motor Controllers 3
262726 Switches and Receptacles 3
262813 Fuses 2
262816 Disconnects and Fused Switches 2

265000 Lighting 6

DIVISION 27 – COMMUNICATIONS: Not Used

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY: Not Used
283176 Fire Alarm System 42

DIVISION 31 - EARTHWORK:
312300 Excavating, Backfilling, and Compacting for Utilities and Structures 5
312500 Erosion and Sedimentation Control 5

DIVISION 32 - EXTERIOR IMPORVEMENTS:
321313 Asphalt Paving.....5

DIVISION 33 - UTILITIES:
331100 Water Distribution 5
334000 Storm Drainage.....5

DIVISION 34 – TRANSPORATION: Not Used

DIVISION 35 – WATERWAY AND MARINE CONSTRUCTION: Not Used

DIVISIONS 40's – PROCESS EQUIPMENT SUBGROUP: Not Used

END OF SECTION

ADVERSTISEMENT FOR BIDS

PUBLIC NOTICE
ADVERTISEMENT FOR BIDS
First Publication December 1, 2016, Second Publication December 6, 2016 Seattle Daily Journal of Commerce and Tacoma News Tribune
December 2, 2016 Federal Way Mirror.

South King Fire and Rescue
Facility Improvements Station 63
Des Moines, WA

Sealed bids will be received by South King Fire and Rescue up to but not later than 2:00 pm, December 22, 2016, at the address listed below, for Facilities Improvements Station 63, at which time they shall be publicly opened and recorded.

The anticipated construction cost is approximately $ 1,266,000, not including sales tax.

This project is subject to meet Washington State prevailing wages rates. All work performed on the project will be subject to the approved wage determination rates in the bid documents.

Equal Opportunity/Affirmative Action: Owner is an equal opportunity and affirmative action employer. Minority-owned and women-owned businesses are encouraged to submit bids.

A non-mandatory pre-bid conference will be held at Fire Station 63, 33414 21st Avenue SW, Federal Way, WA, at 10:00 am, December 8, 2016. The conference is intended to provide a general review between bidders, owner, and architect prior to bidding the project.

Contractors may obtain plans and specifications from American Reprographics Company (ARC), 632 Broadway, Tacoma, WA 98402, telephone (800) 337-8103, fax (253) 272-4064 upon the deposit of $100.00. Please make checks payable to Rice Fergus Miller Arch. Interiors Planning. Plans must be returned in good condition within seven (7) days following bid date to obtain a refund of deposit. After seven days, no refunds will be made. Bid packets and specifications will be available for viewing at www.southkingfire.org and at 31617 1st Avenue South, Federal Way. Plans and specifications may be viewed at the following plan centers: Builder's Exchange of Washington, Everett, WA.

A Bid Security must accompany each bid in accordance with the Instructions to Bidders.

Envelopes containing the sealed bids shall be marked "Bid for Facilities Improvements Station 63" and sent or delivered to:

Physical Address for Hand Delivery, Courier/Overnight Delivery and USPS:
SOUTH KING FIRE & RESCUE
31617 1st AVENUE SOUTH
FEDERAL WAY, WASHINGTON 98003.

The owner reserves the right to reject any or all bids, waive minor irregularities in the bidding process, and to accept the bid deemed best for them.

All questions must be submitted in writing to Rice Fergus Miller, Inc., 275 5th Street, Bremerton, WA 98337, Attention Ed McManamna. Phone: 360-377-8773.

Substitution Requests: Architect will consider requests for substitution received no later than ten working days prior to receipt of Bids. Requests received after that time may be considered or rejected at the discretion of the Architect.

SECTION 002113 - INSTRUCTIONS TO BIDDERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. INCORPORATE *Instructions to Bidders,* AIA Document A701-1997 BY THIS REFERENCE ONLY; it is not bound in Project Manual.

B. Copies may be obtained from American Institute of Architects, 1735 New York Avenue NW, Washington, D.C20006, or local Chapter offices.

C. Following items supplement, modify, change, and add to referenced instructions to Bidders.

1.2 SUPPLEMENTARY INSTRUCTIONS TO BIDDERS:

ARTICLE 3 - BIDDING DOCUMENTS

3.2.1 ADD:
"Submittal of Bid constitutes acceptance of products and procedures specified as sufficient, adequate, and satisfactory for completion of the Contract."

3.2.4 ADD new subparagraph:
"3.2.4 Interpretations: Address all questions in writing to the Architect. They will be answered by addendum addressed to all bidders. Questions received less than three working days before bid opening cannot be answered. Neither Owner nor Architect will be responsible for oral interpretations. Addenda issued during the time of bidding will be incorporated into the Contract."

3.3.2 REVISE:
“ten days prior to the date for receipt of Bids“ to read “ten working days prior to the date for receipt of bids”.

3.4.3 REVISE
“four days prior to the date from receipt of Bids” to read “72 hours prior to the time for receipt of bids”.

3.4.4 ADD:
"Bidder shall fill in the space provided on the Bid Form with the Addenda number of each Addenda received. Omission of this information may be cause for rejection of the entire bid."

ARTICLE 4 - BIDDING PROCEDURES

4.2.4 ADD new subparagraph:
"4.2.4 Each bid must be accompanied by a certified check, cashier’s check, or Bid Bond of a duly licensed bonding company, in the amount of five percent of the Base Bid, plus alternates, made payable to South King Fire and Rescue. Unsuccessful Bid-

ders shall have Bid Bonds returned within thirty (30) days following Bid Award. If Bid Bond is provided in lieu of a certified check or cashier's check, the required bond form is Bid Bond AIA -310."

4.3.5 ADD new subparagraph:
"4.3.5 Bid Proposal must be submitted on or before the time specified in the advertisement for the bids. Failure to properly complete Bid Proposal shall render that bid non-responsive.

"4.4.5 In the event a bidder discovers an error in its bid following the bid opening, the bidder may request to withdraw its bid under the following conditions:

1. Written notification is received by the Owner within 24 hours following bid opening.

2. The bidder provides written documentation of the claimed error to the satisfaction of the Owner within 72 hours following the bid opening.

4.4.6 ADD new subparagraph

"4.4.6 The bidder will allow 30 days from bid opening date from acceptance of its bid by the Owner.

ARTICLE 7 - PERFORMANCE BOND AND PAYMENT BOND

7.1.1 MODIFY Subparagraph to read:
"Provide bonds in accordance with the Supplemental Conditions"

7.1.4 ADD new subparagraph:
"7.1.4 Performance and Payment Bonds in the amount of 100 percent of the amount of the Contract including sales tax are required for this work."

7.2.1 and 7.2.2 MODIFY both Subparagraphs to read:
"Provide bonds in accordance with the Supplemental Conditions"

ARTICLE 8 - FORM OF AGREEMENT BETWEEN OWNER AND CONTRACTOR

ADD new subparagraphs:
"8.1 "Within ten (10) days following presentation of agreement, execute and return to Owner referenced AIA A101-2007 Standard Form of Agreement Between Owner and Contractor.

8.2 Retainage: See provisions of referenced Form of Agreement. Retainage: 5% of each payment throughout project.

8.3 Signatures: Each bid must be signed in ink and in longhand by the bidder with his usual signature. Bids by partnerships must be signed with the partnership name by one of the partners followed by the signature and designation of the partner signing. Bids by corporations must be signed with the legal name of the corporation, followed

by the name of the State of incorporation and by the signature of the president, secretary, or other person authorized to bind it in the matter. The name of each person signing shall be typed or printed below the signature."

PART 2 - PRODUCTS

NOT USED

PART 3 - EXECUTION

NOT USED

END OF SECTION

SECTION 003100 - INFORMATION AVAILABLE TO BIDDERS

PART 1 GENERAL

1.1 KING COUNTY PREVAILING WAGE RATES:

A. The following documents are bound into this project manual:

1. Washington State Prevailing Wage Rates – King County Effective 11/16/16.
2. Benefits Code Key.

Copies of these documents are for contractor reference and convenience only. It is the contractor's responsibility to follow the most current edition.

1.2 HAZARDOUS MATERIALS REPORT

A. The following document is bound into this project manual.

1. Limited Hazardous Materials Survey Report, South King County Fire & Rescue Fire Station #63 Capital Facility Improvements, EHS-International.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

END OF SECTION 003100

State of Washington
Department of Labor & Industries

Prevailing Wage Section - Telephone 360-902-5335
PO Box 44540, Olympia, WA 98504-4540

Washington State Prevailing Wage

The PREVAILING WAGES listed here include both the hourly wage rate and the hourly rate of fringe benefits. On public works projects, worker's wage and benefit rates must add to not less than this total. A brief description of overtime calculation requirements are provided on the Benefit Code Key.

Journey Level Prevailing Wage Rates for the Effective Date: 11/16/2016

County	Trade	Job Classification	Wage	Holiday	Overtime	Note
King	Asbestos Abatement Workers	Journey Level	$45.25	5D	1H	
King	Boilermakers	Journey Level	$64.29	5N	1C	
King	Brick Mason	Journey Level	$54.32	5A	1M	
King	Brick Mason	Pointer-Caulker-Cleaner	$54.32	5A	1M	
King	Building Service Employees	Janitor	$22.84	5S	2F	
King	Building Service Employees	Traveling Waxer/Shampooer	$23.29	5S	2F	
King	Building Service Employees	Window Cleaner (Non-Scaffold)	$23.99	5S	2F	
King	Building Service Employees	Window Cleaner (Scaffold)	$26.78	5S	2F	
King	Cabinet Makers (In Shop)	Journey Level	$22.74		1	
King	Carpenters	Acoustical Worker	$55.51	5D	4C	
King	Carpenters	Bridge, Dock And Wharf Carpenters	$55.51	5D	4C	
King	Carpenters	Carpenter	$55.51	5D	4C	
King	Carpenters	Carpenters on Stationary Tools	$55.64	5D	4C	
King	Carpenters	Creosoted Material	$55.61	5D	4C	
King	Carpenters	Floor Finisher	$55.51	5D	4C	
King	Carpenters	Floor Layer	$55.51	5D	4C	
King	Carpenters	Scaffold Erector	$55.51	5D	4C	
King	Cement Masons	Journey Level	$55.56	7A	1M	
King	Divers & Tenders	Diver	$108.77	5D	4C	8A
King	Divers & Tenders	Diver On Standby	$66.05	5D	4C	
King	Divers & Tenders	Diver Tender	$59.88	5D	4C	
King	Divers & Tenders	Surface Rcv & Rov Operator	$59.88	5D	4C	
King	Divers & Tenders	Surface Rcv & Rov Operator Tender	$55.76	5A	4C	
King	Dredge Workers	Assistant Engineer	$56.44	5D	3F	
King	Dredge Workers	Assistant Mate (Deckhand)	$56.00	5D	3F	
King	Dredge Workers	Boatmen	$56.44	5D	3F	
King	Dredge Workers	Engineer Welder	$57.51	5D	3F	
King	Dredge Workers	Leverman, Hydraulic	$58.67	5D	3F	
King	Dredge Workers	Mates	$56.44	5D	3F	
King	Dredge Workers	Oiler	$56.00	5D	3F	
King	Drywall Applicator	Journey Level	$55.51	5D	1H	
King	Drywall Tapers	Journey Level	$55.66	5P	1E	
King	Electrical Fixture Maintenance Workers	Journey Level	$27.24	5L	1E	
King	Electricians - Inside	Cable Splicer	$69.77	7C	4E	
King	Electricians - Inside	Cable Splicer (tunnel)	$74.95	7C	4E	
King	Electricians - Inside	Certified Welder	$67.41	7C	4E	
King	Electricians - Inside	Certified Welder (tunnel)	$72.37	7C	4E	
King	Electricians - Inside	Construction Stock Person	$37.94	7C	4E	
King	Electricians - Inside	Journey Level	$65.05	7C	4E	
King	Electricians - Inside	Journey Level (tunnel)	$69.77	7C	4E	
King	Electricians - Motor Shop	Craftsman	$15.37		1	
King	Electricians - Motor Shop	Journey Level	$14.69		1	
King	Electricians - Powerline Construction	Cable Splicer	$71.85	5A	4D	
King	Electricians - Powerline Construction	Certified Line Welder	$65.71	5A	4D	
King	Electricians - Powerline Construction	Groundperson	$44.12	5A	4D	
King	Electricians - Powerline Construction	Heavy Line Equipment Operator	$65.71	5A	4D	
King	Electricians - Powerline Construction	Journey Level Lineperson	$65.71	5A	4D	
King	Electricians - Powerline Construction	Line Equipment Operator	$55.34	5A	4D	
King	Electricians - Powerline Construction	Pole Sprayer	$65.71	5A	4D	
King	Electricians - Powerline Construction	Powderperson	$49.16	5A	4D	
King	Electronic Technicians	Journey Level	$31.00		1	
King	Elevator Constructors	Mechanic	$85.45	7D	4A	
King	Elevator Constructors	Mechanic In Charge	$92.35	7D	4A	
King	Fabricated Precast Concrete Products	All Classifications - In-Factory Work Only	$16.55	5B	1R	
King	Fence Erectors	Fence Erector	$15.18		1	
King	Flaggers	Journey Level	$38.36	7A	3I	
King	Glaziers	Journey Level	$58.31	7L	1Y	
King	Heat & Frost Insulators And Asbestos Workers	Journeyman	$65.43	5J	1S	
King	Heating Equipment Mechanics	Journey Level	$75.46	7F	1E	
King	Hod Carriers & Mason Tenders	Journey Level	$46.66	7A	3I	
King	Industrial Power Vacuum Cleaner	Journey Level	$9.47		1	

King	Inland Boatmen	Boat Operator	$56.78	5B	1K	
King	Inland Boatmen	Cook	$53.30	5B	1K	
King	Inland Boatmen	Deckhand	$53.30	5B	1K	
King	Inland Boatmen	Deckhand Engineer	$54.32	5B	1K	
King	Inland Boatmen	Launch Operator	$55.57	5B	1K	
King	Inland Boatmen	Mate	$55.57	5B	1K	
King	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Cleaner Operator, Foamer Operator	$31.49		1	
King	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Grout Truck Operator	$11.48		1	
King	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Head Operator	$24.91		1	
King	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Technician	$19.33		1	
King	Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control	Tv Truck Operator	$20.45		1	
King	Insulation Applicators	Journey Level	$55.51	5D	4C	
King	Ironworkers	Journeyman	$65.53	7N	1O	
King	Laborers	Air, Gas Or Electric Vibrating Screed	$45.25	7A	3I	
King	Laborers	Airtrac Drill Operator	$46.66	7A	3I	
King	Laborers	Ballast Regular Machine	$45.25	7A	3I	
King	Laborers	Batch Weighman	$38.36	7A	3I	
King	Laborers	Brick Pavers	$45.25	7A	3I	
King	Laborers	Brush Cutter	$45.25	7A	3I	
King	Laborers	Brush Hog Feeder	$45.25	7A	3I	
King	Laborers	Burner	$45.25	7A	3I	
King	Laborers	Caisson Worker	$46.66	7A	3I	
King	Laborers	Carpenter Tender	$45.25	7A	3I	
King	Laborers	Caulker	$45.25	7A	3I	
King	Laborers	Cement Dumper-paving	$46.09	7A	3I	
King	Laborers	Cement Finisher Tender	$45.25	7A	3I	
King	Laborers	Change House Or Dry Shack	$45.25	7A	3I	
King	Laborers	Chipping Gun (under 30 Lbs.)	$45.25	7A	3I	
King	Laborers	Chipping Gun(30 Lbs. And Over)	$46.09	7A	3I	
King	Laborers	Choker Setter	$45.25	7A	3I	
King	Laborers	Chuck Tender	$45.25	7A	3I	
King	Laborers	Clary Power Spreader	$46.09	7A	3I	
King	Laborers	Clean-up Laborer	$45.25	7A	3I	
King	Laborers	Concrete Dumper/chute Operator	$46.09	7A	3I	
King	Laborers	Concrete Form Stripper	$45.25	7A	3I	
King	Laborers	Concrete Placement Crew	$46.09	7A	3I	
King	Laborers	Concrete Saw Operator/core Driller	$46.09	7A	3I	
King	Laborers	Crusher Feeder	$38.36	7A	3I	
King	Laborers	Curing Laborer	$45.25	7A	3I	
King	Laborers	Demolition: Wrecking & Moving (incl. Charred Material)	$45.25	7A	3I	
King	Laborers	Ditch Digger	$45.25	7A	3I	
King	Laborers	Diver	$46.66	7A	3I	
King	Laborers	Drill Operator (hydraulic,diamond)	$46.09	7A	3I	
King	Laborers	Dry Stack Walls	$45.25	7A	3I	
King	Laborers	Dump Person	$45.25	7A	3I	
King	Laborers	Epoxy Technician	$45.25	7A	3I	
King	Laborers	Erosion Control Worker	$45.25	7A	3I	
King	Laborers	Faller & Bucker Chain Saw	$46.09	7A	3I	
King	Laborers	Fine Graders	$45.25	7A	3I	
King	Laborers	Firewatch	$38.36	7A	3I	
King	Laborers	Form Setter	$45.25	7A	3I	
King	Laborers	Gabian Basket Builders	$45.25	7A	3I	
King	Laborers	General Laborer	$45.25	7A	3I	
King	Laborers	Grade Checker & Transit Person	$46.66	7A	3I	
King	Laborers	Grinders	$45.25	7A	3I	
King	Laborers	Grout Machine Tender	$45.25	7A	3I	
King	Laborers	Groutmen (pressure)including Post Tension Beams	$46.09	7A	3I	
King	Laborers	Guardrail Erector	$45.25	7A	3I	
King	Laborers	Hazardous Waste Worker (level A)	$46.66	7A	3I	
King	Laborers	Hazardous Waste Worker (level B)	$46.09	7A	3I	
King	Laborers	Hazardous Waste Worker (level C)	$45.25	7A	3I	
King	Laborers	High Scaler	$46.66	7A	3I	
King	Laborers	Jackhammer	$46.09	7A	3I	
King	Laborers	Laserbeam Operator	$46.09	7A	3I	
King	Laborers	Maintenance Person	$45.25	7A	3I	
King	Laborers	Manhole Builder-mudman	$46.09	7A	3I	
King	Laborers	Material Yard Person	$45.25	7A	3I	

King	Laborers	Motorman-dinky Locomotive	$46.09	7A	3I	
King	Laborers	Nozzleman (concrete Pump, Green Cutter When Using Combination Of High Pressure Air & Water On Concrete & Rock, Sandblast, Gunite, Shotcrete, Water Bla	$46.09	7A	3I	
King	Laborers	Pavement Breaker	$46.09	7A	3I	
King	Laborers	Pilot Car	$38.36	7A	3I	
King	Laborers	Pipe Layer Lead	$46.66	7A	3I	
King	Laborers	Pipe Layer/tailor	$46.09	7A	3I	
King	Laborers	Pipe Pot Tender	$46.09	7A	3I	
King	Laborers	Pipe Reliner	$46.09	7A	3I	
King	Laborers	Pipe Wrapper	$46.09	7A	3I	
King	Laborers	Pot Tender	$45.25	7A	3I	
King	Laborers	Powderman	$46.66	7A	3I	
King	Laborers	Powderman's Helper	$45.25	7A	3I	
King	Laborers	Power Jacks	$46.09	7A	3I	
King	Laborers	Railroad Spike Puller - Power	$46.09	7A	3I	
King	Laborers	Raker - Asphalt	$46.66	7A	3I	
King	Laborers	Re-timberman	$46.66	7A	3I	
King	Laborers	Remote Equipment Operator	$46.09	7A	3I	
King	Laborers	Rigger/signal Person	$46.09	7A	3I	
King	Laborers	Rip Rap Person	$45.25	7A	3I	
King	Laborers	Rivet Buster	$46.09	7A	3I	
King	Laborers	Rodder	$46.09	7A	3I	
King	Laborers	Scaffold Erector	$45.25	7A	3I	
King	Laborers	Scale Person	$45.25	7A	3I	
King	Laborers	Sloper (over 20")	$46.09	7A	3I	
King	Laborers	Sloper Sprayer	$45.25	7A	3I	
King	Laborers	Spreader (concrete)	$46.09	7A	3I	
King	Laborers	Stake Hopper	$45.25	7A	3I	
King	Laborers	Stock Piler	$45.25	7A	3I	
King	Laborers	Tamper & Similar Electric, Air & Gas Operated Tools	$46.09	7A	3I	
King	Laborers	Tamper (multiple & Self-propelled)	$46.09	7A	3I	
King	Laborers	Timber Person - Sewer (lagger, Shorer & Cribber)	$46.09	7A	3I	
King	Laborers	Toolroom Person (at Jobsite)	$45.25	7A	3I	
King	Laborers	Topper	$45.25	7A	3I	
King	Laborers	Track Laborer	$45.25	7A	3I	
King	Laborers	Track Liner (power)	$46.09	7A	3I	
King	Laborers	Traffic Control Laborer	$41.02	7A	3I	8R
King	Laborers	Traffic Control Supervisor	$41.02	7A	3I	8R
King	Laborers	Truck Spotter	$45.25	7A	3I	
King	Laborers	Tugger Operator	$46.09	7A	3I	
King	Laborers	Tunnel Work-Compressed Air Worker 0-30 psi	$83.12	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 30.01-44.00 psi	$88.15	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 44.01-54.00 psi	$91.83	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 54.01-60.00 psi	$97.53	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 60.01-64.00 psi	$99.65	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 64.01-68.00 psi	$104.75	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 68.01-70.00 psi	$106.65	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 70.01-72.00 psi	$108.65	7A	3I	8Q
King	Laborers	Tunnel Work-Compressed Air Worker 72.01-74.00 psi	$110.65	7A	3I	8Q
King	Laborers	Tunnel Work-Guage and Lock Tender	$46.76	7A	3I	8Q
King	Laborers	Tunnel Work-Miner	$46.76	7A	3I	8Q
King	Laborers	Vibrator	$46.09	7A	3I	
King	Laborers	Vinyl Seamer	$45.25	7A	3I	
King	Laborers	Watchman	$34.86	7A	3I	
King	Laborers	Welder	$46.09	7A	3I	
King	Laborers	Well Point Laborer	$46.09	7A	3I	
King	Laborers	Window Washer/cleaner	$34.86	7A	3I	
King	Laborers - Underground Sewer & Water	General Laborer & Topman	$45.25	7A	3I	
King	Laborers - Underground Sewer & Water	Pipe Layer	$46.09	7A	3I	
King	Landscape Construction	Irrigation Or Lawn Sprinkler Installers	$13.56		1	
King	Landscape Construction	Landscape Equipment Operators Or Truck Drivers	$28.17		1	
King	Landscape Construction	Landscaping or Planting Laborers	$17.87		1	
King	Lathers	Journey Level	$55.51	5D	1H	

King	Marble Setters	Journey Level	$54.32	5A	1M	
King	Metal Fabrication (In Shop)	Fitter	$15.86		1	
King	Metal Fabrication (In Shop)	Laborer	$9.78		1	
King	Metal Fabrication (In Shop)	Machine Operator	$13.04		1	
King	Metal Fabrication (In Shop)	Painter	$11.10		1	
King	Metal Fabrication (In Shop)	Welder	$15.48		1	
King	Millwright	Journey Level	$57.01	5D	4C	
King	Modular Buildings	Cabinet Assembly	$11.56		1	
King	Modular Buildings	Electrician	$11.56		1	
King	Modular Buildings	Equipment Maintenance	$11.56		1	
King	Modular Buildings	Plumber	$11.56		1	
King	Modular Buildings	Production Worker	$9.47		1	
King	Modular Buildings	Tool Maintenance	$11.56		1	
King	Modular Buildings	Utility Person	$11.56		1	
King	Modular Buildings	Welder	$11.56		1	
King	Painters	Journey Level	$40.60	6Z	2B	
King	Pile Driver	Journey Level	$55.76	5D	4C	
King	Plasterers	Journey Level	$53.20	7Q	1R	
King	Playground & Park Equipment Installers	Journey Level	$9.47		1	
King	Plumbers & Pipefitters	Journey Level	$75.06	6Z	1G	
King	Power Equipment Operators	Asphalt Plant Operators	$58.69	7A	3C	8P
King	Power Equipment Operators	Assistant Engineer	$55.21	7A	3C	8P
King	Power Equipment Operators	Barrier Machine (zipper)	$58.17	7A	3C	8P
King	Power Equipment Operators	Batch Plant Operator, Concrete	$58.17	7A	3C	8P
King	Power Equipment Operators	Bobcat	$55.21	7A	3C	8P
King	Power Equipment Operators	Brokk - Remote Demolition Equipment	$55.21	7A	3C	8P
King	Power Equipment Operators	Brooms	$55.21	7A	3C	8P
King	Power Equipment Operators	Bump Cutter	$58.17	7A	3C	8P
King	Power Equipment Operators	Cableways	$58.69	7A	3C	8P
King	Power Equipment Operators	Chipper	$58.17	7A	3C	8P
King	Power Equipment Operators	Compressor	$55.21	7A	3C	8P
King	Power Equipment Operators	Concrete Pump: Truck Mount With Boom Attachment Over 42 M	$58.69	7A	3C	8P
King	Power Equipment Operators	Concrete Finish Machine -laser Screed	$55.21	7A	3C	8P
King	Power Equipment Operators	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure.	$57.72	7A	3C	8P
King	Power Equipment Operators	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	$58.17	7A	3C	8P
King	Power Equipment Operators	Conveyors	$57.72	7A	3C	8P
King	Power Equipment Operators	Cranes Friction: 200 tons and over	$60.47	7A	3C	8P
King	Power Equipment Operators	Cranes: 20 Tons Through 44 Tons With Attachments	$58.17	7A	3C	8P
King	Power Equipment Operators	Cranes: 100 Tons Through 199 Tons, Or 150' Of Boom (Including Jib With Attachments)	$59.28	7A	3C	8P
King	Power Equipment Operators	Cranes: 200 tons- 299 tons, or 250’ of boom including jib with attachments	$59.88	7A	3C	8P
King	Power Equipment Operators	Cranes: 300 tons and over or 300’ of boom including jib with attachments	$60.47	7A	3C	8P
King	Power Equipment Operators	Cranes: 45 Tons Through 99 Tons, Under 150' Of Boom (including Jib With Attachments)	$58.69	7A	3C	8P
King	Power Equipment Operators	Cranes: A-frame - 10 Tons And Under	$55.21	7A	3C	8P
King	Power Equipment Operators	Cranes: Friction cranes through 199 tons	$59.88	7A	3C	8P
King	Power Equipment Operators	Cranes: Through 19 Tons With Attachments A-frame Over 10 Tons	$57.72	7A	3C	8P
King	Power Equipment Operators	Crusher	$58.17	7A	3C	8P
King	Power Equipment Operators	Deck Engineer/deck Winches (power)	$58.17	7A	3C	8P
King	Power Equipment Operators	Derricks, On Building Work	$58.69	7A	3C	8P
King	Power Equipment Operators	Dozers D-9 & Under	$57.72	7A	3C	8P
King	Power Equipment Operators	Drill Oilers: Auger Type, Truck Or Crane Mount	$57.72	7A	3C	8P
King	Power Equipment Operators	Drilling Machine	$59.28	7A	3C	8P
King	Power Equipment Operators	Elevator And Man-lift: Permanent And Shaft Type	$55.21	7A	3C	8P
King	Power Equipment Operators	Finishing Machine, Bidwell And Gamaco & Similar Equipment	$58.17	7A	3C	8P
King	Power Equipment Operators	Forklift: 3000 Lbs And Over With Attachments	$57.72	7A	3C	8P
King	Power Equipment Operators	Forklifts: Under 3000 Lbs. With Attachments	$55.21	7A	3C	8P
King	Power Equipment Operators	Grade Engineer: Using Blue Prints, Cut Sheets, Etc	$58.17	7A	3C	8P
King	Power Equipment Operators	Gradechecker/stakeman	$55.21	7A	3C	8P
King	Power Equipment Operators	Guardrail Punch	$58.17	7A	3C	8P
King	Power Equipment Operators	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	$58.69	7A	3C	8P
King	Power Equipment Operators	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	$58.17	7A	3C	8P
King	Power Equipment Operators	Horizontal/directional Drill Locator	$57.72	7A	3C	8P

King	Power Equipment Operators	Horizontal/directional Drill Operator	$58.17	7A	3C	8P
King	Power Equipment Operators	Hydralifts/boom Trucks Over 10 Tons	$57.72	7A	3C	8P
King	Power Equipment Operators	Hydralifts/boom Trucks, 10 Tons And Under	$55.21	7A	3C	8P
King	Power Equipment Operators	Loader, Overhead 8 Yards. & Over	$59.28	7A	3C	8P
King	Power Equipment Operators	Loader, Overhead, 6 Yards. But Not Including 8 Yards	$58.69	7A	3C	8P
King	Power Equipment Operators	Loaders, Overhead Under 6 Yards	$58.17	7A	3C	8P
King	Power Equipment Operators	Loaders, Plant Feed	$58.17	7A	3C	8P
King	Power Equipment Operators	Loaders: Elevating Type Belt	$57.72	7A	3C	8P
King	Power Equipment Operators	Locomotives, All	$58.17	7A	3C	8P
King	Power Equipment Operators	Material Transfer Device	$58.17	7A	3C	8P
King	Power Equipment Operators	Mechanics, All (leadmen - $0.50 Per Hour Over Mechanic)	$59.28	7A	3C	8P
King	Power Equipment Operators	Motor Patrol Graders	$58.69	7A	3C	8P
King	Power Equipment Operators	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	$58.69	7A	3C	8P
King	Power Equipment Operators	Oil Distributors, Blower Distribution & Mulch Seeding Operator	$55.21	7A	3C	8P
King	Power Equipment Operators	Outside Hoists (elevators And Manlifts), Air Tuggers,strato	$57.72	7A	3C	8P
King	Power Equipment Operators	Overhead, Bridge Type Crane: 20 Tons Through 44 Tons	$58.17	7A	3C	8P
King	Power Equipment Operators	Overhead, Bridge Type: 100 Tons And Over	$59.28	7A	3C	8P
King	Power Equipment Operators	Overhead, Bridge Type: 45 Tons Through 99 Tons	$58.69	7A	3C	8P
King	Power Equipment Operators	Pavement Breaker	$55.21	7A	3C	8P
King	Power Equipment Operators	Pile Driver (other Than Crane Mount)	$58.17	7A	3C	8P
King	Power Equipment Operators	Plant Oiler - Asphalt, Crusher	$57.72	7A	3C	8P
King	Power Equipment Operators	Posthole Digger, Mechanical	$55.21	7A	3C	8P
King	Power Equipment Operators	Power Plant	$55.21	7A	3C	8P
King	Power Equipment Operators	Pumps - Water	$55.21	7A	3C	8P
King	Power Equipment Operators	Quad 9, Hd 41, D10 And Over	$58.69	7A	3C	8P
King	Power Equipment Operators	Quick Tower - No Cab, Under 100 Feet In Height Based To Boom	$55.21	7A	3C	8P
King	Power Equipment Operators	Remote Control Operator On Rubber Tired Earth Moving Equipment	$58.69	7A	3C	8P
King	Power Equipment Operators	Rigger And Bellman	$55.21	7A	3C	8P
King	Power Equipment Operators	Rigger/Signal Person, Bellman (Certified)	$57.72	7A	3C	8P
King	Power Equipment Operators	Rollagon	$58.69	7A	3C	8P
King	Power Equipment Operators	Roller, Other Than Plant Mix	$55.21	7A	3C	8P
King	Power Equipment Operators	Roller, Plant Mix Or Multi-lift Materials	$57.72	7A	3C	8P
King	Power Equipment Operators	Roto-mill, Roto-grinder	$58.17	7A	3C	8P
King	Power Equipment Operators	Saws - Concrete	$57.72	7A	3C	8P
King	Power Equipment Operators	Scraper, Self Propelled Under 45 Yards	$58.17	7A	3C	8P
King	Power Equipment Operators	Scrapers - Concrete & Carry All	$57.72	7A	3C	8P
King	Power Equipment Operators	Scrapers, Self-propelled: 45 Yards And Over	$58.69	7A	3C	8P
King	Power Equipment Operators	Service Engineers - Equipment	$57.72	7A	3C	8P
King	Power Equipment Operators	Shotcrete/gunite Equipment	$55.21	7A	3C	8P
King	Power Equipment Operators	Shovel , Excavator, Backhoe, Tractors Under 15 Metric Tons.	$57.72	7A	3C	8P
King	Power Equipment Operators	Shovel, Excavator, Backhoe: Over 30 Metric Tons To 50 Metric Tons	$58.69	7A	3C	8P
King	Power Equipment Operators	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	$58.17	7A	3C	8P
King	Power Equipment Operators	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	$59.28	7A	3C	8P
King	Power Equipment Operators	Shovel, Excavator, Backhoes: Over 90 Metric Tons	$59.88	7A	3C	8P
King	Power Equipment Operators	Slipform Pavers	$58.69	7A	3C	8P
King	Power Equipment Operators	Spreader, Topsider & Screedman	$58.69	7A	3C	8P
King	Power Equipment Operators	Subgrader Trimmer	$58.17	7A	3C	8P
King	Power Equipment Operators	Tower Bucket Elevators	$57.72	7A	3C	8P
King	Power Equipment Operators	Tower Crane Up To 175' In Height Base To Boom	$59.28	7A	3C	8P
King	Power Equipment Operators	Tower Crane: over 175’ through 250’ in height, base to boom	$59.88	7A	3C	8P
King	Power Equipment Operators	Tower Cranes: over 250’ in height from base to boom	$60.47	7A	3C	8P
King	Power Equipment Operators	Transporters, All Track Or Truck Type	$58.69	7A	3C	8P
King	Power Equipment Operators	Trenching Machines	$57.72	7A	3C	8P
King	Power Equipment Operators	Truck Crane Oiler/driver - 100 Tons And Over	$58.17	7A	3C	8P
King	Power Equipment Operators	Truck Crane Oiler/driver Under 100 Tons	$57.72	7A	3C	8P
King	Power Equipment Operators	Truck Mount Portable Conveyor	$58.17	7A	3C	8P
King	Power Equipment Operators	Welder	$58.69	7A	3C	8P
King	Power Equipment Operators	Wheel Tractors, Farmall Type	$55.21	7A	3C	8P
King	Power Equipment Operators	Yo Yo Pay Dozer	$58.17	7A	3C	8P

King	Power Equipment Operators- Underground Sewer & Water	Asphalt Plant Operators	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Assistant Engineer	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Barrier Machine (zipper)	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Batch Plant Operator, Concrete	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Bobcat	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Brokk - Remote Demolition Equipment	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Brooms	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Bump Cutter	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cableways	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Chipper	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Compressor	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Concrete Pump: Truck Mount With Boom Attachment Over 42 M	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Concrete Finish Machine -laser Screed	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure.	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Conveyors	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes Friction: 200 tons and over	$60.47	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: 20 Tons Through 44 Tons With Attachments	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: 100 Tons Through 199 Tons, Or 150' Of Boom (Including Jib With Attachments)	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: 200 tons- 299 tons, or 250’ of boom including jib with attachments	$59.88	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: 300 tons and over or 300’ of boom including jib with attachments	$60.47	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: 45 Tons Through 99 Tons, Under 150' Of Boom (including Jib With Attachments)	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: A-frame - 10 Tons And Under	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: Friction cranes through 199 tons	$59.88	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Cranes: Through 19 Tons With Attachments A-frame Over 10 Tons	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Crusher	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Deck Engineer/deck Winches (power)	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Derricks, On Building Work	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Dozers D-9 & Under	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Drill Oilers: Auger Type, Truck Or Crane Mount	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Drilling Machine	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Elevator And Man-lift: Permanent And Shaft Type	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Finishing Machine, Bidwell And Gamaco & Similar Equipment	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Forklift: 3000 Lbs And Over With Attachments	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Forklifts: Under 3000 Lbs. With Attachments	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Grade Engineer: Using Blue Prints, Cut Sheets, Etc	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Gradechecker/stakeman	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Guardrail Punch	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Horizontal/directional Drill Locator	$57.72	7A	3C	8P

King	Power Equipment Operators- Underground Sewer & Water	Horizontal/directional Drill Operator	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Hydralifts/boom Trucks Over 10 Tons	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Hydralifts/boom Trucks, 10 Tons And Under	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Loader, Overhead 8 Yards. & Over	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Loader, Overhead, 6 Yards. But Not Including 8 Yards	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Loaders, Overhead Under 6 Yards	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Loaders, Plant Feed	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Loaders: Elevating Type Belt	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Locomotives, All	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Material Transfer Device	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Mechanics, All (leadmen - $0.50 Per Hour Over Mechanic)	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Motor Patrol Graders	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Oil Distributors, Blower Distribution & Mulch Seeding Operator	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Outside Hoists (elevators And Manlifts), Air Tuggers,strato	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Overhead, Bridge Type Crane: 20 Tons Through 44 Tons	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Overhead, Bridge Type: 100 Tons And Over	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Overhead, Bridge Type: 45 Tons Through 99 Tons	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Pavement Breaker	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Pile Driver (other Than Crane Mount)	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Plant Oiler - Asphalt, Crusher	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Posthole Digger, Mechanical	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Power Plant	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Pumps - Water	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Quad 9, Hd 41, D10 And Over	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Quick Tower - No Cab, Under 100 Feet In Height Based To Boom	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Remote Control Operator On Rubber Tired Earth Moving Equipment	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Rigger And Bellman	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Rigger/Signal Person, Bellman (Certified)	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Rollagon	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Roller, Other Than Plant Mix	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Roller, Plant Mix Or Multi-lift Materials	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Roto-mill, Roto-grinder	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Saws - Concrete	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Scraper, Self Propelled Under 45 Yards	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Scrapers - Concrete & Carry All	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Scrapers, Self-propelled: 45 Yards And Over	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Service Engineers - Equipment	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Shotcrete/gunite Equipment	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Shovel , Excavator, Backhoe, Tractors Under 15 Metric Tons.	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Shovel, Excavator, Backhoe: Over 30 Metric Tons To 50 Metric Tons	$58.69	7A	3C	8P

King	Power Equipment Operators- Underground Sewer & Water	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Shovel, Excavator, Backhoes: Over 90 Metric Tons	$59.88	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Slipform Pavers	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Spreader, Topsider & Screedman	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Subgrader Trimmer	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Tower Bucket Elevators	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Tower Crane Up To 175' In Height Base To Boom	$59.28	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Tower Crane: over 175’ through 250’ in height, base to boom	$59.88	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Tower Cranes: over 250’ in height from base to boom	$60.47	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Transporters, All Track Or Truck Type	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Trenching Machines	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Truck Crane Oiler/driver - 100 Tons And Over	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Truck Crane Oiler/driver Under 100 Tons	$57.72	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Truck Mount Portable Conveyor	$58.17	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Welder	$58.69	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Wheel Tractors, Farmall Type	$55.21	7A	3C	8P
King	Power Equipment Operators- Underground Sewer & Water	Yo Yo Pay Dozer	$58.17	7A	3C	8P
King	Power Line Clearance Tree Trimmers	Journey Level In Charge	$47.08	5A	4A	
King	Power Line Clearance Tree Trimmers	Spray Person	$44.64	5A	4A	
King	Power Line Clearance Tree Trimmers	Tree Equipment Operator	$47.08	5A	4A	
King	Power Line Clearance Tree Trimmers	Tree Trimmer	$42.01	5A	4A	
King	Power Line Clearance Tree Trimmers	Tree Trimmer Groundperson	$31.65	5A	4A	
King	Refrigeration & Air Conditioning Mechanics	Journey Level	$74.66	6Z	1G	
King	Residential Brick Mason	Journey Level	$54.32	5A	1M	
King	Residential Carpenters	Journey Level	$28.20		1	
King	Residential Cement Masons	Journey Level	$22.64		1	
King	Residential Drywall Applicators	Journey Level	$41.69	5D	4C	
King	Residential Drywall Tapers	Journey Level	$55.66	5P	1E	
King	Residential Electricians	Journey Level	$30.44		1	
King	Residential Glaziers	Journey Level	$38.40	7L	1H	
King	Residential Insulation Applicators	Journey Level	$26.28		1	
King	Residential Laborers	Journey Level	$23.03		1	
King	Residential Marble Setters	Journey Level	$24.09		1	
King	Residential Painters	Journey Level	$24.46		1	
King	Residential Plumbers & Pipefitters	Journey Level	$34.69		1	
King	Residential Refrigeration & Air Conditioning Mechanics	Journey Level	$74.66	6Z	1G	
King	Residential Sheet Metal Workers	Journey Level (Field or Shop)	$45.99	7F	1R	
King	Residential Soft Floor Layers	Journey Level	$45.86	5A	3D	
King	Residential Sprinkler Fitters (Fire Protection)	Journey Level	$42.73	5C	2R	
King	Residential Stone Masons	Journey Level	$54.32	5A	1M	
King	Residential Terrazzo Workers	Journey Level	$48.86	5A	1M	
King	Residential Terrazzo/Tile Finishers	Journey Level	$21.46		1	
King	Residential Tile Setters	Journey Level	$25.17		1	
King	Roofers	Journey Level	$46.46	5A	3H	
King	Roofers	Using Irritable Bituminous Materials	$49.46	5A	3H	
King	Sheet Metal Workers	Journey Level (Field or Shop)	$75.46	7F	1E	
King	Shipbuilding & Ship Repair	Boilermaker	$41.72	7M	1H	
King	Shipbuilding & Ship Repair	Carpenter	$41.06	7T	2B	
King	Shipbuilding & Ship Repair	Electrician	$41.09	7T	4B	
King	Shipbuilding & Ship Repair	Heat & Frost Insulator	$65.43	5J	1S	
King	Shipbuilding & Ship Repair	Laborer	$41.08	7T	4B	
King	Shipbuilding & Ship Repair	Machinist	$41.32	7T	4B	
King	Shipbuilding & Ship Repair	Operator	$41.03	7T	4B	
King	Shipbuilding & Ship Repair	Painter	$41.05	7T	4B	
King	Shipbuilding & Ship Repair	Pipefitter	$41.05	7T	4B	
King	Shipbuilding & Ship Repair	Rigger	$41.12	7T	4B	
King	Shipbuilding & Ship Repair	Sheet Metal	$41.04	7T	4B	

King	Shipbuilding & Ship Repair	Shipfitter	$41.12	7T	4B	
King	Shipbuilding & Ship Repair	Trucker	$41.01	7T	4B	
King	Shipbuilding & Ship Repair	Warehouse	$41.02	7T	4B	
King	Shipbuilding & Ship Repair	Welder/Burner	$41.12	7T	4B	
King	Sign Makers & Installers (Electrical)	Sign Installer	$22.92		1	
King	Sign Makers & Installers (Electrical)	Sign Maker	$21.36		1	
King	Sign Makers & Installers (Non-Electrical)	Sign Installer	$27.28		1	
King	Sign Makers & Installers (Non-Electrical)	Sign Maker	$33.25		1	
King	Soft Floor Layers	Journey Level	$45.86	5A	3D	
King	Solar Controls For Windows	Journey Level	$12.44		1	
King	Sprinkler Fitters (Fire Protection)	Journey Level	$72.49	5C	1X	
King	Stage Rigging Mechanics (Non Structural)	Journey Level	$13.23		1	
King	Stone Masons	Journey Level	$54.32	5A	1M	
King	Street And Parking Lot Sweeper Workers	Journey Level	$19.09		1	
King	Surveyors	Assistant Construction Site Surveyor	$57.72	7A	3C	8P
King	Surveyors	Chainman	$57.17	7A	3C	8P
King	Surveyors	Construction Site Surveyor	$58.69	7A	3C	8P
King	Telecommunication Technicians	Journey Level	$22.76		1	
King	Telephone Line Construction - Outside	Cable Splicer	$37.60	5A	2B	
King	Telephone Line Construction - Outside	Hole Digger/Ground Person	$20.79	5A	2B	
King	Telephone Line Construction - Outside	Installer (Repairer)	$36.02	5A	2B	
King	Telephone Line Construction - Outside	Special Aparatus Installer I	$37.60	5A	2B	
King	Telephone Line Construction - Outside	Special Apparatus Installer II	$36.82	5A	2B	
King	Telephone Line Construction - Outside	Telephone Equipment Operator (Heavy)	$37.60	5A	2B	
King	Telephone Line Construction - Outside	Telephone Equipment Operator (Light)	$34.94	5A	2B	
King	Telephone Line Construction - Outside	Telephone Lineperson	$34.93	5A	2B	
King	Telephone Line Construction - Outside	Television Groundperson	$19.73	5A	2B	
King	Telephone Line Construction - Outside	Television Lineperson/Installer	$26.31	5A	2B	
King	Telephone Line Construction - Outside	Television System Technician	$31.50	5A	2B	
King	Telephone Line Construction - Outside	Television Technician	$28.23	5A	2B	
King	Telephone Line Construction - Outside	Tree Trimmer	$34.93	5A	2B	
King	Terrazzo Workers	Journey Level	$48.86	5A	1M	
King	Tile Setters	Journey Level	$21.65		1	
King	Tile, Marble & Terrazzo Finishers	Finisher	$39.69	5A	1B	
King	Traffic Control Stripers	Journey Level	$44.35	7A	1K	
King	Truck Drivers	Asphalt Mix Over 16 Yards (W. WA-Joint Council 28)	$51.25	5D	3A	8L
King	Truck Drivers	Asphalt Mix To 16 Yards (W. WA-Joint Council 28)	$50.41	5D	3A	8L
King	Truck Drivers	Dump Truck & Trailer	$51.25	5D	3A	8L
King	Truck Drivers	Dump Truck (W. WA-Joint Council 28)	$50.41	5D	3A	8L
King	Truck Drivers	Other Trucks (W. WA-Joint Council 28)	$51.25	5D	3A	8L
King	Truck Drivers	Transit Mixer	$43.23		1	
King	Well Drillers & Irrigation Pump Installers	Irrigation Pump Installer	$17.71		1	
King	Well Drillers & Irrigation Pump Installers	Oiler	$12.97		1	
King	Well Drillers & Irrigation Pump Installers	Well Driller	$18.00		1	

****

Overtime Codes

Overtime calculations are based on the hourly rate actually paid to the worker. On public works projects, the hourly rate must be not less than the prevailing rate of wage minus the hourly rate of the cost of fringe benefits actually provided for the worker.

1. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

B. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

C. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

D. The first two (2) hours before or after a five-eight (8) hour workweek day or a four-ten (10) hour workweek day and the first eight (8) hours worked the next day after either workweek shall be paid at one and one-half times the hourly rate of wage. All additional hours worked and all worked on Sundays and holidays shall be paid at double the hourly rate of wage.

E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.

G. The first ten (10) hours worked on Saturdays and the first ten (10) hours worked on a fifth calendar weekday in a four-ten hour schedule, shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

H. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions or equipment breakdown) shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

I. All hours worked on Sundays and holidays shall also be paid at double the hourly rate of wage.

J. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage.

K. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

M. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

N. All hours worked on Saturdays (except makeup days) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Overtime Codes Continued

1. O. The first ten (10) hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays, holidays and after twelve (12) hours, Monday through Friday and after ten (10) hours on Saturday shall be paid at double the hourly rate of wage.

P. All hours worked on Saturdays (except makeup days if circumstances warrant) and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

Q. The first two (2) hours after eight (8) regular hours Monday through Friday and up to ten (10) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays (except Christmas day) shall be paid at double the hourly rate of wage. All hours worked on Christmas day shall be paid at two and one-half times the hourly rate of wage.

R. All hours worked on Sundays and holidays shall be paid at two times the hourly rate of wage.

S. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays and all other overtime hours worked, except Labor Day, shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.

U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays (except Labor Day) shall be paid at two times the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.

V. All hours worked on Sundays and holidays (except Thanksgiving Day and Christmas day) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Thanksgiving Day and Christmas day shall be paid at double the hourly rate of wage.

W. All hours worked on Saturdays and Sundays (except make-up days due to conditions beyond the control of the employer)) shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

X. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over twelve (12) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage. When holiday falls on Saturday or Sunday, the day before Saturday, Friday, and the day after Sunday, Monday, shall be considered the holiday and all work performed shall be paid at double the hourly rate of wage.

Y. All hours worked outside the hours of 5:00 am and 5:00 pm (or such other hours as may be agreed upon by any employer and the employee) and all hours worked in excess of eight (8) hours per day (10 hours per day for a 4 x 10 workweek) and on Saturdays and holidays (except labor day) shall be paid at one and one-half times the hourly rate of wage. (except for employees who are absent from work without prior approval on a scheduled workday during the workweek shall be paid at the straight-time rate until they have worked 8 hours in a day (10 in a 4 x 10 workweek) or 40 hours during that workweek.) All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and Labor Day shall be paid at double the hourly rate of wage.

Z. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid the straight time rate of pay in addition to holiday pay.

Overtime Codes Continued

2. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

   B. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.

   C. All hours worked on Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at two times the hourly rate of wage.

   F. The first eight (8) hours worked on holidays shall be paid at the straight hourly rate of wage in addition to the holiday pay. All hours worked in excess of eight (8) hours on holidays shall be paid at double the hourly rate of wage.

   G. All hours worked on Sunday shall be paid at two times the hourly rate of wage. All hours worked on paid holidays shall be paid at two and one-half times the hourly rate of wage including holiday pay.

   H. All hours worked on Sunday shall be paid at two times the hourly rate of wage. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.

   O. All hours worked on Sundays and holidays shall be paid at one and one-half times the hourly rate of wage.

   R. All hours worked on Sundays and holidays and all hours worked over sixty (60) in one week shall be paid at double the hourly rate of wage.

   U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked over 12 hours in a day or on Sundays and holidays shall be paid at double the hourly rate of wage.

   W. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage. On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The first eight (8) hours worked on the fifth day shall be paid at one and one-half times the hourly rate of wage. All other hours worked on the fifth, sixth, and seventh days and on holidays shall be paid at double the hourly rate of wage.

3. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

   A. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal shift, and all work on Saturdays shall be paid at time and one-half the straight time rate. Hours worked over twelve hours (12) in a single shift and all work performed after 6:00 pm Saturday to 6:00 am Monday and holidays shall be paid at double the straight time rate of pay. Any shift starting between the hours of 6:00 pm and midnight shall receive an additional one dollar ($1.00) per hour for all hours worked that shift. The employer shall have the sole discretion to assign overtime work to employees. Primary consideration for overtime work shall be given to employees regularly assigned to the work to be performed on overtime situations. After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

   C. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays shall be paid at double the hourly rate of wage. After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

Overtime Codes Continued

3. D. All hours worked between the hours of 6:00 pm and 6:00 am, Monday through Saturday, shall be paid at a premium rate of 15% over the hourly rate of wage. All other hours worked after 6:00 am on Saturdays, shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

   E. All hours worked Sundays and holidays shall be paid at double the hourly rate of wage. Each week, once 40 hours of straight time work is achieved, then any hours worked over 10 hours per day Monday through Saturday shall be paid at double the hourly wage rate.

   F. All hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sunday shall be paid at two times the hourly rate of wage. All hours worked on paid holidays shall be paid at two and one-half times the hourly rate of wage including holiday pay.

   H. All work performed on Sundays between March 16th and October 14th and all Holidays shall be compensated for at two (2) times the regular rate of pay. Work performed on Sundays between October 15th and March 15th shall be compensated at one and one half (1-1/2) times the regular rate of pay.

   I. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. In the event the job is down due to weather conditions during a five day work week (Monday through Friday,) or a four day-ten hour work week (Tuesday through Friday,) then Saturday may be worked as a voluntary make-up day at the straight time rate. However, Saturday shall not be utilized as a make-up day when a holiday falls on Friday. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

4. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

   A. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage.

   B. All hours worked over twelve (12) hours per day and all hours worked on holidays shall be paid at double the hourly rate of wage.

   C. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay. On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay. All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.

Overtime Codes Continued

4. D. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturday, Sundays and holidays shall be paid at double the hourly rate of pay. Rates include all members of the assigned crew.

EXCEPTION:
On all multipole structures and steel transmission lines, switching stations, regulating, capacitor stations, generating plants, industrial plants, associated installations and substations, except those substations whose primary function is to feed a distribution system, will be paid overtime under the following rates:

The first two (2) hours after eight (8) regular hours Monday through Friday of overtime on a regular workday, shall be paid at one and one-half times the hourly rate of wage. All hours in excess of ten (10) hours will be at two (2) times the hourly rate of wage. The first eight (8) hours worked on Saturday will be paid at one and one-half (1-1/2) times the hourly rate of wage. All hours worked in excess of eight (8) hours on Saturday, and all hours worked on Sundays and holidays will be at the double the hourly rate of wage.

All overtime eligible hours performed on the above described work that is energized, shall be paid at the double the hourly rate of wage.

E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal four-day, ten hour work week, and Saturday shall be paid at one and one half (1½) times the regular shift rate for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

F. All hours worked between the hours of 6:00 pm and 6:00 am, Monday through Saturday, shall be paid at a premium rate of 20% over the hourly rate of wage. All hours worked on Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.

G. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Holiday Codes

5. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, and Christmas Day (7).

B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, the day before Christmas, and Christmas Day (8).

C. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).

D. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8).

H. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Day after Thanksgiving Day, And Christmas (6).

Holiday Codes Continued

5. I. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).

J. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, Friday after Thanksgiving Day, Christmas Eve Day, And Christmas Day (7).

K. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9).

L. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (8).

N. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, The Friday After Thanksgiving Day, And Christmas Day (9).

P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday And Saturday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9). If A Holiday Falls On Sunday, The Following Monday Shall Be Considered As A Holiday.

Q. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).

R. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Day After Thanksgiving Day, One-Half Day Before Christmas Day, And Christmas Day. (7 1/2).

S. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, And Christmas Day (7).

T. Paid Holidays: New Year's Day, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, Christmas Day, And The Day Before Or After Christmas (9).

Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).

6. A. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).

E. Paid Holidays: New Year's Day, Day Before Or After New Year's Day, Presidents Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and a Half-Day On Christmas Eve Day. (9 1/2).

G. Paid Holidays: New Year's Day, Martin Luther King Jr. Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and Christmas Eve Day (11).

H. Paid Holidays: New Year's Day, New Year's Eve Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, Christmas Day, The Day After Christmas, And A Floating Holiday (10).

I. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, And Christmas Day (7).

Holiday Codes Continued

6. T. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Last Working Day Before Christmas Day, And Christmas Day (9).

   Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). If a holiday falls on Saturday, the preceding Friday shall be considered as the holiday. If a holiday falls on Sunday, the following Monday shall be considered as the holiday.

7. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any Holiday Which Falls On A Sunday Shall Be Observed As A Holiday On The Following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

   B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   C. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   D. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Unpaid Holidays: President's Day. Any paid holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any paid holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   E. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   F. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the last working day before Christmas day and Christmas day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   G. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

   H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

   J. Holidays: New Year's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

Holiday Codes Continued

7. K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

L. Holidays: New Year's Day, Memorial Day, Labor Day, Independence Day, Thanksgiving Day, the Last Work Day before Christmas Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

M. Paid Holidays: New Year's Day, The Day after or before New Year's Day, President's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, And the Day after or before Christmas Day (10). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

N. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. When Christmas falls on a Saturday, the preceding Friday shall be observed as a holiday.

P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

Q. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.

R. Paid Holidays: New Year's Day, the day after or before New Year's Day, President's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and the day after or before Christmas Day (10). If any of the listed holidays fall on Saturday, the preceding Friday shall be observed as the holiday. If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.

S. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, Christmas Day, the Day after Christmas, and A Floating Holiday (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.

T. Paid Holidays: New Year's Day, the Day after or before New Year's Day, President's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and The Day after or before Christmas Day. (10). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

Note Codes

8. A. In addition to the hourly wage and fringe benefits, the following depth premiums apply to depths of fifty feet or more:
Over 50' To 100' -$2.00 per Foot for Each Foot Over 50 Feet
Over 100' To 150' -$3.00 per Foot for Each Foot Over 100 Feet
Over 150' To 220' -$4.00 per Foot for Each Foot Over 150 Feet
Over 220' -$5.00 per Foot for Each Foot Over 220 Feet

Note Codes Continued

8. C. In addition to the hourly wage and fringe benefits, the following depth premiums apply to depths of fifty feet or more:
Over 50’ To 100' -$1.00 per Foot for Each Foot Over 50 Feet
Over 100' To 150' -$1.50 per Foot for Each Foot Over 100 Feet
Over 150' To 200' -$2.00 per Foot for Each Foot Over 150 Feet
Over 200' -Divers May Name Their Own Price

D. Workers working with supplied air on hazmat projects receive an additional $1.00 per hour.

L. Workers on hazmat projects receive additional hourly premiums as follows -Level A: $0.75, Level B: $0.50, And Level C: $0.25.

M. Workers on hazmat projects receive additional hourly premiums as follows: Levels A & B: $1.00, Levels C & D: $0.50.

N. Workers on hazmat projects receive additional hourly premiums as follows -Level A: $1.00, Level B: $0.75, Level C: $0.50, And Level D: $0.25.

P. Workers on hazmat projects receive additional hourly premiums as follows -Class A Suit: $2.00, Class B Suit: $1.50, Class C Suit: $1.00, And Class D Suit $0.50.

Q. The highest pressure registered on the gauge for an accumulated time of more than fifteen (15) minutes during the shift shall be used in determining the scale paid.

R. Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. These classifications are only effective on or after August 31, 2012.

S. Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.

T. Effective August 31, 2012 – A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.

U. Workers on hazmat projects receive additional hourly premiums as follows – Class A Suit: $2.00, Class B Suit: $1.50, And Class C Suit: $1.00. Workers performing underground work receive an additional $0.40 per hour for any and all work performed underground, including operating, servicing and repairing of equipment. The premium for underground work shall be paid for the entire shift worked. Workers who work suspended by a rope or cable receive an additional $0.50 per hour. The premium for work suspended shall be paid for the entire shift worked. Workers who do “pioneer” work (break open a cut, build road, etc.) more than one hundred fifty (150) feet above grade elevation receive an additional $0.50 per hour.

EHS–International, Inc.

1011 SW Klickitat Way, Suite 104
Seattle, Washington 98134
Phone 206-381-1128
Toll Free 800-636-2959
Fax 206-254-4279

LIMITED HAZARDOUS MATERIALS SURVEY REPORT

SOUTH KING COUNTY FIRE & RESCUE FIRE STATION #63 CAPITAL FACILITY IMPROVEMENTS

33414 21st Avenue South
Auburn, WA



June 14th, 2016
Revised: October 10th, 2016

Prepared For:

Howard Struve
Rice Fergus Miller Architecture & Planning
275 Fifth Street, Suite 100
Bremerton, WA

- Environmental Consulting
- Hazardous Materials Management
- Industrial Hygiene Services
- Construction Management
- Indoor Air Quality

EHS–International, Inc.

Limited Hazardous Materials Survey Report

South King County Fire & Rescue
Fire Station #63 Capital Facility Improvements
33414 21st Avenue S.
Auburn, Washington

EHSI Project No.: # 10854

The material and data in this report were prepared under the supervision and direction of the undersigned.

Report Approved By:



Herb Brod, CIH
Technical Director

TABLE OF CONTENTS

Acronym List ..... **iv**

1.0 EXECUTIVE SUMMARY **1**
1.1 BACKGROUND 1
1.2 EXTENT OF CURRENT SURVEY 1
1.3 MATERIALS FOUND 1
1.4 OPINIONS AND RECOMMENDATIONS 2
1.5 LIMITATIONS/DISCLAIMER 2

2.0 LIMITED HAZARDOUS MATERIALS SURVEY REPORT **4**
2.1 BACKGROUND 4
2.2 BUILDING DESCRIPTION 4
2.3 SAMPLING METHODOLOGY 4
2.3.1 Asbestos-Containing Materials *4*
2.3.2 Lead-Containing Paint/Lead-Containing Materials *5*
2.3.3 Arsenic-Containing Materials *5*
2.4 SAMPLING RESULTS 5
2.4.1 Asbestos-Containing Materials *5*
2.4.2 Lead-Containing Paint and Building Materials *16*
2.4.3 Arsenic-Containing Building Materials *19*
2.4.4 Toxicity Characteristic Leaching Procedure Sampling *20*
2.4.5 Polychlorinated Biphenyls *20*
2.4.6 Mercury-Containing Thermostats and Fluorescent Light Tubes *20*

3.0 LIMITATIONS **21**

4.0 STANDARD OF CARE **21**

5.0 CERTIFIED AHERA BUILDING INSPECTORS **22**

APPENDICES

A ..... Asbestos Analytical Laboratory Reports and Field Data Forms
B ..... Lead and Arsenic Laboratory Reports and Field Data Forms
C ..... Certified AHERA Building Inspector Certificates
D ..... Laboratory Certifications for Asbestos, Lead, and Arsenic Analysis
E ..... Sample Location Drawings for Asbestos, Lead, and Arsenic

ACRONYM LIST

ACM	Asbestos-Containing Material
AHERA	Asbestos Hazard Emergency Response Act
AIHA	American Industrial Hygiene Association
As	Arsenic
BMU	Brick Masonry Unit
CFR	Code of Federal Regulations
CMU	Concrete Masonry Unit
DOSH	Washington State Department of Labor and Industries, Division of Occupational Safety and Health
EA	Each
Ecology	Washington State Department of Ecology
EHSI	EHS-International, Inc.
ELLAP	Environmental Lead Laboratory Accreditation Program
GWB	Gypsum Wall Board
Hg	Mercury
JC	Joint Compound
LCM	Lead-Containing Material
LCP	Lead-Containing Paint
LF	Linear Feet
L&I	Washington State Department of Labor and Industries
µg/m^3	Micrograms Per Cubic Meter
mg/L	Milligrams Per Liter
N/A	Not Applicable
ND	None Detected
NIS	Not in Scope
NVL	NVL Laboratories, Inc.
NVLAP	National Voluntary Laboratory Accreditation Program
OSHA	US Occupational Safety and Health Administration
Pb	Lead
PCBs	Polychlorinated Biphenyls
PLM	Polarized Light Microscopy
ppm	Parts per Million
PSCAA	Puget Sound Clean Air Agency
QA	Quality Assurance
RCW	Revised Code of Washington
SACT	Suspended Acoustical Ceiling Tiles
SAT	Seattle Asbestos Test, LLC
Small Bore	Pipe TSI ≤ 6″ OD
SVF	Sheet Vinyl Flooring
TCLP	Toxic Characteristic Leachate Procedure
TSI	Thermal System Insulation
WAC	Washington Administrative Code
WT	Weight
w/	With
XRF	x-ray fluorescence

1.0 EXECUTIVE SUMMARY

1.1 BACKGROUND

The South King County Fire & Rescue (SKC F&R) has contracted Rice Fergus Miller Architecture & Planning (RFMA) to lead the design team for the Fire Station #63 (FS #63) renovation project located at 33414 21st Avenue South in Auburn, WA. In conjunction with that project, RFMA contracted EHS-International, Inc. (EHSI), a hazardous materials and industrial hygiene consulting firm, to conduct a Limited Hazardous Materials Survey. The intent of the survey is to specifically identify and quantify asbestos-containing building materials (ACM), lead-containing paint (LCP), other lead-containing building materials (LCM), arsenic (As)-containing concrete masonry unit (CMU) or brick masonry unit (BMU) mortar, polychlorinated biphenyl (PCB)-containing light ballasts, and mercury (Hg)-containing light tubes and lamps that may be impacted by the project.

1.2 EXTENT OF CURRENT SURVEY

EHSI inspected all accessible interior and exterior materials potentially impacted by the proposed project. Accessible suspect materials were sampled including, but not limited to: interior wall systems, ceiling and floor systems, stair treads and risers, duct sealant, thermal system insulation (TSI) on piping, sink undercoating, interior and exterior caulking, window glazing putty, BMU mortar, CMU mortar, and roofing materials and sealants. EHSI accomplished representative destructive inspection; however, in areas inaccessible for inspection (e.g., fire door cores, wall cabinet mastics, enclosed plaster wall chases, electrical panel components and materials above hard lid ceilings) suspect materials were assumed to be ACM.

1.3 MATERIALS IMPACTED BY THIS PROJECT

SUMMARY OF ASBESTOS-CONTAINING MATERIALS FIRE STATION #63	
ASBESTOS MATERIAL DESCRIPTION	**LOCATION**
ACM gray door frame caulking (around single metal door frame)	LT Office / Bed Room
ACM gray duct seam sealant (on 5" outside diameter (OD) metal furnace flue)	Furnace Room
ACM brown window frame caulking (around 5'x5' metal framed window)	LT Office / Bed Room
Non-ACM new white seam caulking on **ACM old black asphaltic caulking** (on 1'x1' metal ducting associated w/ old exhaust fan)	Roof over Apparatus Room
Non-ACM new gray window frame caulking on **ACM old gray window frame caulking** (around 6'x5' metal framed window)	Second Floor Exterior

SUMMARY OF ASBESTOS-CONTAINING MATERIALS FIRE STATION #63	
ASBESTOS MATERIAL DESCRIPTION	**LOCATION**
2'x3' Electrical panels with assumed ACM internals	Lobby, Apparatus Room, Electrical Room/ Hose Tower First Floor, Hose Tower Second Floor, Exterior Radio Equipment and Generator Area
Small electrical switch gear panels with assumed ACM internals	Exterior N. Side and Roof
Assumed ACM glue dots associated w/ wood wall cabinets (5'x14')	Shop
Assumed ACM thermal system insulation (TSI) on small bore pipe elbows and fittings on fiberglass runs (concealed in plumbing walls & ceilings)	Restroom 1, Restroom 2, Furnace Room, and Restroom 8
Assumed ACM insulation on 12"x12" metal ducting concealed beneath slab	Throughout
Assumed ACM mastic associated with 4'x9' plaster wall panels on BMU wall	Exterior North and West Sides
Assumed ACM windows concealed under 4'x9' exterior plaster wall panels	Exterior North and West Sides

Key: ACM = Asbestos-Containing Material, **BMU =** brick masonry unit, **OD** = outside diameter, **small bore =** pipe TSI ≤ 6" OD, **TSI** = Thermal System Insulation

1.4 OPINIONS AND RECOMMENDATIONS

This will be a renovation project, therefore, EHSI recommends that all impacted ACM and assumed ACM identified in paragraph 1.3 be removed and disposed prior to demolition/renovation.

Any suspect materials not identified as having been surveyed in this report must be treated as an ACM until determined otherwise by a Certified Asbestos Building Inspector and NVLAP certified laboratory.

Washington State Department of Labor and Industries (L&I) Division of Occupational Safety and Health (DOSH) and the US Occupational Safety and Health Administration (OSHA) require employers to conduct a hazard assessment and take appropriate worker protection precautions whenever building materials are disturbed that have detectable quantities of lead and/or arsenic. Since the type of work planned (e.g., sawing, grinding, select demolition) will disturb the LCP/LCM and/or As-containing BMU mortar, the contractor should perform an initial exposure assessment to determine if personal protective measures, employee training, medical monitoring, and work practices are required.

1.5 LIMITATIONS/DISCLAIMER

This report does **not** represent a comprehensive hazardous materials investigation for the subject property. This investigation has been conducted by EHSI under a specific scope of work authorized by RFMA for a specific purpose. Due to continued occupancy, fire door cores, cabinet mastics, electrical panel components and materials above hard lid ceilings and inside

closed plumbing chases were not sampled and are assumed to be present and assumed to be ACMs. This report and accompanying appendices include the supporting information for this executive summary.

2.0 LIMITED HAZARDOUS MATERIALS SURVEY REPORT

2.1 BACKGROUND

The SKC F&R has contracted RFMA to lead the design team for the FS #63 renovation project located at 33414 21st Avenue South in Auburn, WA. In conjunction with that project, RFMA contracted EHSI, a hazardous materials and industrial hygiene consulting firm, to accomplish a pre-renovation limited hazardous materials survey of the existing FS #63 Building. For this limited hazardous materials survey, EHSI was tasked to use applicable federal, state and local guidelines in the accomplishment of its survey. EHSI was further tasked to provide a written survey report including: identification of all suspect materials; a determination of whether suspect materials were: ACM, LCP, LCM, As-containing CMU and BMU mortar, PCB-containing light ballasts, and Hg-containing light tubes/lamps; and to provide analytical reports indicating the presence and quantity of the hazardous materials.

This Limited Hazardous Materials Survey Report meets the Washington State "Good Faith Survey" requirements as cited in Revised Code of Washington (RCW) 49.26.016 and implemented by L&I DOSH regulation, Washington Administrative Code (WAC) 296-62-07721, and Regulation III, Article 4 of the Puget Sound Clean Air Agency (PSCAA).

On April 22nd, April 25th, and April 26th, 2016 EHSI conducted a Limited Hazardous Materials (ACM, LCP, LCM, As-containing CMU and BMU mortar, PCB-ballasts, and Hg-containing light tubes) Survey of FS #63. On September 27, 2016, EHSI conducted a design site check to confirm location and quantity of materials being impacted by the proposed project and during that design site check, collected additional suspect ACM confirmation samples for analysis.

2.2 BUILDING DESCRIPTION

FS #63 is located at 33414 21st Avenue S., Auburn, Washington. The facility is comprised of a two-story brick and CMU building with slab-on-grade construction. The main floor houses a dormitory, offices, an apparatus bay, restrooms, a shop, furnace room, hot water heater room, radio room, and fitness room. The second floor houses beanery and watch, media room, and restrooms. The building has a flat roof system. Windows are metal-framed and partially operable. Interior finishes include: Painted and textured gypsum wallboard (GWB) walls and ceilings, 2'x4' suspended acoustical ceiling tiles (SACT), with flush-mounted and recessed fluorescent light fixtures throughout the building. Flooring includes: Sheet vinyl flooring (SVF), carpet, and bare concrete floors. Forced air central heating for the building is provided by furnaces in the furnace rooms on the ground floor and top of stairs. Domestic hot water is provided by an electric water heater located in the hot water heater room on the ground floor.

2.3 SAMPLING METHODOLOGY

2.3.1 Asbestos-Containing Materials

The EHSI field inspectors are asbestos Building Inspectors, certified under the requirements of the United States Environmental Protection Agency (USEPA) AHERA regulation 40 Code of Federal Regulations (CFR) 763, Subpart E. Copies of their certificates are provided in Appendix C. The number of bulk samples collected and their locations are based on the AHERA

regulation and the guidelines provided by the USEPA Document 560/5-85-030a, October 1985, *Asbestos in Buildings: Simplified Sampling Scheme for Friable Surfacing Materials*.

EHSI collected samples and obtained analytical data for suspect ACM identified in the facility. Once collected, each bulk sample was sealed in an unadulterated plastic bag to eliminate the possibility of cross-contamination. "Chain-of-Custody" tracking was followed to maintain sample integrity during handling and data reporting at EHSI and the analytical laboratory. As specified in 40 CFR Chapter 1 (1-1-87 edition) Part 763, Subpart F, and Appendix A, each sample was analyzed using polarized light microscopy (PLM) / dispersion staining techniques, in accordance with USEPA Method 600/R-93/116. Samples were analyzed for asbestos content by Seattle Asbestos Test, LLC (SAT) located in Seattle, Washington. SAT participates in the National Institute for Standards and Technology (NIST) National Voluntary Laboratory Accreditation Program (NVLAP). Only materials containing more than 1% total asbestos were classified as "asbestos-containing" based on USEPA, state, and local regulations.

Samples in the report labeled as ##QA are quality assurance (QA) samples. Split samples were taken from the same location and they were sent to separate laboratories. QA samples were submitted to, NVL Laboratories, Inc. (NVL) in Seattle, WA, another NVLAP laboratory. Copies of both laboratories' NVLAP certifications are included in Appendix D.

2.3.2 Lead-Containing Paint/Lead-Containing Materials

EHSI used a Niton Model XLp x-ray fluorescence (XRF) Spectrum Analyzer to measure lead content on interior and exterior paint coatings and other suspect LCM. Measurements were representative of all layers of paint and/or LCM. A summary of Lead Paint XRF results is provided in Table 3. Bulk quality assurance samples were taken for a representative number of LBP and LCM and were brought to NVL located in Seattle, Washington, an accredited laboratory for Atomic Absorption Spectroscopy (USEPA Method-7000B) by the American Industrial Hygiene Association (AIHA) under the Environmental Lead Laboratory Accreditation Program (ELLAP). Copies of laboratory reports and field data forms for lead are in Appendix B. A copy of NVL's certification for analysis is provided in Appendix D.

2.3.3 Arsenic-Containing Materials

EHSI collected samples and obtained analytical data for BMU mortar and CMU mortar from the building walls. Once collected, each bulk sample was sealed in an unadulterated plastic bag to eliminate the possibility of cross-contamination. "Chain-of-Custody" tracking was followed to maintain sample integrity during handling and data reporting at EHSI and the analytical laboratory. A summary of arsenic laboratory results is provided in Table 4. Samples were brought to NVL, an accredited laboratory for Inductively Coupled Plasma Spectroscopy (USEPA Method-6010) by the Washington State Department of Ecology. Copies of laboratory reports and field data forms for arsenic are in Appendix B. A copy of NVL's certification for analysis is provided in Appendix D.

2.4 SAMPLING RESULTS

2.4.1 Asbestos-Containing Materials

Seventy-three (73) bulk samples of suspect ACM were collected as part of the survey. Four (4) of those samples were split for quality assurance analyses. Three (3) additional samples

of suspect ACM were collected as part of the design check. Limited destructive inspection was conducted to identify hidden and/or concealed materials. Copies of the asbestos analytical laboratory results are included in Appendix A. Asbestos and lead sample location drawings are provided in Appendix E. Asbestos sampling information including: sample number, material description, sample location, and analytical results are summarized in Table 1. The ACM and assumed ACM identified during this survey, including the quantity and location, is summarized in Table 2. Suspect materials not sampled due to continued occupancy were assumed to be ACM.

TABLE 1
SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS
FIRE STATION #63

SAMPLE NUMBER	SAMPLE LOCATION	MATERIAL DESCRIPTION	ASBESTOS %	TYPE OF ASBESTOS
First Floor				
10854-63-01	LT Office / Bed Room	Layer 1: 4" Black cove base Layer 2: Clear, white, and tan mastic	L1: ND L2: ND	N/A N/A
10854-63-02	LT Office / Bed Room	Layer 1: Multi-color carpet Layer 2: Tan mastic (on concrete)	L1: ND L2: ND	N/A N/A
10854-63-03	Restroom 2	Layer 1: 4" Light gray cove base Layer 2: Off-white and tan mastic Layer 3: JC w/ paint and paper	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-04	Restroom 2	Layer 1: Gray broken rock pattern SVF Layer 2: Gray paper backing Layer 3: Tan mastic Layer 4: Concrete	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A
10854-63-05QA	Fitness Room	Layer 1: 6" Black cove base Layer 2: White and tan mastic Layer 3: Old brown mastic w/ paint (on CMU)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-06	NE Entry	Layer 1: Wood pattern SVF Layer 2: White fibrous backing Layer 3: Tan mastic Layer 4: Gray leveling compound Layer 5: Black mastic Layer 6: Concrete	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND	N/A N/A N/A N/A N/A N/A
10854-63-07	Restroom 2	Layer 1: White texturing skim coat w/ paint and paper Layer 2: GWB wall w/ paper (corner)	L1: ND L2: ND	N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-08	Restroom 2	Layer 1: White texturing skim coat w/ paint and paper Layer 2: GWB wall w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A
10854-63-09	Storage Area Under Stairs	Layer 1: White texturing skim coat w/ paint Layer 2: GWB ceiling w/ paper (ceiling edge)	L1: ND L2: ND	N/A N/A
10854-63-10	Storage Area Under Stairs	Layer 1: White texturing skim coat w/ paint Layer 2: GWB ceiling w/ paper (mid-ceiling)	L1: ND L2: ND	N/A N/A
10854-63-11	Bedroom 1	Layer 1: JC w/ paint Layer 2: GWB w/ paper (corner wall)	L1: ND L2: ND	N/A N/A
10854-63-12	Bedroom 1	Layer 1: White JC skim coat w/ paint Layer 2: GWB w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A
10854-63-13	Hallway 100	Layer 1: Trace white JC skim coat w/ paint Layer 2: GWB w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A
10854-63-14	Restroom 2	Layer 1: Wood wainscoting Layer 2: Tan glue dot	L1: ND L2: ND	N/A N/A
10854-63-15	Restroom 2	White caulking at horizontal seams (between wall and wainscoting)	ND	N/A
10854-63-16	Restroom 2	Tan door frame caulking w/ paint (around single metal door frame)	ND	N/A
10854-63-17*	**LT Office / Bed Room**	**Gray door frame caulking w/ paint (around single metal door frame)**	**1.25%**	**Chrysotile**
10854-63-18*	**Fitness Room**	**Gray door frame caulking w/ paint (on wooden door frame)**	**1.5%**	**Chrysotile**
10854-63-19	Fitness Room	Layer 1: White caulking w/ paint Layer 2: Brown wood block (around 1'x1' in-door window: on wood single door)	L1: ND L2: ND	N/A N/A
10854-63-20*[1]	Fitness Room	Gray caulking w/ paint (around 1'x1' in-door window; on metal single door)	0.75%	Chrysotile
10854-63-21	Hallway 100	2'x4' pin-hole and worm track pattern SACT w/ paint	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-22*[2]	Radio Room	Layer 1: JC w/ paint Layer 2: GWB ceiling w/ paper (ceiling edge)	L1: 0.5% L2: ND	Chrysotile N/A
10854-63-23	Radio Room	GWB ceiling w/ paint and paper (mid ceiling)	ND	N/A
10854-63-24	Radio Room	Layer 1: Brown tac board (4'x8') Layer 2: Tan glue dot	L1: ND L2: ND	N/A N/A
10854-63-25	Furnace Room	Layer 1: 4"x4" green ceramic wall tile Layer 2: White grout Layer 3: Gray mortar Layer 4: Green paint (on CMU wall)	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A
10854-63-26*	**Furnace Room**	**Gray duct seam sealant (on 5" OD metal furnace flue)**	**1.25%**	**Chrysotile**
10854-63-27	Furnace Room	Dark gray sealant (at the base of furnace; on 3'x5' metal platform)	ND	N/A
10854-63-28	Hot Water Tank Room	Beige/blue pipe dope (on 1" sprinkler pipe fittings)	ND	N/A
10854-63-29	Shop	Layer 1: White repair patch w/ paint Layer 2: Concrete (foundation below CMU)	L1: ND L2: ND	N/A N/A
10854-63-30	Hose Tower	Gray CMU mortar w/ paint	ND	N/A
10854-63-31	Hose Tower	Layer 1: Gray brick mortar Layer 2: Red brick	L1: ND L2: ND	N/A N/A
10854-63-32	Apparatus Bay	Layer 1: Silver foil Layer 2: Beige/clear mastic Layer 3: Gray duct seam sealant w/ trace silver paint (on 6" OD engine exhaust system)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-33	Stairs	Layer 1: Brown stair tread Layer 2: Beige/clear mastic Layer 3: Red paint (on metal)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-34QA[X]*	**LT Office / Bedroom**	**Brown window frame caulking w/ paint (around 5'x5' metal framed window)**	**1.25%**	**Chrysotile**
10854-63-35	LT Office / Bed Room	Layer 1: Beige glue dot Layer 2: Wood radiator enclosure top	L1: ND L2: ND	N/A N/A
10854-63-36	LT Office / Bed Room	Tan glue dot (beneath 6"x5' wood window sill)	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-37	LT Office / Bed Room	Layer 1: Black paper backing w/ black mastic Layer 2: Yellow fiberglass batt insulation (above drop ceiling)	L1: ND L2: ND	N/A N/A
10854-63-38	NE Entry	Layer 1: Black pipe wrap Layer 2: Clear plastic (on 2" copper pipe)	L1: ND L2: ND	N/A N/A
10854-63-39	Apparatus Bay	Black expansion joint w/ paint (on various locations on concrete floor and exterior walls)	ND	N/A
Second Floor				
10854-63-40	Beanery & Watch	Layer 1: Multi-color carpet Layer 2: White carpet pad Layer 3: Tan mastic Layer 4: Black mastic Layer 5: Wood	L1: ND L2: ND L3: ND L4: ND L5: ND	N/A N/A N/A N/A N/A
10854-63-41	Beanery & Watch	Layer 1: Wood pattern SVF Layer 2: Light gray soft elastic backing Layer 3: Clear mastic Layer 4: White fibrous backing Layer 5: Tan mastic Layer 6: ¼" Plywood Layer 7: Black mastic Layer 8: Wood	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND	N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-42	Restroom 5	Layer 1: Gray broken rock pattern SVF Layer 2: Gray paper backing w/ tan mastic Layer 3: ¼" Particle board Layer 4: Trace black mastic Layer 5: Wood	L1: ND L2: ND L3: ND L4: ND L5: ND	N/A N/A N/A N/A N/A
10854-63-43	Stairwell	Layer 1: Trace white texturing skim coat w/ paint Layer 2: GWB wall w/ paper (corner wall)	L1: ND L2: ND	N/A N/A
10854-63-44	Stairwell	Layer 1: Trace white texturing skim coat w/ paint Layer 2: GWB wall w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-45	Restroom 5	Layer 1: Trace white texturing skim coat w/ paint and paper Layer 2: GWB wall w/ paper (mid wall)	L1: ND L2: ND	N/A N/A
10854-63-46	Restroom 4	Layer 1: White vinyl covering Layer 2: 2'x4' GWB SACT w/ paper	L1: ND L2: ND	N/A N/A
10854-63-47	Beanery & Watch	White sink undercoat	ND	N/A N/A
Exterior				
10854-63-48	East Side	Gray seam caulking/pipe dope (around 4"x4" seismic metal bracket and on sprinkler pipe fittings)	ND	N/A
10854-63-49	NW Corner	Layer 1: Gray foam window seal Layer 2: Trace clear mastic Layer 3: White paper (between sash and glass on 5'x5' metal framed window)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-50QA[X]	**East Side**	**Layer 1: Gray door frame caulking w/ paint** **Layer 2: Trace white sandy/brittle material with rusted material (on single metal door frame between BMU and frame)**	**L1: 4%** **L2: 3%**	**Chrysotile** **Chrysotile**
10854-63-51	**East Side**	**Gray door frame caulking w/ paint (on double metal door frame between BMU and metal frame)**	**4%**	**Chrysotile**
10854-63-52	East Side	Beige/gray window frame caulking (on 4'x6' metal framed window)	ND	N/A
10854-63-53	East Entry Awning	Layer 1: Black asphaltic 3-tab roofing Layer 2: Black asphaltic tar Layer 3: Black asphaltic 3-tab roofing Layer 4: Black asphaltic felt paper (on wood decking)	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A
10854-63-54	East Entry Awning	Trace brown awning metal flashing sealant	ND	N/A
10854-63-55	Exterior N Side	Gray plaster wall panel (4'x9') w/ paint (on brick)	ND	N/A
10854-63-56	Exterior NW corner	Gray plaster wall panel (4'x9') w/ paint (on brick)	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-57	Exterior N side	Gray plaster wall panel (4'x9') w/ paint (on brick)	ND	N/A
10854-63-58	Roof over Fitness Room	White roof flashing sealant w/ paint (on 6" metal flashing)	ND	N/A
10854-63-59	Roof over Apparatus Room	Tan conduit penetration sealant (around 3" conduit)	ND	N/A
10854-63-60	**Roof over Apparatus Room**	Layer 1: New white seam caulking **Layer 2: Old black asphaltic caulking (on 1'x1' metal ducting associated w/ old exhaust fan)**	ND **L2: 4%**	N/A **Chrysotile**
10854-63-61	Roof Over Apparatus Room	Silver/gray exhaust system seam sealant (8" OD)	ND	N/A
10854-63-62	Roof Over Apparatus Room	8" OD flex duct (associated with circulation fan)	ND	N/A
10854-63-63	Roof Over Apparatus Room	Black asphaltic vapor barrier (under wood siding)	ND	N/A
10854-63-64	Roof Over Fitness	Layer 1: Gray window glazing putty w/ paint Layer 2: Brown window glazing putty (around 2'x3' indoor window in metal door at the top of Hose Tower)	L1: ND L2: ND	N/A N/A
10854-63-65	Second Floor Stairwell	Yellow seam caulking w/ paint (between rungs and CMU wall)	ND	N/A
10854-63-66	Hose Tower Top Level	Gray interior window glazing putty (on 5'x5' metal framed window)	ND	N/A
10854-63-67	Roof Over Hose Tower	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil (on wood decking)	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-68	Roof Over Fitness Room	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil Layer 5: Black asphaltic tar Layer 6: Black asphaltic built-up roofing on brown paper Layer 7: Black asphaltic tar Layer 8: Brown fiber board insulation on tar (tarred onto wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND	N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-69	Roof Over Apparatus Room	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil Layer 5: White felt Layer 6: Yellow poly-iso insulation Layer 7: White felt Layer 8: Yellow poly-iso insulation Layer 9: White felt (on wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND L9: ND	N/A N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-70	Roof Over L.T. Office/ Bedroom	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil Layer 5: Black asphaltic tar Layer 6: Black asphaltic built-up roofing on brown paper Layer 7: Black asphaltic tar Layer 8: Brown fiber board insulation on tar (tarred onto wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND	N/A N/A N/A N/A N/A N/A N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-71	Roof Over Beanery/ Dayroom	Layer 1: White/blue membrane roofing Layer 2: Brown asphaltic felt paper Layer 3: Yellow poly-iso insulation Layer 4: Black asphaltic felt paper Layer 5: Black asphaltic tar Layer 6: Black asphaltic felt paper Layer 7: Brown paper Layer 8: Black asphaltic tar Layer 9: Black asphaltic felt paper Layer 10: Brown fiber board insulation (tarred onto wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND L9: ND L10: ND	N/A N/A N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-72QA[X]	**Second Floor Exterior**	**Layer 1: Old gray/dark gray window frame caulking w/ paint (under layer 2)** Layer 2: New gray window frame caulking (around 6'x5' metal framed window)	**L1: 4%** L2: ND	**Chrysotile** N/A
10854-63-73	Roof Over Fitness Room	Layer 1: White/blue membrane roofing Layer 2: Brown asphaltic felt paper Layer 3: Yellow poly-iso insulation Layer 4: Black asphaltic felt paper Layer 5: Black asphaltic tar Layer 6: Multiple layers of black asphaltic felt paper Layer 7: Brown paper Layer 8: Black asphaltic tar Layer 9: Black asphaltic felt paper Layer 10: Brown fiber board insulation (tarred onto wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND L9: ND L10: ND	N/A N/A N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-02-01	Hallway 100	Tan & white debris/insulation (at duct vent in floor)	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-02-02	Furnace Room	Layer 1: Dark gray duct seam sealant Layer 2: Clear duct seam sealant (on return air duct work)	L1: ND L2: ND	N/A N/A
10854-63-02-03	Bedroom 4	Layer 1: Green insulation Layer 2: Black coating (in 1' diameter recessed ceiling speaker casing)	L1: ND L2: ND	N/A N/A

Key: BMU = Brick Masonry Unit; **CMU** = Concrete Masonry Unit; **GWB** = Gypsum Wall Board; **JC** = Joint Compound; **OD** = Outside Diameter (includes OD of TSI); **ND** = None Detected; **N/A** = Not Applicable, **SACT** = Suspended Acoustical Ceiling Tile; **SVF** = Sheet Vinyl Flooring; **w/** =with;

[X] When QA lab and primary lab sample results differed, EHSI reported the most restrictive (e.g., highest % asbestos) in Table 1. Analytical results for all analyses are provided in Appendix A.

* Point Counted Results. EHSI re-submitted these samples which were reported to have greater than 1% asbestos concentration for re-analysis using the more precise EPA "Point Count" method. The "Point Count" analytical method is recommended by the EPA for samples with less than 10% asbestos. Only the "Point Count" re-analysis concentrations are listed in Table 1. Analytical results for all analyses are provided in Appendix A.

[1] Preliminary analytical reports indicated that the gray caulking w/ paint around the 1'x1' in-door window; on metal single door in the Fitness Room contains approximately 2% Chrysotile asbestos. (Sample # 10854-63-20) EHSI re-submitted the gray caulking sample reported to have greater than 1% asbestos concentration for re-analysis using the more precise EPA "Point Count" method. The "Point Count" analytical method is recommended by the EPA for samples with less than 10% asbestos. Based on the results of that re-analysis, the gray caulking w/ paint found around the 1'x1' in-door window on the metal single door in the Fitness Room was determined to be a **non-ACM** (e.g., containing ≤ 1% asbestos fibers). Only the "Point Count" re-analysis concentrations are listed in Table 1. Analytical results for all analyses are provided in Appendix A.

[2] Preliminary analytical reports indicated that the joint compound w/ paint found on the GWB ceiling in the Radio Room contains approximately 2% Chrysotile asbestos. (Sample # 10854-63-22) EHSI re-submitted the joint compound sample reported to have greater than 1% asbestos concentration for re-analysis using the more precise EPA "Point Count" method. The "Point Count" analytical method is recommended by the EPA for samples with less than 10% asbestos. Based on the results of that re-analysis, the joint compound w/ paint found on the GWB ceiling in the Radio Room was determined to be a **non-ACM** (e.g., containing ≤ 1% asbestos fibers). Only the "Point Count" re-analysis concentrations are listed in Table 1. Analytical results for all analyses are provided in Appendix A.

Materials containing <1% asbestos are regulated as "unclassified" asbestos materials and fall under separate requirements for worker protection, training, work practices and waste disposal. L&I DOSH requires special worker exposure precautions and qualifications when dealing with ACM used on GWB seams and nail holes. Similar requirements exist for walls and

ceilings skim-coated with material that contains less than one percent (<1%) asbestos fibers. Refer to L&I DOSH regulations and WISHA Regional Directives (WRD) as indicated above.

Table 2 summarizes materials identified by EHSI as containing greater than 1% asbestos fibers during its survey, and un-sampled materials assumed to be ACM. **The Table 2 Summary of Asbestos Containing Materials is for engineering cost estimating purposes and is not intended for bid quantifications.**

TABLE 2
SUMMARY OF ASBESTOS-CONTAINING MATERIALS
FIRE STATION #63

ASBESTOS MATERIAL DESCRIPTION	LOCATION	TOTAL	QUANTITY EXPECTED TO BE IMPACTED
ACM gray door frame caulking w/ paint (around single metal door frame)	LT Office / Bed Room	5 EA	2 EA
ACM gray door frame caulking w/ paint (on wooden door frame)	Fitness Room	2 EA	NIS
ACM gray duct seam sealant (on 5" OD metal furnace flue)	Furnace Room	6 LF	6 LF
ACM brown window frame caulking (around 5'x5' metal framed window)	LT Office / Bed Room	6 EA	3 EA
ACM gray door frame caulking w/ paint on ACM trace white sandy/brittle material with rusted material (on single metal door frame between brick and frame)	Exterior East Side	3 EA	NIS-
ACM gray door frame caulking w/ paint (on double metal door frame between brick and frame)	Exterior East Side	1 EA	NIS
Non-ACM new white seam caulking on **ACM old black asphaltic caulking** (on 1'x1' metal ducting associated w/ old exhaust fan)	Roof over Apparatus Room	5 LF	5 LF
Non-ACM new gray window frame caulking on **ACM old gray window frame caulking** (around 6'x5' metal framed window)	Second Floor Exterior	6 EA	6 EA
Assumed ACM internal components in radiator (1'x4'x7') concealed behind wood enclosure	L.T. Office/ Bedroom	1 EA	NIS
Fire door with assumed ACM fire core	L.T. Office/ Bedroom	1 EA	NIS
2'x3' Electrical panels with assumed ACM internals	Lobby, Apparatus Room, Electrical Room/ Hose Tower First Floor, Hose Tower Second Floor, Exterior Radio Equipment and Generator Area	9 EA	1 EA
2'x4' Electrical panels with assumed ACM internals	Electrical Room/ Hose Tower First Floor	3 EA	NIS

TABLE 2 SUMMARY OF ASBESTOS-CONTAINING MATERIALS FIRE STATION #63			
ASBESTOS MATERIAL DESCRIPTION	**LOCATION**	**TOTAL**	**QUANTITY EXPECTED TO BE IMPACTED**
Small electrical switch gear panels with assumed ACM internals	Apparatus Bay, Exterior N. Side and Roof	4 EA	2 EA
Assumed ACM glue dots associated w/ wood wall cabinets (5'x14')	Shop	2 EA	2 EA
Assumed ACM internal components in ceiling mounted unit-heaters (2'x3'x3.5')	Apparatus Room	3 EA	NIS
Assumed ACM TSI on small bore pipe elbows and fittings on fiberglass runs (concealed in plumbing walls & ceilings)	Restroom 1, Restroom 2, Furnace Room, and Restroom 8	120 EA	40 EA
Assumed ACM insulation on 12"x12" metal ducting concealed beneath slab	Throughout	400 LF	40 LF
Assumed ACM mastic associated with 4'x9' plaster wall panels on brick wall	Exterior North and West Sides	9 EA	9 EA
Assumed ACM windows concealed under 4'x9' exterior plaster wall panels	Exterior North and West Sides	4 EA	1 EA

Key: ACM = Asbestos-Containing Material; **BMU =** Brick Masonry Unit, **EA** = Each, **LF** = Linear Feet; **NIS =** Not in Scope, **OD** = Outside Diameter; **SF** = Square Feet; **small bore =** Pipe TSI ≤ 6" OD, **TSI** = Thermal System Insulation.

ACM identified in this survey should not be disturbed unless handled by personnel who are properly trained and certified in asbestos work. Demolition and/or renovation activities by contractors may expose concealed suspect ACM. Contractors should be aware of the potential for concealed suspect ACM and have preplanned contingencies for the handling of suspect ACM discovered during renovation and/or demolition work. Any concealed suspect ACM material that was not sampled or was assumed to be ACM and included in this report, must be treated as ACM until proven otherwise by a Certified AHERA Building Inspector and a certified laboratory. Contingency plans should include stopping work on identification of concealed suspect ACM, evacuation of the area, and sampling by a Certified AHERA Building Inspector. Concealed suspect material may include, but is not limited to: non-fiberglass pipe or roof drain insulation; spray-applied coatings; cementitious board; asphalt or paper vapor barriers; vinyl floorings and mastics.

2.4.2 Lead-Containing Paint and Building Materials

Forty-five (45) samples were analyzed for lead using the X-Ray fluorescence (XRF) analyzer. Results marked with "<u>≤</u>LOD" are less than the limit of detection. XRF paint sample results ranged from 0.5 milligrams of lead per square centimeter (mg Pb/cm^2) to less than the LOD. XRF sample results for other LCM ranged from 0.05 milligrams of lead per square centimeter (mg Pb/cm^2) to less than the LOD. The results are provided in Table 3 of this report. The results indicate that none of the materials were found to contain ≥1.0 mg/cm^2 lead using the XRF instrument and nine (9) of the surfaces were found to contain detectable levels of lead using the XRF. **Bolded results indicate materials coated with "lead-based paint" (e.g.,**

>1.0 mg/cm²) as defined by USEPA regulation 40CFR745 and Washington State Department of Commerce (Commerce) regulation WAC 365-230. XRF readings for other lead-containing materials were < LOD.

Table 3 summarizes XRF lead samples, including sample number, material description, substrate, color, location and analytical results.

TABLE 3
XRF SAMPLING
SUMMARY OF PAINTED COMPONENTS AND MATERIALS
FIRE STATION #63

Read. #	Component	Substrate	Color	Room	Building	Lead Conc. (mg/cm²)
1	SELF-CALIBRATION	N/A	N/A	N/A	N/A	0.67
2	CALIBRATION	N/A	RED	N/A	N/A	1.2
3	CALIBRATION	N/A	RED	N/A	N/A	1.1
4	CALIBRATION	N/A	RED	N/A	N/A	1.0
5	WALL	DRYWALL	WHITE	STAIRWELL	MAIN	< LOD
6	TRIM	WOOD	WHITE	STAIRWELL	MAIN	< LOD
7	WALL	CMU	OFF-WHITE	STAIRWELL	MAIN	< LOD
8	STAIR HANDRAIL	METAL	BROWN	STAIRWELL	MAIN	< LOD
9	STAIR RUNG	METAL	BROWN	STAIRWELL	MAIN	< LOD
10	WALL	BMU	WHITE	LOBBY	MAIN	< LOD
11	WALL	BMU	WHITE	LOBBY	MAIN	< LOD
12	DOOR	METAL	BROWN	LOBBY	MAIN	< LOD
13	DOORFRAME	METAL	BROWN	LOBBY	MAIN	< LOD
14	DRAINPIPE	METAL	WHITE	LOBBY	MAIN	< LOD
15	CONDUIT	METAL	WHITE	LOBBY	MAIN	< LOD
16	CONDUIT	METAL	WHITE	LOBBY	MAIN	< LOD
17	WALL	CMU	BEIGE	APPARATUS ROOM	MAIN	< LOD
18	WALL CORNER GUARD	METAL	BEIGE	APPARATUS ROOM	MAIN	0.06
19	SELF-CALIBRATION	N/A	N/A	N/A	N/A	0.65
20	CONDUIT	METAL	BEIGE	APPARATUS ROOM	MAIN	< LOD
21	CABINETS	WOOD	TAN	SHOP	MAIN	0.05
22	DUCT	METAL	TAN	SHOP	MAIN	< LOD
23	ELECTRICAL PANEL	METAL	DARK GRAY	SHOP	MAIN	< LOD
24	LADDER	METAL	YELLOW	SHOP	MAIN	0.5
25	DOOR	METAL	BEIGE	HOSE TOWER	MAIN	0.14
26	CEILING	DRYWALL	BEIGE	RADIO	MAIN	0.09
27	WALL	CERAMIC	LIGHT BLUE	FURNACE	MAIN	0.05

TABLE 3
XRF SAMPLING
SUMMARY OF PAINTED COMPONENTS AND MATERIALS
FIRE STATION #63

Read. #	Component	Substrate	Color	Room	Building	Lead Conc. (mg/cm^2)
28	WALL	DRYWALL	WHITE	HALLWAY	MAIN	< LOD
29	WALL	PLASTER	OFF-WHITE	EXTERIOR	MAIN	< LOD
30	DOWNSPOUT	METAL	OFF-WHITE	EXTERIOR	MAIN	< LOD
31	DOOR	METAL	BROWN	EXTERIOR	MAIN	< LOD
32	DOORFRAME	METAL	BROWN	EXTERIOR	MAIN	< LOD
33	STAIR RUNG	METAL	BROWN	EXTERIOR	MAIN	< LOD
34	PILLAR	CONCRETE	BROWN	EXTERIOR	MAIN	0.05
35	GARAGE DOOR	METAL	WHITE	EXTERIOR	MAIN	< LOD
36	DOWNSPOUT	METAL	BROWN	EXTERIOR	MAIN	< LOD
37	CONDUIT	METAL	BROWN	EXTERIOR	MAIN	< LOD
38	AWNING	WOOD	WHITE	EXTERIOR	MAIN	< LOD
39	PARAPET FLASHING	METAL	BROWN	EXTERIOR	MAIN	< LOD
40	SIDING	WOOD	OFF-WHITE	EXTERIOR	MAIN	< LOD
41	WALL	CMU	OFF-WHITE	EXTERIOR	MAIN	0.05
42	WALL	DRYWALL	BLUE	BEANERY & WATCH	MAIN	< LOD
43	CALIBRATION	N/A	RED	N/A	N/A	1.0
44	CALIBRATION	N/A	RED	N/A	N/A	1.0
45	CALIBRATION	N/A	RED	N/A	N/A	1.0

Key: CMU = Concrete Masonry Unit, **LOD**=Limit of Detection; **N/A** = Non-Applicable.

In addition to the XRF samples, EHSI collected three (3) bulk QA samples for laboratory analysis. Results marked with the "<" symbol are less than the lab reporting limit. Building materials and paint containing detectable levels of lead are considered regulated by DOSH.

Table 4 summarizes bulk QA lead samples, including sample number, material description, substrate, color, location, and analytical results.

Copies of the analytical laboratory report and field data forms for lead paint are included in Appendix B of this report.

TABLE 4 SUMMARY OF LEAD BULK QA SAMPLING AND ANALYTICAL RESULTS FS #63					
SAMPLE NUMBER	**LOCATION**	**COMPONENT**	**SUBSTRATE**	**COLOR**	**RESULTS % Pb by WT**
10854-63-Pb01	First Floor, Hose Tower	Wall	Mortar / CMU	Gray	0.0096
10854-63-Pb02	First Floor, Hose Tower	Wall	Mortar / Brick	Gray	<0.0031
10854-63-Pb03	First Floor, Mechanical Room	Wall	GWB	Off-White / Beige	<0.0048

Key: CMU = Concrete Masonry Unit; **GWB** = Gypsum Wall Board; **<0.00XX** = Less than the lab reporting limit for lead for that sample.

DOSH requires employers to conduct a hazard assessment and take appropriate worker protection precautions whenever paint is disturbed that has detectable quantities of lead. Since the type of work planned (e.g., sawing, grinding, demolition) will disturb the lead-containing paint, the contractor should perform an initial exposure assessment to determine if personal protective measures and work practices are required.

EHSI also observed eleven (11) Pb vent pipes on the roof of FS #63, that if disturbed will require recycling.

2.4.3 Arsenic-Containing Building Materials

EHSI collected two (2) arsenic bulk mortar samples for laboratory analysis. The results of those analyses are reported in Table 6.

Arsenic results for this inspection are reported in Appendix B. Table 5 summarizes arsenic samples, including sample number, material description, substrate, color and analytical results.

TABLE 5 SUMMARY OF ARSENIC BULK SAMPLING AND ANALYTICAL RESULTS FS #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**COMPONENT/ SUBSTRATE**	**COLOR**	**RESULTS IN PPM**
10854-63-As01	First Floor, Hose Tower	Mortar / CMU Wall	Gray	<18.0
10854-63-As02	First Floor, Hose Tower	Mortar / BMU Wall	Gray	22.0

DOSH requires employers to conduct a hazard assessment and take appropriate worker protection precautions whenever material is disturbed that has detectable quantities of arsenic. Since the type of work planned (e.g., sawing, grinding, demolition) will disturb the arsenic-containing materials, the contractor should perform an initial exposure assessment to determine if personal protective measures and work practices are required DOSH permissible exposure limit for arsenic is 0.2 mg/m^3 within an 8-hour time period.

2.4.4 Toxicity Characteristic Leaching Procedure Sampling

Ecology requires testing using the "toxicity characteristic leaching procedure" (TCLP) and segregation of construction debris if it is potentially contaminated with dangerous waste (e.g., lead-containing paint/lead-containing materials). Washington State Department of Ecology (Ecology) has set a dangerous waste threshold for both leachable arsenic and lead at 5.0 milligrams per liter (mg/L).

Because the potential waste streams will be determined by the contractor, a TCLP was not conducted as part of the Limited Hazardous Materials Survey; however, based on the relatively low levels of lead in the sample results, EHSI does not anticipate TCLP to fail for lead or arsenic.

2.4.5 Polychlorinated Biphenyls

Ballasts

Only electronic fluorescent light ballasts were observed. All fluorescent tubes and lamps contain mercury. Any fluorescent lamps/tubes to be disturbed during the project must be recycled as Washington Department of Ecology (Ecology) Universal Waste. Electronic fluorescent light ballasts may be disposed of as general construction debris. A Summary of ballasts and Hg-containing light tubes is provided in Table 6.

Transformers

EHSI did not observe any oil-filled transformers that will be impacted by the planned work in the FS #63 Building.

2.4.6 Mercury-Containing Thermostats and Fluorescent Light Tubes

EHSI observed four (4) Hg-containing thermostats throughout FS #63. All fluorescent light tubes quantified in Table 6 are assumed to contain Hg. Hg wastes are regulated as "universal wastes" under Ecology's regulation WAC 173-303. Hg-containing building materials must be recycled or disposed of as hazardous waste. Hg-containing fluorescent light tubes are quantified in Table 6.

TABLE 6
SUMMARY OF LIGHT FIXTURE INSPECTION RESULTS
FIRE STATION #63

LIGHT TYPE	NUMBER OF FIXTURES	NUMBER OF TUBES	APPROX. NUMBER OF MAGNETIC BALLASTS
2'x4' Recessed light fixture w/ 4 bulbs and 2 electronic ballasts	25	100	0
2'x4' Mounted light fixture w/ 4 bulbs and 2 electronic ballasts	8	24	0
2'x2' Recessed light fixture w/ 2 U-shaped bulbs and 1 electronic ballast	3	6	0
6"x1' wall mounted light fixture w/ 4 bulbs and 2 electronic ballasts	4	16	0

TABLE 6 SUMMARY OF LIGHT FIXTURE INSPECTION RESULTS FIRE STATION #63			
LIGHT TYPE	**NUMBER OF FIXTURES**	**NUMBER OF TUBES**	**APPROX. NUMBER OF MAGNETIC BALLASTS**
1'x4' Recessed light fixture w/ 2 bulbs and 1 electronic ballast	5	10	0
1'x8' Mounted light fixture w/ 4 bulbs and 2 electronic ballasts	12	48	0
HID lamps	6	6	0
CFL bulbs	4	4	0
Total	**68**	**214**	**0**

Key: CFL = compact fluorescent light, **HID** = high intensity discharge, **w/** = with

3.0 LIMITATIONS

This survey was limited to those materials accessible using standard survey methods. Limited representative destructive inspection was accomplished; however, in areas inaccessible for inspection, (e.g., fire door cores, wall cabinet mastics, electrical and materials above hard lid ceilings and inside closed plumbing chases) suspect materials were assumed to be present and assumed to be ACM.

This survey was limited to the chemicals and materials identified herein. No effort was made to identify hazardous materials in soil, water, or air, other than those listed herein. Any survey regardless of how extensive can miss concealed materials. Contractors should be aware of the potential that demolition activities may expose concealed suspect ACM and should have preplanned contingencies for handling these materials when discovered during demolition work. Any concealed, suspect ACM material that was not sampled or that was assumed to be ACM by this survey report when encountered must be treated as ACM until sampled by a Certified AHERA Building Inspector and analyzed by a certified laboratory.

4.0 STANDARD OF CARE

The recommendations and conclusions contained in this report represent the professional opinions of EHSI. These opinions are derived in accordance with federal, state, and local environmental and health and safety laws and regulations. This survey was accomplished in accordance with applicable federal, state, and local regulations and industry standards in effect at the time. Other than this, no other warranty is implied or intended.

5.0 CERTIFIED AHERA BUILDING INSPECTORS

The Certified AHERA Building Inspectors listed below surveyed FS #63 on April 22nd, 25th, and 26th, 2016 and September 27th, 2016 in accordance with federal, state, and local requirements.

Nadir Khan
Certified AHERA Building Inspector
Certificate Number: 10801-02-05
Expiration Date: December 11, 2016

Andrew Wells
Certified AHERA Building Inspector
Certificate Number: 2015-07-28-04
Expiration Date: July 28, 2016

Rory Peterson
Certified AHERA Building Inspector
Certificate Number: 158525
Expiration Date: August 17, 2017

APPENDIX A

Asbestos Analytical Laboratory Report and Field Data Forms

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#: 10854-01B
Batch#: 201610622
Date Received: 4/26/2016
Samples Rec'd: 60
Date Analyzed: 4/27/2016
Samples Analyzed: 60
Project Loc.: South King County Fire and Rescce Stution 63

Analyzed by: Cassie Huang/ Cici Xu

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
1	10854-63-01	1	Black rubbery material		None detected	Rubber/binder	2	Cellulose
		2	Clear/white/tan mastic		None detected	Mastic/binder	3	Cellulose
2	10854-63-02	1	Multi-color woven fibrous material		None detected	Filler, Binder	83	Synthetic fibers
		2	Tan mastic		None detected	Mastic/binder	4	Cellulose
3	10854-63-03	1	Light gray rubbery material		None detected	Rubber/binder	3	Cellulose
		2	Off-white/tan mastic		None detected	Mastic/binder	4	Cellulose
		3	White powdery material with paint and paper		None detected	Binder/filler, Paint	33	Cellulose
4	10854-63-04	1	Gray sheet vinyl		None detected	Vinyl/binder		None detected
		2	Gray fibrous material		None detected	Binder/filler	64	Cellulose
		3	Tan mastic		None detected	Mastic/binder	2	Cellulose
		4	Gray sandy/brittle material		None detected	Sand, Filler, Binder	3	Cellulose
5	10854-63-05	1	Black rubbery material		None detected	Rubber/binder	2	Cellulose
		2	White/tan mastic		None detected	Mastic/binder	2	Cellulose
		3	Brown mastic		None detected	Mastic/binder	2	Cellulose
6	10854-63-06	1	Beige sheet vinyl		None detected	Vinyl/binder		None detected
		2	White fibrous material		None detected	Binder/filler	65	Cellulose
		3	Tan mastic		None detected	Mastic/binder	3	Cellulose
		4	Gray brittle material		None detected	Filler, Binder	3	Cellulose
		5	Black mastic		None detected	Mastic/binder	2	Cellulose
		6	Gray sandy/brittle material		None detected	Sand, Filler, Binder	2	Cellulose
7	10854-63-07	1	White powdery material with paint and paper		None detected	Binder/filler, Paint	34	Cellulose
		2	Brown/gray chalky material with paper		None detected	Binder/filler, Gypsum/binder	23	Cellulose

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.:	Ms. Derica Escamilla/ Mr. Nadir Khan	**Client:**	EHS International, Inc.	**Address:**	1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#:	10854-01B	**Batch#:**	201610622	**Date Received:**	4/26/2016
Samples Rec'd:	60	**Date Analyzed:**	4/27/2016	**Samples Analyzed:**	60
Project Loc.:	South King County Fire and Rescce Stution 63				

Analyzed by: Cassie Huang/ Cici Xu

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
8	10854-63-08	1	White powdery material with paint and paper		**None detected**	Binder/filler, Paint	32	Cellulose
		2	Brown/gray chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	21	Cellulose
9	10854-63-09	1	White powdery material with paint		**None detected**	Binder/filler, Paint	5	Cellulose
		2	Brown/gray chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	23	Cellulose, Glass fibers
10	10854-63-10	1	White powdery material with paint		**None detected**	Binder/filler, Paint	5	Cellulose
		2	Brown/gray chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	25	Cellulose, Glass fibers
11	10854-63-11	1	White powdery material with paint		**None detected**	Binder/filler, Paint	4	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	22	Cellulose, Glass fibers
12	10854-63-12	1	White powdery material with paint		**None detected**	Binder/filler, Paint	4	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	23	Cellulose, Glass fibers
13	10854-63-13	1	Trace white powdery material with paint		**None detected**	Binder/filler, Paint	5	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	24	Cellulose, Glass fibers
14	10854-63-14	1	Brown wood debris		**None detected**	Wood debris	7	Cellulose
		2	Tan mastic		**None detected**	Mastic/binder	3	Cellulose
15	10854-63-15	1	White soft/elastic material		**None detected**	Binder, Filler	4	Cellulose
16	10854-63-16	1	Tan soft/elastic material with paint		**None detected**	Binder, Filler, Paint	3	Cellulose
17	10854-63-17	1	Gray soft material with paint	**2**	**Chrysotile**	Filler, Binder, Paint	2	Cellulose
18	10854-63-18	1	Gray soft material with paint	**2**	**Chrysotile**	Filler, Binder, Paint	3	Cellulose
19	10854-63-19	1	White soft/elastic material with paint		**None detected**	Binder, Filler, Paint	4	Cellulose
		2	Brown wood block		**None detected**	Wood aggregates	4	Cellulose
20	10854-63-20	1	Gray brittle material with paint	**2**	**Chrysotile**	Filler, Binder, Paint	2	Cellulose
21	10854-63-21	1	Gray fibrous material with paint		**None detected**	Paint, Filler, Perlite	65	Cellulose
22	10854-63-22	1	Tan powdery material with paint	**2**	**Chrysotile**	Binder/filler, Paint	5	Cellulose

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.:	Ms. Derica Escamilla/ Mr. Nadir Khan	**Client:**	EHS International, Inc.	**Address:**	1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#:	10854-01B	**Batch#:**	201610622	**Date Received:**	4/26/2016
Samples Rec'd:	60	**Date Analyzed:**	4/27/2016	**Samples Analyzed:**	60
Project Loc.:	South King County Fire and Rescce Stution 63				

Analyzed by: Cassie Huang/ Cici Xu

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	24	Cellulose, Glass fibers
23	10854-63-23	1	White chalky material with paint and paper		**None detected**	Binder/filler, Gypsum/binder, Paint	33	Cellulose, Glass fibers
24	10854-63-24	1	Brown cork		**None detected**	Cork		None detected
		2	Tan mastic		**None detected**	Mastic/binder	2	Cellulose
25	10854-63-25	1	Green ceramic		**None detected**	Ceramic/binder		None detected
		2	White brittle/sandy material		**None detected**	Binder, Sand	2	Cellulose
		3	Gray brittle material		**None detected**	Filler, Binder	3	Cellulose
		4	Green paint		**None detected**	Paint/binder	2	Cellulose
26	10854-63-26	1	Gray soft material	2	**Chrysotile**	Filler, Binder	3	Cellulose
27	10854-63-27	1	Gray soft/elastic material		**None detected**	Binder, Filler	4	Cellulose
28	10854-63-28	1	Beige/blue soft material		**None detected**	Filler, Binder	3	Cellulose
29	10854-63-29	1	White brittle material with paint		**None detected**	Filler, Binder, Paint	2	Cellulose
		2	Gray sandy/brittle material		**None detected**	Sand, Filler, Binder	3	Cellulose
30	10854-63-30	1	Gray sandy/brittle material with paint		**None detected**	Sand, Filler, Binder, Paint	4	Cellulose
31	10854-63-31	1	Gray sandy/brittle material		**None detected**	Sand, Filler, Binder	3	Cellulose
		2	Red sandy/brittle material		**None detected**	Sand, Filler, Binder	2	Cellulose
32	10854-63-32	1	Silver foil		**None detected**	Foil/binder		None detected
		2	Beige/clear mastic		**None detected**	Mastic/binder	3	Cellulose
		3	Gray soft/elastic material with trace silver paint		**None detected**	Binder, Filler, Paint	4	Cellulose
33	10854-63-33	1	Brown/gray rubbery material		**None detected**	Rubber/binder	2	Cellulose
		2	Beige mastic		**None detected**	Mastic/binder	3	Cellulose
		3	Red paint		**None detected**	Paint	2	Cellulose
34	10854-63-34	1	Brown soft material with paint	3	**Chrysotile**	Filler, Binder, Paint	3	Cellulose

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.:	Ms. Derica Escamilla/ Mr. Nadir Khan	**Client:**	EHS International, Inc.	**Address:**	1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#:	10854-01B	**Batch#:**	201610622	**Date Received:**	4/26/2016
Samples Rec'd:	60	**Date Analyzed:**	4/27/2016	**Samples Analyzed:**	60
Project Loc.:	South King County Fire and Rescce Stution 63				

Analyzed by: Cassie Huang/ Cici Xu

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
35	10854-63-35	1	Beige mastic		None detected	Mastic/binder	2	Cellulose
		2	Brown wood debris		None detected	Wood debris	6	Cellulose
36	10854-63-36	1	Tan mastic		None detected	Mastic/binder	2	Cellulose
37	10854-63-37	1	Black paper with black mastic		None detected	Filler, Asphalt/binder	70	Cellulose
		2	Yellow fibrous material		None detected	Filler	90	Glass fibers
38	10854-63-38	1	Black soft/elastic material		None detected	Binder, Filler	4	Cellulose
		2	Clear plastic		None detected	Plastic		None detected
39	10854-63-39	1	Black asphaltic material with fibrous material and paint		None detected	Asphalt/binder, Binder/filler, Paint	23	Cellulose
40	10854-63-40	1	Multi-color woven fibrous material		None detected	Filler, Binder	84	Synthetic fibers
		2	White woven fibrous material		None detected	Filler, Binder	81	Synthetic fibers
		3	Tan mastic		None detected	Mastic/binder	2	Cellulose
		4	Black mastic		None detected	Mastic/binder	3	Cellulose
		5	Brown wood block		None detected	Wood aggregates	5	Cellulose
41	10854-63-41	1	Brown sheet vinyl		None detected	Vinyl/binder		None detected
		2	Light gray soft/elastic material		None detected	Binder, Filler	4	Cellulose
		3	Clear mastic		None detected	Mastic/binder	3	Cellulose
		4	White woven fibrous material		None detected	Binder, Filler	58	Synthetic fibers
		5	Tan mastic		None detected	Mastic/binder	3	Cellulose
		6	Brown wood debris		None detected	Wood debris	7	Cellulose
		7	Black mastic		None detected	Mastic/binder	3	Cellulose
		8	Brown wood block		None detected	Wood aggregates	4	Cellulose
42	10854-63-42	1	Gray sheet vinyl		None detected	Vinyl/binder		None detected

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#: 10854-01B
Batch#: 201610622
Date Received: 4/26/2016
Samples Rec'd: 60
Date Analyzed: 4/27/2016
Samples Analyzed: 60
Project Loc.: South King County Fire and Rescce Stution 63

Analyzed by: Cassie Huang/ Cici Xu
Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
		2	Gray fibrous material with tan mastic		**None detected**	Binder/filler, Mastic/binder	65	Cellulose
		3	Brown wood debris		**None detected**	Wood debris	6	Cellulose
		4	Trace black mastic		**None detected**	Mastic/binder	4	Cellulose
		5	Brown wood block		**None detected**	Wood aggregates	4	Cellulose
43	10854-63-43	1	Trace white powdery material with paint		**None detected**	Binder/filler, Paint	2	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	25	Cellulose, Glass fibers
44	10854-63-44	1	Trace white powdery material with paint		**None detected**	Binder/filler, Paint	3	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	24	Cellulose, Glass fibers
45	10854-63-45	1	Trace white powdery material with paint and paper		**None detected**	Binder/filler, Paint	32	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	27	Cellulose, Glass fibers
46	10854-63-46	1	White soft/elastic material		**None detected**	Binder, Filler	2	Cellulose
		2	White chalky material with paper		**None detected**	Binder/filler, Gypsum/binder	33	Cellulose, Glass fibers
47	10854-63-47	1	White soft/loose material		**None detected**	Filler, Fine particles	5	Cellulose
48	10854-63-48	1	Gray soft/elastic material		**None detected**	Binder, Filler	3	Cellulose
49	10854-63-49	1	Gray foamy material		**None detected**	Synthetic foam		None detected
		2	Trace clear mastic		**None detected**	Mastic/binder	3	Cellulose
		3	White paper		**None detected**	Filler	72	Cellulose
50	10854-63-50	1	Gray soft material with paint	**4**	**Chrysotile**	Filler, Binder, Paint	4	Cellulose
51	10854-63-51	1	Gray soft material with paint	**4**	**Chrysotile**	Filler, Binder, Paint	3	Cellulose
52	10854-63-52	1	Beige/gray soft/elastic material		**None detected**	Binder, Filler	4	Cellulose
53	10854-63-53	1	Black asphaltic material with sand		**None detected**	Asphalt/binder, Sand	25	Glass fibers
		2	Black asphaltic material		**None detected**	Asphalt/binder	3	Cellulose

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Job#: 10854-01B
Batch#: 201610622
Date Received: 4/26/2016

Samples Rec'd: 60
Date Analyzed: 4/27/2016
Samples Analyzed: 60

Project Loc.: South King County Fire and Rescce Stution 63

Analyzed by: Cassie Huang/ Cici Xu
Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
		3	Black asphaltic material with sand		**None detected**	Asphalt/binder, Sand	16	Glass fibers
		4	Black asphaltic material with fibrous material		**None detected**	Asphalt/binder, Binder/filler	19	Cellulose
54	10854-63-54	1	Trace brown soft/elastic material		**None detected**	Binder, Filler	2	Cellulose
55	10854-63-55	1	Gray sandy/brittle material with paint		**None detected**	Sand, Filler, Binder, Paint	3	Cellulose
56	10854-63-56	1	Gray sandy/brittle material with paint		**None detected**	Sand, Filler, Binder, Paint	2	Cellulose
57	10854-63-57	1	Gray sandy/brittle material with paint		**None detected**	Sand, Filler, Binder, Paint	2	Cellulose
58	10854-63-58	1	White soft/elastic material with paint		**None detected**	Binder, Filler, Paint	4	Cellulose
59	10854-63-59	1	Tan soft/elastic material		**None detected**	Binder, Filler	3	Cellulose
60	10854-63-60	1	White soft/elastic material with paint		**None detected**	Binder, Filler, Paint	2	Cellulose
		2	Black soft material	**4**	**Chrysotile**	Filler, Binder, Asphalt/binder	4	Cellulose

20161022

Space Survey (Asbestos)

Project Number: 10854
Project Name: SKCFER Fire station 63
Location / Building: FS# 63
Inspectors: Nadir. K & Andrew. W

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattl, WA 98134
(206) 381-1128 Fax:(206)254-4279

Date 4/22/16
Page 1

Sample No.	Location	Material Description (color, size, use, substrate & layers)	Quantity
10854-63-01	First Floor LT office/Bed Room	4" Black cove base on clear mastic on white mastic on tan mastic	
-02	"	Multi-color carpet on tan mastic (on con)	
-03	"Restroom" 2	4" Light gray cove base on off-white on tan mastic on JC	RRs
-04	"	Gray broken rock pattern SVF w/gray paper backing on tan mastic on concrete.	RRs
-05	"Fitness Room"	6" Black cove base on white mastic on tan mastic on old brown mastic (on CMU)	~150 LF
-06	"NE Entry"	wood pattern SVF on white fibrous backing on tan mastic on gray leveling compound on black mastic on concrete	~100 SF
-07	"Restroom 2"	Texturing w/paint on JC/GwB (corner-wall) NOTE → Brown Grp	
-08	"	Texturing w/paint on GwB (mid-wall)	
-09	" " Storage understairs	Texturing w/paint on JC/GwB (ceiling-edge)	
-10	"	Texturing w/paint on GwB (mid-ceiling)	
-11	" " Bedroom 1 "	JC/GwB w/paint (corner-wall)	
-12	"	GwB w/paint (mid-wall)	
-13	" " Hallway 100 "		
-14	"Restroom 2"	Wood wainscoting on tan glue dot (All walls of Restrooms 4' from floor ~ 1200 SF)	
-15	"	White Caulking at horizontal seams (between wall / wood wainscoting)	
-16	"	Tan door frame Caulking w/paint (around single Metal door frame →)	
-17	" " LT office/Bed Room	Gray door frame w/paint ( )	
-18	" " Fitness Room "	(on wooden door frame)	
-19	"	White Caulking w/paint (around 1'x1' in-door window; on wood single door SAME DOOR AS SAMPLE # 18)	1 EA
-20	"	Gray Caulking w/paint (around 1'x1' in-door window; on metal single door)	1 EA

Space Survey - (Asbestos)

Proj[illegible]mber: 10854

Project Name: SKCFER Fire Station 63

Location / Building: FS # 63

Inspectors: Nadir. K & Andrew. W

20160622

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattl, WA 98134
(206) 381-1128 Fax:(206)254-4279

Date 4/22/16

Sample No.	Location	Material Description (color, size, use, substrate & layers)	Quantity
10854-63-21	First Floor Hallway 100	2'x4' pin-hole & worm tack pattern SACT w/paint.	
-22	" Radio Room "	JC/GwB w/paint (ceiling-edge)	
-23	"	GwB w/paint (mid-ceiling)	
-24	"	Brown tac board on tan glue dot (4'x8')	1 EA
-25	" Furnace Room "	4"x4" ceramic wall tile w/ white grout on gray mortar on green paint (on CMU)	~150SF
-26	"	Gray duct seam sealand (on 5" OD Metal Furnace flue)	~6LF
-27	"	Dark gray sealant (at the base of Furnace; on metal platform 3'x5')	1 EA
-28	" " " Hot water Tank Room	Beige/blue pipe dope on 1" sprinkler pipe	Throughout ~400LF.
-29	" Shop " "	White repair patch (on concrete foundation below CMU)	5SF
-30	" Hose Tower "	Gray CMU mortar w/paint.	
-31	"	Gray brick mortar w/ Red brick.	
-32	Apparatus Bay	silver foil on gray duct seam sealant (on 6" OD Engine exhaust system)	~60 LF
-33	" " " stairs	Brown stair tread on beige mastic on Red paint (on metal)	
-34	" LT office/Bed Room	Brown window frame caulking (around 5'x5' metal framed window)	3 EA + 3 EA → 6 Total
-35	"	Beige glue dot (associated with radiator enclosure Top)	
-36	"	Tan glue dot (beneath 6"x5' wood window sill SAME AS → #34)	2 EA
-37	" LT office/Bed Room	Yellow fiberglass batt insulation on black paper backing (above drop ceiling)	
-38	" NE Entry "	Black pipe wrap on clear plastic (on 2" copper pipe)	~2 LF
-39	" Apparatus Bay	Black expansion joint (on concrete floor various locations + Exterior walls)	~270LF
-40	Second Floor Beanery & Watch	Multi-color carpet on white carpet pad on tan mastic on black mastic on wood	1200 SF

Space Survey – (Asbestos)

20161022

Project Number: 10854
Project Name: SKCFER Fire Station 63
Location / Building: FS #63
Inspectors: Nadir K & Andrew W

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattl, WA 98134
(206) 381-1128 Fax:(206)254-4279

Date 4/25/16

Sample No.	Location	Material Description (color, size, use, substrate & layers)	Quantity
10854-63-41	Second Floor Beanery & watch	Wood pattern SVF on white fibrous backing on tan mastic on 1/4" ply-wood on black mastic on wood.	~800SF
-42	" " Restroom 5	Gray broken rock pattern SVF w/ gray paper backing on tan mastic on 1/4" particle-board on black mastic on wood.	~ 200 SF Total
-43	" " Stairwell "	Texturing w/paint on JC/GwB (corner-wall)	
-44	"Stairwell"	Texturing w/paint on GwB (Mid-wall)	
-45	"Restroom 5"		
-46	" " Restroom 4 "	white vinyl covering on 2'x4' GwB SACT	100 SF Total
-47	" " Beanery & watch	white sink under-coat	2 EA
-48	Exterior East Side	Gray Seam Caulking (around 4"x4" seismic metal brackets & sprinkler pipe)	
-49	Exterior NW corner	Gray foam window seal on white paper (between sash and glass on 5'x5' Metal framed window) (same as -48)	3 EA
-50	Exterior E side	Gray door frame caulking (on single metal door frame between brick & frame) w/paint	3 EA
-51	Exterior E side	(on double metal door frame between brick & frame)	1 EA
-52	↓	Beige/Gray window frame Caulking (on 4'x6' Metal framed window)	+ 6 EAS (9EA Total) 3 EA
-53	Exterior E Eantry Awaning	Three-tab shingle w/granules on black asphaltic felt-paper	70 SF
-54	↓	Brown awaning metal flashing sealant	~10 LF
-55	Exterior N side	Gray plaster wall panel w/paint (4'x9') (on brick)	16 EA
-56	Exterior NW corner	↓	
-57	Exterior N side	↓	
-58	Roof over Fitness Room	white roof flashing sealant w/paint (on 6" metal flashing)	Throughout.
-59	Roof over Apparatus Room	Tan conduit penetration sealant. (around 3" conduit)	(2 EA)
-60	↓	New White Seam Caulking on old black asphaltic caulking (on 1'x' Metal ducting associated with old exhaust fan)	~5LF

20161062 2

SEATTLE ASBESTOS TEST, LLC

Analyzing Quality

Lynnwood Lab: 19711 Scriber Lake Road, Suite D, WA 98036, Tel:425.673.9850, Fax:425.673.9810
Bellevue Lab: 12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Email: admin@seattleasbestostest.com, Website: www.seattleasbestostest.com

CHAIN OF CUSTODY

☒ Bulk Asbestos ☐ Point Count 400 ☐ Point Count 1000 ☐ Point Count Gravimetric ☐ Other (Specify) _____

☐ 1 Hour ☐ 2 Hours ☐ Same day (4 to 6 Hrs.) ☐ 1 Day ☒ 5 Days

EHS International, Inc.

1011 SW Klickitat Way, Suite 104, Seattle, WA 98134 Tel: (206) 381-1128 Fax: (206) 254-4279

Number of Samples 60 PO# 10854-01B Project Location South King County Fire and Rescue Station 63

Project Manager (Check one or more):

☐	Brett Racine	206.940.2236	brettr@ehsintl.com	☐	Cameron Peacock	206.818.4168	cameronp@ehsintl.com
☐	Clinton Holzhauer	425.766.5697	clintonh@ehsintl.com	☒	Derica Escamilla	425.638.3757	dericae@ehsintl.com
☐	Herb Brod	425.766.1546	herbb@ehsintl.com	☐	Kurt Easthouse	425.922.9230	kurte@ehsintl.com
☐	Lisa Kollasch	425.999.7886	lisak@ehsintl.com	☒	Nadir Khan	425.471.2166	nadirk@ehsintl.com
☐	Rory Peterson	425.766.8342	roryp@ehsintl.com	☐			

SEQ#	CLIENT SAMPLE #	SAMPLE DESCRIPTION	LOCATION	NOTES
1	10854-63-01			
2				
3				
4				
5				
6		See Data sheets		
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20	10854-63-60			

	Print Name	Signature	Company	Date	Time
Sampled:	Andrew Wells		EHS International, Inc.	4/25/16	15:15
Relinquished:	Andrew Wells		EHS International, Inc.	4/26/16	17:15
Delivered:			EHS International, Inc.		
Received:	Cassie Hwang		Seattle Asbestos Test	4/26/16	17:15
Analyzed:			Seattle Asbestos Test	4/27/16	15:38
Reported:			Seattle Asbestos Test		

Seattle Asbestos Test warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted and disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. Seattle Asbestos Test accepts no legal responsibility for the purpose for which the client uses the test results. By signing on this form, the clients agree to relieve Seattle Asbestos Test of any liability that may arise from the test results. It is the client's responsibility to make sure the samples are appropriately taken according to federal and local regulations. Invoices paid late may be charged of interest, and invoices go to collection may be charged 17% to 25% of collection fee. NSF checks will be charged of $50.

Results reporting method: ☐ Phone ☐ Fax ☒ Email ☐ Pick-up

☐ Composite all wallboard samples ☐ Text result to phone ☐ Point count ..... % or less asbestos

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.: Mr. Derica Escamilla **Client:** EHS International, Inc. **Address:** 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Job#: 10854-01B **Batch#:** 201610656 **Date Received:** 4/28/2016

Samples Rec'd: 13 **Date Analyzed:** 4/29/2016 **Samples Analyzed:** 13

Project Loc.: South King County Fire and Rescue Station 63

Analyzed by: Cici Xu Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
1	10854-63-61	1	Silver/gray soft/elastic material		None detected	Binder, Filler	3	Cellulose
2	10854-63-62	1	Black soft/elastic material with woven fibrous material		None detected	Filler, Binder	29	Synthetic fibers
3	10854-63-63	1	Black asphaltic fibrous material		None detected	Filler, Asphalt, Binder	68	Cellulose
4	10854-63-64	1	Gray brittle material with paint		None detected	Filler, Binder, Paint	2	Cellulose
		2	Brown soft/elastic material		None detected	Binder, Filler	4	Cellulose
5	10854-63-65	1	Yellow soft/elastic material with paint		None detected	Binder, Filler, Paint	3	Cellulose
6	10854-63-66	1	Gray soft/elastic material		None detected	Binder, Filler	4	Cellulose
7	10854-63-67	1	White/blue soft/elastic material with woven fibrous material		None detected	Filler, Binder	30	Synthetic fibers
		2	Silver foil		None detected	Foil/binder		None detected
		3	Yellow foamy material		None detected	Synthetic foam		None detected
		4	Silver foil		None detected	Foil/binder		None detected
8	10854-63-68	1	White/blue soft/elastic material with woven fibrous material		None detected	Filler, Binder	30	Synthetic fibers
		2	Silver foil		None detected	Foil/binder		None detected
		3	Yellow foamy material		None detected	Synthetic foam		None detected
		4	Silver foil		None detected	Foil/binder		None detected
		5	Black asphaltic material		None detected	Asphalt/binder	13	Glass fibers
		6	Black asphaltic material with fibrous material		None detected	Asphalt/binder, Binder/filler	25	Cellulose, Glass fibers
		7	Black asphaltic material		None detected	Asphalt/binder	3	Cellulose
		8	Brown fibrous material		None detected	Binder, Filler, Perlite	83	Cellulose
9	10854-63-69	1	White/blue soft/elastic material with woven fibrous material		None detected	Filler, Binder	31	Synthetic fibers

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.:	Mr. Derica Escamilla	**Client:**	EHS International, Inc.	**Address:**	1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#:	10854-01B	**Batch#:**	201610656	**Date Received:**	4/28/2016
Samples Rec'd:	13	**Date Analyzed:**	4/29/2016	**Samples Analyzed:**	13
Project Loc.:	South King County Fire and Rescue Station 63				

Analyzed by: Gilcl Xu

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
		2	Silver foil		**None detected**	Foil/binder		None detected
		3	Yellow foamy material		**None detected**	Synthetic foam		None detected
		4	Silver foil		**None detected**	Foil/binder		None detected
		5	Yellow paper		**None detected**	Filler	73	Cellulose, Glass fibers
		6	Yellow foamy material		**None detected**	Synthetic foam		None detected
		7	Yellow paper		**None detected**	Filler	74	Cellulose, Glass fibers
		8	Yellow foamy material		**None detected**	Synthetic foam		None detected
		9	Yellow paper		**None detected**	Filler	72	Cellulose, Glass fibers
10	10854-63-70	1	White/blue soft/elastic material with woven fibrous material		**None detected**	Filler, Binder	30	Synthetic fibers
		2	Silver foil		**None detected**	Foil/binder		None detected
		3	Yellow foamy material		**None detected**	Synthetic foam		None detected
		4	Silver foil		**None detected**	Foil/binder		None detected
		5	Black asphaltic material with sand		**None detected**	Asphalt/binder, Sand	15	Glass fibers
		6	Black asphaltic material with fibrous material		**None detected**	Asphalt/binder, Binder/filler	24	Cellulose, Glass fibers
		7	Black asphaltic material		**None detected**	Asphalt/binder	3	Cellulose
		8	Brown paper		**None detected**	Filler	75	Cellulose
11	10854-63-71	1	White/blue soft/elastic material with woven fibrous material		**None detected**	Filler, Binder	30	Synthetic fibers
		2	Black asphaltic fibrous material		**None detected**	Filler, Asphalt, Binder	67	Cellulose
		3	Yellow foamy material		**None detected**	Synthetic foam		None detected
		4	Black asphaltic fibrous material		**None detected**	Filler, Asphalt, Binder	70	Cellulose, Glass fibers
		5	Black asphaltic material		**None detected**	Asphalt/binder	15	Glass fibers

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.:	Mr. Derica Escamilla	**Client:**	EHS International, Inc.	**Address:**	1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#:	10854-01B	**Batch#:**	201610656	**Date Received:**	4/28/2016
Samples Rec'd:	13	**Date Analyzed:**	4/29/2016	**Samples Analyzed:**	13
Project Loc.:	South King County Fire and Rescue Station 63				

Analyzed by: Cici Xu

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
		6	Black asphaltic material with fibrous material		**None detected**	Asphalt/binder, Binder/filler	24	Cellulose, Glass fibers
		7	Brown paper		**None detected**	Filler	74	Cellulose
		8	Black asphaltic material		**None detected**	Asphalt/binder	3	Cellulose
		9	Black asphaltic fibrous material		**None detected**	Filler, Asphalt, Binder	70	Cellulose, Glass fibers
		10	Brown fibrous material		**None detected**	Binder, Filler, Perlite	82	Cellulose
12	10854-63-72	1	Gray soft material	3	**Chrysotile**	Filler, Binder	3	Cellulose
		2	Gray soft/elastic material		**None detected**	Binder, Filler	4	Cellulose
13	10854-63-73	1	White/blue soft/elastic material with woven fibrous material		**None detected**	Filler, Binder	29	Synthetic fibers
		2	Black asphaltic fibrous material		**None detected**	Filler, Asphalt, Binder	68	Cellulose
		3	Yellow foamy material		**None detected**	Synthetic foam		None detected
		4	Black asphaltic fibrous material		**None detected**	Filler, Asphalt, Binder	69	Cellulose, Glass fibers
		5	Black asphaltic material with sand		**None detected**	Asphalt/binder, Sand	12	Glass fibers
		6	Multi-layer black asphaltic material with fibrous material		**None detected**	Asphalt/binder, Binder/filler	26	Cellulose, Glass fibers
		7	Black asphaltic material		**None detected**	Asphalt/binder	3	Cellulose
		8	Black asphaltic material with fibrous material		**None detected**	Asphalt/binder, Binder/filler	23	Cellulose, Glass fibers
		9	Black asphaltic fibrous material		**None detected**	Filler, Asphalt, Binder	69	Cellulose
		10	Brown fibrous material		**None detected**	Binder, Filler, Perlite	85	Cellulose

Space Survey - (Asbestos)

Proj[illegible]mber: 10854

Project Name: SKCF+R Fire Station 63

Location / Building: FS# 63

Inspectors: Nadir. K & Andrew. W

20161656

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattl, WA 98134
(206) 381-1128 Fax:(206)254-4279

Date 4/25/16

Sample No.	Location	Material Description (color, size, use, substrate & layers)	Quantity
10854-63-61	Roof over Apparatus Room	Silver/gray exhaust seam sealant (8" Round)	7 LF EA → Total 10
-62	?	8" Round flex duct (associated in circulation fan)	1 EA
-63	?	Black asphaltic vapor barrier under wood siding	~2000 SF
-64	Roof over fitness	Gray window glazing (around 2'x3' Indoor window in metal door → Top of Tower.)	1 EA
-65	Second Floor stairwell	Yellow seam caulking. (between rung and cmu wall)	~40 LF
-66	Hose Tower top level	Gray interior window glazing putty (on 5'x5' Metal framed window)	3 EA
-67	Roof over Hose Tower	white/blue membrane roofing on silver foil on yellow poly-iso insulation on silver foil (on wood)	
-68	Roof over Fitness Room	white/blue membrane roofing on silver foil on yellow poly-iso insulation on silver foil on black asphaltic built-up roof on brown paper on tar on brown fiber board insulation on tar (taped to wood deck).	
-69	Roof over Apparatus Room	white/blue membrane roofing on silver foil on yellow poly-iso insulation on silver foil on three layers on poly-iso w/ white felt	
-70	Roof over Lt office/bedroom	SAME AS #68	
-71	Roof over Beanery/Dayroom 2nd Floor	SAME AS #68 → No silver foil on poly_iso.	
-72	Exterior	New gray window frame caulking on old gray window frame caulking (around 6'x5' metal framed wind...	6 EA
-73	Roof over Fitness Room	SAME AS #68 → No silver foil on poly-iso.	

on top and bott...

20161065b

SEATTLE ASBESTOS TEST, LLC

Analyzing Quality

Lynnwood Lab: 19711 Scriber Lake Road, Suite D, WA 98036, Tel:425.673.9850, Fax:425.673.9810
Bellevue Lab: 12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Email: admin@seattleasbestostest.com, Website: www.seattleasbestostest.com

CHAIN OF CUSTODY

☒ Bulk Asbestos ☐ Point Count 400 ☐ Point Count 1000 ☐ Point Count Gravimetric ☐ Other (Specify) _____

☐ 1 Hour ☐ 2 Hours ☐ Same day (4 to 6 Hrs.) ☐ 1 Day ☒ 5 Days

EHS International, Inc.

1011 SW Klickitat Way, Suite 104, Seattle, WA 98134 Tel: (206) 381-1128 Fax: (206) 254-4279

Number of Samples 13 PO# 10854-01B Project Location South King County Fire and Rescue Station 63

Project Manager (Check one or more):

☐	Brett Racine	206.940.2236	brettr@ehsintl.com	☐	Cameron Peacock	206.818.4168	cameronp@ehsintl.com
☐	Clinton Holzhauer	425.766.5697	clintonh@ehsintl.com	☒	Derica Escamilla	425.638.3757	dericae@ehsintl.com
☐	Herb Brod	425.766.1546	herbb@ehsintl.com	☐	Kurt Easthouse	425.922.9230	kurte@ehsintl.com
☐	Lisa Kollasch	425.999.7886	lisak@ehsintl.com	☒	Nadir Khan	425.471.2166	nadirk@ehsintl.com
☐	Rory Peterson	425.766.8342	roryp@ehsintl.com	☐			

SEQ#	CLIENT SAMPLE #	SAMPLE DESCRIPTION	LOCATION	NOTES
1	10854-63-61			
2		Please		
3		See		
4		Data		
5		Sheet		
6				
7				
8				
9				
10				
11				
12				
13	10854-63-73			
14				
15				
16				
17				
18				
19				
20				

	Print Name	Signature	Company	Date	Time
Sampled:	Nadir Khan	Nadir Khan	EHS International, Inc.	4/26/16	12:00pm.
Relinquished:	Andrew Wells		EHS International, Inc.	4/28/16	13:25
Delivered:			EHS International, Inc.		
Received:	Cristina Carlson		Seattle Asbestos Test	4/28/16	13:25
Analyzed:			Seattle Asbestos Test	4/29/16	11:30
Reported:			Seattle Asbestos Test		

Seattle Asbestos Test warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted and disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. Seattle Asbestos Test accepts no legal responsibility for the purpose for which the client uses the test results. By signing on this form, the clients agree to relieve Seattle Asbestos Test of any liability that may arise from the test results. It is the client's responsibility to make sure the samples are appropriately taken according to federal and local regulations. Invoices paid late may be charged of interest, and invoices go to collection may be charged 17% to 25% of collection fee. NSF checks will be charged of $50.

Results reporting method: ☐ Phone ☐ Fax ☒ Email ☐ Pick-up

☐ Composite all wallboard samples ☐ Text result to phone ☐ Point count ..... % or less asbestos

Page ( ) of ( )

May 2, 2016

Nadir Khan
EHS International
1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

RE: Bulk Asbestos Fiber Analysis; NVL Batch # 1608789.00

Client Project: 10854-01B
Location: SKCF & R Station 63

Dear Mr. Khan,

Enclosed please find test results for the 3 sample(s) submitted to our laboratory for analysis on 4/26/2016.

Examination of these samples was conducted for the presence of identifiable asbestos fibers using polarized light microscopy (PLM) with dispersion staining in accordance with both **EPA 600/M4-82-020**, Interim Method for the Determination of Asbestos in Bulk Insulation Samples and **EPA 600/R-93/116** Method for the Determination of Asbestos in Bulk Building Materials.

For samples containing more than one separable layer of materials, the report will include findings for each layer (labeled Layer 1 and Layer 2, etc. for each individual layer). The asbestos concentration in the sample is determined by calibrated visual estimation.

For those samples with asbestos concentrations between 1 and 10 percent based on visual estimation, the EPA recommends a procedure known as point counting (NESHAPS, 40 CFR Part 61). Point counting is a statistically more accurate means of quantification for samples with low concentrations of asbestos.

The detection limit for the calibrated visual estimation is <1%, 400 point counts is 0.25% and 1000 point counts is 0.1%

Samples are archived for two weeks following analysis. Samples that are not retrieved by the client are discarded after two weeks.

Thank you for using our laboratory services. Please do not hesitate to call if there is anything further we can assist you with.

Sincerely,

Nick Ly, Technical Director

Enc.: Sample Results

Lab Code: 102063-0

1.888.NVL.LABS
1.888.(685.5227)
www.nvllabs.com

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

Bulk Asbestos Fibers Analysis

By Polarized Light Microscopy

Client: EHS International
Address: 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

Attention: Mr. Nadir Khan
Project Location: SKCF & R Station 63

Batch #: 1608789.00
Client Project #: 10854-01B
Date Received: 4/26/2016
Samples Received: 3
Samples Analyzed: 3
Method: EPA/600/R-93/116 & EPA/600/M4-82-020

Lab ID: 16209227 **Client Sample #: 10854-63-05QA**
Location: SKCF & R Station 63
Comments: No tan mastic present.

Layer 1 of 3	**Description:** Black rubbery material			
	Non-Fibrous Materials:	Other Fibrous Materials:	%	**Asbestos Type: %**
	Rubber/Binder	None Detected	ND	**None Detected ND**
Layer 2 of 3	**Description:** White soft mastic			
	Non-Fibrous Materials:	Other Fibrous Materials:	%	**Asbestos Type: %**
	Mastic/Binder	Cellulose	2%	**None Detected ND**
Layer 3 of 3	**Description:** Brown brittle mastic with tan paint			
	Non-Fibrous Materials:	Other Fibrous Materials:	%	**Asbestos Type: %**
	Mastic/Binder, Paint	Talc fibers	6%	**None Detected ND**

Lab ID: 16209228 **Client Sample #: 10854-63-34QA**
Location: SKCF & R Station 63

Layer 1 of 1	**Description:** Brown caulking material material with paint			
	Non-Fibrous Materials:	Other Fibrous Materials:	%	**Asbestos Type: %**
	Binder/Filler, Caulking compound, Paint	Cellulose	3%	**Chrysotile 2%**

Lab ID: 16209229 **Client Sample #: 10854-63-50QA**
Location: SKCF & R Station 63

Layer 1 of 2	**Description:** Gray soft caulking material with paint			
	Non-Fibrous Materials:	Other Fibrous Materials:	%	**Asbestos Type: %**
	Binder/Filler, Caulking compound, Paint	Cellulose	2%	**Chrysotile 3%**
Layer 2 of 2	**Description:** Trace white sandy/brittle material with rusted material			
	Non-Fibrous Materials:	Other Fibrous Materials:	%	**Asbestos Type: %**
	Binder/Filler, Sand, Mineral grains	Cellulose	2%	**Chrysotile 3%**

Sampled by: Client
Analyzed by: Lori Tseng **Date:** 04/29/2016
Reviewed by: Nick Ly **Date:** 05/02/2016

Nick Ly, Technical Director

Note: If samples are not homogeneous, then subsamples of the components were analyzed separately. All bulk samples are analyzed using both EPA 600/R-93/116 and 600/M4-82-020 Methods with the following measurement uncertainties for the reported % Asbestos (1%=0-3%, 5%=1-9%, 10%=5-15%, 20%=10-30%, 50%=40-60%). This report relates only to the items tested. If sample was not collected by NVL personnel, then the accuracy of the results is limited by the methodology and acuity of the sample collector. This report shall not be reproduced except in full, without written approval of NVL Laboratories, Inc. It shall not be used to claim product endorsement by NVLAP or any other agency of the US Government

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

Bulk Asbestos Fibers Analysis

By Polarized Light Microscopy

Client: EHS International
Address: 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

Attention: Mr. Nadir Khan
Project Location: SKCF & R Station 63

Batch #: 1608789.00
Client Project #: 10854-01B
Date Received: 4/26/2016
Samples Received: 3
Samples Analyzed: 3
Method: EPA/600/R-93/116
& EPA/600/M4-82-020

Metal

Sampled by: Client
Analyzed by: Lori Tseng **Date:** 04/29/2016
Reviewed by: Nick Ly **Date:** 05/02/2016

Nick Ly, Technical Director

Note: If samples are not homogeneous, then subsamples of the components were analyzed separately. All bulk samples are analyzed using both EPA 600/R-93/116 and 600/M4-82-020 Methods with the following measurement uncertainties for the reported % Asbestos (1%=0-3%, 5%=1-9%, 10%=5-15%, 20%=10-30%, 50%=40-60%). This report relates only to the items tested. If sample was not collected by NVL personnel, then the accuracy of the results is limited by the methodology and acuity of the sample collector. This report shall not be reproduced except in full, without written approval of NVL Laboratories, Inc. It shall not be used to claim product endorsement by NVLAP or any other agency of the US Government

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

ASBESTOS LABORATORY SERVICES

Company EHS International
Address 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134
Project Manager Mr. Nadir Khan
Phone (206) 381-1128

NVL Batch Number **1608789.00**
TAT 5 Days **AH** No
Rush TAT
Due Date 5/3/2016 **Time** 4:55 PM
Email nadirk@ehsintl.com
Fax (206) 254-4279

Project Name/Number: 10854-01B **Project Location:** SKCF & R Station 63

Subcategory PLM Bulk
Item Code ASB-02 EPA 600/R-93-116 Asbestos by PLM <bulk>

Total Number of Samples 3 Rush Samples

	Lab ID	Sample ID	Description	A/R
1	16209227	10854-63-05QA		A
2	16209228	10854-63-34QA		A
3	16209229	10854-63-50QA		A

	Print Name	Signature	Company	Date	Time
Sampled by	Client				
Relinquished by	Client				

Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Christina Molnar		NVL	4/26/16	1655
Analyzed by	Lori Tseng		NVL	4/29/16	7:45 PM
Results Called by					
☐ **Faxed** ☐ **Emailed**					

Special Instructions:

Date: 4/26/2016
Time: 5:06 PM
Entered By: Justin Shearer

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
Tel: 206.547.0100 Emerg.Pager: 206.344.1878
Fax: 206.634.1936 1.888.NVL.LABS (685.5227)

CHAIN of CUSTODY SAMPLE LOG

1608789

Client EHS International, Inc.
Street 1011 SW Klickitat Way
Suite 104
Seattle, WA 98134
Project Manager Nadia Khan
Project Location SKCF&R Station 63

NVL Batch Number
Client Job Number 10854-01B
Total Samples 3
Turn Around Time ☐ 1-Hr ☐ 24-Hrs ☐ 4 Days ☐ 2-Hrs ☐ 2 Days ■ 5 Days ☐ 4-Hrs ☐ 3 Days ☐ 6 to 10 Days
Please call for TAT less than 24 Hrs

Email address Nadia K @ehsintl.com
Derica E @ehsintl.com

Phone: (206) 381-1128 **Fax:** (206) 254-4279

☐ **Asbestos Air** ☐ PCM (NIOSH 7400) ☐ TEM (NIOSH 7402) ☐ TEM (AHERA) ☐ TEM (EPA Level II) ☐ Other

■ **Asbestos Bulk** ■ PLM (EPA/600/R-93/116) ☐ PLM (EPA Point Count) ☐ PLM (EPA Gravimetry) ☐ TEM Bulk

☐ **Mold/Fungus** ☐ Mold Air ☐ Mold Bulk ☐ **Rotometer Calibration**

METALS	Inst./Det Limit	Matrix	RCRA Metals ☐ All 8	Other Metals
☐ Total Metals ☐ TCLP	☐ FAA (ppm) ☐ ICP (ppm) ☐ GFAA (ppb)	☐ Air Filter ☐ Drinking water ☐ Dust/wipe (Area) ☐ Soil ☐ Paint Chips in % ☐ Paint Chips in cm ☐ Waste Water ☐ Other	☐ Arsenic (As) ☐ Barium (Ba) ☐ Cadmium (Cd) ☐ Chromium (Cr) ☐ Lead (Pb) ☐ Mercury (Hg) ☐ Selenium (Se) ☐ Silver (Ag)	☐ All 3 ☐ Copper (Cu) ☐ Nickel (Ni) ☐ Zinc (Zn)

☐ **Other Types of Analysis** ☐ Fiberglass ☐ Nuisance Dust ☐ Other (Specify) _____
☐ Silica ☐ Respirable Dust

Condition of Package: ■ Good ☐ Damaged (no spillage) ☐ Severe damage (spillage)

Seq. #	Lab ID	Client Sample Number	Comments (e.g Sample area, Sample Volume, etc)	A/R
1		10854-63-05QA	6" Black Cove Base on white on tan mastic on old brown mastic (on CMU)	
2				
3				
4		10854-63-34QA	Brown window frame caulking (around 5'x5'- metal framed window)	
5				
6				
7		10854-63-50QA	Gray door frame caulking w/ paint	
8				
9				
10				
11				
12				
13				
14				
15				

	Print Below	Sign Below	Company	Date	Time
Sampled by	Andrew Wells		EHSI	4/25/16	15:15
Relinquished by	Andrew Wells		EHSI	4/26/16	16:50
Received by	Christina Molnar		NVL	4/26/16	1655
Analyzed by					
Results Called by					
Results Faxed by					

Special Instructions: Unless requested in writing, all samples will be disposed of two (2) weeks after analysis.

Please e-mail results.

April 29, 2016

Nadir Khan
EHS International
1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

RE: Bulk Asbestos Fiber Analysis; NVL Batch # 1608969.00

Client Project: 10854-01B
Location: South King County Fire and Rescue Station 63

Dear Mr. Khan,

Enclosed please find test results for the 1 sample(s) submitted to our laboratory for analysis on 4/28/2016.

Examination of these samples was conducted for the presence of identifiable asbestos fibers using polarized light microscopy (PLM) with dispersion staining in accordance with both **EPA 600/M4-82-020**, Interim Method for the Determination of Asbestos in Bulk Insulation Samples and **EPA 600/R-93/116** Method for the Determination of Asbestos in Bulk Building Materials.

For samples containing more than one separable layer of materials, the report will include findings for each layer (labeled Layer 1 and Layer 2, etc. for each individual layer). The asbestos concentration in the sample is determined by calibrated visual estimation.

For those samples with asbestos concentrations between 1 and 10 percent based on visual estimation, the EPA recommends a procedure known as point counting (NESHAPS, 40 CFR Part 61). Point counting is a statistically more accurate means of quantification for samples with low concentrations of asbestos.

The detection limit for the calibrated visual estimation is <1%, 400 point counts is 0.25% and 1000 point counts is 0.1%

Samples are archived for two weeks following analysis. Samples that are not retrieved by the client are discarded after two weeks.

Thank you for using our laboratory services. Please do not hesitate to call if there is anything further we can assist you with.

Sincerely,

Nick Ly, Technical Director

Enc.: Sample Results

Lab Code: 102063-0

1.888.NVL.LABS
1.888.(685.5227)
www.nvllabs.com

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

Bulk Asbestos Fibers Analysis

By Polarized Light Microscopy

Client: EHS International
Address: 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

Attention: Mr. Nadir Khan
Project Location: South King County Fire and Rescue Station 63

Batch #: 1608969.00
Client Project #: 10854-01B
Date Received: 4/28/2016
Samples Received: 1
Samples Analyzed: 1
Method: EPA/600/R-93/116
& EPA/600/M4-82-020

Lab ID: 16210149 **Client Sample #: 10854-63-72QA**

Location: South King County Fire and Rescue Station 63

Layer 1 of 2 **Description:** Gray soft elastic material

Non-Fibrous Materials:	Other Fibrous Materials:%	**Asbestos Type: %**
Caulking compound, Binder/Filler, Calcareous particles	None Detected ND	**None Detected ND**

Layer 2 of 2 **Description:** Dark gray soft material with paint

Non-Fibrous Materials:	Other Fibrous Materials:%	**Asbestos Type: %**
Caulking compound, Binder/Filler, Calcareous particles	Cellulose <1%	**Chrysotile 4%**
Paint		

Sampled by: Client
Analyzed by: Welly Hsieh **Date:** 04/29/2016
Reviewed by: Nick Ly **Date:** 04/29/2016

Nick Ly, Technical Director

Note: If samples are not homogeneous, then subsamples of the components were analyzed separately. All bulk samples are analyzed using both EPA 600/R-93/116 and 600/M4-82-020 Methods with the following measurement uncertainties for the reported % Asbestos (1%=0-3%, 5%=1-9%, 10%=5-15%, 20%=10-30%, 50%=40-60%). This report relates only to the items tested. If sample was not collected by NVL personnel, then the accuracy of the results is limited by the methodology and acuity of the sample collector. This report shall not be reproduced except in full, without written approval of NVL Laboratories, Inc. It shall not be used to claim product endorsement by NVLAP or any other agency of the US Government

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

ASBESTOS LABORATORY SERVICES

Company EHS International
Address 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134
Project Manager Mr. Nadir Khan
Phone (206) 381-1128

NVL Batch Number **1608969.00**
TAT 5 Days **AH** No
Rush TAT
Due Date 5/5/2016 **Time** 1:10 PM
Email nadirk@ehsintl.com
Fax (206) 254-4279

Project Name/Number: 10854-01B **Project Location:** South King County Fire and Rescue Station 63

Subcategory PLM Bulk
Item Code ASB-02 EPA 600/R-93-116 Asbestos by PLM <bulk>

Total Number of Samples 1 Rush Samples

	Lab ID	Sample ID	Description	A/R
1	16210149	10854-63-72QA		A

	Print Name	Signature	Company	Date	Time
Sampled by	Client				
Relinquished by	Client				

Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Maxwell Raymond		NVL	4/28/16	1310
Analyzed by	Welly Hsieh		NVL	4/29/16	3:44 PM
Results Called by					
☐ **Faxed** ☐ **Emailed**					

Special Instructions:

Date: 4/28/2016
Time: 4:18 PM
Entered By: Fatima Khan

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
Tel: 206.547.0100 Emerg.Pager: 206.344.1878
Fax: 206.634.1936 1.888.NVL.LABS (685.5227)

CHAIN of CUSTODY SAMPLE LOG

1608969

Client EHS International, Inc.
Street 1011 SW Klickitat Way
Suite 104
Seattle, WA 98134
Project Manager Nadir Khan
Project Location South King County Fire & Rescue Station 63

NVL Batch Number
Client Job Number 10854-01B
Total Samples 1
Turn Around Time ☐ 1-Hr ☐ 24-Hrs ☐ 4 Days ☐ 2-Hrs ☐ 2 Days ☒ 5 Days ☐ 4-Hrs ☐ 3 Days ☐ 6 to 10 Days
Please call for TAT less than 24 Hrs

Email address Nadir K @ehsintl.com
Derica E @ehsintl.com

Phone: (206) 381-1128 **Fax:** (206) 254-4279

☐ **Asbestos Air**	☐ PCM (NIOSH 7400)	☐ TEM (NIOSH 7402)	☐ TEM (AHERA)	☐ TEM (EPA Level II)	☐ Other	
☒ **Asbestos Bulk**	☒ PLM (EPA/600/R-93/116)	☐ PLM (EPA Point Count)	☐ PLM (EPA Gravimetry)	☐ TEM Bulk		
☐ **Mold/Fungus**	☐ Mold Air	☐ Mold Bulk	☐ **Rotometer Calibration**			

METALS	**Inst./Det Limit**	**Matrix**		**RCRA Metals** ☐ All 8		**Other Metals**
☐ Total Metals	☐ FAA (ppm)	☐ Air Filter	☐ Paint Chips in cm	☐ Arsenic (As)	☐ Mercury (Hg)	☐ **All 3**
☐ TCLP	☐ ICP (ppm)	☐ Drinking water	☐ Waste Water	☐ Barium (Ba)	☐ Selenium (Se)	☐ Copper (Cu)
	☐ GFAA (ppb)	☐ Dust/wipe (Area)	☐ Other	☐ Cadmium (Cd)	☐ Silver (Ag)	☐ Nickel (Ni)
		☐ Soil		☐ Chromium (Cr)		☐ Zinc (Zn)
		☐ Paint Chips in %		☐ Lead (Pb)		

☐ **Other Types of Analysis** ☐ Fiberglass ☐ Nuisance Dust ☐ Other (Specify) _____
☐ Silica ☐ Respirable Dust

Condition of Package: ☒ Good ☐ Damaged (no spillage) ☐ Severe damage (spillage)

Seq. #	Lab ID	Client Sample Number	Comments (e.g Sample area, Sample Volume, etc)	A/R
1		10854-63-72QA	new gray window frame caulking on old gray window frame caulking	
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				

	Print Below	Sign Below	Company	Date	Time
Sampled by	NADZR KHAN	Nadir K. Khan	EHSI	4/26/16	12:00pm
Relinquished by	Andrea Wells		EHSI	4/28/16	13:10
Received by				4/28/16	1BT
Analyzed by					
Results Called by					
Results Faxed by					

Special Instructions: Unless requested in writing, all samples will be disposed of two (2) weeks after analysis.

Please e-mail results.

SEATTLE ASBESTOS TEST

NVLAP Accreditation Lab Codes: 200768 and 200876

19701 Scriber Lake Road, Suite 103, Lynnwood, WA 98036, Tel:425.673.9850, Fax:425.673.9810
12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Website:www.seattleasbestostest.com, Email:admin@seattleasbestostest.com

PLM by Point Count (400 points)

Attention: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Client Job #: 10854-01B
Laboratory Batch #: 201610778
Date Received: 5/6/2016
Samples Received: 6
Date Analyzed: 5/10/2016

Project: South King County Fire and Rescce Stution 63

Sample Requested for Point Count 10854-63-17

Previous Analytical Information

Previously Analyzed by: Cassie Huang/ Cici Xu
Previous Batch #: 201610622
Previous Lab ID: 17
Previous Description: Gray soft material with paint
Layer to be Point Counted: 1
Asbestos Type Found: Chrysotile
Asbestos Percentage Found: 2

Point Count Analytical Procedures

New Lab ID: 1

	Asbestos Points	Non-Asbestos Points	Total Points Counted
Slide 1	1	49	50
Slide 2	0	50	50
Slide 3	1	49	50
Slide 4	1	49	50
Slide 5	0	50	50
Slide 6	0	50	50
Slide 7	2	48	50
Slide 8	0	50	50
Total	5	395	400

Point Count Summary Results

Type of Asbestos: Chrysotile
Percentage of Asbestos: 1.25%

Analyzed By: Cassie Huang

Reviewed by: Steve Zhang, President

SEATTLE ASBESTOS TEST

NVLAP Accreditation Lab Codes: 200768 and 200876

19701 Scriber Lake Road, Suite 103, Lynnwood, WA 98036, Tel:425.673.9850, Fax:425.673.9810
12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Website:www.seattleasbestostest.com, Email:admin@seattleasbestostest.com

PLM by Point Count (400 points)

Attention: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Client Job #: 10854-01B
Laboratory Batch #: 201610778
Date Received: 5/6/2016
Samples Received: 6
Date Analyzed: 5/10/2016

Project: South King County Fire and Rescce Stution 63

Sample Requested for Point Count 10854-63-18

Previous Analytical Information

Previously Analyzed by: Cassie Huang/ Cici Xu
Previous Batch #: 201610622
Previous Lab ID: 18
Previous Description: Gray soft material with paint
Layer to be Point Counted: 1
Asbestos Type Found: Chrysotile
Asbestos Percentage Found: 2

Point Count Analytical Procedures

New Lab ID: 2

	Asbestos Points	Non-Asbestos Points	Total Points Counted
Slide 1	0	50	50
Slide 2	1	49	50
Slide 3	2	48	50
Slide 4	1	49	50
Slide 5	0	50	50
Slide 6	1	49	50
Slide 7	0	50	50
Slide 8	1	49	50
Total	6	394	400

Point Count Summary Results

Type of Asbestos: Chrysotile
Percentage of Asbestos: 1.5%

Analyzed By: Cassie Huang

Reviewed by: Steve Zhang, President

SEATTLE ASBESTOS TEST

NVLAP Accreditation Lab Codes: 200768 and 200676

19701 Scriber Lake Road, Suite 103, Lynnwood, WA 98036, Tel:425.673.9850, Fax:425.673.9810
12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Website:www.seattleasbestostest.com, Email:admin@seattleasbestostest.com

PLM by Point Count (400 points)

Attention: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Client Job #: 10854-01B
Laboratory Batch #: 201610778
Date Received: 5/6/2016
Samples Received: 6
Date Analyzed: 5/10/2016

Project: South King County Fire and Rescce Stution 63

Sample Requested for Point Count 10854-63-20

Previous Analytical Information

Previously Analyzed by: Cassie Huang/ Cici Xu
Previous Batch #: 201610622
Previous Lab ID: 20
Previous Description: Gray brittle material with paint
Layer to be Point Counted: 1
Asbestos Type Found: Chrysotile
Asbestos Percentage Found: 2

Point Count Analytical Procedures

New Lab ID: 3

	Asbestos Points	Non-Asbestos Points	Total Points Counted
Slide 1	0	50	50
Slide 2	1	49	50
Slide 3	0	50	50
Slide 4	0	50	50
Slide 5	1	49	50
Slide 6	0	50	50
Slide 7	1	49	50
Slide 8	0	50	50
Total	3	397	400

Point Count Summary Results

Type of Asbestos: Chrysotile
Percentage of Asbestos: 0.75%

Analyzed By: Cassie Huang

Reviewed by: Steve Zhang, President

SEATTLE ASBESTOS TEST

NVLAP Accreditation Lab Codes: 200768 and 200876

19701 Scriber Lake Road, Suite 103, Lynnwood, WA 98036, Tel:425.673.9850, Fax:425.673.9810
12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Website:www.seattleasbestostest.com, Email:admin@seattleasbestostest.com

PLM by Point Count (400 points)

Attention: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Client Job #: 10854-01B
Laboratory Batch #: 201610778
Date Received: 5/6/2016
Samples Received: 6
Date Analyzed: 5/10/2016

Project: South King County Fire and Rescce Stution 63

Sample Requested for Point Count 10854-63-22

Previous Analytical Information

Previously Analyzed by: Cassie Huang/ Cici Xu
Previous Batch #: 201610622
Previous Lab ID: 22
Previous Description: Tan powdery material with paint
Layer to be Point Counted: 1
Asbestos Type Found: Chrysotile
Asbestos Percentage Found: 2

Point Count Analytical Procedures

New Lab ID: 4

	Asbestos Points	Non-Asbestos Points	Total Points Counted
Slide 1	0	50	50
Slide 2	0	50	50
Slide 3	0	50	50
Slide 4	1	49	50
Slide 5	0	50	50
Slide 6	0	50	50
Slide 7	0	50	50
Slide 8	1	49	50
Total	2	398	400

Point Count Summary Results

Type of Asbestos: Chrysotile
Percentage of Asbestos: 0.5%

Analyzed By: Cassie Huang

Reviewed by: Steve Zhang, President

SEATTLE ASBESTOS TEST

NVLAP Accreditation Lab Codes: 200768 and 200876

19701 Scriber Lake Road, Suite 103, Lynnwood, WA 98036, Tel:425.673.9850, Fax:425.673.9810
12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Website:www.seattleasbestostest.com, Email:admin@seattleasbestostest.com

PLM by Point Count (400 points)

Attention: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Client Job #: 10854-01B
Laboratory Batch #: 201610778
Date Received: 5/6/2016
Samples Received: 6
Date Analyzed: 5/10/2016

Project: South King County Fire and Rescce Stution 63

Sample Requested for Point Count 10854-63-26

Previous Analytical Information

Previously Analyzed by: Cassie Huang/ Cici Xu
Previous Batch #: 201610622
Previous Lab ID: 26
Previous Description: Gray soft material
Layer to be Point Counted: 1
Asbestos Type Found: Chrysotile
Asbestos Percentage Found: 2

Point Count Analytical Procedures

New Lab ID: 5

	Asbestos Points	Non-Asbestos Points	Total Points Counted
Slide 1	1	49	50
Slide 2	1	49	50
Slide 3	0	50	50
Slide 4	0	50	50
Slide 5	1	49	50
Slide 6	1	49	50
Slide 7	0	50	50
Slide 8	1	49	50
Total	5	395	400

Point Count Summary Results

Type of Asbestos: Chrysotile
Percentage of Asbestos: 1.25%

Analyzed By: Cassie Huang

Reviewed by: Steve Zhang, President

SEATTLE ASBESTOS TEST

NVLAP Accreditation Lab Codes: 200768 and 200876

19701 Scriber Lake Road, Suite 103, Lynnwood, WA 98036, Tel:425.673.9850, Fax:425.673.9810
12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Website:www.seattleasbestostest.com, Email:admin@seattleasbestostest.com

PLM by Point Count (400 points)

Attention: Ms. Derica Escamilla/ Mr. Nadir Khan
Client: EHS International, Inc.
Address: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134

Client Job #: 10854-01B
Laboratory Batch #: 201610778
Date Received: 5/6/2016
Samples Received: 6
Date Analyzed: 5/10/2016

Project: South King County Fire and Rescce Stution 63

Sample Requested for Point Count 10854-63-34

Previous Analytical Information

Previously Analyzed by: Cassie Huang/ Cici Xu
Previous Batch #: 201610622
Previous Lab ID: 34
Previous Description: Brown soft material with paint
Layer to be Point Counted: 1
Asbestos Type Found: Chrysotile
Asbestos Percentage Found: 3

Point Count Analytical Procedures

New Lab ID: 6

	Asbestos Points	Non-Asbestos Points	Total Points Counted
Slide 1	1	49	50
Slide 2	0	50	50
Slide 3	1	49	50
Slide 4	1	49	50
Slide 5	0	50	50
Slide 6	1	49	50
Slide 7	0	50	50
Slide 8	1	49	50
Total	5	395	400

Point Count Summary Results

Type of Asbestos: Chrysotile
Percentage of Asbestos: 1.25%

Analyzed By: Cassie Huang

Reviewed by: Steve Zhang, President

May 9, 2016

NVL LABS
INDUSTRIAL HYGIENE SERVICES
Laboratory | Management | Training

Nadir Khan
EHS International
1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

RE: Bulk Asbestos Fiber Concentration by Point Count
NVL Batch # 1609673

Client Project: 10854-01B
Location: SKCF & R Station 63

Dear Mr. Khan,

At your request, NVL Laboratories conducted analysis of your sample to determine the asbestos concentration using point count procedures.

The sample was analyzed for the presence of asbestos fibers using polarized light microscopy (PLM) with dispersion staining in accordance with U.S. EPA method 600/R -93/116.

Eight slides of thoroughly homogenized material are prepared for any given sample that requires point counting. In order to be counted as a point, the crosshairs of the microscope must center on either a fiber or a particle. The analyst counts at least 50 points per slide preparation. A minimum of 400 non-empty points are counted, then the number of counted asbestos fibers are divided by the total number of points counted to arrive at the percentage of asbestos in the sample.

Please see the conclusion section of the lab reports for point count results.

It has been a pleasure to be of service to you. Please feel free to call if there is anything further we can assist you with.

Sincerely,

Nick Ly, Technical Director

NVLAP®
Lab Code:102063

Enc.: Sample Results

1.888.NVL.LABS
1.888.(685.5227)
www.nvllabs.com

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

PLM Point Count
Bulk Asbestos Fibers Analysis

Client: EHS International
Address: 1011 SW Klickitat Way. Suite 104
Seattle. WA 98134
Attention: Mr. Nadir Khan
Project Location: SKCF & R Station 63

Batch #: 1609673.00
Client Project #: 10854-01B
Date Received: 5/6/2016
Samples Received: 1
Samples Analyzed: 1
Method: EPA/600R-93/116

Lab ID : 16214791 **Client Sample #: 10854-63-34QA LAYER 1 OF 1**

Sample Description: Brown caulking material with paint, Layer 1 of 1

Introduction: This sample was initially analyzed for Asbestos content using Polarized Light Microscopy (PLM). Asbestos fibers were observed and quantity was determined using calibrated visual area estimation. Asbestos content was originally found to be 2 % in Layer 1 . Corresponding Lab ID 16209228

Prep Slide #	Asbestos Point	Non Asbestos Point	Total Points Counted
1	1	49	50
2	0	50	50
3	0	50	50
4	2	48	50
5	0	50	50
6	0	50	50
7	0	50	50
8	0	50	50
Total	3	397	400

Conclusion: This Sample Contains 0.8 % ASBESTOS

Sampled by: Client
Analyzed by: Lori Tseng **Date:** 05/09/2016
Reviewed by: Nick Ly **Date:** 05/09/2016

Nick Ly, Technical Director

Note: If samples are not homogeneous, then subsamples of the components were analyzed separately. All bulk samples are analyzed using EPA 600/R-93/116 Method with the following measurement uncertainties for the reported % Asbestos (1%=0-3%, 5%=1-9%, 10%=5-15%, 20%=10-30%, 50%=40-60%). This report relates only to the items tested. If sample was not collected by NVL personnel, then the accuracy of the results is limited by the methodology and acuity of the sample collector. This report shall not be reproduced except in full, without written approval of NVL Laboratories, Inc. It shall not be used to claim product endorsement by NVLAP or any other agency of the US Government.

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

ASBESTOS LABORATORY SERVICES

Company EHS International
Address 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134
Project Manager Mr. Nadir Khan
Phone (206) 381-1128

NVL Batch Number **1609673.00**
TAT 5 Days **AH** No
Rush TAT
Due Date 5/13/2016 **Time** 12:00 PM
Email nadirk@ehsintl.com
Fax (206) 254-4279

Project Name/Number: 10854-01B **Project Location:** SKCF & R Station 63

Subcategory PLM Bulk
Item Code ASB-03 EPA 600/R-93-116 Asbestos by PLM (400 points) <bulk>

Total Number of Samples 1 Rush Samples

	Lab ID	Sample ID	Description	A/R
1	16214791	10854-63-34QA Layer 1	of 1	A

	Print Name	Signature	Company	Date	Time
Sampled by	Client				
Relinquished by	Emailed by Client				

Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Maxwell Raymond		NVL	5/6/16	1200
Analyzed by	Lori Tseng		NVL	5/9/16	
Results Called by					
☐ **Faxed** ☐ **Emailed**					

Special Instructions: Original Batch 1608789, Lori T.

Date: 5/6/2016
Time: 4:18 PM
Entered By: Maxwell Raymond

1609673

Maxwell Raymond

From: Andrew Wells <AndrewW@EHSINTL.COM>
Sent: Friday, May 06, 2016 11:59 AM
To: Client Services
Cc: Nadir Khan; Derica Escamilla
Subject: Point Count for SKCF&R Fire Station 63 (Batch 1608789.00)

Follow Up Flag: Follow up
Flag Status: Flagged

To whom it may concern,

We are requesting a point count for the following sample on a 5-day TAT:

Batch #: 1608789.00
EHSI Sample #: 10854-63-34QA
Lab ID: 16209228
Layer 1 of 1

Please email results to Nadir and Derica.

Best Regards,

Andrew Wells
Industrial Hygienist | Environmental Consultant
ehsi
EHS-International, Inc.
1011 SW Klickitat Way
Suite 104
Seattle, WA 98134
(206) 381-1128 | Office
(425) 495-4723 | Mobile
(206) 254-4279 | Fax
AndrewW@ehsintl.com
www.ehsintl.com

SEATTLE ASBESTOS TEST

Seattle Laboratory: 4500 9th Ave. NE, Suite 300, Seattle, WA 98105, Tel: 206.633.1111, Fax: 206.633.4747, NVLAP Lab Code: 201057-0

ANALYTICAL LABORATORY REPORT

PLM by Method EPA/600/R-93/116

Attn.:	Mr. Nadir Khan/ Mr. Rory Peterson	**Client:**	EHS International, Inc.	**Address:**	1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Job#:	10854-02B	**Batch#:**	201613141	**Date Received:**	9/27/2016
Samples Rec'd:	3	**Date Analyzed:**	9/30/2016	**Samples Analyzed:**	3
Project Loc.:	SKF&R Station 63				

Analyzed by: Carolyn Yeo/ Cassie Huang

Reviewed by: Steve (Fanyao) Zhang, President

Lab ID	Client Sample ID	Layer	Description	%	Asbestos Fibers	Non-fibrous Components	%	Non-asbestos Fibers
1	10854-63-02-01	1	Tan/white powdery material with trace sand		**None detected**	Filler, Binder, Sand, Debris	3	Cellulose
2	10854-63-02-02	1	Gray soft/elastic material		**None detected**	Binder, Filler	4	Cellulose
		2	Clear soft/elastic material		**None detected**	Binder, Filler	2	Cellulose
3	10854-63-02-03	1	Green fibrous material		**None detected**	Filler, Fine particles	82	Cellulose
		2	Black soft/elastic material		**None detected**	Binder, Filler	3	Cellulose

20161141

Space Survey - (Asbestos)

Project Number: 10854-02B

Project Name: SKFD R Station 63

Location / Building: Fire Station 63

Inspectors: Rory Peterson & Mike Ruark

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattl, WA 98134
(206) 381-1128 Fax:(206)254-4279

Date 9/27/16

Sample No.	Location	Material Description (color, size, use, substrate & layers)	Quantity
10854-63-02-01	Hallway 100	Tan & White Debris / Insulation (at duct vent in floor)	
10854-63-02-02	Furnace Room	Dark Gray Duct Seam Sealant (on Return Air Ductwork)	
10854-63-02-03	Bedroom 4	Green Insulation on Black Coating (in 1' Diameter Ceiling speakers) (Recessed in 2 of 2)	

20161314|

SEATTLE ASBESTOS TEST, LLC

Lynnwood Lab: 19711 Scriber Lake Road, Suite D, WA 98036, Tel:425.673.9850, Fax:425.673.9810
Bellevue Lab: 12727 Northup Way, Suite 1, Bellevue, WA 98005, Tel:425.861.1111, Fax:425.861.1118
Email: admin@seattleasbestostest.com, Website: www.seattleasbestostest.com

Analyzing Quality

CHAIN OF CUSTODY

- [x] Bulk Asbestos
- [ ] 1 Hour
- [ ] Point Count 400
- [ ] 2 Hours
- [ ] Point Count 1000
- [ ] Same day (4 to 6 Hrs.)
- [ ] Point Count Gravimetric
- [ ] 1 Day
- [ ] Other (Specify)
- [x] 5 Days

EHS International, Inc.

1011 SW Klickitat Way, Suite 104, Seattle, WA 98134 Tel: (206) 381-1128 Fax: (206) 254-4279

Number of Samples 3 PO# 10854-02B Project Location SKF 2R Station 63

Project Manager (Check one or more):

[ ]	Brett Racine	206.940.2236	brettr@ehsintl.com	[ ]	Cameron Peacock	206.818.4168	cameronp@ehsintl.com
[ ]	Clinton Holzhauer	425.766.5697	clintonh@ehsintl.com	[ ]	Derica Escamilla	425.638.3757	dericae@ehsintl.com
[ ]	Herb Brod	425.766.1546	herbb@ehsintl.com	[ ]	Kurt Easthouse	425.922.9230	kurte@ehsintl.com
[ ]	Lisa Kollasch	425.999.7886	lisak@ehsintl.com	[x]	Nadir Khan	425.471.2166	nadirk@ehsintl.com
[x]	Rory Peterson	425.766.8342	roryp@ehsintl.com	[ ]			

SEQ#	CLIENT SAMPLE #	SAMPLE DESCRIPTION	LOCATION	NOTES
1	10854.63-02-01	See Data Sheet		
2	↓			
3	10854-63-02-03			
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

	Print Name	Signature	Company	Date	Time
Sampled:	Rory Peterson		EHS International, Inc.	9/27/16	7:00 - 15:30
Relinquished:	Rory Peterson		EHS International, Inc.	9/27/16	11:00
Delivered:	Eric Arroyo	Eric Arroyo	EHS International, Inc.	9/27/16	11:50
Received:	Carolyn Yee	Carolyn Yee	Seattle Asbestos Test	9/27/16	11:49
Analyzed:	Carolyn Yee		Seattle Asbestos Test	9/27/16	14:46
Reported:			Seattle Asbestos Test		

Seattle Asbestos Test warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted and disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. Seattle Asbestos Test accepts no legal responsibility for the purpose for which the client uses the test results. By signing on this form, the clients agree to relieve Seattle Asbestos Test of any liability that may arise from the test results. It is the client's responsibility to make sure the samples are appropriately taken according to federal and local regulations. Invoices paid late may be charged of interest, and invoices go to collection may be charged 17% to 25% of collection fee. NSF checks will be charged of $50.

Results reporting method: [ ] Phone [ ] Fax [x] Email [ ] Pick-up

[ ] Composite all wallboard samples [ ] Text result to phone [ ] Point count ..... % or less asbestos

APPENDIX B

Lead and Arsenic Laboratory Reports and Field Data Forms

April 27, 2016

Nadir Khan
EHS International
1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

NVL LABS
INDUSTRIAL HYGIENE SERVICES
Laboratory | Management | Training

RE: Metals Analysis; NVL Batch # 1608792.00

Dear Mr. Khan,

Enclosed please find the test results for samples submitted to our laboratory for analysis. Preparation of these samples was conducted following protocol outlined in EPA Method SW 846 -3051 unless stated otherwise. Analysis of these samples was performed using analytical instruments in accordance with U.S. EPA, NIOSH, OSHA and other ASTM methods.

For matrix materials submitted as paint, dust wipe, soil or TCLP samples, analysis for the presence of total metals is conducted using published U.S. EPA Methods. Paint and soil results are usually expressed in mg/Kg which is equivalent to parts per million (ppm). Lead (Pb) in paint is usually expressed in mg/Kg (ppm) , Percent (%) or mg/cm^2 by area. Dust wipe sample results are usually expressed in ug/wipe and ug/ft^2. TCLP samples are reported in mg/L (ppm). For air filter samples, analyses are conducted using NIOSH and OSHA Methods. Results are expressed in ug/filter and ug/m^3. Other matrix materials are analyzed accordingly using published methods or specified by client. The reported test results pertain only to items tested and are not blank corrected.

For recent regulation updates pertaining to current regulatory levels or permissible exposure levels, please call your local regulatory agencies for more details.

This report is considered highly confidential and will not be released without your approval. Samples are archived for two weeks following analysis. Samples that are not retrieved by the client are discarded after two weeks.

Thank you for using our laboratory services. if you need further assistance please feel free to call us at 206-547-0100 or 1-888-NVLLABS.

Sincerely,



Shalini Patel, Laboratory Analyst

ilac-MRA
AIHA LAP, LLC
ACCREDITED LABORATORY
INDUSTRIAL HYGIENE & ENVIRONMENTAL LEAD
ISO/IEC 17025:2005
WWW.ANAACCREDITEDLABS.ORG
LAB # 101861

1.888.NVL.LABS
1.888.(685.5227)
www.nvllabs.com

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

Analysis Report

Total Lead (Pb)

Client: EHS International
Address: 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

Attention: Mr. Nadir Khan
Project Location: SKCF&R Station 63

Batch #: 1608792.00
Matrix: Paint
Method: EPA 3051/7000B
Client Project #: 10854-01B
Date Received: 4/26/2016
Samples Received: 3
Samples Analyzed: 3

Lab ID	Client Sample #	Sample Weight (g)	RL in mg/Kg	Results in mg/Kg	Results in percent
16209235	10854-63-Pb-01	0.2131	46.0	96.0	0.0096
16209236	10854-63-Pb-02	0.3161	31.0	< 31.0	< 0.0031
16209237	10854-63-Pb-03	0.2072	48.0	< 48.0	< 0.0048

Sampled by: Client
Analyzed by: Yasuyuki Hida
Reviewed by: Shalini Patel
Date Analyzed: 04/27/2016
Date Issued: 04/27/2016



Shalini Patel, Laboratory Analyst

mg/ Kg =Milligrams per kilogram
Percent = Milligrams per kilogram / 10000
RL = Reporting Limit
'<' = Below the reporting Limit
Note : Method QC results are acceptable unless stated otherwise.
Unless otherwise indicated, the condition of all samples was acceptable at time of receipt.

Bench Run No: 2016-0427-6

1608792

Lead **Survey Form**

Project Number: 10854
Project Name: SKCFER Fire Station 63
Location/Building FS# 63
Inspectors: Nadir.K & Andrew.W

Date: 4/22/16
Page: 1 of 1

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattle, WA 98134
(206) 381-1128 Fax:(206)254-4279

Sample #	Building	Floor / Space Name	Componant	Substrate	Color	Quantity (If applicable)	Condition/Comments
10854-63-Pb01	FS # 63	First floor / Hose Tower	mortar on wall	CMU	Gray		
-Pb02	FS# 63	First floor / Hose Tower	Mortar on wall	Brick	Gray		
-Pb03	FS# 63	Second floor / Mech Room	wall	GwB	offwhite/ Beige		

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

LEAD LABORATORY SERVICES

Company EHS International
Address 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134
Project Manager Mr. Nadir Khan
Phone (206) 381-1128

NVL Batch Number **1608792.00**
TAT 5 Days **AH** No
Rush TAT
Due Date 5/3/2016 **Time** 4:55 PM
Email nadirk@ehsintl.com
Fax (206) 254-4279

Project Name/Number: 10854-01B **Project Location:** SKCF&R Station 63

Subcategory Flame AA (FAA)
Item Code FAA-02 EPA 7000B Lead by FAA <paint>

Total Number of Samples 3 Rush Samples

	Lab ID	Sample ID	Description	A/R
1	16209235	10854-63-Pb-01		A
2	16209236	10854-63-Pb-02		A
3	16209237	10854-63-Pb-03		A

	Print Name	Signature	Company	Date	Time
Sampled by	Client				
Relinquished by	Client				

Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Christina Molnar		NVL	4/26/16	1655
Analyzed by	Yasuyuki Hida		NVL	4/27/16	
Results Called by					
☐ **Faxed** ☐ **Emailed**					

Special Instructions:

Date: 4/26/2016
Time: 5:35 PM
Entered By: Justin Shearer

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
Tel: 206.547.0100 Emerg.Pager: 206.344.1878
Fax: 206.634.1936 1.888.NVL.LABS (685.5227)

CHAIN of CUSTODY SAMPLE LOG

1608792

Client EHS International, Inc.
Street 1011 SW Klickitat Way
Suite 104
Seattle, WA 98134
Project Manager Nadir Khan
Project Location SKCFER Station 63

NVL Batch Number
Client Job Number 10854-01B
Total Samples 3
Turn Around Time ☐ 1-Hr ☐ 24-Hrs ☐ 4 Days ☐ 2-Hrs ☐ 2 Days ● 5 Days ☐ 4-Hrs ☐ 3 Days ☐ 6 to 10 Days
Please call for TAT less than 24 Hrs

Email address NadirK @ehsintl.com
Derica E @ehsintl.com

Phone: (206) 381-1128 **Fax:** (206) 254-4279

☐ **Asbestos Air**	☐ PCM (NIOSH 7400)	☐ TEM (NIOSH 7402)	☐ TEM (AHERA)	☐ TEM (EPA Level II)	☐ Other	
☐ **Asbestos Bulk**	☐ PLM (EPA/600/R-93/116)	☐ PLM (EPA Point Count)	☐ PLM (EPA Gravimetry)	☐ TEM Bulk		
☐ **Mold/Fungus**	☐ Mold Air	☐ Mold Bulk	☐ **Rotometer Calibration**			

METALS	**Inst./Det Limit**	**Matrix**		**RCRA Metals** ☐ All 8		**Other Metals** ☐ **All 3**
● Total Metals	● FAA (ppm)	☐ Air Filter	☐ Paint Chips in cm	☐ Arsenic (As)	☐ Mercury (Hg)	☐ Copper (Cu)
☐ TCLP	☐ ICP (ppm)	☐ Drinking water	☐ Waste Water	☐ Barium (Ba)	☐ Selenium (Se)	☐ Nickel (Ni)
	☐ GFAA (ppb)	☐ Dust/wipe (Area)	● Other	☐ Cadmium (Cd)	☐ Silver (Ag)	☐ Zinc (Zn)
		☐ Soil		☐ Chromium (Cr)		
		☐ Paint Chips in %		● Lead (Pb)		

☐ **Other Types of Analysis** ☐ Fiberglass ☐ Nuisance Dust ☐ Other (Specify) _____
☐ Silica ☐ Respirable Dust

Condition of Package: ● Good ☐ Damaged (no spillage) ☐ Severe damage (spillage)

Seq. #	Lab ID	Client Sample Number	Comments (e.g Sample area, Sample Volume, etc)	A/R
1		10854-63-Pb01	SEE DATA SHEET	
2		↓		
3		10854-63-Pb03		
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				

	Print Below	Sign Below	Company	Date	Time
Sampled by	Andrew Wells		EHSI	4/25/16	15:15
Relinquished by	Andrew Wells		EHSI	4/26/16	16:50
Received by	Christine Molnar			4/26/16	1655
Analyzed by					
Results Called by					
Results Faxed by					

Special Instructions: Unless requested in writing, all samples will be disposed of two (2) weeks after analysis.

Please e-mail results.

April 28, 2016

Nadir Khan
EHS International
1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

NVL LABS
INDUSTRIAL HYGIENE SERVICES
Laboratory | Management | Training

RE: Metals Analysis; NVL Batch # 1608791.00

Dear Mr. Khan,

Enclosed please find the test results for samples submitted to our laboratory for analysis. Preparation of these samples was conducted following protocol outlined in EPA Method SW 846 -3051 unless stated otherwise. Analysis of these samples was performed using analytical instruments in accordance with U.S. EPA, NIOSH, OSHA and other ASTM methods.

For matrix materials submitted as paint, dust wipe, soil or TCLP samples, analysis for the presence of total metals is conducted using published U.S. EPA Methods. Paint and soil results are usually expressed in mg/Kg which is equivalent to parts per million (ppm). Lead (Pb) in paint is usually expressed in mg/Kg (ppm) , Percent (%) or mg/cm^2 by area. Dust wipe sample results are usually expressed in ug/wipe and ug/ft^2. TCLP samples are reported in mg/L (ppm). For air filter samples, analyses are conducted using NIOSH and OSHA Methods. Results are expressed in ug/filter and ug/m^3. Other matrix materials are analyzed accordingly using published methods or specified by client. The reported test results pertain only to items tested and are not blank corrected.

For recent regulation updates pertaining to current regulatory levels or permissible exposure levels, please call your local regulatory agencies for more details.

This report is considered highly confidential and will not be released without your approval. Samples are archived for two weeks following analysis. Samples that are not retrieved by the client are discarded after two weeks.

Thank you for using our laboratory services. if you need further assistance please feel free to call us at 206-547-0100 or 1-888-NVLLABS.

Sincerely,

Nick Ly, Technical Director

ilac-MRA
AIHA LAP, LLC
ACCREDITED LABORATORY
INDUSTRIAL HYGIENE & ENVIRONMENTAL LEAD
ISO/IEC 17025:2005
WWW.AIHAACCREDITEDLABS.ORG
LAB # 101861

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

Analysis Report

Total Metals

Client: EHS International
Address: 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134

Attention: Mr. Nadir Khan
Project Location: SKCF&R Station 63

Batch #: 1608791.00
Matrix: Bulk
Method: EPA 3051/6010C
Client Project #: 10854-01B
Date Received: 4/26/2016
Samples Received: 2
Samples Analyzed: 2

Lab ID	Client Sample #	Elements	Sample wt (g)	RL mg / kg	Results in mg / kg	Results in ppm
16209233	10854-63-As01	Arsenic (As)	0.2197	18.0	< 18.0	< 18.0
16209234	10854-63-As02	Arsenic (As)	0.2032	20.0	22.0	22.0

Sampled by: Client
Analyzed by: Shalini Patel
Reviewed by: Nick Ly
Date Analyzed: 04/28/2016
Date Issued: 04/28/2016

Nick Ly, Technical Director

mg/ kg = Milligrams per kilogram
ppm = Parts per million
RL = Reporting Limit
'<' = Below the reporting Limit

Note : Method QC results are acceptable unless stated otherwise.
Unless otherwise indicated, the condition of all samples was acceptable at time of receipt.

Bench Run No: 2016-0428-01

1608791

Arsenic Survey Form

Project Number: 10854
Project Name: SKCF&R Fire station 63
Location/Building: FS # 63
Inspectors: Nadir. K & Andrew. W

Date: 4/22/16
Page: 1 of 1

EHS-INTERNATIONAL, INC.
1011 SW Klickitat Way, Suite 104
Seattle, WA 98134
(206) 381-1128 Fax:(206)254-4279

Sample #	Building	Floor / Space Name	Componant	Substrate	Color	Quantity (if applicable)	Condition/Comments
10854-63-AS01	FS# 63	First floor / Hose Tower	Mortar on wall	CMU	Gray		
- AS02	FS# 63	First floor / Hose Tower	Mortar on wall	Brick	↓		

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
p 206.547.0100 | f 206.634.1936 | www.nvllabs.com

METAL LABORATORY SERVICES

Company EHS International
Address 1011 SW Klickitat Way. Suite 104
Seattle, WA 98134
Project Manager Mr. Nadir Khan
Phone (206) 381-1128

NVL Batch Number **1608791.00**
TAT 5 Days **AH** No
Rush TAT
Due Date 5/3/2016 **Time** 4:55 PM
Email nadirk@ehsintl.com
Fax (206) 254-4279

Project Name/Number: 10854-01B **Project Location:** SKCF&R Station 63

Subcategory Inductively Coupled Plasma (ICP) - Group Tests
Item Code ICP-M2 EPA 6010B (price per analyte) <paint>
Metals Arsenic (As)

Total Number of Samples 2 Rush Samples

	Lab ID	Sample ID	Description	A/R
1	16209233	10854-63-As01		A
2	16209234	10854-63-As02		A

	Print Name	Signature	Company	Date	Time
Sampled by	Client				
Relinquished by	Client				

Office Use Only	Print Name	Signature	Company	Date	Time
Received by	Christina Molnar		NVL	4/26/16	1655
Analyzed by	Shalini Patel		NVL	4/28/16	
Results Called by					
☐ **Faxed** ☐ **Emailed**					

Special Instructions:

Date: 4/26/2016
Time: 5:31 PM
Entered By: Justin Shearer

NVL Laboratories, Inc.
4708 Aurora Ave N, Seattle, WA 98103
Tel: 206.547.0100 Emerg.Pager: 206.344.1878
Fax: 206.634.1936 1.888.NVL.LABS (685.5227)

CHAIN of CUSTODY SAMPLE LOG

1608791

Client: EHS International, Inc.
Street: 1011 SW Klickitat Way, Suite 104, Seattle, WA 98134
Project Manager: Nadir Khan
Project Location: SKCF&R Station 63

NVL Batch Number:
Client Job Number: 10854-01B
Total Samples: 2
Turn Around Time: ☐ 1-Hr ☐ 24-Hrs ☐ 4 Days ☐ 2-Hrs ☐ 2 Days ☒ 5 Days ☐ 4-Hrs ☐ 3 Days ☐ 6 to 10 Days
Please call for TAT less than 24 Hrs

Email address: Nadir K @ehsintl.com
Derica E @ehsintl.com

Phone: (206) 381-1128 Fax: (206) 254-4279

☐ **Asbestos Air** ☐ PCM (NIOSH 7400) ☐ TEM (NIOSH 7402) ☐ TEM (AHERA) ☐ TEM (EPA Level II) ☐ Other

☐ **Asbestos Bulk** ☐ PLM (EPA/600/R-93/116) ☐ PLM (EPA Point Count) ☐ PLM (EPA Gravimetry) ☐ TEM Bulk

☐ **Mold/Fungus** ☐ Mold Air ☐ Mold Bulk ☐ **Rotometer Calibration**

METALS	Inst./Det Limit	Matrix	RCRA Metals	Other Metals
☒ Total Metals ☐ TCLP	☐ FAA (ppm) ☒ ICP (ppm) ☐ GFAA (ppb)	☐ Air Filter ☐ Drinking water ☐ Dust/wipe (Area) ☐ Soil ☐ Paint Chips in % ☐ Paint Chips in cm ☐ Waste Water ☒ Other	☒ Arsenic (As) ☐ Barium (Ba) ☐ Cadmium (Cd) ☐ Chromium (Cr) ☐ Lead (Pb) ☐ All 8 ☐ Mercury (Hg) ☐ Selenium (Se) ☐ Silver (Ag)	☐ All 3 ☐ Copper (Cu) ☐ Nickel (Ni) ☐ Zinc (Zn)

☐ **Other Types of Analysis** ☐ Fiberglass ☐ Nuisance Dust ☐ Other (Specify) ☐ Silica ☐ Respirable Dust

Condition of Package: ☒ Good ☐ Damaged (no spillage) ☐ Severe damage (spillage)

Seq. #	Lab ID	Client Sample Number	Comments (e.g Sample area, Sample Volume, etc)	A/R
1		10854-63-As01	SEE DATA SHEET	
2		10854-63-As02		
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				

	Print Below	Sign Below	Company	Date	Time
Sampled by	Andrew Wells		EHSI	4/25/16	15:15
Relinquished by	Andrew Wells		EHSI	4/26/16	16:50
Received by	Christina Molnar		NVL	4/26/16	1655
Analyzed by					
Results Called by					
Results Faxed by					

Special Instructions: Unless requested in writing, all samples will be disposed of two (2) weeks after analysis.

Please e-mail results.

APPENDIX C

Certified AHERA Building Inspector Certificates

Certificate of Training

EHS - International, Inc. certifies that

NADIR KHAN

has successfully completed the

4-Hour AHERA Building Inspector Refresher Training

in accordance with

40 CFR 763, Subpart E, Appendix C

on this 11th day of December in Seattle, WA

Expires December 11, 2016

Training Administrator Herb Brod

December 11, 2015	***10801-02-05***
Class Date	Student Number

EHS–International, Inc.

1011 SW Klickitat Way, Suite 104 ▪ Seattle, Washington 98134

(206) 381-1128 Phone ▪ (206) 254-4279 Fax

Certificate of Training

EHS - International, Inc. certifies that

Andrew Wells

has successfully completed the
4-Hour AHERA Building Inspector Refresher Training
in accordance with
40 CFR 763, Subpart E, Appendix C
on this 28th day of July in Seattle, WA
Expires July 28, 2016

Training Administrator Derica Escamilla

July 28, 2015	*2015-07-28-04*
Class Date	Student Number

EHS–International, Inc.

1011 SW Klickitat Way, Suite 104 □ Seattle, Washington 98134
(206) 381-1128 Phone □ (206) 254-4279 Fax

Certificate of Completion

This is to certify that

Rory M. Peterson

has satisfactorily completed
4 hours of refresher training as an

Asbestos Building Inspector

to comply with the training requirements of
TSCA Title II / 40 CFR 763 (AHERA)

Certificate #
158525

Instructor
EPA Provider Certificate #1085

ARGUS PACIFIC
TRAINING • CONSULTING
A Terracon COMPANY

Aug 17, 2016
Date(s) of Training
Exam Score: NA
Expiration Date: Aug 17, 2017

ARGUS PACIFIC, INC. • 1900 W NICKERSON ST, SUITE 315 • SEATTLE, WASHINGTON • 98119 • 206.285.3373 • WWW.ARGUSPACIFIC.COM

APPENDIX D

Laboratory Certifications for Asbestos, Lead, and Arsenic Analysis

United States Department of Commerce
National Institute of Standards and Technology

Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 201057-0

Seattle Asbestos Test Seattle

Seattle, WA

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

Asbestos Fiber Analysis

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2016-07-01 through 2017-06-30

Effective Dates

DEPARTMENT OF COMMERCE * UNITED STATES OF AMERICA *

For the National Voluntary Laboratory Accreditation Program

AIHA Laboratory Accreditation Programs, LLC

acknowledges that

NVL Laboratories, Inc.

4708 Aurora Avenue N., Seattle, WA 98103

Laboratory ID: 101861

along with all premises from which key activities are performed, as listed above, has fulfilled the requirements of the AIHA Laboratory Accreditation Programs (AIHA-LAP), LLC accreditation to the ISO/IEC 17025:2005 international standard, *General Requirements for the Competence of Testing and Calibration Laboratories* in the following:

LABORATORY ACCREDITATION PROGRAMS

✓	**INDUSTRIAL HYGIENE**	Accreditation Expires: 05/01/2017
✓	**ENVIRONMENTAL LEAD**	Accreditation Expires: 05/01/2017
✓	**ENVIRONMENTAL MICROBIOLOGY**	Accreditation Expires: 05/01/2017
☐	**FOOD**	Accreditation Expires:
✓	**UNIQUE SCOPES**	Accreditation Expires: 05/01/2017

Specific Field(s) of Testing (FoT)/Method(s) within each Accreditation Program for which the above named laboratory maintains accreditation is outlined on the attached **Scope of Accreditation**. Continued accreditation is contingent upon successful on-going compliance with ISO/IEC 17025:2005 and AIHA-LAP, LLC requirements. This certificate is not valid without the attached **Scope of Accreditation**. Please review the AIHA-LAP, LLC website (www.aihaaccreditedlabs.org) for the most current Scope.

Gerald R Schultz

Gerald Schultz, CIH
Chairperson, Analytical Accreditation Board

Cheryl O. Morton

Cheryl O. Morton
Managing Director, AIHA Laboratory Accreditation Programs, LLC

Revision 14: 03/26/2014

Date Issued: 04/30/2015

United States Department of Commerce
National Institute of Standards and Technology

Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 102063-0

NVL Laboratories, Inc.

Seattle, WA

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

Asbestos Fiber Analysis

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005. This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2015-09-25 through 2016-09-30

Effective Dates

DEPARTMENT OF COMMERCE * UNITED STATES OF AMERICA *

For the National Voluntary Laboratory Accreditation Program

NVLAP® National Voluntary Laboratory Accreditation Program

SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

NVL Laboratories, Inc.
4708 Aurora Avenue N.
Seattle, WA 98103
Mr. Nghiep Vi Ly
Phone: 206-547-0100 Fax: 206-634-1936
Email: nick.l@nvllabs.com
http://www.nvllabs.com

ASBESTOS FIBER ANALYSIS

NVLAP LAB CODE 102063-0

Bulk Asbestos Analysis

Code	*Description*
18/A01	EPA 600/M4-82-020: Interim Method for the Determination of Asbestos in Bulk Insulation Samples
18/A03	EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

For the National Voluntary Laboratory Accreditation Program

The State of Washington Department of Ecology

NVL Laboratories, Inc.
Seattle, WA

has complied with provisions set forth in Chapter 173-50 WAC and is hereby recognized by the Department of Ecology as an ACCREDITED LABORATORY for the analytical parameters listed on the accompanying Scope of Accreditation. This certificate is effective July 18, 2015 and shall expire July 17, 2016.

Witnessed under my hand on June 30, 2015

Alan D. Rue
Lab Accreditation Unit Supervisor

Laboratory ID
C797

WASHINGTON STATE DEPARTMENT OF ECOLOGY

ENVIRONMENTAL LABORATORY ACCREDITATION PROGRAM

SCOPE OF ACCREDITATION

NVL Laboratories, Inc.

Seattle, WA

is accredited for the analytes listed below using the methods indicated. Full accreditation is granted unless stated otherwise in a note. Accreditation for U.S. Environmental Protection Agency (EPA) "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods" (SW-846) is for the latest version of the method. SM refers to EPA approved editions of "Standard Methods for the Examination of Water and Wastewater." ASTM is the American Society for Testing and Materials. Other references are described in notes.

Matrix/Analyte	Method	Notes
Drinking Water		
Copper	EPA 200.9 Rev 2.2 (1994)	
Lead	EPA 200.9 Rev 2.2 (1994)	
Solid and Chemical Materials		
Arsenic	EPA 6010C_(2/07)	
Barium	EPA 6010C_(2/07)	
Cadmium	EPA 6010C_(2/07)	
Chromium	EPA 6010C_(2/07)	
Copper	EPA 6010C_(2/07)	
Lead	EPA 6010C_(2/07)	
Nickel	EPA 6010C_(2/07)	
Selenium	EPA 6010C_(2/07)	
Silver	EPA 6010C_(2/07)	
Zinc	EPA 6010C_(2/07)	
Mercury	EPA 7471B_(1/98)	
Aroclor-1016 (PCB-1016)	EPA 8082A_(2/07)	1
Aroclor-1221 (PCB-1221)	EPA 8082A_(2/07)	1
Aroclor-1232 (PCB-1232)	EPA 8082A_(2/07)	1
Aroclor-1242 (PCB-1242)	EPA 8082A_(2/07)	1
Aroclor-1248 (PCB-1248)	EPA 8082A_(2/07)	1
Aroclor-1254 (PCB-1254)	EPA 8082A_(2/07)	1

Matrix/Analyte	Method	Notes
Aroclor-1260 (PCB-1260)	EPA 8082A_(2/07)	1

Accredited Parameter Note Detail

(1) Interim accreditation pending the successful completion of an on-site audit to verify method capabilities (WAC 173-50-100).



06/30/2015

Authentication Signature
Alan D. Rue, Lab Accreditation Unit Supervisor

Date

APPENDIX E

Sample Location Drawings for Asbestos, Lead, and Arsenic

GENERAL NOTES

1. DRAWING IS SCHEMATIC AND SAMPLE LOCATIONS ARE APPROXIMATE.
2. REFER TO REPORT FOR MORE INFORMATION ABOUT THE SAMPLED MATERIALS.

SAMPLE LEGEND

10854-63-XX — BULK ASBESTOS SAMPLE LOCATIONS


10854-63-AsXX — BULK ARSENIC SAMPLE LOCATIONS

10854-63-PbXX — BULK LEAD SAMPLE LOCATIONS

JOB NUMBER

SAMPLE NUMBER

10854-63-02-XX — BULK ASBESTOS SAMPLE LOCATIONS TAKEN 9/27/16



MAIN FLOOR PLAN

NOT TO SCALE

PROJECT NORTH

EHS-International, Inc.
1011 SW Klickitat Way, Suite 104
Seattle, Washington 98134
Ph: 206.381.1128
Fax: 206.254.4279

SOUTH KING COUNTY FIRE DEPARTMENT

STATION 63 ASSESSMENT
33414 21st AVE S
FEDERAL WAY, WA

PROJECT MANAGER: D ESCAMILLA

INSPECTORS: N KHAN, A WELLS, R PETERSON

SURVEY DATES: 4/22/16–4/26/16, 9/27/16

EHSI PROJECT #: 10854–63–01B

DRAWN BY: DIMALANTA

SCALE: NTS

ISSUE DATE: 10/10/16

MAIN FLOOR PLAN

SL-1

GENERAL NOTES


1. DRAWING IS SCHEMATIC AND SAMPLE LOCATIONS ARE APPROXIMATE.
2. REFER TO REPORT FOR MORE INFORMATION ABOUT THE SAMPLED MATERIALS.

SAMPLE LEGEND

10854-63-XX	BULK ASBESTOS SAMPLE LOCATIONS
10854-63-AsXX	BULK ARSENIC SAMPLE LOCATIONS
10854-63-PbXX	BULK LEAD SAMPLE LOCATIONS
10854-63-02-XX	BULK ASBESTOS SAMPLE LOCATIONS TAKEN 9/27/16

JOB NUMBER

SAMPLE NUMBER



SECOND FLOOR PLAN

NOT TO SCALE

PROJECT NORTH

EHS-International, Inc.
1011 SW Klickitat Way, Suite 104
Seattle, Washington 98134
Ph: 206.381.1128
Fax: 206.254.4279

SOUTH KING COUNTY FIRE DEPARTMENT

STATION 63 ASSESSMENT
33414 21st AVE S
FEDERAL WAY, WA

PROJECT MANAGER: D ESCAMILLA

INSPECTORS: N KHAN, A WELLS, R PETERSON

SURVEY DATES: 4/22/16–4/26/16, 9/27/16

EHSI PROJECT #: 10854–63–01B

DRAWN BY: DIMALANTA

SCALE: NTS

ISSUE DATE: 10/10/16

SECOND FLOOR PLAN

SL-2

SECTION 004113 BID FORM

TO: **South King Fire and Rescue**

ADDRESS: 33414 21st Avenue SW, Federal Way, WA 98003

I have received Bid Documents titled "**Facility Improvements Station 63**", dated **December 1, 2016**.

I have received Addenda Nos._____ and have included their provisions in my Bid.

I have examined both Documents and the site/job conditions, and submit the following Bid.

In submitting this Bid, I agree:

1. To hold my bid open in accordance with referenced Instruction to Bidders, as modified and supplemented.

2. To enter into and execute referenced Contract, if awarded, on basis of this bid and to furnish bonds and insurance required by Bidding Documents.

3. To accomplish the work in accordance with the Contract Documents.

4. To complete the work by the time stipulated in the Project Manual.

OVERHEAD, PROFIT, AND THE LIKE

All bid prices listed in this form include overhead, profit, bonds, and all other expenses involved.

SALES TAX

All bid prices listed in this Bid Form **DO NOT INCLUDE** applicable local and Washington State Sales Tax.

BID AMOUNT

I WILL CONSTRUCT THIS PROJECT FOR THE FOLLOWING PRICE:

Base Bid Price (Lump sum):

_____ DOLLARS

$_____

PRINCIPAL SUBCONTRACTORS
For any subcontract amount that exceeds 10% of the contractors base bid price, contractor shall list such subcontractor and subcontract amount below (affix addition sheets as necessary):

1) _____$_____

2) _____$_____

3) _____$_____

Provide the name of Subcontractor used for the following:

1) Heating_____

2) Ventilating & Air Conditioning _____

3) Plumbing _____

4) Electrical _____

CONTRACT TIME
The Owner anticipates Notice of Award of this contract on or about 30 days of bid receipt. Owner shall execute contract and issue Notice to Proceed upon satisfactory receipt of Certificate of Insurance, Bonds, and related documents as required by the Instructions to Bidders, the General Conditions of the Contract, and Supplemental Conditions.

If this Bid is accepted, we will Substantially Complete the work within **150** calendar days from Notice to Proceed.

THIS BID PROPOSAL SUBMITTED BY:

NAME OF FIRM_____

SIGNED BY_____TITLE_____

PRINTED NAME_____

ADDRESS_____

CITY/STATE/ZIP_____

TELEPHONE_____

DATE_____

NOTE:
If Bidder is a corporation write State of Incorporation, and if partnership, give full names and address of all partners below.

_____

_____

END OF SECTION

SECTION 005213 AGREEMENT FORM

PART 1 - GENERAL

1.1 FORM OF CONTRACT

The Standard *Form of Agreement Between Owner and Contractor where the basis of payment is a Stipulated Sum*, AIA Document A101-2007, is included BY THIS REFERENCE ONLY; it is not bound in project manual. The Contractor and all subcontractors shall read and be governed by them.

1.2 AVAILABILITY

Copies may be obtained from American Institute of Architects, 1735 New York Avenue NW, Washington, D.C. 20006, or local Chapter offices.

PART 2 - PRODUCTS

NOT USED

PART 3 - EXECUTION

NOT USED

END OF SECTION

SECTION 007213 – GENERAL CONDITIONS OF THE CONTRACT

PART 1 - GENERAL

1.1 STANDARD FORM

The General *Conditions of the Contract for Construction*, AIA Document A201-2007, is included as part of the Contract BY THIS REFERENCE ONLY; it is not bound in project manual. The Contractor and all subcontractors shall read and be governed by them.

1.2 AVAILABILITY

Copies may be obtained from American Institute of Architects, 1735 New York Avenue NW, Washington, D.C. 20006, or local Chapter offices.

1.3 CONFLICTS

In event of conflicts in the Contract Documents, including conflicts between referenced General Conditions and other parts of the Project Manual and Drawings, the Architect reserves the right to determine which governs, and in what order or precedence. See Article 3 of General Conditions and Division 00 Section “Supplemental Conditions”.

PART 2 - PRODUCTS

NOT USED

PART 3 - EXECUTION

NOT USED

END OF SECTION

SECTION 007300 - SUPPLEMENTAL CONDITIONS

The following supplements modify, change, delete from, or add to the referenced "General Conditions of the Contract for Construction." Where any article of the General Conditions is Modified or any Paragraph, Subparagraph, or Clause is modified or deleted by Section 007300, the unaltered provisions of that Article, Paragraph, Subparagraph, or Clause remain in effect.
Modification to the General Conditions:

ARTICLE 1
CONTRACT DOCUMENTS

1.1.1 THE CONTRACT DOCUMENTS

Add the following new subparagraphs 1.1.1.1 and 1.1.1.2:

1.1.1.1 In the event of a conflict or discrepancy among or in the Contract Documents, interpretation shall be governed in the following priority:

1. Agreement (A-101)
2. Supplemental Conditions
3. General Conditions (A-201)
4. Addenda
5. Schedules
6. Drawings
7. Specifications
8. Instructions to Bidders and Accepted Bid

1.1.1.2 In the event of any inconsistencies, conflicts or ambiguities between the Contract Documents, or within an individual document not clarified by addendum, the resolution of such inconsistencies, conflict or ambiguity shall be provided in accordance with the Architect's interpretation. All conflicts are to be referred to the Architect for resolution and incorporation into a Contract Modification, if appropriate.

1.2 CORRELATION AND INTENT OF THE CONTRACT DOCUMENTS

Add the following new subparagraphs 1.2.1.1 and 1.2.1.2:

1.2.1.1 Such execution of the Contract also constitutes a representation by the Contractor that it can fully perform the Contract and deal with all issues arising out of the Contract Documents or conditions of the site of the Work for the Contract Amount. The failure of the Contractor fully to acquaint itself with any applicable condition or matter shall not in any way relieve the Contractor from the responsibility for performing the Work in accordance with the Contract Documents and within the Contract Time and the Contract Sum.

1.2.1.2 Contractor to make the following representation to Owner:

A. Contractor is financially solvent, able to pay its debts as they mature, and possesses sufficient working capital to complete the Work and perform Contractor's obligations required by the Contract Documents; and

B. Contractor is able to furnish the plant, tools, materials, supplies, equipment and labor required to complete the Work and perform the obligations required by the Contract Documents and has sufficient experience and competence to do so.

ARTICLE 2
OWNER

2.2 INFORMATION AND SERVICES REQUIRED OF THE OWNER

Delete subparagraph 2.2.5 and substitute the following:

2.2.5 The Contractor will be furnished free of charge 5 copies of Drawings and Project Manuals. Additional sets will be furnished at the cost of reproduction, postage and handling.

Add the following new subparagraphs 2.5 through 2.5.1:

2.5 OWNER'S RIGHT AND RESPONSIBILITES

2.5.1 The Owner will not have control over or charge of and will not be responsible for construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Work, since these are solely the Contractor's responsibility as provided in Paragraph 3.3. The Owner will not be responsible for the Contractor's failure to carry out the Work in accordance with the Contract Documents. The Owner will not have control over or charge of and will not be responsible for acts or omissions of the Contractor, Subcontractors, or their agents or employees, or of any other persons performing portion of the Work.

ARTICLE 3
CONTRACTOR

3.3 SUPERVISION AND CONSTRUCTION PROCEDURES

Add the following to subparagraph 3.3.1:

3.3.1 If the Contractor has any concerns, objections or reservations concerning such specific instructions, the Contractor must raise and resolve such issues with the Architect and the Owner prior to performing such specific instructions.

3.4 LABOR AND MATERIALS

Add the following to subparagraph 3.4.3:

3.4.3 At no change to the Contract Sum or Contract Time, the Owner may provide written notice requiring the Contractor to remove from the Work any employee, subcontractor employee, or other person carrying out the Contract whom the Owner reasonably considers objectionable.

Add the following subparagraph 3.4.4 through 3.4.4.6:

3.4.4 PREVAILING WAGES

3.4.4.1 The Washington State Department of Labor and Industries Prevailing Wage Rates are part of the Contract.

3.4.4.2 Copies of the Washington State Department of Labor and Industries Prevailing Wage Rates are bound in the Project Manual for reference and convenience only. It is the Contractor's responsibility to follow the most current edition.

3.4.4.3 No worker may be paid less than the prevailing minimum hourly wage rate established by the State Department of Labor and Industries. Statements of Intent to Pay Prevailing Wages and Affidavits of Wages Paid are required. The Contractor shall fully comply with all current applicable labor laws and regulations, including without limitation

RWC Chapters 39.12 (Prevailing Wages); 49.28 (Hours of labor); and 49.70 (Worker Right to Know).

3.4.4.4 Any fabricator or manufacturer that produces nonstandard items and is considered by the Department of Labor and Industries as a contractor must comply with all of the requirements of RCW 39.12, including but not limited to the filing of the "Statement of Intent to Pay Prevailing Wages" and "Affidavit of Wages Paid" with the Department of Labor and Industries Industrial Statistician.

3.4.4.5 The Owner reserves the right to perform wage rate interviews and/or require Contractor submission of certified payrolls for all Contractor and Subcontractor personnel.

3.4.4.6 Contractor shall provide Owner with copies of the Intent to Pay Prevailing Wage forms as filed with the State of Washington for the contractor's forces and for all subcontractors.

3.6 TAXES

Change subparagraph 3.6 to read:

3.6 The Contractor shall pay all applicable State and Local Sales, Consumer, Use and other similar taxes for Work or portions thereof provided by the Contractor. The Owner shall include these taxes in his payments to the Contractor who shall pay the taxes to the proper authorities in accordance with the applicable laws and regulations governing this project. Sales tax will not be included in bid amount.

3.7 PERMITS, FEES, NOTICES, AND COMPLIANCE WITH LAWS

Delete subparagraph 3.7.1 and substitute the following:

3.7.1 The **Owner** shall secure and pay for the **Plan Review Fees**, **Building Permit**, **and (where applicable) L&I Electrical Plan Review Fees.** The Contractor shall secure and pay for all other permits and governmental fees, licenses and inspections necessary for proper execution of and completion of the Contract which are legally required when bids are received.

3.9 SUPERINTENDENT

Add the following to subparagraphs 3.9.3:

During the construction period should the initial superintendent fall ill, retire, be laid off or terminated employment, the Owner reserves the right to review and accept the replacement as stated above.

Add the following subparagraph 3.9.4:

3.9.4 The Superintendent shall remain on the Project whenever Subcontractors are present unless the job is closed down due to a legal holiday, a general strike, conditions beyond the control of the Contractor, termination of the Contract in accordance with the Contract Documents, or Final Completion is attained.

3.10 CONTRACTOR'S CONSTRUCTION SCHEDULE

Change this entire paragraph 3.10 to read:

3.10.1 Within (**5)** calendar days following Notice to Proceed, the Contractor shall submit to the Owner and the Architect for review and comment, three copies of a CPM Schedule in form satisfactory to the Owner for Contractor's construction/erection of the Work. The initial and any

revisions of the Project Schedule shall be prepared and submitted in paper form. With each approved monthly payment request, provide an updated Progress Schedule. Not less than 5% (in retention) of Progress Payments to the Contractor may be withheld by the Owner until such initial and updated Progress Schedules have been timely submitted for review by the Owner and the Architect.

3.10.2 The Project Schedule shall consist of a network diagram with activity descriptions and durations and supporting data which will explain the Contractor's planning of the work. Contractor shall provide, if requested by Owner, cost allocation and resource estimates for each activity.

3.10.2.1 The CPM Schedule diagram shall include:

(a) The order and interdependence of the Contractor's activities and the major points of the interface or interrelation with the activities of others, including Specific Dates for completion.
(b) Conformance with and identification of the Specific Dates specified in the Contract Documents.
(c) The descriptions of work by activity.
(d) The time required for preparation, and review of shop drawings, mock-ups, manufacturing, and delivery of Contractor-furnished permanent plant materials, especially long lead items.
(e) Critical Path (or Paths).
(f) Testing of equipment and materials. The CPM Schedule shall provide a complete and detailed sequence of operations of the Work within the time limits specified in the Contract.

3.10.2.2 The identity and duration of all activities to be included in this CPM Schedule shall meet the following criteria:

(a) Activity descriptions shall be clear and concise. The beginning and end of each activity shall be readily verifiable.
(b) Responsibility for each activity shall be identified with a single performing organization.
(c) The identity of any potential problems or constraints related to the implementation of the overall construction plan.

3.10.2.3 A schedule for the purchase of items required for performance of the Work, showing lead items between purchase order placement and delivery dates, shall be integrated with the Progress Schedule upon request of the Owner. The Contractor shall furnish the Architect with copies of all purchase orders and acknowledgements and fabrication, production, and shipping schedules for all major items on the critical path within 10 days of Contractor's receipt of each purchase order, acknowledgment or schedule. Neither the Architect nor the Owner shall be deemed to have approved or accepted any such material, or its schedule, nor deemed to have waived this requirement if some or all of the material is not received.

3.10.3 The CPM Schedule shall indicate an early completion date for the project that is not later than the project's required completion date. All activity durations shall be given in calendar days. The CPM Schedule shall also indicate each of the following:

(a) Interfaces with the work of outside contractors, e.g., utilities, power, and with any separate contractor.
(b) Descriptions of activity including activity numbers.
(c) Estimated duration time for each activity.
(d) Early start date for each activity.
(e) Late start date for each activity.
(f) Early finish date for each activity.
(g) Late finish date for each activity.

(h) Float available for each batch of activities containing float.
(i) Actual start date for each activity begun.
(j) Actual finish date for each activity completed.
(k) Identification of all Critical Path activities in the mathematical analysis.
(l) The Critical Path for the project, with said path of activities being clearly and easily recognizable on the time-scaled CPM Schedule Diagram. The relationship between all non-critical activities and activities on the Critical Path shall be clearly shown on the CPM Schedule Diagram.

3.10.4 It is to be expressly understood and agreed by the Contractor that the schedule is an estimate to be revised from time-to-time as progress proceeds, and that the Owner does not guarantee that Contractor can start work activities on the "early start" or "late start" dates or complete work activities on the "early finish' or "late finish" date shown in the Schedule, or as same may be upgraded or revised; nor does the Owner guarantee that Contractor can proceed at all times in the sequence established by said Schedule. If Contractor's schedule indicates that Owner or separate contractor is to perform an activity by a specific date, or within a certain duration, Owner or any separate contractor under contract with the Owner shall not be bound to said date or duration unless Owner expressly and specifically agrees in writing to same; the Owner's or the Architect's overall review and approval or acceptance of the Schedule does not constitute an agreement to specific dates, durations or sequences for activities of the Owner of any separate contractor.

3.10.5 Should any of the conditions exist such that certain activities shown on the Contractor's CPM Schedule fall behind schedule to the extent that any of the specific dates are in jeopardy, the Contractor shall be required to, at no extra cost to the Owner, prepare and submit to the Owner a supplemental Recovery Schedule, in a form and detail appropriate to the need, to explain and display how he intends to reschedule those activities to regain compliance with the CPM Schedule during the immediately subsequent pay period.

3.10.6 The Contractor shall do the following after determination of the requirement for a Recovery Schedule:

(a) Within three (3) calendar days, the Contractor shall submit a Recovery Schedule to the Owner for review. The Recovery Schedule shall be prepared to a similar level of detail as the CPM Schedule and shall have a maximum duration of one (1) month.
(b) Any revisions necessary as a result of this review shall be resubmitted by the Contractor with any necessary revisions for acceptance within two (2) calendar days of the review. The approved Recovery Schedule shall then be the Schedule which the Contractor shall use in planning, organizing, directing, coordinating, performing and executing the Work (including all activities of subcontractors, equipment vendors, and suppliers) for its one (1) month duration, to regain compliance with the CPM Schedule.

3.10.7 Should the Contractor, after approval of the initial CPM Schedule desire to change his plan of construction, he shall submit his requested revisions to the Owner including a description of the logic for rescheduling the work, methods of maintaining adherence to Intermediate Milestones and Specific Dates. The Contractor shall revise his Schedule to include the effect of changes, acts of God or other conditions or events which have affected the CPM Schedule, If the requested changes are acceptable to the Owner, they will be incorporated by the Contractor into the CPM Schedule in the next reporting period. The resultant cost to the Owner for significant changes or a significant number of changes to the CPM Schedule shall be paid for by the Contractor.

3.10.8 When the Owner orders changes by Change Order which have the potential to impact the Contract Milestones or Specific Dates stipulated, a Network will be prepared by the

Contractor and provided to the Project Manager. After the Network has been accepted by the Owner, it will be incorporated into the CPM Schedule by the Contractor.

3.10.9 Failure of the Contractor to substantially comply with any of the scheduling requirements of this Contract at no cost to the Owner shall constitute cause that the Contractor is failing to prosecute the Work with such diligence as will insure its completion within the Contract times and shall be considered cause for termination by the Owner, pursuant to Article 14 of the General Conditions; and may also result in the Owner's withholding of Progress Payment(s) until the Contractor complies.

3.10.10 Float time is defined as the amount of time between earliest start date and the latest start date or between the earliest finish date or the latest finish date of a chain of activities on the CPM Schedule. Float time is not for the exclusive use or benefit of either the Contractor of the Owner. Contractor's work shall proceed according to start dates, and the Owner shall have the right to reserve and apportion float time according to the needs of the project. The Contractor acknowledges and agrees that actual delays, affecting paths of activities containing float time, will not have any effect upon Contract Completion times, providing that the actual delay does not exceed the float time associated with those activities. Extensions of time for performance as described in the Contract Documents will be granted only to the extent that time adjustments for the activity or activities affected by any condition or event which entitles the Contractor to a time extension exceeds the total float or slack time along the actual critical path of activities affected at the time of Notice to Proceed of a Change Order or the commencement of any delay, claim or condition for which an adjustment is claimed or warranted under the Contract Documents.

3.10.11 The Schedule Duration shall be based on the Contract Time of Completion listed on the Bid Form. The Owner shall not be obligated to accept any Early Completion Schedule suggested by the Contractor. The Contract Time for Completion shall establish the Schedule Completion Date. If the Contractor feels that the work can be completed in less than the Specified Contract Time, then the Surplus Time shall be considered Project Float. This Float time shall be shown on the Project Schedule. It shall be available to accommodate changes in the work and unforeseen conditions. Neither the Contractor nor the Owner have exclusive right to this Float Time. It belongs to the project.

3.11 DOCUMENTS AND SAMPLES AT THE SITE

Add the following new subparagraphs 3.11.1 and 3.11.2:

3.11.1 In addition, the Contractor shall keep the approved permit set of plans at the jobsite during construction, in good condition. Prior to final acceptance, the Contractor shall deliver this permit set to the Architect.

3.11.2 Satisfactory maintenance of up-to-date record drawings will be a requirement for approval of monthly Progress Payments.

ARTICLE 5
SUBCONTRACTORS

5.3 SUBCONTRACTUAL RELATIONS

Add the following new subparagraph:

5.3.1 The Contractor shall schedule, supervise and coordinate the operations of all Subcontractors. No subcontracting of any of the Work shall relieve the Contractor from its responsibility for the performance of the Work in accordance with the Contract Documents or from its responsibility for the performance of any other of its obligations under the Contract Documents.

ARTICLE 6
CONSTRUCTION BY OWNER OR BY SEPARATE CONTRACTORS

6.2 MUTUAL RESPONSIBILITY

Add the following to paragraph:

6.2.1 If the Contractor receives items from a separate contractor or from the Owner for storage, erection or installation, the Contractor shall acknowledge receipt for items delivered, and thereafter will be held responsible for care, storage and any necessary replacement of item or items received.

At subparagraph 6.2.4, delete the word "wrongfully."

ARTICLE 7
CHANGES IN THE WORK

7.2 CHANGE ORDERS

Add the following paragraphs 7.2.2 through 7.2.5:

7.2.2 Change proposal disagreements shall be submitted by the Contractor to the Architect in a form satisfactory to the Owner for such submittals. The total cost of any change, including a claim shall be limited to the reasonable value thereof, to be determined in the following manner:

7.2.3 ADDITIVE CHANGES:

1a. Direct Labor Costs: This is defined as the estimated labor costs determined by either the estimated number of craft hours and the hourly costs necessary to perform the change in work; or the unit labor costs necessary to perform the change in work; or the unit labor costs applied to the material quantities, provided said unit labor costs are developed from the above craft man hour cost; whichever is applicable, according to industry practice. The hourly cost shall be based on the following:

1. Basic Wages: Current minimum prevailing hourly wage rates, including vacation pay, for all labor, crew foreman, and general foreman performing and/or directly supervising the work on site. These rates, whichever are applicable, are established by the State of Washington, Department of Labor and Industries.
2. Fringe Benefits: Fringe benefits established by the State of Washington, Department of Labor and Industries or contributed to labor trust funds as itemized fringe benefits, whichever is applicable.
3. Worker's Insurance: Direct contributions to the State of Washington as Industrial Insurance; Medical Aid; and Supplemental Pension, by the class and rates established by the State of Washington, Department of Labor and Industries.
4. Federal Insurance's: Direct contributions required by the Federal Insurance Compensation Act (FICA); Federal Unemployment Tax Act (FUTA); and the State Unemployment Compensation Act (SUCA).
5. Costs incurred by the Washington Industrial Safety and Health Act (WISHA); established as 2% of 1, 2, 3, and 4 above.
6. Travel allowances and/or subsistence if applicable not to exceed those established by Regional Labor Union Agreements shall be itemized and identified separately.

1b. Direct Material Costs: This is defined as an itemization of the estimated quantity of materials necessary to perform the change in the work and the cost thereof. These costs shall be by the unit cost applied to the quantity and extended. The unit costs shall be based on the following:
   1. The net costs after all offered or available discounts or rebates.
   2. Freight costs; express charges; or special delivery costs when applicable.

   No lump sum costs will be allowed except when approved in advance by the Architect

1c. Construction Equipment Usage Costs:
   1. Rental Equipment: This is defined as an itemization of and the estimated length of time construction equipment will be used on change order work at the site. The rental costs applied thereof will be the rates established by the following whichever is applicable:
      a) The current hourly rental rates established by agreement between the Associated General Contractors (AGC) and Washington State Department of Highways.
      b) The current rental rates established by the State of Washington, utilities and Transportation Commission for trucks used on highways.
      c) The current rental rates established by the National Electrical Contractor's Association (NECA) for equipment used on electrical work.
      d) The current rental rates established by the mechanical Contractor's Association for equipment used on mechanical work.
      e) If equipment is required for which a rental rate is not established in any of the above, an agreed rental rate shall be established for that equipment. Such rates and the use of the equipment on the work must be approved by the Architect prior to performing the work.
      f) The rates in effect at the time of performance of the work are the maximum rates allowable for equipment of modern design and in good working condition and include full compensation for furnishing all fuel, oil, lubrication, repairs, maintenance, and insurance.
   2. Small Tools, Expendable and Consumable Supplies:
      a) These are general in nature and are defined as tools for which the initial purchase price is under $250 and are normally furnished by the performing contractor.
      b) The allowable rate for small tools will be:
         - General Contractors, 3% direct labor costs
         - Specialty Contractors, 5% direct labor costs
      c) Expendable and consumable supplies directly associated with the change in work to be itemized.

1d. Subcontractor Proposals: Subcontractors' proposals are to be itemized as in 1a, 1b, and 1c above.

1e. Overhead and Profit by the Contractor Actually Performing the Work: A total amount, not to exceed 10% of items 1a, 1b, and 1c above will be allowed. This is to compensate such contractor for all personnel not defined in 1a above; temporary construction facilities; home office costs; office architecting and estimating costs; profit, and any other cost incidental to the performance of the change in work.

1f. Overhead and Profit by the Contractor and Subcontractor when Subcontractor actually performs the Work:
   1. A total amount not to exceed 8% of the total amount of subcontractors proposal as defined in 1d above will be allowed to the Contractor for all overhead and profit to

supervise and administer the subcontractors actually performing the change in the work. The Subcontractor doing the work will be allowed no more than 10%. Lower tier sub-subcontractors will be allowed no more than 7%.

2. No direct costs of the Contractor will be allowed to be added to a subcontractor's proposal. Contractor's direct cost, if required, must be submitted as outlined in 1a, 1b, 1c and 1g.

1g. Cost of Any Increase or Decrease in Premium for Insurance and Bond Caused by the Change:

1. Contractor's Liability Insurance: To the above, the costs of the Contractor's Liability Insurance may be increased or decreased.
2. Bond: To the above, the cost of the Contractor's Bond may be increased or decreased.

7.2.4 DEDUCTIVE CHANGES

2a. Items 1a (labor), 1b (material), 1c (equipment), 1d (subcontractor), 1e (overhead and profit, Contractor), 1f (overhead and profit, subcontractor), 1g (insurance and bond) will be itemized for deleted changes in the work.

7.2.5 ADDITIVE CHANGES AND DEDUCTIVE CHANGES TOGETHER

3a. If a change in the work involves both additive and deductive changes, the appropriate overhead and profit amount allowed will be added to the net difference of items 1a, 1b, 1c, and 1d.

3b. If other additive unrelated changed items are included in the same change proposal, the appropriate overhead and profit allowed is to be applied to these individual change items.

ARTICLE 8
TIME

8.2 PROGRESS AND COMPLETION

Add the following new subparagraphs 8.2.4 and 8.2.5:

8.2.4 The Contractor shall furnish such manpower, materials, facilities, and equipment and shall work such hours, including night shifts, overtime operations and Sundays and holidays, as may be necessary to insure the progress and completion of the Work in accordance with the approved and currently updated Progress Schedule. If work actually in place falls behind the currently updated and approved Progress Schedule and it becomes apparent from the current schedule that the Work will not be completed within the Contract Time, the Contractor agrees that he will, as necessary, take some or all of the following actions at no additional cost to the Owner, as required to substantially eliminate tardiness of Work:

1. Increase the manpower in such quantities and crafts as will substantially eliminate, in the opinion of the Owner, the backlog of Work.
2. Increase the number of working hours per shift, shifts per working day, working days per week, or the amount of equipment, or any combination of the foregoing sufficiently to substantially eliminate, in the opinion of the Owner, the backlog of Work; and
3. Reschedule activities to achieve maximum practical concurrency of accomplishment of activities.

8.2.5 The Contractor and Owner acknowledge and contemplate that delay in substantial completion and final completion will cause the Owner substantial damages which are difficult to determine precisely. To the extent the Owner is unable to beneficially occupy each of the facilities which are the subject of this Contract, the Owner is expected to experience damages and costs including but not limited to the following: Loss of use of the facility; the costs of

delayed move-in and the disruption of Owner activities and schedule; and rescheduling and shift changes to paid personnel. The parties therefore agree that the following sums of liquidated damages shall be paid to the Owner (or the Owner may withhold payments otherwise due to the Contractor) in liquidation of these difficult to measure damages and/or delay costs reasonably anticipated as a result of delays beyond the dates as established in the Contract, as they may be extended by agreement of the parties by change order during the course of the project:

SUBSTANTIAL COMPLETION: For each calendar day after the date fixed for Substantial Completion and until Substantial Completion of the facilities, the Contractor shall pay the Owner the sum of **One hundred dollars ($100)**. The Owner shall not be required to accept Substantial Completion of anything less than the entirety of the project but shall have the option to do so. This sum is to be fixed, agreed, liquidated damages and not to be construed as in any sense a penalty.
FINAL COMPLETION: Actual damages will be assessed for failure to achieve Final Completion within **(30)** days after Substantial Completion. Actual damages will be calculated on the basis of direct architectural, administrative, and other related costs attributed to the Project from the date when Final Completion should have been achieved, to the date Final Completion is actually achieved. Owner may offset these costs against any payment due to the Contractor by reduction in retainage.

8.3 DELAYS AND EXTENSIONS OF TIME

Change subparagraph 8.3.3 to read:
8.3.3 Except as provided in this subparagraph, the Contractor's sole remedy for delays shall be an extension of time. Except for unreasonable delays in performance caused by the acts or omissions of the Owner, the Contractor shall not be entitled to damages, extra compensation or equitable adjustment for direct, indirect or impact damages for delay, including but not limited to cost of acceleration, home office overhead or lost profits. All claims for damages or extensions of time are subject to the requirements of Article 15. In the event the Contractor is entitled to damages from the Owner for delay, it is agreed that the Contractor's sole damages for each day of delay shall be limited to the daily liquidated damage rate provided for the Owner in subparagraph 8.2.5 above.

ARTICLE 9
PAYMENT AND COMPLETION

9.3 APPLICATIONS FOR PAYMENT
Add the following new subparagraph:
9.3.1.3 Until Substantial Completion, the Owner shall pay 95 percent of the amount due the Contractor on account of progress payments.
Add the following new subparagraph:
9.3.4 If authorized by the Owner, the Application for Payment may include request for payment for material delivered to the Project site and suitably stored, or for completed preparatory work. Payment may similarly be requested, subject to Owner's approval, for material stored off the Project site, provided the Contractor complies with or furnishes satisfactory evidence of the following:

1. The material will be placed in a warehouse that is structurally sound, dry, lighted and suitable for the materials to be stored;

2. The warehouse is located within a 25-mile radius of the project. Other locations may be utilized, if approved in writing, by Owner;
3. Only materials for the Project are stored within the warehouse (or a secure portion of a warehouse set aside for the Project);
4. Contractor furnishes Owner a certificate of insurance extending Contractor's insurance coverage for damage, fire, and theft to cover the full value of all materials stored, or in transit;
5. The warehouse (or secure portion thereof) is continuously under lock and key, and only Contractor's authorized personnel shall have access;
6. Owner shall at all times have the right of access in company of the Contractor;
7. Contractor and its surety assume total responsibility for the stored materials; and
8. Contractor furnishes to Owner certified lists of materials stored, bills of lading, invoices, and other information as may be required, and shall also furnish notice to owner when materials are moved from storage to the Project site.

9.5 DECISIONS TO WITHHOLD CERTIFICATION

Add the following to subparagraph 9.5.1:

The Architect may also decide not to certify payment or, because of subsequently discovered evidence or subsequent observations, may nullify the whole or part of a Certificate for Payment previously issued, or the Owner may refuse to process an application for payment to such extent as may be necessary in the Owner's or Architect's opinion to protect the Owner from loss because of:

Add the following new subparagraphs 9.5.1.8 through 9.5.1.12:

9.5.1.8 Unsatisfactory prosecution of the Work by the Contractor, including but not limited to failure to carry out the Work in accordance with the Contract Documents.

9.5.1.9 Failure or refusal of the Contractor to fully comply with requirements in the Contract Documents for preparation and submission of scheduling of the Work and updates thereof, or failure to present statements of Intents or Affidavits pertaining to prevailing wages paid as may be required by statue.

9.5.1.10 Liquidated damages.

9.5.1.11 Failure to provide adequate security measures to protect materials stored on site for which the Contractor is seeking payment for.

9.5.1.12 Failure to provide evidence that the performance and payment bonds have been increased to equal the sum of Change Orders.

9.6 PROGRESS PAYMENTS

Add the following new subparagraphs 9.6.8 through 9.6.13:

9.6.8 Upon Commencement of the Work and at the option of the Contractor, an escrow account may be established by the Contractor in a financial institution chosen by the Contractor and approved by the Owner.

9.6.9 The escrow agreement shall provide that the financial institution will act as escrow agent, will pay interest on funds deposited in such account in accordance with the provisions of the escrow agreement and will disburse funds from the account upon the direction of the Owner as set forth below. Compensation to the escrow agent for establishing and maintaining the escrow account shall be paid from interest accrued in the escrow account.

9.6.10 As each progress payment is made, the retainage with respect to that payment shall be deposited by the Owner in the escrow account.

9.6.11 The interest earned on funds in the account shall accrue for the benefit of the Contractor until the substantial completion date named in the Construction Contract or the expiration of any

authorized extension of such date. Interest earned after such date shall accrue for the benefit of the Owner. Cost of compensation to the escrow agent paid out of interest earned shall be borne by the Contractor.

9.6.12 When the Contractor has fulfilled all of the requirements of the Contract providing for reduction of retained funds, the escrow agent shall release to the Contractor one-half of the accrued funds but none of the interest thereon. When the Work has been fully completed in a satisfactory manner and the Architect has issued a final Certificate for Payment, the escrow agent shall pay to the Contractor the full amount of funds remaining in the account, including net balance of the interest paid to the account, but less any interest that may have accrued for the benefit of the Owner, which shall be paid to the Owner.

9.6.13 If, after Substantial Completion of the Work, final completion thereof is materially delayed through no fault of the Contractor, the escrow agent shall make payment to the Contractor as provided in Subparagraph 9.10.3

9.8 SUBSTANTIAL COMPLETION

Change subparagraph 9.8.1 to read:

9.8.1 Substantial Completion is the stage in the progress of the Work (or portion thereof designated and approved by the Architect and Owner) when the construction is sufficiently complete, in accordance with the Contract Documents, so the Owner can fully occupy under necessary permits the Work (or portion thereof designated by the Owner) for the use for which it is intended. All Work other than incidental corrective or punch list work and final cleaning shall have been completed.

Add the following new subparagraph:

9.8.6 The acceptance of Substantial Completion payment shall constitute a waiver of all claims by the Contractor except those previously made in writing and identified by the Contractor as unsettled at the time of the application for payment for the Substantial Completion payment, and except for the Contract Sums due at Final Acceptance.

9.10 FINAL COMPLETION AND FINAL PAYMENT

Add the following to this subparagraph 9.10.1:

The Architect's final Certificate of Payment shall establish the date of Final Completion. If the Contractor notifies the Architect that the punch list items are completed and requests an inspection to determine compliance, and the Architect determines that some or all the punch list items are not completed, the Contractor shall be responsible to the Owner for all costs, including Architect's fees, for any future Architect's inspections after the first inspection to determine subsequent compliance with the punch list.

ARTICLE 10
PROTECTION OF PERSONS AND PROPERTY

Add the following new subparagraph10.2.8:

10.2.8 At all times until final acceptance of the Work, the Contractor shall protect from damage, weather, deterioration, theft, vandalism, and, malicious mischief all materials, equipment, tools, and other items incorporated or to be incorporated in the Work, or consumed or used in the performance of the Work, and all Work in process and completed Work.

ARTICLE 11
INSURANCE

11.1 CONTRACTOR'S LIABILITY INSURANCE

Add the following new subparagraphs 11.1.1.9 and 11.1.1.10:

11.1.1.9 Liability Insurance shall include all major divisions of coverage and be on a comprehensive basis including:

1. Premises operations (including X, C and U coverage's as applicable).
2. Independent Contractors' Protective.
3. Products and Completed Operations.
4. Personal Injury Liability with Employment Exclusion deleted.
5. Contractual, including specified provision for Contractor's obligation under Paragraph 3.18.
6. Owned, non-owned and hired motor vehicles.
7. Broad Form Property Damage including Completed Operations.

11.1.1.10 If the General Liability coverage's are provided by a Commercial General Liability Policy on a claims-made basis, the policy date or Retroactive Date shall predate the Contract; the termination date of the policy or applicable extended reporting period shall be no earlier than the termination date of coverage's required to be maintained after final payment, certified in accordance with Subparagraph 9.10.2.

Add the following subparagraph 11.1.2.1:

11.1.2.1 The insurance required by Subparagraph 11.1.1 shall be written for not less than the following limits, or greater if required by law:

1. Worker's Compensation:

   (a) State: Statutory

   (b) Applicable Federal: Statutory

   (c) Employer's Liability $100,000 per Accident

Comprehensive or Commercial General Liability (including Premises-operations; Independent Contractors' Protective; Products and Completed Operations; Broad Form Property Damage):

   (a) Bodily Injury:
   $1,000,000 Each Occurrence
   $2,000,000 Aggregate
   (b) Property Damage:
   $1,000,000 Each Occurrence
   $2,000,000 Aggregate
   (c) Products and Completed Operations to be maintained for a minimum period of 2 years after final payment.
   (d) Property Damage Liability insurance shall provide Explosion, Collapse, and Underground coverage.
   (e) Broad Form Property Damage Coverage shall include Completed Operations.

3. Contractual Liability:
   (a) Bodily Injury:
   $1,000,000 Each Occurrence
   $2,000,000 Aggregate
   (b) Property Damage:
   $1,000,000 Each Occurrence
   $2,000,000 Aggregate

4. Personal Injury, with Employment Exclusion deleted:
$2,000,000 Aggregate
5. Business Auto Liability (including owned, non-owned and hired vehicles):
(a) Bodily Injury:
$1,000,000 Each Person
$1,000,000 Each Occurrence
(b) Property Damage:
$1,000,000 Each Occurrence

Add the following subparagraphs 11.1.3.1 through 1.1.3.3:

11.1.3.1 The certificate of insurance shall name the Owner as "Additional Insured." Certificate is required at time contract is signed.

11.1.3.2 The Contractor shall provide an original of the executed insurance policy Endorsement to the Owner prior to commencement of the work.

11.1.3.3 Upon request of the Owner, the Contractor shall provide complete, certified copies of all required insurance policies.

11.4 PERFORMANCE AND PAYMENT BONDS

Delete Subparagraph 11.4.1 and substitute the following:

11.4.1 The Contractor shall provide bonds covering faithful performance of the Contract and payment of obligations arising thereunder. Bonds may be obtained through the Contractor's usual source and the cost thereof shall be included in the Contract Sum. The amount of each bond shall be equal 100 percent of the Contract Sum including all change orders and sales tax.

Add the following new subparagraphs:

11.4.1.1 The Contractor shall deliver the required bonds to the Owner no later than ten days following the Notice of Award and shall also be submitted with the signed and executed contract.

11.4.1.2 Bonds shall be obtained from companies holding certificates of authority as acceptable sureties pursuant to 31 CFR part 223.

11.4.1.3 Provide bonds executed by surety company or companies authorized to transact business in State in which the project is being constructed. Required form: Performance Bond and Payment Bond AIA-A312, March 1984. Bonding company as approved by Owner.

11.4.1.4 Provide originals of the executed bonds to the Owner, complete with original ink signatures and original stamps/embossing.

11.4.1.5 Provide proof of bond rider adjustments in the bond sum for Change Orders in conjunction with requests for progress payments.

Add the following paragraph 11.5:

11.5 HOLD HARMLESS STATEMENT

11.5.1 The Contractor agrees to defend, indemnify and save harmless the Owner, Architect, and their agents, and employees against any and all loss, damage, liability, claims, demands or costs resulting from injury or harm to persons or property (including, with limitation, the Contractor's employees or property) arising out of or in any way connected with Contractor's performance hereof, excepting only such injury or harm as may have been caused solely by the fault or negligence of the Owner, Architect, and their agents, and employees, and shall be deemed to include those of subcontractors.

ARTICLE 13
MISCELLANEOUS PROVISIONS

13.5 TESTS AND INSPECTIONS
Add the following new subparagraph:
13.5.7 No acceptance by the Owner of any Work shall be construed to result from any inspection, tests or failures to inspect by the Owner, the Owner's representative, the Architect or any other person. No inspection, test, failure to inspect or test, or failure to discover any defect or non conformity by the Owner, the Owner's representative, the Architect or any other person shall relieve the Contractor of its responsibility for meeting the requirements of the Contract Documents or impair the Owner's right to reject defective or nonconforming items or right to avail itself of any other remedy to which the Owner may be entitled, notwithstanding the Owner's knowledge of the defect or nonconformity, its substantially or the ease of discovery.

Add the following new paragraphs 13.8 through 13.8.1.2:
13.8 EQUAL OPPORTUNITY

13.8.1 The Contractor shall maintain policies of employment as follows:

13.8.1.1 The Contractor and the Contractor's Subcontractors shall not discriminate against any employee or applicant for employment because of race, religion, color, sex, marital status, physical and mental disabilities, or national origin. The Contractor shall take affirmative action to insure that applicants are employed, and that employees are treated during employment without regard to their race, religion, color, sex or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices setting forth policies of nondiscrimination.

13.8.1.2 The Contractor and the Contractor's Subcontractors shall, in all solicitations or advertisements for employees placed by them or on their behalf, state that all qualified applicants will receive consideration for employment without regard to race, religion, color, sex, marital status, physical and mental disabilities, or national origin.

ARTICLE 14
TERMINATION OR SUSPENSION OF THE CONTRACT

14.2 TERMINATION BY THE OWNER FOR CAUSE
Change subparagraph 14.2.1 to read:
14.2.1 The Owner may, upon seven days' written notice to the Contractor, terminate (without prejudice to any right or remedy of the Owner) the whole or any portion of the Work for cause, including the following circumstances:
1. the Contractor fails to prosecute the Work or any portion thereof with sufficient diligence to ensure the Substantial Completion of the Work within the Contract Time;
2. the Contractor is in material default of any provision of the Contract;

3. the Contractor is adjudged bankrupt, makes a general assignment for the benefit of its creditors, or if a receiver is appointed on account of its insolvency;
4. the Contractor fails to supply a sufficient number of properly skilled workers or proper materials;
5. the Contractor fails to make prompt payment due to Subcontractors or for materials or labor;
6. the Contractor disregards laws, ordinances, rules, regulations or orders of any public authority having jurisdiction; or
7. the Contractor materially breaches any provision of the Contract Documents.

Add the following new subparagraph:

14.2.5 If the Owner terminates in whole or part the Work pursuant to paragraph 14.2, the Owner may procure, upon such terms and in such manner as it deems appropriate, supplies or services similar to those terminated, and the Contractor shall be liable to the Owner for any excess costs for such similar supplies or services. The Contractor shall continue to perform of this Contract to the extent not terminated hereunder.

ARTICLE 15
ADMINISTRATION OF THE CONTRACT

15.1 CLAIMS AND DISPUTES

Add the following new subparagraphs 15.1.7 and 15.1.8:

15.1.7 All Claims filed against Owner shall be subject to audit at any time following the filing of the Claim. Failure of Contractor, or Subcontractor of any tier, to maintain and retain sufficient records to allow Owner to verify all or a portion of the Claim or to permit Owner access to the books and records of Contractor, or Subcontractors of any tier, shall constitute a waiver of the Claim and shall bar recovery. The audit may be performed by employees of Owner or a representative of Owner. Contractor, and its Subcontractors, shall provide adequate facilities acceptable to Owner, for the audit during normal business hours. Contractor, and all Subcontractors, shall make a good faith effort to cooperate with Owner's auditors.

15.1.8 The Contract Documents and the rights of the parties herein shall be governed by the laws of the State of Washington. Venue for all dispute resolution proceedings (including, but not limited to, mediation, arbitration, and litigation) shall be in the county in which the Owner's principal place of business is located, unless otherwise specified.

END OF SECTION

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Work covered by Contract Documents.
2. Work by Owner.
3. Work under separate contracts.
4. Owner-furnished products.
5. Access to site.
6. Work restrictions.
7. Specification and drawing conventions.

B. Related Requirements:

1. Division 01 Section "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of Project is defined by the Contract Documents and consists of the following:

1. Interior remodeling and structural, plumbing, mechanical, and electrical improvements as shown.

B. Type of Contract:

1. Project will be constructed under a single prime contract.

1.4 WORK BY OWNER

A. General: Cooperate fully with Owner so work may be carried out smoothly, without interfering with or delaying work under this Contract or work by Owner. Coordinate the Work of this Contract with work performed by Owner.

B. Preceding Work: Owner will perform the following construction operations at Project site. Those operations are scheduled to be substantially complete before work under this Contract begins.

1. Move portions of existing occupants and equipment out of the building prior to the start of construction to provide the contractor with a reasonably unhindered access to the construction work areas.

All efforts are to be coordinated with the Contractor for mutually agreeable times and access.

C. Concurrent Work: Owner may perform construction operations at Project site. Those operations will be conducted simultaneously with work under this Contract, the owner or the owner's separate contractor shall coordinate mutually agreeable time and access with the Contractor.

D. Work Provided by Owner under Separate contract: the following work will be performed by Owner using Owner-provided contractors or forces, concurrently with the Work of this Contract:

1. Security and surveillance system installation: Owner will contract with Presidio for design-build work related to door security and site surveillance.

2. Installation of chain link fence, gates, hardware, and operators.

3. Fuel tank and pump replacement.

4. Point-source vehicle exhaust system maintenance.

1.5 OWNER-FURNISHED PRODUCTS

A. Owner will furnish products indicated. The Work includes receiving, unloading, handling, storing, protecting, and installing Owner-furnished products.

B. Owner-Furnished Products:

1. Bunker Gear Extractor and Dryer.

2. Bunker Gear Racks.

1.6 ACCESS TO SITE

A. General: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.

B. Use of Site: Limit use of Project site to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1.7 WORK RESTRICTIONS

A. Work Restrictions, General: Comply with restrictions on construction operations.

1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.

B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 5:00 p.m., Monday through Friday, unless otherwise indicated.

1. Hours for Utility Shutdowns: Coordinate with owner for a mutually agreeable time.

C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:

1. Notify Owner not less than two days in advance of proposed utility interruptions.
2. Obtain Owner's written permission before proceeding with utility interruptions.

D. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.

1. Notify Owner not less than two days in advance of proposed disruptive operations.
2. Obtain Owner's written permission before proceeding with disruptive operations.

E. Nonsmoking Building: Smoking is not permitted on-site

1.8 SPECIFICATION AND DRAWING CONVENTIONS

A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:

1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
2. Abbreviations: Materials and products are identified by abbreviations published as part of the schedules on Drawings.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SECTION 011110 - SUMMARY OF HAZARDOUS MATERIALS WORK

PART 1 - GENERAL

1.1 DEFINITIONS

A Hazardous Materials Consultant:

1. EHS – International, Inc. (EHSI)
   1011 SW Klickitat Way, Suite 104
   Seattle, WA 98134
   Phone: (206) 381-1128
   Fax: (206) 254-4279
   Contact: Derica Escamilla
   Email: dericae@ehsintl.com

1.2 WORK COVERED BY CONTRACT DOCUMENTS-HAZARDOUS MATERIALS

A The Work shall include the providing of all supplies, tools, equipment, transportation, utilities, services, superintendence, labor, and the furnishing of all materials, items and accessories needed for the impact of Asbestos-Containing Materials (ACM), Lead Containing Paint (LCP), Lead Containing Material (LCM), Arsenic-Containing Material, and Mercury-Containing Light Tubes and Thermostats, in strict conformance with the Contract Documents and all applicable regulations.

B Drawings and general provisions of the Contract, including Divisions 0 and 1 Specification Sections, apply to work of this section.

1.3 ASBESTOS-CONTAINING MATERIALS (ACMs)

A Presence of Asbestos: Fire Station #63 has been surveyed with the objective of identifying the presence of ACMs. ACMs present are included in the Abatement Sub-contractor's work under contract to the Contractor as indicated in the Limited Hazardous Materials Survey Report Summary (attached to this Section), the Hazardous Materials Removal Design Drawings, and as specified in Section 028200. Note: Not all ACM present will be removed within the scope of work, refer to the Hazardous Materials Removal Drawings.

B A certified asbestos sub-contractor, working directly for the Contractor, will remove all ACMs expected to be impacted by the Work prior to commencement of that portion of the Work. If identified ACMs or suspect materials not identified by the survey report as having been sampled will be impacted by the Work during the project, stop prior to impacting the identified/suspect materials and contact the Owner and the hazardous materials consultant, prior to proceeding with work. The contractor will have an asbestos abatement contractor available on an on-call basis to remove any new identified/suspect materials. All asbestos-containing materials removed shall be prepared for disposal and

disposed of per WISHA and EPA regulations. No claim for delay of work or additional scope will be allowed for incidental non-friable asbestos removal by the Contractor.

C Damage of Asbestos by the Contractor: Damage to ACMs not within the scope of work, caused by the Contractor, shall be removed/repaired at the Owner's choice to the satisfaction of the Owner by the Contractor using certified asbestos workers, at the expense of the Contractor.

D Asbestos-related work

1. Any asbestos related work must be accomplished by a certified asbestos contractor.

E Work Occurring near ACMs

1. All personnel performing work in such locations shall be trained and certified to have completed Class IV asbestos training ({e.g., working in close proximity to ACM, but not disturbing it} - two-hour awareness training) as dictated by Washington Department of Labor and Industries Division of Occupational Safety and Health (L&I DOSH) regulations and according to these specifications.

F Materials with <1% asbestos impacted by other trades

1. All personnel performing work in such locations shall be trained and certified to have completed Class IV asbestos training ({e.g., working in close proximity to ACM, but not disturbing it} – two- hour awareness training) as dictated by L&I DOSH regulations and according to these specifications.

G Gray caulking w/ paint (around 1’x1’ in-door window; on metal single door) and JC/GWB, contain <1% asbestos fibers. The selective demolition of these materials is within the scope of this project. Refer to Section 02 82 00 for worker training, work practices, personal protective equipment, worker exposure monitoring and competent person requirements.

H The Contractor shall ensure that copies of the Limited Hazardous Materials Survey Report are made available to, and are retained on the Project site by all Subcontractors.

I Off-Limit Areas: Non-asbestos certified personnel shall not enter any building areas/crawl spaces marked by "Danger Asbestos Hazard" signs or outside of the cleaned area without appropriate training.

1.4 LEAD RELATED ACTIVITIES

A The Owner’s consultant has conducted limited lead x-ray fluorescence analyzer (XRF) and bulk paint sampling investigations of the areas of impact at Fire Station #63. Detectable levels of lead in painted/glazed surfaces were identified at the property within the proposed work areas.

B The work requires the disturbance and disposal of lead-containing materials from Fire Station #63 as specified herein. The lead work shall be performed in accordance with

all current applicable lead regulations and these specifications. These work activities are identified as specified in Section 028300 and in the Hazardous Materials Removal Drawings.

1. Interior and exterior paint surface tests and other lead-containing materials (LCM) (e.g., ceramic tiles) using an XRF measured at a variety of lead levels with results ranging from 0.5 milligrams per square centimeter (mg/cm2) to less than the detectable level. In addition, lead-containing paint (LCP) and LCM bulk QA samples indicate analytical results ranged from 0.0096 % Pb by weight to less than the lab reporting limit. The lead sampling data is included in the Limited Hazardous Material Survey Report which is provided as an appendix to this Specification Section.

2. Based on the specified work scope that includes limited demolition, the Contractor will as a minimum:

   a Accomplish initial exposure assessments for each category of lead work (disturbance) in accordance with WAC 296-155-176.
   b Accomplish dust control using wet methods or as required in accordance with WAC 296-155-176.
   c Accomplish waste stream sampling as needed for hazardous lead concentrations in accordance with WAC 173-303.

3. All construction work will potentially generate fugitive dust. It is the responsibility of the Contractor to control the release of all fugitive dust and to comply with the most recent regulations concerning respirable dust from L&I DOSH, the Puget Sound Clean Air Agency (PSCAA), and any other applicable federal, state and local government agencies. The Contractor is responsible for cleaning all areas affected by any fugitive dust from the proposed contract work.

4. L&I DOSH requires employers to conduct a hazard assessment and take appropriate worker protection precautions whenever paint is disturbed that has detectable concentrations of lead. Since the type of work planned (e.g., demolition) will disturb the LCP/LCM, the contractor should perform an initial exposure assessment to determine if personal protective measures and work practices are required.

5. It is the Contractor's responsibility to insure all subcontractors disturbing LCP/LCM are included in the Section 028300 pre-work submittals.

1.5 ARSENIC RELATED ACTIVITIES

A The Owner's consultant has conducted limited arsenic bulk sampling investigation of the areas of impact at Fire Station #63. Detectable levels of arsenic in brick masonry unit (BMU) mortar were identified on site.

B The work requires the disturbance and disposal of arsenic-containing materials from Fire Station #63 as specified herein. The arsenic work shall be performed in accordance with all current applicable lead regulations and these specifications. These work activities are

identified as specified in Section 028400 and the Hazardous Materials Removal Drawings.

1. The bulk arsenic sample results ranged from 22.0 parts per million (ppm) to less than the lab reporting limit. The arsenic sampling data is included in the Limited Hazardous Material Survey Report which is provided as an appendix to this Specification Section.

2. Based on the specified work scope that includes limited demolition, the Contractor will as a minimum:

   a Accomplish initial exposure assessments for each category of arsenic work (disturbance) in accordance with WAC 296-848-20060.
   b Accomplish dust control using wet methods or as required in accordance with WAC 296-848.
   c Accomplish waste stream sampling as needed for hazardous arsenic concentrations in accordance with WAC 173-303.
   d All construction work will potentially generate fugitive dust. It is the responsibility of the Contractor to control the release of all fugitive dust and to comply with the most recent regulations concerning respirable dust from L&I DOSH and PSCAA and any other applicable federal, state and local government agencies. The Contractor is responsible for cleaning all areas affected by any fugitive dust from the proposed contract work.

3. It is the Contractor's responsibility to insure all subcontractors disturbing arsenic are included in the Section 028400 pre-work submittals

1.6 MERCURY LIGHT TUBE REMEDIATION

A The work requires the disturbance and the recycling of Mercury (Hg)-containing light tubes and high intensity discharge (HID) lamps from Fire Station #63 as specified herein. Hg-light tube and HID lamp work shall be performed in accordance with all current applicable regulations and these specifications. These work activities are identified as specified in Section 028500 and the Hazardous Materials Removal Drawings.

1.7 CONTRACTOR'S USE OF PREMISES

A No work impacting ACM's, nor LCM/LCP is to occur at Fire Station #63, except during the contract period.

1. Refer to Section 011100, Summary of Work for additional requirements related to the Contractor's use of the premises.

1.8 SEGREGATION OF WORK AREAS

1. Segregate work areas from the surrounding occupied and unoccupied areas using dust proof partitions and critical barriers.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

Appendix A

Abridged Limited Hazardous Materials Survey Report for Fire Station #63

LIMITED HAZARDOUS MATERIALS SURVEY REPORT

SOUTH KING COUNTY FIRE & RESCUE
FIRE STATION #63 CAPITAL FACILITY IMPROVEMENTS

33414 21st Avenue South
Auburn, WA



June 14th, 2016
Revised: October 10th, 2016

Prepared For:

Howard Struve
Rice Fergus Miller Architecture & Planning
275 Fifth Street, Suite 100
Bremerton, WA

EHS–International, Inc.

Limited Hazardous Materials
Survey Report

South King County Fire & Rescue
Fire Station #63 Capital Facility Improvements
33414 21st Avenue S.
Auburn, Washington

EHSI Project No.: # 10854

The material and data in this report were prepared under the supervision and direction of the undersigned.

Report Approved By:

Herb Brod, CIH
Technical Director

TABLE OF CONTENTS

Acronym List ..... **av**

1.0 EXECUTIVE SUMMARY ***1***
1.1 BACKGROUND *1*
1.2 EXTENT OF CURRENT SURVEY *1*
1.3 MATERIALS FOUND *1*
1.4 OPINIONS AND RECOMMENDATIONS *2*
1.5 LIMITATIONS/DISCLAIMER *2*

2.0 LIMITED HAZARDOUS MATERIALS SURVEY REPORT ***3***
2.1 BACKGROUND *3*
2.2 BUILDING DESCRIPTION *3*
2.3 SAMPLING METHODOLOGY *3*
2.3.1 Asbestos-Containing Materials *3*
2.3.2 Lead-Containing Paint/Lead-Containing Materials *4*
2.3.3 Arsenic-Containing Materials *4*
2.4 SAMPLING RESULTS *4*
2.4.1 Asbestos-Containing Materials *4*
2.4.2 Lead-Containing Paint and Building Materials *16*
2.4.3 Arsenic-Containing Building Materials *19*
2.4.4 Toxicity Characteristic Leaching Procedure Sampling *19*
2.4.5 Polychlorinated Biphenyls *19*
2.4.6 Mercury-Containing Thermostats and Fluorescent Light Tubes *20*

3.0 LIMITATIONS *20*

4.0 STANDARD OF CARE ***21***

5.0 CERTIFIED AHERA BUILDING INSPECTORS ***22***

APPENDICES

A ..... Asbestos Analytical Laboratory Reports and Field Data Forms
B ..... Lead and Arsenic Laboratory Reports and Field Data Forms
C ..... Certified AHERA Building Inspector Certificates
D ..... Laboratory Certifications for Asbestos, Lead, and Arsenic Analysis
E ..... Sample Location Drawings for Asbestos, Lead, and Arsenic

ACRONYM LIST

ACM..... Asbestos-Containing Material
AHERA ..... Asbestos Hazard Emergency Response Act
AIHA ..... American Industrial Hygiene Association
As ..... Arsenic
BMU..... Brick Masonry Unit
CFR ..... Code of Federal Regulations
CMU ..... Concrete Masonry Unit
DOSH ..... Washington State Department of Labor and Industries, Division of Occupational Safety and Health
EA..... Each
Ecology..... Washington State Department of Ecology
EHSI ..... EHS-International, Inc.
ELLAP ..... Environmental Lead Laboratory Accreditation Program
GWB..... Gypsum Wall Board
Hg..... Mercury
JC ..... Joint Compound
LCM..... Lead-Containing Material
LCP..... Lead-Containing Paint
LF ..... Linear Feet
L&I ..... Washington State Department of Labor and Industries
$\mu g/m^3$ ..... Micrograms Per Cubic Meter
mg/L..... Milligrams Per Liter
N/A..... Not Applicable
ND ..... None Detected
NIS..... Not in Scope
NVL..... NVL Laboratories, Inc.
NVLAP..... National Voluntary Laboratory Accreditation Program
OSHA ..... US Occupational Safety and Health Administration
Pb ..... Lead
PCBs ..... Polychlorinated Biphenyls
PLM ..... Polarized Light Microscopy
ppm..... Parts per Million
PSCAA ..... Puget Sound Clean Air Agency
QA ..... Quality Assurance
RCW ..... Revised Code of Washington
SACT..... Suspended Acoustical Ceiling Tiles
SAT..... Seattle Asbestos Test, LLC
Small Bore ..... Pipe TSI ≤ 6” OD
SVF..... Sheet Vinyl Flooring
TCLP ..... Toxic Characteristic Leachate Procedure
TSI..... Thermal System Insulation
WAC ..... Washington Administrative Code
WT..... Weight
w/..... With
XRF ..... x-ray fluorescence

1.0 EXECUTIVE SUMMARY

1.1 BACKGROUND

The South King County Fire & Rescue (SKC F&R) has contracted Rice Fergus Miller Architecture & Planning (RFMA) to lead the design team for the Fire Station #63 (FS #63) renovation project located at 33414 21st Avenue South in Auburn, WA. In conjunction with that project, RFMA contracted EHS-International, Inc. (EHSI), a hazardous materials and industrial hygiene consulting firm, to conduct a Limited Hazardous Materials Survey. The intent of the survey is to specifically identify and quantify asbestos-containing building materials (ACM), lead-containing paint (LCP), other lead-containing building materials (LCM), arsenic (As)-containing concrete masonry unit (CMU) or brick masonry unit (BMU) mortar, polychlorinated biphenyl (PCB)-containing light ballasts, and mercury (Hg)-containing light tubes and lamps that may be impacted by the project.

1.2 EXTENT OF CURRENT SURVEY

EHSI inspected all accessible interior and exterior materials potentially impacted by the proposed project. Accessible suspect materials were sampled including, but not limited to: interior wall systems, ceiling and floor systems, stair treads and risers, duct sealant, thermal system insulation (TSI) on piping, sink undercoating, interior and exterior caulking, window glazing putty, BMU mortar, CMU mortar, and roofing materials and sealants. EHSI accomplished representative destructive inspection; however, in areas inaccessible for inspection (e.g., fire door cores, wall cabinet mastics, enclosed plaster wall chases, electrical panel components and materials above hard lid ceilings) suspect materials were assumed to be ACM.

1.3 MATERIALS IMPACTED BY THIS PROJECT

SUMMARY OF ASBESTOS-CONTAINING MATERIALS FIRE STATION #63	
ASBESTOS MATERIAL DESCRIPTION	**LOCATION**
ACM gray door frame caulking (around single metal door frame)	LT Office / Bed Room
ACM gray duct seam sealant (on 5” outside diameter (OD) metal furnace flue)	Furnace Room
ACM brown window frame caulking (around 5’x5’ metal framed window)	LT Office / Bed Room
Non-ACM new white seam caulking on **ACM old black asphaltic caulking** (on 1’x1’ metal ducting associated w/ old exhaust fan)	Roof over Apparatus Room
Non-ACM new gray window frame caulking on **ACM old gray window frame caulking** (around 6’x5’ metal framed window)	Second Floor Exterior
2’x3’ Electrical panels with assumed ACM internals	Lobby, Apparatus Room, Electrical Room/ Hose Tower First Floor, Hose Tower Second Floor, Exterior Radio Equipment and Generator Area

SUMMARY OF ASBESTOS-CONTAINING MATERIALS FIRE STATION #63	
ASBESTOS MATERIAL DESCRIPTION	**LOCATION**
Small electrical switch gear panels with assumed ACM internals	Exterior N. Side and Roof
Assumed ACM glue dots associated w/ wood wall cabinets (5'x14')	Shop
Assumed ACM thermal system insulation (TSI) on small bore pipe elbows and fittings on fiberglass runs (concealed in plumbing walls & ceilings)	Restroom 1, Restroom 2, Furnace Room, and Restroom 8
Assumed ACM insulation on 12"x12" metal ducting concealed beneath slab	Throughout
Assumed ACM mastic associated with 4'x9' plaster wall panels on BMU wall	Exterior North and West Sides
Assumed ACM windows concealed under 4'x9' exterior plaster wall panels	Exterior North and West Sides

Key: ACM = Asbestos-Containing Material, **BMU =** brick masonry unit, **OD** = outside diameter, **small bore =** pipe TSI ≤ 6" OD, **TSI** = Thermal System Insulation

1.4 OPINIONS AND RECOMMENDATIONS

This will be a renovation project, therefore, EHSI recommends that all impacted ACM and assumed ACM identified in paragraph 1.3 be removed and disposed prior to demolition/renovation.

Any suspect materials not identified as having been surveyed in this report must be treated as an ACM until determined otherwise by a Certified Asbestos Building Inspector and NVLAP certified laboratory.

Washington State Department of Labor and Industries (L&I) Division of Occupational Safety and Health (DOSH) and the US Occupational Safety and Health Administration (OSHA) require employers to conduct a hazard assessment and take appropriate worker protection precautions whenever building materials are disturbed that have detectable quantities of lead and/or arsenic. Since the type of work planned (e.g., sawing, grinding, select demolition) will disturb the LCP/LCM and/or As-containing BMU mortar, the contractor should perform an initial exposure assessment to determine if personal protective measures, employee training, medical monitoring, and work practices are required.

1.5 LIMITATIONS/DISCLAIMER

This report does **not** represent a comprehensive hazardous materials investigation for the subject property. This investigation has been conducted by EHSI under a specific scope of work authorized by RFMA for a specific purpose. Due to continued occupancy, fire door cores, cabinet mastics, electrical panel components and materials above hard lid ceilings and inside closed plumbing chases were not sampled and are assumed to be present and assumed to be ACMs. This report and accompanying appendices include the supporting information for this executive summary.

2.0 LIMITED HAZARDOUS MATERIALS SURVEY REPORT

2.1 BACKGROUND

The SKC F&R has contracted RFMA to lead the design team for the FS #63 renovation project located at 33414 21st Avenue South in Auburn, WA. In conjunction with that project, RFMA contracted EHSI, a hazardous materials and industrial hygiene consulting firm, to accomplish a pre-renovation limited hazardous materials survey of the existing FS #63 Building. For this limited hazardous materials survey, EHSI was tasked to use applicable federal, state and local guidelines in the accomplishment of its survey. EHSI was further tasked to provide a written survey report including: identification of all suspect materials; a determination of whether suspect materials were: ACM, LCP, LCM, As-containing CMU and BMU mortar, PCB-containing light ballasts, and Hg-containing light tubes/lamps; and to provide analytical reports indicating the presence and quantity of the hazardous materials.

This Limited Hazardous Materials Survey Report meets the Washington State "Good Faith Survey" requirements as cited in Revised Code of Washington (RCW) 49.26.016 and implemented by L&I DOSH regulation, Washington Administrative Code (WAC) 296-62-07721, and Regulation III, Article 4 of the Puget Sound Clean Air Agency (PSCAA).

On April 22nd, April 25th, and April 26th, 2016 EHSI conducted a Limited Hazardous Materials (ACM, LCP, LCM, As-containing CMU and BMU mortar, PCB-ballasts, and Hg-containing light tubes) Survey of FS #63. On September 27, 2016, EHSI conducted a design site check to confirm location and quantity of materials being impacted by the proposed project and during that design site check, collected additional suspect ACM confirmation samples for analysis.

2.2 BUILDING DESCRIPTION

FS #63 is located at 33414 21st Avenue S., Auburn, Washington. The facility is comprised of a two-story brick and CMU building with slab-on-grade construction. The main floor houses a dormitory, offices, an apparatus bay, restrooms, a shop, furnace room, hot water heater room, radio room, and fitness room. The second floor houses beanery and watch, media room, and restrooms. The building has a flat roof system. Windows are metal-framed and partially operable. Interior finishes include: Painted and textured gypsum wallboard (GWB) walls and ceilings, 2'x4' suspended acoustical ceiling tiles (SACT), with flush-mounted and recessed fluorescent light fixtures throughout the building. Flooring includes: Sheet vinyl flooring (SVF), carpet, and bare concrete floors. Forced air central heating for the building is provided by furnaces in the furnace rooms on the ground floor and top of stairs. Domestic hot water is provided by an electric water heater located in the hot water heater room on the ground floor.

2.3 SAMPLING METHODOLOGY

2.3.1 Asbestos-Containing Materials

The EHSI field inspectors are asbestos Building Inspectors, certified under the requirements of the United States Environmental Protection Agency (USEPA) AHERA regulation 40 Code of Federal Regulations (CFR) 763, Subpart E. Copies of their certificates are provided in Appendix C. The number of bulk samples collected and their locations are based on the AHERA regulation and the guidelines provided by the USEPA Document 560/5-85-030a, October 1985, *Asbestos in Buildings: Simplified Sampling Scheme for Friable Surfacing Materials*.

EHSI collected samples and obtained analytical data for suspect ACM identified in the facility. Once collected, each bulk sample was sealed in an unadulterated plastic bag to eliminate the possibility of cross-contamination. “Chain-of-Custody” tracking was followed to maintain sample integrity during handling and data reporting at EHSI and the analytical laboratory. As specified in 40 CFR Chapter 1 (1-1-87 edition) Part 763, Subpart F, and Appendix A, each sample was analyzed using polarized light microscopy (PLM) / dispersion staining techniques, in accordance with USEPA Method 600/R-93/116. Samples were analyzed for asbestos content by Seattle Asbestos Test, LLC (SAT) located in Seattle, Washington. SAT participates in the National Institute for Standards and Technology (NIST) National Voluntary Laboratory Accreditation Program (NVLAP). Only materials containing more than 1% total asbestos were classified as “asbestos-containing” based on USEPA, state, and local regulations.

Samples in the report labeled as ##QA are quality assurance (QA) samples. Split samples were taken from the same location and they were sent to separate laboratories. QA samples were submitted to, NVL Laboratories, Inc. (NVL) in Seattle, WA, another NVLAP laboratory. Copies of both laboratories’ NVLAP certifications are included in Appendix D.

2.3.2 Lead-Containing Paint/Lead-Containing Materials

EHSI used a Niton Model XLp x-ray fluorescence (XRF) Spectrum Analyzer to measure lead content on interior and exterior paint coatings and other suspect LCM. Measurements were representative of all layers of paint and/or LCM. A summary of Lead Paint XRF results is provided in Table 3. Bulk quality assurance samples were taken for a representative number of LBP and LCM and were brought to NVL located in Seattle, Washington, an accredited laboratory for Atomic Absorption Spectroscopy (USEPA Method-7000B) by the American Industrial Hygiene Association (AIHA) under the Environmental Lead Laboratory Accreditation Program (ELLAP). Copies of laboratory reports and field data forms for lead are in Appendix B. A copy of NVL’s certification for analysis is provided in Appendix D.

2.3.3 Arsenic-Containing Materials

EHSI collected samples and obtained analytical data for BMU mortar and CMU mortar from the building walls. Once collected, each bulk sample was sealed in an unadulterated plastic bag to eliminate the possibility of cross-contamination. “Chain-of-Custody” tracking was followed to maintain sample integrity during handling and data reporting at EHSI and the analytical laboratory. A summary of arsenic laboratory results is provided in Table 4. Samples were brought to NVL, an accredited laboratory for Inductively Coupled Plasma Spectroscopy (USEPA Method-6010) by the Washington State Department of Ecology. Copies of laboratory reports and field data forms for arsenic are in Appendix B. A copy of NVL’s certification for analysis is provided in Appendix D.

2.4 SAMPLING RESULTS

2.4.1 Asbestos-Containing Materials

Seventy-three (73) bulk samples of suspect ACM were collected as part of the survey. Four (4) of those samples were split for quality assurance analyses. Three (3) additional samples of suspect ACM were collected as part of the design check. Limited destructive inspection was conducted to identify hidden and/or concealed materials. Copies of the asbestos analytical laboratory results are included in Appendix A. Asbestos and lead sample location drawings are provided in Appendix E. Asbestos sampling information including: sample number, material

description, sample location, and analytical results are summarized in Table 1. The ACM and assumed ACM identified during this survey, including the quantity and location, is summarized in Table 2. Suspect materials not sampled due to continued occupancy were assumed to be ACM.

TABLE 1
SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS
FIRE STATION #63

SAMPLE NUMBER	SAMPLE LOCATION	MATERIAL DESCRIPTION	ASBESTOS %	TYPE OF ASBESTOS
First Floor				
10854-63-01	LT Office / Bed Room	Layer 1: 4" Black cove base Layer 2: Clear, white, and tan mastic	L1: ND L2: ND	N/A N/A
10854-63-02	LT Office / Bed Room	Layer 1: Multi-color carpet Layer 2: Tan mastic (on concrete)	L1: ND L2: ND	N/A N/A
10854-63-03	Restroom 2	Layer 1: 4" Light gray cove base Layer 2: Off-white and tan mastic Layer 3: JC w/ paint and paper	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-04	Restroom 2	Layer 1: Gray broken rock pattern SVF Layer 2: Gray paper backing Layer 3: Tan mastic Layer 4: Concrete	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A
10854-63-05QA	Fitness Room	Layer 1: 6" Black cove base Layer 2: White and tan mastic Layer 3: Old brown mastic w/ paint (on CMU)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-06	NE Entry	Layer 1: Wood pattern SVF Layer 2: White fibrous backing Layer 3: Tan mastic Layer 4: Gray leveling compound Layer 5: Black mastic Layer 6: Concrete	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND	N/A N/A N/A N/A N/A N/A
10854-63-07	Restroom 2	Layer 1: White texturing skim coat w/ paint and paper Layer 2: GWB wall w/ paper (corner)	L1: ND L2: ND	N/A N/A
10854-63-08	Restroom 2	Layer 1: White texturing skim coat w/ paint and paper Layer 2: GWB wall w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-09	Storage Area Under Stairs	Layer 1: White texturing skim coat w/ paint Layer 2: GWB ceiling w/ paper (ceiling edge)	L1: ND L2: ND	N/A N/A
10854-63-10	Storage Area Under Stairs	Layer 1: White texturing skim coat w/ paint Layer 2: GWB ceiling w/ paper (mid-ceiling)	L1: ND L2: ND	N/A N/A
10854-63-11	Bedroom 1	Layer 1: JC w/ paint Layer 2: GWB w/ paper (corner wall)	L1: ND L2: ND	N/A N/A
10854-63-12	Bedroom 1	Layer 1: White JC skim coat w/ paint Layer 2: GWB w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A
10854-63-13	Hallway 100	Layer 1: Trace white JC skim coat w/ paint Layer 2: GWB w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A
10854-63-14	Restroom 2	Layer 1: Wood wainscoting Layer 2: Tan glue dot	L1: ND L2: ND	N/A N/A
10854-63-15	Restroom 2	White caulking at horizontal seams (between wall and wainscoting)	ND	N/A
10854-63-16	Restroom 2	Tan door frame caulking w/ paint (around single metal door frame)	ND	N/A
10854-63-17*	**LT Office / Bed Room**	**Gray door frame caulking w/ paint (around single metal door frame)**	**1.25%**	**Chrysotile**
10854-63-18*	**Fitness Room**	**Gray door frame caulking w/ paint (on wooden door frame)**	**1.5%**	**Chrysotile**
10854-63-19	Fitness Room	Layer 1: White caulking w/ paint Layer 2: Brown wood block (around 1'x1' in-door window: on wood single door)	L1: ND L2: ND	N/A N/A
10854-63-20*[1]	Fitness Room	Gray caulking w/ paint (around 1'x1' in-door window; on metal single door)	0.75%	Chrysotile
10854-63-21	Hallway 100	2'x4' pin-hole and worm track pattern SACT w/ paint	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-22*[2]	Radio Room	Layer 1: JC w/ paint Layer 2: GWB ceiling w/ paper (ceiling edge)	L1: 0.5% L2: ND	Chrysotile N/A
10854-63-23	Radio Room	GWB ceiling w/ paint and paper (mid ceiling)	ND	N/A
10854-63-24	Radio Room	Layer 1: Brown tac board (4'x8') Layer 2: Tan glue dot	L1: ND L2: ND	N/A N/A
10854-63-25	Furnace Room	Layer 1: 4"x4" green ceramic wall tile Layer 2: White grout Layer 3: Gray mortar Layer 4: Green paint (on CMU wall)	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A
10854-63-26*	**Furnace Room**	**Gray duct seam sealant (on 5" OD metal furnace flue)**	**1.25%**	**Chrysotile**
10854-63-27	Furnace Room	Dark gray sealant (at the base of furnace; on 3'x5' metal platform)	ND	N/A
10854-63-28	Hot Water Tank Room	Beige/blue pipe dope (on 1" sprinkler pipe fittings)	ND	N/A
10854-63-29	Shop	Layer 1: White repair patch w/ paint Layer 2: Concrete (foundation below CMU)	L1: ND L2: ND	N/A N/A
10854-63-30	Hose Tower	Gray CMU mortar w/ paint	ND	N/A
10854-63-31	Hose Tower	Layer 1: Gray brick mortar Layer 2: Red brick	L1: ND L2: ND	N/A N/A
10854-63-32	Apparatus Bay	Layer 1: Silver foil Layer 2: Beige/clear mastic Layer 3: Gray duct seam sealant w/ trace silver paint (on 6" OD engine exhaust system)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-33	Stairs	Layer 1: Brown stair tread Layer 2: Beige/clear mastic Layer 3: Red paint (on metal)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-34QA[X]*	**LT Office / Bedroom**	**Brown window frame caulking w/ paint (around 5'x5' metal framed window)**	**1.25%**	**Chrysotile**
10854-63-35	LT Office / Bed Room	Layer 1: Beige glue dot Layer 2: Wood radiator enclosure top	L1: ND L2: ND	N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-36	LT Office / Bed Room	Tan glue dot (beneath 6”x5’ wood window sill)	ND	N/A
10854-63-37	LT Office / Bed Room	Layer 1: Black paper backing w/ black mastic Layer 2: Yellow fiberglass batt insulation (above drop ceiling)	L1: ND L2: ND	N/A N/A
10854-63-38	NE Entry	Layer 1: Black pipe wrap Layer 2: Clear plastic (on 2” copper pipe)	L1: ND L2: ND	N/A N/A
10854-63-39	Apparatus Bay	Black expansion joint w/ paint (on various locations on concrete floor and exterior walls)	ND	N/A
Second Floor				
10854-63-40	Beanery & Watch	Layer 1: Multi-color carpet Layer 2: White carpet pad Layer 3: Tan mastic Layer 4: Black mastic Layer 5: Wood	L1: ND L2: ND L3: ND L4: ND L5: ND	N/A N/A N/A N/A N/A
10854-63-41	Beanery & Watch	Layer 1: Wood pattern SVF Layer 2: Light gray soft elastic backing Layer 3: Clear mastic Layer 4: White fibrous backing Layer 5: Tan mastic Layer 6: ¼” Plywood Layer 7: Black mastic Layer 8: Wood	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND	N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-42	Restroom 5	Layer 1: Gray broken rock pattern SVF Layer 2: Gray paper backing w/ tan mastic Layer 3: ¼” Particle board Layer 4: Trace black mastic Layer 5: Wood	L1: ND L2: ND L3: ND L4: ND L5: ND	N/A N/A N/A N/A N/A
10854-63-43	Stairwell	Layer 1: Trace white texturing skim coat w/ paint Layer 2: GWB wall w/ paper (corner wall)	L1: ND L2: ND	N/A N/A
10854-63-44	Stairwell	Layer 1: Trace white texturing skim coat w/ paint Layer 2: GWB wall w/ paper (mid-wall)	L1: ND L2: ND	N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-45	Restroom 5	Layer 1: Trace white texturing skim coat w/ paint and paper Layer 2: GWB wall w/ paper (mid wall)	L1: ND L2: ND	N/A N/A
10854-63-46	Restroom 4	Layer 1: White vinyl covering Layer 2: 2'x4' GWB SACT w/ paper	L1: ND L2: ND	N/A N/A
10854-63-47	Beanery & Watch	White sink undercoat	ND	N/A N/A
Exterior				
10854-63-48	East Side	Gray seam caulking/pipe dope (around 4"x4" seismic metal bracket and on sprinkler pipe fittings)	ND	N/A
10854-63-49	NW Corner	Layer 1: Gray foam window seal Layer 2: Trace clear mastic Layer 3: White paper (between sash and glass on 5'x5' metal framed window)	L1: ND L2: ND L3: ND	N/A N/A N/A
10854-63-50QA[X]	**East Side**	**Layer 1: Gray door frame caulking w/ paint** **Layer 2: Trace white sandy/brittle material with rusted material (on single metal door frame between BMU and frame)**	**L1: 4%** **L2: 3%**	**Chrysotile** **Chrysotile**
10854-63-51	**East Side**	**Gray door frame caulking w/ paint (on double metal door frame between BMU and metal frame)**	**4%**	**Chrysotile**
10854-63-52	East Side	Beige/gray window frame caulking (on 4'x6' metal framed window)	ND	N/A
10854-63-53	East Entry Awning	Layer 1: Black asphaltic 3-tab roofing Layer 2: Black asphaltic tar Layer 3: Black asphaltic 3-tab roofing Layer 4: Black asphaltic felt paper (on wood decking)	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A
10854-63-54	East Entry Awning	Trace brown awning metal flashing sealant	ND	N/A
10854-63-55	Exterior N Side	Gray plaster wall panel (4'x9') w/ paint (on brick)	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-56	Exterior NW corner	Gray plaster wall panel (4'x9') w/ paint (on brick)	ND	N/A
10854-63-57	Exterior N side	Gray plaster wall panel (4'x9') w/ paint (on brick)	ND	N/A
10854-63-58	Roof over Fitness Room	White roof flashing sealant w/ paint (on 6" metal flashing)	ND	N/A
10854-63-59	Roof over Apparatus Room	Tan conduit penetration sealant (around 3" conduit)	ND	N/A
10854-63-60	**Roof over Apparatus Room**	Layer 1: New white seam caulking **Layer 2: Old black asphaltic caulking (on 1'x1' metal ducting associated w/ old exhaust fan)**	ND **L2: 4%**	N/A **Chrysotile**
10854-63-61	Roof Over Apparatus Room	Silver/gray exhaust system seam sealant (8" OD)	ND	N/A
10854-63-62	Roof Over Apparatus Room	8" OD flex duct (associated with circulation fan)	ND	N/A
10854-63-63	Roof Over Apparatus Room	Black asphaltic vapor barrier (under wood siding)	ND	N/A
10854-63-64	Roof Over Fitness	Layer 1: Gray window glazing putty w/ paint Layer 2: Brown window glazing putty (around 2'x3' indoor window in metal door at the top of Hose Tower)	L1: ND L2: ND	N/A N/A
10854-63-65	Second Floor Stairwell	Yellow seam caulking w/ paint (between rungs and CMU wall)	ND	N/A
10854-63-66	Hose Tower Top Level	Gray interior window glazing putty (on 5'x5' metal framed window)	ND	N/A
10854-63-67	Roof Over Hose Tower	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil (on wood decking)	L1: ND L2: ND L3: ND L4: ND	N/A N/A N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-68	Roof Over Fitness Room	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil Layer 5: Black asphaltic tar Layer 6: Black asphaltic built-up roofing on brown paper Layer 7: Black asphaltic tar Layer 8: Brown fiber board insulation on tar (tarred onto wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND	N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-69	Roof Over Apparatus Room	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil Layer 5: White felt Layer 6: Yellow poly-iso insulation Layer 7: White felt Layer 8: Yellow poly-iso insulation Layer 9: White felt (on wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND L9: ND	N/A N/A N/A N/A N/A N/A N/A N/A N/A
10854-63-70	Roof Over L.T. Office/ Bedroom	Layer 1: White/blue membrane roofing Layer 2: Silver foil Layer 3: Yellow poly-iso insulation Layer 4: Silver foil Layer 5: Black asphaltic tar Layer 6: Black asphaltic built-up roofing on brown paper Layer 7: Black asphaltic tar Layer 8: Brown fiber board insulation on tar (tarred onto wood decking)	L1: ND L2: ND L3: ND L4: ND L5: ND L6: ND L7: ND L8: ND	N/A N/A N/A N/A N/A N/A N/A N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-71	Roof Over Beanery/ Dayroom	Layer 1: White/blue membrane roofing	L1: ND	N/A
		Layer 2: Brown asphaltic felt paper	L2: ND	N/A
		Layer 3: Yellow poly-iso insulation	L3: ND	N/A
		Layer 4: Black asphaltic felt paper	L4: ND	N/A
		Layer 5: Black asphaltic tar	L5: ND	N/A
		Layer 6: Black asphaltic felt paper	L6: ND	N/A
		Layer 7: Brown paper	L7: ND	N/A
		Layer 8: Black asphaltic tar	L8: ND	N/A
		Layer 9: Black asphaltic felt paper	L9: ND	N/A
		Layer 10: Brown fiber board insulation (tarred onto wood decking)	L10: ND	N/A
10854-63-72QA[X]	**Second Floor Exterior**	**Layer 1: Old gray/dark gray window frame caulking w/ paint (under layer 2)**	**L1: 4%**	**Chrysotile**
		Layer 2: New gray window frame caulking (around 6'x5' metal framed window)	L2: ND	N/A
10854-63-73	Roof Over Fitness Room	Layer 1: White/blue membrane roofing	L1: ND	N/A
		Layer 2: Brown asphaltic felt paper	L2: ND	N/A
		Layer 3: Yellow poly-iso insulation	L3: ND	N/A
		Layer 4: Black asphaltic felt paper	L4: ND	N/A
		Layer 5: Black asphaltic tar	L5: ND	N/A
		Layer 6: Multiple layers of black asphaltic felt paper	L6: ND	N/A
		Layer 7: Brown paper	L7: ND	N/A
		Layer 8: Black asphaltic tar	L8: ND	N/A
		Layer 9: Black asphaltic felt paper	L9: ND	N/A
		Layer 10: Brown fiber board insulation (tarred onto wood decking)	L10: ND	N/A
10854-63-02-01	Hallway 100	Tan & white debris/insulation (at duct vent in floor)	ND	N/A

TABLE 1 SUMMARY OF ASBESTOS BULK SAMPLING AND ANALYTICAL RESULTS FIRE STATION #63				
SAMPLE NUMBER	**SAMPLE LOCATION**	**MATERIAL DESCRIPTION**	**ASBESTOS %**	**TYPE OF ASBESTOS**
10854-63-02-02	Furnace Room	Layer 1: Dark gray duct seam sealant Layer 2: Clear duct seam sealant (on return air duct work)	L1: ND L2: ND	N/A N/A
10854-63-02-03	Bedroom 4	Layer 1: Green insulation Layer 2: Black coating (in 1' diameter recessed ceiling speaker casing)	L1: ND L2: ND	N/A N/A

Key: BMU = Brick Masonry Unit; **CMU** = Concrete Masonry Unit; **GWB** = Gypsum Wall Board; **JC** = Joint Compound; **OD** = Outside Diameter (includes OD of TSI); **ND** = None Detected; **N/A** = Not Applicable, **SACT** = Suspended Acoustical Ceiling Tile; **SVF** = Sheet Vinyl Flooring; **w/**=with;

[X] When QA lab and primary lab sample results differed, EHSI reported the most restrictive (e.g., highest % asbestos) in Table 1. Analytical results for all analyses are provided in Appendix A.

* Point Counted Results. EHSI re-submitted these samples which were reported to have greater than 1% asbestos concentration for re-analysis using the more precise EPA "Point Count" method. The "Point Count" analytical method is recommended by the EPA for samples with less than 10% asbestos. Only the "Point Count" re-analysis concentrations are listed in Table 1. Analytical results for all analyses are provided in Appendix A.

[1] Preliminary analytical reports indicated that the gray caulking w/ paint around the 1'x1' in-door window; on metal single door in the Fitness Room contains approximately 2% Chrysotile asbestos. (Sample # 10854-63-20) EHSI re-submitted the gray caulking sample reported to have greater than 1% asbestos concentration for re-analysis using the more precise EPA "Point Count" method. The "Point Count" analytical method is recommended by the EPA for samples with less than 10% asbestos. Based on the results of that re-analysis, the gray caulking w/ paint found around the 1'x1' in-door window on the metal single door in the Fitness Room was determined to be a **non-ACM** (e.g., containing ≤ 1% asbestos fibers). Only the "Point Count" re-analysis concentrations are listed in Table 1. Analytical results for all analyses are provided in Appendix A.

[2] Preliminary analytical reports indicated that the joint compound w/ paint found on the GWB ceiling in the Radio Room contains approximately 2% Chrysotile asbestos. (Sample # 10854-63-22) EHSI re-submitted the joint compound sample reported to have greater than 1% asbestos concentration for re-analysis using the more precise EPA "Point Count" method. The "Point Count" analytical method is recommended by the EPA for samples with less than 10% asbestos. Based on the results of that re-analysis, the joint compound w/ paint found on the GWB ceiling in the Radio Room was determined to be a **non-ACM** (e.g., containing ≤ 1% asbestos fibers). Only the "Point Count" re-analysis concentrations are listed in Table 1. Analytical results for all analyses are provided in Appendix A.

Materials containing <1% asbestos are regulated as "unclassified" asbestos materials and fall under separate requirements for worker protection, training, work practices and waste disposal. L&I DOSH requires special worker exposure precautions and qualifications when dealing with

ACM used on GWB seams and nail holes. Similar requirements exist for walls and ceilings skim-coated with material that contains less than one percent (<1%) asbestos fibers. Refer to L&I DOSH regulations and WISHA Regional Directives (WRD) as indicated above.

Table 2 summarizes materials identified by EHSI as containing greater than 1% asbestos fibers during its survey, and un-sampled materials assumed to be ACM. **The Table 2 Summary of Asbestos Containing Materials is for engineering cost estimating purposes and is not intended for bid quantifications.**

TABLE 2
SUMMARY OF ASBESTOS-CONTAINING MATERIALS
FIRE STATION #63

ASBESTOS MATERIAL DESCRIPTION	LOCATION	TOTAL	QUANTITY EXPECTED TO BE IMPACTED
ACM gray door frame caulking w/ paint (around single metal door frame)	LT Office / Bed Room	5 EA	2 EA
ACM gray door frame caulking w/ paint (on wooden door frame)	Fitness Room	2 EA	NIS
ACM gray duct seam sealant (on 5" OD metal furnace flue)	Furnace Room	6 LF	6 LF
ACM brown window frame caulking (around 5'x5' metal framed window)	LT Office / Bed Room	6 EA	3 EA
ACM gray door frame caulking w/ paint on ACM trace white sandy/brittle material with rusted material (on single metal door frame between brick and frame)	Exterior East Side	3 EA	NIS-
ACM gray door frame caulking w/ paint (on double metal door frame between brick and frame)	Exterior East Side	1 EA	NIS
Non-ACM new white seam caulking on **ACM old black asphaltic caulking** (on 1'x1' metal ducting associated w/ old exhaust fan)	Roof over Apparatus Room	5 LF	5 LF
Non-ACM new gray window frame caulking on **ACM old gray window frame caulking** (around 6'x5' metal framed window)	Second Floor Exterior	6 EA	6 EA
Assumed ACM internal components in radiator (1'x4'x7') concealed behind wood enclosure	L.T. Office/ Bedroom	1 EA	NIS
Fire door with assumed ACM fire core	L.T. Office/ Bedroom	1 EA	NIS

TABLE 2 SUMMARY OF ASBESTOS-CONTAINING MATERIALS FIRE STATION #63			
ASBESTOS MATERIAL DESCRIPTION	**LOCATION**	**TOTAL**	**QUANTITY EXPECTED TO BE IMPACTED**
2'x3' Electrical panels with assumed ACM internals	Lobby, Apparatus Room, Electrical Room/ Hose Tower First Floor, Hose Tower Second Floor, Exterior Radio Equipment and Generator Area	9 EA	1 EA
2'x4' Electrical panels with assumed ACM internals	Electrical Room/ Hose Tower First Floor	3 EA	NIS
Small electrical switch gear panels with assumed ACM internals	Apparatus Bay, Exterior N. Side and Roof	4 EA	2 EA
Assumed ACM glue dots associated w/ wood wall cabinets (5'x14')	Shop	2 EA	2 EA
Assumed ACM internal components in ceiling mounted unit-heaters (2'x3'x3.5')	Apparatus Room	3 EA	NIS
Assumed ACM TSI on small bore pipe elbows and fittings on fiberglass runs (concealed in plumbing walls & ceilings)	Restroom 1, Restroom 2, Furnace Room, and Restroom 8	120 EA	40 EA
Assumed ACM insulation on 12"x12" metal ducting concealed beneath slab	Throughout	400 LF	40 LF
Assumed ACM mastic associated with 4'x9' plaster wall panels on brick wall	Exterior North and West Sides	9 EA	9 EA
Assumed ACM windows concealed under 4'x9' exterior plaster wall panels	Exterior North and West Sides	4 EA	1 EA

Key: ACM = Asbestos-Containing Material; **BMU =** Brick Masonry Unit, **EA** = Each, **LF** = Linear Feet; **NIS =** Not in Scope, **OD** = Outside Diameter; **SF** = Square Feet; **small bore =** Pipe TSI ≤ 6" OD, **TSI** = Thermal System Insulation.

ACM identified in this survey should not be disturbed unless handled by personnel who are properly trained and certified in asbestos work. Demolition and/or renovation activities by contractors may expose concealed suspect ACM. Contractors should be aware of the potential for concealed suspect ACM and have preplanned contingencies for the handling of suspect ACM discovered during renovation and/or demolition work. Any concealed suspect ACM material that was not sampled or was assumed to be ACM and included in this report, must be treated as ACM until proven otherwise by a Certified AHERA Building Inspector and a certified laboratory. Contingency plans should include stopping work on identification of concealed

suspect ACM, evacuation of the area, and sampling by a Certified AHERA Building Inspector. Concealed suspect material may include, but is not limited to: non-fiberglass pipe or roof drain insulation; spray-applied coatings; cementitious board; asphalt or paper vapor barriers; vinyl floorings and mastics.

2.4.2 Lead-Containing Paint and Building Materials

Forty-five (45) samples were analyzed for lead using the X-Ray fluorescence (XRF) analyzer. Results marked with "≤LOD" are less than the limit of detection. XRF paint sample results ranged from 0.5 milligrams of lead per square centimeter (mg Pb/cm^2) to less than the LOD. XRF sample results for other LCM ranged from 0.05 milligrams of lead per square centimeter (mg Pb/cm^2) to less than the LOD. The results are provided in Table 3 of this report. The results indicate that none of the materials were found to contain ≥1.0 mg/cm^2 lead using the XRF instrument and nine (9) of the surfaces were found to contain detectable levels of lead using the XRF. **Bolded results indicate materials coated with "lead-based paint" (e.g., >1.0 mg/cm^2) as defined by USEPA regulation 40CFR745 and Washington State Department of Commerce (Commerce) regulation WAC 365-230.** XRF readings for other lead-containing materials were < LOD.

Table 3 summarizes XRF lead samples, including sample number, material description, substrate, color, location and analytical results.

TABLE 3
XRF SAMPLING
SUMMARY OF PAINTED COMPONENTS AND MATERIALS
FIRE STATION #63

Read. #	Component	Substrate	Color	Room	Building	Lead Conc. (mg/cm^2)
1	SELF-CALIBRATION	N/A	N/A	N/A	N/A	0.67
2	CALIBRATION	N/A	RED	N/A	N/A	1.2
3	CALIBRATION	N/A	RED	N/A	N/A	1.1
4	CALIBRATION	N/A	RED	N/A	N/A	1.0
5	WALL	DRYWALL	WHITE	STAIRWELL	MAIN	< LOD
6	TRIM	WOOD	WHITE	STAIRWELL	MAIN	< LOD
7	WALL	CMU	OFF-WHITE	STAIRWELL	MAIN	< LOD
8	STAIR HANDRAIL	METAL	BROWN	STAIRWELL	MAIN	< LOD
9	STAIR RUNG	METAL	BROWN	STAIRWELL	MAIN	< LOD
10	WALL	BMU	WHITE	LOBBY	MAIN	< LOD
11	WALL	BMU	WHITE	LOBBY	MAIN	< LOD
12	DOOR	METAL	BROWN	LOBBY	MAIN	< LOD
13	DOORFRAME	METAL	BROWN	LOBBY	MAIN	< LOD

TABLE 3 XRF SAMPLING SUMMARY OF PAINTED COMPONENTS AND MATERIALS FIRE STATION #63						
Read. #	**Component**	**Substrate**	**Color**	**Room**	**Building**	**Lead Conc. (mg/cm^2)**
14	DRAINPIPE	METAL	WHITE	LOBBY	MAIN	< LOD
15	CONDUIT	METAL	WHITE	LOBBY	MAIN	< LOD
16	CONDUIT	METAL	WHITE	LOBBY	MAIN	< LOD
17	WALL	CMU	BEIGE	APPARATUS ROOM	MAIN	< LOD
18	WALL CORNER GUARD	METAL	BEIGE	APPARATUS ROOM	MAIN	0.06
19	SELF-CALIBRATION	N/A	N/A	N/A	N/A	0.65
20	CONDUIT	METAL	BEIGE	APPARATUS ROOM	MAIN	< LOD
21	CABINETS	WOOD	TAN	SHOP	MAIN	0.05
22	DUCT	METAL	TAN	SHOP	MAIN	< LOD
23	ELECTRICAL PANEL	METAL	DARK GRAY	SHOP	MAIN	< LOD
24	LADDER	METAL	YELLOW	SHOP	MAIN	0.5
25	DOOR	METAL	BEIGE	HOSE TOWER	MAIN	0.14
26	CEILING	DRYWALL	BEIGE	RADIO	MAIN	0.09
27	WALL	CERAMIC	LIGHT BLUE	FURNACE	MAIN	0.05
28	WALL	DRYWALL	WHITE	HALLWAY	MAIN	< LOD
29	WALL	PLASTER	OFF-WHITE	EXTERIOR	MAIN	< LOD
30	DOWNSPOUT	METAL	OFF-WHITE	EXTERIOR	MAIN	< LOD
31	DOOR	METAL	BROWN	EXTERIOR	MAIN	< LOD
32	DOORFRAME	METAL	BROWN	EXTERIOR	MAIN	< LOD
33	STAIR RUNG	METAL	BROWN	EXTERIOR	MAIN	< LOD
34	PILLAR	CONCRETE	BROWN	EXTERIOR	MAIN	0.05
35	GARAGE DOOR	METAL	WHITE	EXTERIOR	MAIN	< LOD
36	DOWNSPOUT	METAL	BROWN	EXTERIOR	MAIN	< LOD

TABLE 3 XRF SAMPLING SUMMARY OF PAINTED COMPONENTS AND MATERIALS FIRE STATION #63						
Read. #	**Component**	**Substrate**	**Color**	**Room**	**Building**	**Lead Conc. (mg/cm^2)**
37	CONDUIT	METAL	BROWN	EXTERIOR	MAIN	< LOD
38	AWNING	WOOD	WHITE	EXTERIOR	MAIN	< LOD
39	PARAPET FLASHING	METAL	BROWN	EXTERIOR	MAIN	< LOD
40	SIDING	WOOD	OFF-WHITE	EXTERIOR	MAIN	< LOD
41	WALL	CMU	OFF-WHITE	EXTERIOR	MAIN	0.05
42	WALL	DRYWALL	BLUE	BEANERY & WATCH	MAIN	< LOD
43	CALIBRATION	N/A	RED	N/A	N/A	1.0
44	CALIBRATION	N/A	RED	N/A	N/A	1.0
45	CALIBRATION	N/A	RED	N/A	N/A	1.0

Key: CMU = Concrete Masonry Unit, **LOD**=Limit of Detection; **N/A** = Non-Applicable.

In addition to the XRF samples, EHSI collected three (3) bulk QA samples for laboratory analysis. Results marked with the "<" symbol are less than the lab reporting limit. Building materials and paint containing detectable levels of lead are considered regulated by DOSH.

Table 4 summarizes bulk QA lead samples, including sample number, material description, substrate, color, location, and analytical results.

Copies of the analytical laboratory report and field data forms for lead paint are included in Appendix B of this report.

TABLE 4 SUMMARY OF LEAD BULK QA SAMPLING AND ANALYTICAL RESULTS FS #63					
SAMPLE NUMBER	**LOCATION**	**COMPONENT**	**SUBSTRATE**	**COLOR**	**RESULTS % Pb by WT**
10854-63-Pb01	First Floor, Hose Tower	Wall	Mortar / CMU	Gray	0.0096
10854-63-Pb02	First Floor, Hose Tower	Wall	Mortar / Brick	Gray	<0.0031
10854-63-Pb03	First Floor, Mechanical Room	Wall	GWB	Off-White / Beige	<0.0048

Key: CMU = Concrete Masonry Unit; **GWB** = Gypsum Wall Board; **<0.00XX** = Less than the lab reporting limit for lead for that sample.

DOSH requires employers to conduct a hazard assessment and take appropriate worker protection precautions whenever paint is disturbed that has detectable quantities of lead. Since the type of work planned (e.g., sawing, grinding, demolition) will disturb the lead-containing paint, the contractor should perform an initial exposure assessment to determine if personal protective measures and work practices are required.

EHSI also observed eleven (11) Pb vent pipes on the roof of FS #63, that if disturbed will require recycling.

2.4.3 Arsenic-Containing Building Materials

EHSI collected two (2) arsenic bulk mortar samples for laboratory analysis. The results of those analyses are reported in Table 6.

Arsenic results for this inspection are reported in Appendix B. Table 5 summarizes arsenic samples, including sample number, material description, substrate, color and analytical results.

TABLE 5
SUMMARY OF ARSENIC BULK SAMPLING AND ANALYTICAL RESULTS
FS #63

SAMPLE NUMBER	SAMPLE LOCATION	COMPONENT/ SUBSTRATE	COLOR	RESULTS IN PPM
10854-63-As01	First Floor, Hose Tower	Mortar / CMU Wall	Gray	<18.0
10854-63-As02	First Floor, Hose Tower	Mortar / BMU Wall	Gray	22.0

DOSH requires employers to conduct a hazard assessment and take appropriate worker protection precautions whenever material is disturbed that has detectable quantities of arsenic. Since the type of work planned (e.g., sawing, grinding, demolition) will disturb the arsenic-containing materials, the contractor should perform an initial exposure assessment to determine if personal protective measures and work practices are required DOSH permissible exposure limit for arsenic is 0.2 mg/m^3 within an 8-hour time period.

2.4.4 Toxicity Characteristic Leaching Procedure Sampling

Ecology requires testing using the “toxicity characteristic leaching procedure” (TCLP) and segregation of construction debris if it is potentially contaminated with dangerous waste (e.g., lead-containing paint/lead-containing materials). Washington State Department of Ecology (Ecology) has set a dangerous waste threshold for both leachable arsenic and lead at 5.0 milligrams per liter (**mg/L)**.

Because the potential waste streams will be determined by the contractor, a TCLP was not conducted as part of the Limited Hazardous Materials Survey; however, based on the relatively low levels of lead in the sample results, EHSI does not anticipate TCLP to fail for lead or arsenic.

2.4.5 Polychlorinated Biphenyls

Ballasts

Only electronic fluorescent light ballasts were observed. All fluorescent tubes and lamps contain mercury. Any fluorescent lamps/tubes to be disturbed during the project must be recycled as

Washington Department of Ecology (Ecology) Universal Waste. Electronic fluorescent light ballasts may be disposed of as general construction debris. A Summary of ballasts and Hg-containing light tubes is provided in Table 6.

Transformers

EHSI did not observe any oil-filled transformers that will be impacted by the planned work in the FS #63 Building.

2.4.6 Mercury-Containing Thermostats and Fluorescent Light Tubes

EHSI observed four (4) Hg-containing thermostats throughout FS #63. All fluorescent light tubes quantified in Table 6 are assumed to contain Hg. Hg wastes are regulated as "universal wastes" under Ecology's regulation WAC 173-303. Hg-containing building materials must be recycled or disposed of as hazardous waste. Hg-containing fluorescent light tubes are quantified in Table 6.

TABLE 6
SUMMARY OF LIGHT FIXTURE INSPECTION RESULTS
FIRE STATION #63

LIGHT TYPE	NUMBER OF FIXTURES	NUMBER OF TUBES	APPROX. NUMBER OF MAGNETIC BALLASTS
2'x4' Recessed light fixture w/ 4 bulbs and 2 electronic ballasts	25	100	0
2'x4' Mounted light fixture w/ 4 bulbs and 2 electronic ballasts	8	24	0
2'x2' Recessed light fixture w/ 2 U-shaped bulbs and 1 electronic ballast	3	6	0
6"x1' wall mounted light fixture w/ 4 bulbs and 2 electronic ballasts	4	16	0
1'x4' Recessed light fixture w/ 2 bulbs and 1 electronic ballast	5	10	0
1'x8' Mounted light fixture w/ 4 bulbs and 2 electronic ballasts	12	48	0
HID lamps	6	6	0
CFL bulbs	4	4	0
Total	**68**	**214**	**0**

Key: CFL = compact fluorescent light, **HID** = high intensity discharge, **w/** = with

3.0 LIMITATIONS

This survey was limited to those materials accessible using standard survey methods. Limited representative destructive inspection was accomplished; however, in areas inaccessible for inspection, (e.g., fire door cores, wall cabinet mastics, electrical and materials above hard lid ceilings and inside closed plumbing chases) suspect materials were assumed to be present and assumed to be ACM.

This survey was limited to the chemicals and materials identified herein. No effort was made to identify hazardous materials in soil, water, or air, other than those listed herein. Any survey regardless of how extensive can miss concealed materials. Contractors should be aware of the potential that demolition activities may expose concealed suspect ACM and should have preplanned contingencies for handling these materials when discovered during demolition work. Any concealed, suspect ACM material that was not sampled or that was assumed to be ACM by this survey report when encountered must be treated as ACM until sampled by a Certified AHERA Building Inspector and analyzed by a certified laboratory.

4.0 STANDARD OF CARE

The recommendations and conclusions contained in this report represent the professional opinions of EHSI. These opinions are derived in accordance with federal, state, and local environmental and health and safety laws and regulations. This survey was accomplished in accordance with applicable federal, state, and local regulations and industry standards in effect at the time. Other than this, no other warranty is implied or intended.

5.0 CERTIFIED AHERA BUILDING INSPECTORS

The Certified AHERA Building Inspectors listed below surveyed FS #63 on April 22nd, 25th, and 26th, 2016 and September 27th, 2016 in accordance with federal, state, and local requirements.

Nadir Khan
Certified AHERA Building Inspector
Certificate Number: 10801-02-05
Expiration Date: December 11, 2016

Andrew Wells
Certified AHERA Building Inspector
Certificate Number: 2015-07-28-04
Expiration Date: July 28, 2016

Rory Peterson
Certified AHERA Building Inspector
Certificate Number: 158525
Expiration Date: August 17, 2017

(Note: The above report fulfills the requirements of WAC 296-62-07721 for a "Good Faith Inspection" report. Some of the report enclosures have been deleted for brevity from the Contract Specifications Appendix. The full report is available for review from Rice Fergus Miller Architects or EHS-International, Inc.).

END OF SECTION 011110

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for substitutions.

1.3 DEFINITIONS

A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

1.4 ACTION SUBMITTALS

A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Substitution Request Form: Standard AIA or CSI form.
2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
    a. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
    b. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
    c. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
    d. Samples, where applicable or requested.
    e. Certificates and qualification data, where applicable or requested.
    f. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.

g. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
h. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
i. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
j. Cost information, including a proposal of change, if any, in the Contract Sum.
k. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
l. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.

3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.
c. High Speed Rolling Door substitutions will only be approved during the bidding period.

1.5 PROCEDURES

A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

A. Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.

1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:

    a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
    b. Substitution request is fully documented and properly submitted.
    c. Requested substitution is compatible with other portions of the Work.
    d. Requested substitution has been coordinated with other portions of the Work.
    e. Requested substitution provides specified warranty.

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.3 PROPOSAL REQUESTS

A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.

1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
2. Within 20 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.

    a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    c. Include costs of labor and supervision directly attributable to the change.
    d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
    e. Quotation Form: Use CSI Form 13.6D, "Proposal Worksheet Summary," and Form 13.6C, "Proposal Worksheet Detail."

B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.

1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Division 01 Section "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
7. Proposal Request Form: Use CSI Form 13.6A, "Change Order Request (Proposal)," with attachments CSI Form 13.6D, "Proposal Worksheet Summary," and Form 13.6C, "Proposal Worksheet Detail."

1.4 CHANGE ORDER PROCEDURES

A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.5 CONSTRUCTION CHANGE DIRECTIVE

A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.

1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.

1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.

B. Related Requirements:

1. Division 01 Section "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.

1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.

1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:

a. Application for Payment forms with continuation sheets.
b. Submittal schedule.
c. Items required to be indicated as separate activities in Contractor's construction schedule.

2. Submit the schedule of values to Architect at earliest possible date, but no later than seven days before the date scheduled for submittal of initial Applications for Payment.

B. Format and Content: Use Project Manual table of contents and specifications noted on Drawings as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.

1. Identification: Include the following Project identification on the schedule of values:

   a. Project name and location.
   b. Name of Architect
   c. Contractor's name and address.
   d. Date of submittal.

2. Arrange schedule of values consistent with format of AIA Document G703.
3. Arrange the schedule of values in tabular form with separate columns to indicate the following for each item listed:

   a. Related Specification Section or Division.
   b. Description of the Work.
   c. Name of subcontractor
   d. Name of manufacturer or fabricator
   e. Name of supplier
   f. Change Orders (numbers) that affect value.
   g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.

      1) Labor.
      2) Materials.
      3) Equipment.

4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.

5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.

   a. Differentiate between items stored on-site and items stored off-site. If required, include evidence of insurance.

7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
8. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.

9. Purchase Contracts: Provide a separate line item in the schedule of values for each purchase contract. Show line-item value of purchase contract. Indicate owner payments or deposits, if any, and balance to be paid by Contractor.
10. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.

    a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.

11. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.

    1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.

B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.

C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.

D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

    1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
    2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
    3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
    4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.

E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.

1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
3. Provide summary documentation for stored materials indicating the following:

    a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.
    b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
    c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.

F. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.

1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.

G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.

1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
2. When an application shows completion of an item, submit conditional final or full waivers.
3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.

H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:

1. List of subcontractors.
2. Schedule of values.
3. Contractor's construction schedule (preliminary if not final).
4. Combined Contractor's construction schedule (preliminary if not final) incorporating Work of multiple contracts, with indication of acceptance of schedule by each Contractor.
5. Products list (preliminary if not final).
6. Schedule of unit prices.
7. Submittal schedule (preliminary if not final).
8. List of Contractor's staff assignments.
9. List of Contractor's principal consultants.

10. Copies of building permits.
11. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
12. Initial progress report.
13. Report of preconstruction conference.
14. Certificates of insurance and insurance policies.
15. Performance and payment bonds.
16. Data needed to acquire Owner's insurance.

I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:

1. Evidence of completion of Project closeout requirements.
2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
3. Updated final statement, accounting for final changes to the Contract Sum.
4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
6. AIA Document G707, "Consent of Surety to Final Payment."
7. Evidence that claims have been settled.
8. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:

1. General coordination procedures.
2. Coordination drawings.
3. Requests for Information (RFIs).
4. Project meetings.

B. Each contractor shall participate in coordination requirements. Certain areas of responsibility are assigned to a specific contractor.

C. Related Requirements:
1. Division 01 Section "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
2. Division 01 Section "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
3. Division 01 Section "Closeout Procedures" for coordinating closeout of the Contract.

1.3 DEFINITIONS

A. RFI: Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.4 GENERAL COORDINATION PROCEDURES

A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.

1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
3. Make adequate provisions to accommodate items scheduled for later installation.

B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.

1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.

C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:

1. Preparation of Contractor's construction schedule.
2. Preparation of the schedule of values.
3. Installation and removal of temporary facilities and controls.
4. Delivery and processing of submittals.
5. Progress meetings.
6. Preinstallation conferences.
7. Project closeout activities.
8. Startup and adjustment of systems.

D. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. See other Sections for disposition of salvaged materials that are designated as Owner's property.

1.5 COORDINATION DRAWINGS

A. Coordination Drawings, General: Prepare coordination drawings according to requirements in individual Sections, and additionally where installation is not completely shown on Shop Drawings, where limited space availability necessitates coordination, or if coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity.

1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:

a. Use applicable Drawings as a basis for preparation of coordination drawings. Prepare sections, elevations, and details as needed to describe relationship of various systems and components.
b. Coordinate the addition of trade-specific information to the coordination drawings by multiple contractors in a sequence that best provides for coordination of the information and resolution of conflicts between installed components before submitting for review.
c. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
d. Indicate space requirements for routine maintenance and for anticipated replacement of components during the life of the installation.
e. Show location and size of access doors required for access to concealed dampers, valves, and other controls.
f. Indicate required installation sequences.
g. Indicate dimensions shown on the Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.

B. Coordination Drawing Organization: Organize coordination drawings as follows:

1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid. Supplement plan drawings with section drawings where required to adequately represent the Work.
2. Plenum Space: Indicate subframing for support of ceiling and wall systems, mechanical and electrical equipment, and related Work. Locate components within ceiling plenum to accommodate layout of light fixtures indicated on Drawings. Indicate areas of conflict between light fixtures and other components.
3. Mechanical Rooms: Provide coordination drawings for mechanical rooms showing plans and elevations of mechanical, plumbing, fire-protection, fire-alarm, and electrical equipment.
4. Structural Penetrations: Indicate penetrations and openings required for all disciplines.
5. Slab Edge and Embedded Items: Indicate slab edge locations and sizes and locations of embedded items for metal fabrications, sleeves, anchor bolts, bearing plates, angles, door floor closers, slab depressions for floor finishes, curbs and housekeeping pads, and similar items.
6. Mechanical and Plumbing Work: Show the following:

a. Sizes and bottom elevations of ductwork, piping, and conduit runs, including insulation, bracing, flanges, and support systems.
b. Dimensions of major components, such as dampers, valves, diffusers, access doors, cleanouts and electrical distribution equipment.
c. Fire-rated enclosures around ductwork.

7. Electrical Work: Show the following:

    a. Runs of vertical and horizontal conduit 1-1/4 inches in diameter and larger.
    b. Light fixture, exit light, emergency battery pack, smoke detector, and other fire-alarm locations.
    c. Panel board, switch board, switchgear, transformer, busway, generator, and motor control center locations.
    d. Location of pull boxes and junction boxes, dimensioned from column center lines.

8. Fire-Protection System: Show the following:

    a. Locations of standpipes, mains piping, branch lines, pipe drops, and sprinkler heads.

9. Review: Architect will review coordination drawings to confirm that the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility. If Architect determines that coordination drawings are not being prepared in sufficient scope or detail, or are otherwise deficient, Architect will so inform Contractor, who shall make changes as directed and resubmit.
10. Coordination Drawing Prints: Prepare coordination drawing prints according to requirements in Division 01 Section "Submittal Procedures."

C. Coordination Digital Data Files: Prepare coordination digital data files according to the following requirements:

1. File Preparation Format: Same digital data software program, version, and operating system as original Drawings.
2. File Preparation Format: DWG, Version 2004 or later, operating in Microsoft Windows operating system.
3. File Submittal Format: Submit or post coordination drawing files using format same as file preparation format.

1.6 REQUESTS FOR INFORMATION (RFIs)

A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.

1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.

B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:

1. Project name.
2. Project number.
3. Date.
4. Name of Contractor.
5. Name of Architect.
6. RFI number, numbered sequentially.
7. RFI subject.
8. Specification Section number and title and related paragraphs, as appropriate.
9. Drawing number and detail references, as appropriate.
10. Field dimensions and conditions, as appropriate.
11. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
12. Contractor's signature.
13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.

    a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.

C. RFI Forms: AIA Document G716.

1. Attachments shall be electronic files in Adobe Acrobat PDF format.

D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.

1. The following Contractor-generated RFIs will be returned without action:

    a. Requests for approval of submittals.
    b. Requests for approval of substitutions.
    c. Requests for approval of Contractor's means and methods.
    d. Requests for coordination information already indicated in the Contract Documents.
    e. Requests for adjustments in the Contract Time or the Contract Sum.
    f. Requests for interpretation of Architect's actions on submittals.
    g. Incomplete RFIs or inaccurately prepared RFIs.

2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Division 01 Section "Contract Modification Procedures."

a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.

E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly.

1. Project name.
2. Name and address of Contractor.
3. Name and address of Architect.
4. RFI number including RFIs that were returned without action or withdrawn.
5. RFI description.
6. Date the RFI was submitted.
7. Date Architect's response was received.
8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
9. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.7 PROJECT MEETINGS

A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.

B. Preconstruction Conference: Architect will schedule and conduct Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.

1. Conduct the conference to review responsibilities and personnel assignments.
2. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
3. Agenda: Discuss items of significance that could affect progress, including the following:

a. Tentative construction schedule.

b. Critical work sequencing and long-lead items.
c. Designation of key personnel and their duties.
d. Lines of communications.
e. Procedures for processing field decisions and Change Orders.
f. Procedures for RFIs.
g. Procedures for testing and inspecting.
h. Procedures for processing Applications for Payment.
i. Distribution of the Contract Documents.
j. Submittal procedures.
k. Preparation of record documents.
l. Use of the premises and existing buildings.
m. Work restrictions.
n. Working hours.
o. Owner's occupancy requirements.
p. Responsibility for temporary facilities and controls.
q. Procedures for moisture and mold control.
r. Procedures for disruptions and shutdowns.
s. Construction waste management and recycling.
t. Parking availability.
u. Office, work, and storage areas.
v. Equipment deliveries and priorities.
w. First aid.
x. Security.
y. Progress cleaning.

4. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.

C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.

1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:

a. Contract Documents.
b. Options.
c. Related RFIs.
d. Deliveries.
e. Submittals.
f. Possible conflicts.
g. Compatibility requirements.
h. Time schedules.
i. Weather limitations.
j. Manufacturer's written instructions.

k. Warranty requirements.
l. Space and access limitations.
m. Testing and inspecting requirements.
n. Installation procedures.
o. Coordination with other work.
p. Required performance results.

3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.

D. Project Closeout Conference: Schedule and conduct a project closeout conference, at a time convenient to Owner and Architect, but no later than 60 days prior to the scheduled date of Substantial Completion.

1. Conduct the conference to review requirements and responsibilities related to Project closeout.
2. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the meeting. Participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
3. Agenda: Discuss items of significance that could affect or delay Project closeout, including the following:

a. Preparation of record documents.
b. Procedures required prior to inspection for Substantial Completion and for final inspection for acceptance.
c. Submittal of written warranties.
d. Requirements for preparing operations and maintenance data.
e. Requirements for delivery of material samples, attic stock, and spare parts.
f. Requirements for demonstration and training.
g. Preparation of Contractor's punch list.
h. Procedures for processing Applications for Payment at Substantial Completion and for final payment.
i. Submittal procedures.
j. Owner's partial occupancy requirements.
k. Installation of Owner's furniture, fixtures, and equipment.
l. Responsibility for removing temporary facilities and controls.

4. Minutes: Entity conducting meeting will record and distribute meeting minutes.

E. Coordination Meetings: Conduct Project coordination meetings at bi-monthly intervals. Project coordination meetings are in addition to specific meetings held for other

purposes, such as progress meetings and preinstallation conferences. This will be required for Fire Prop installation, and others a seen fit by Architect or Owner

1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.

    a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
    c. Review present and future needs of each contractor present, including the following:

        1) Interface requirements.
        2) Sequence of operations.
        3) Status of submittals.
        4) Deliveries.
        5) Off-site fabrication.
        6) Access.
        7) Site utilization.
        8) Temporary facilities and controls.
        9) Work hours.
        10) Hazards and risks.
        11) Progress cleaning.
        12) Quality and work standards.
        13) Change Orders.

3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:

1. Contractor's construction schedule.
2. Daily construction reports.
3. Material location reports.
4. Site condition reports.

B. Related Requirements:

1. Division 01 Section "Submittal Procedures" for submitting schedules and reports.
2. Division 01 Section "Quality Requirements" for submitting a schedule of tests and inspections.

1.3 DEFINITIONS

A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.

1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
2. Predecessor Activity: An activity that precedes another activity in the network.
3. Successor Activity: An activity that follows another activity in the network.

B. Cost Loading: The allocation of the schedule of values for the completion of an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum unless otherwise approved by Architect.

C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.

D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.

E. Event: The starting or ending point of an activity.

F. Float: The measure of leeway in starting and completing an activity.

1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.

G. Resource Loading: The allocation of manpower and equipment necessary for the completion of an activity as scheduled.

1.4 INFORMATIONAL SUBMITTALS

A. Format for Submittals: Submit required submittals in the following format:
1. Three paper copies.

B. Startup Network Diagram: Of size required to display entire network for entire construction period. Show logic ties for activities.

C. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.

1. Submit a working electronic copy of schedule, using software indicated, and labeled to comply with requirements for submittals. Include type of schedule (initial or updated) and date on label.

D. CPM Reports: Concurrent with CPM schedule, submit each of the following reports. Format for each activity in reports shall contain activity number, activity description, cost and resource loading, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.

1. Activity Report: List of all activities sorted by activity number and then early start date, or actual start date if known.
2. Logic Report: List of preceding and succeeding activities for all activities, sorted in ascending order by activity number and then early start date, or actual start date if known.
3. Total Float Report: List of all activities sorted in ascending order of total float.

E. Daily Construction Reports: Submit at weekly intervals.

F. Material Location Reports: Submit at monthly intervals.

G. Site Condition Reports: Submit at time of discovery of differing conditions.

H. Qualification Data: For scheduling consultant.

1.5 QUALITY ASSURANCE

A. Scheduling Consultant Qualifications: An experienced specialist in CPM scheduling and reporting, with capability of producing CPM reports and diagrams within 24 hours of Architect's request.

1.6 COORDINATION

A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.

B. Coordinate Contractor's construction schedule with the schedule of values, list of subcontracts, submittal schedule, progress reports, payment requests, and other required schedules and reports.

1. Secure time commitments for performing critical elements of the Work from entities involved.
2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

A. Time Frame: Extend schedule from date established for the Notice to Proceed to date of Substantial Completion.

1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.

B. Activities: Treat each story or separate area as a separate numbered activity for each main element of the Work. Comply with the following:

1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.

3. Submittal Review Time: Include review and resubmittal times indicated in Division 01 Section "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.

C. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Phasing: Arrange list of activities on schedule by phase.
2. Work under More Than One Contract: Include a separate activity for each contract.
3. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
4. Products Ordered in Advance: Include a separate activity for each product. Include delivery date indicated in Division 01 Section "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
5. Owner-Furnished Products: Include a separate activity for each product. Include delivery date indicated in Division 01 Section "Summary." Delivery dates indicated stipulate the earliest possible delivery date.
6. Work Restrictions: Show the effect of the following items on the schedule:

    a. Coordination with existing construction.
    b. Limitations of continued occupancies.
    c. Uninterruptible services.
    d. Partial occupancy before Substantial Completion.
    e. Use of premises restrictions.
    f. Provisions for future construction.
    g. Seasonal variations.
    h. Environmental control.

7. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:

    a. Subcontract awards.
    b. Submittals.
    c. Purchases.
    d. Mockups.
    e. Fabrication.
    f. Sample testing.
    g. Deliveries.
    h. Installation.
    i. Tests and inspections.

j. Adjusting.
k. Curing.
l. Building flush-out.
m. Startup and placement into final use and operation.

8. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:

a. Structural completion.
b. Permanent space enclosure.
c. Completion of mechanical installation.
d. Completion of electrical installation.
e. Substantial Completion.

D. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion.

E. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:

1. Unresolved issues.
2. Unanswered Requests for Information.
3. Rejected or unreturned submittals.
4. Notations on returned submittals.
5. Pending modifications affecting the Work and Contract Time.

F. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, and equipment required to achieve compliance, and date by which recovery will be accomplished.

G. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.

1. Use Microsoft Project or other mutually agreed program.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

A. General: Prepare network diagrams using AON (activity-on-node) format.

B. Startup Network Diagram: Submit diagram within 14 days of date established for the Notice to Proceed. Outline significant construction activities for the first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.

C. CPM Schedule: Prepare Contractor's construction schedule using a time-scaled CPM network analysis diagram for the Work.

1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 30 days after date established for the Notice to Proceed.

    a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates, regardless of Architect's approval of the schedule.

2. Conduct educational workshops to train and inform key Project personnel, including subcontractors' personnel, in proper methods of providing data and using CPM schedule information.
3. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
4. Use "one workday" as the unit of time for individual activities. Indicate nonworking days and holidays incorporated into the schedule in order to coordinate with the Contract Time.

D. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the startup network diagram, prepare a skeleton network to identify probable critical paths.

1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:

    a. Preparation and processing of submittals.
    b. Mobilization and demobilization.
    c. Purchase of materials.
    d. Delivery.
    e. Fabrication.
    f. Utility interruptions.
    g. Installation.
    h. Work by Owner that may affect or be affected by Contractor's activities.
    i. Testing.
    j. Punch list and final completion.
    k. Activities occurring following final completion.

2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.

4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.

E. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall project schedule.

F. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:

1. Contractor or subcontractor and the Work or activity.
2. Description of activity.
3. Main events of activity.
4. Immediate preceding and succeeding activities.
5. Early and late start dates.
6. Early and late finish dates.
7. Activity duration in workdays.
8. Total float or slack time.
9. Average size of workforce.
10. Dollar value of activity (coordinated with the schedule of values).

G. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:

1. Identification of activities that have changed.
2. Changes in early and late start dates.
3. Changes in early and late finish dates.
4. Changes in activity durations in workdays.
5. Changes in the critical path.
6. Changes in total float or slack time.
7. Changes in the Contract Time.

2.3 REPORTS

A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:

1. List of subcontractors at Project site.
2. List of separate contractors at Project site.
3. Approximate count of personnel at Project site.
4. Equipment at Project site.
5. Material deliveries.
6. High and low temperatures and general weather conditions, including presence of rain or snow.
7. Accidents.
8. Meetings and significant decisions.
9. Unusual events (see special reports).

10. Stoppages, delays, shortages, and losses.
11. Meter readings and similar recordings.
12. Emergency procedures.
13. Orders and requests of authorities having jurisdiction.
14. Change Orders received and implemented.
15. Construction Change Directives received and implemented.
16. Services connected and disconnected.
17. Equipment or system tests and startups.
18. Partial completions and occupancies.
19. Substantial Completions authorized.

B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

A. Scheduling Consultant: Engage a consultant to provide planning, evaluation, and reporting using CPM scheduling.

1. In-House Option: Owner may waive the requirement to retain a consultant if Contractor employs skilled personnel with experience in CPM scheduling and reporting techniques. Submit qualifications.
2. Meetings: Scheduling consultant shall attend all meetings related to Project progress, alleged delays, and time impact.

B. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.

1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
3. As the Work progresses, indicate final completion percentage for each activity.

C. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.

1. Post copies in Project meeting rooms and temporary field offices.
2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have

completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

B. Related Requirements:

1. Division 01 Section "Payment Procedures" for submitting Applications for Payment and the schedule of values.
2. Division 01 Section "Operation and Maintenance Data" for submitting operation and maintenance manuals.
3. Division 01 Section "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.3 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

A. Architect's Digital Data Files: Electronic digital data files of the Contract Drawings may be provided by Architect for Contractor's use in preparing submittals if desired.

1. The following conditions apply:

a. Architect makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
b. Digital Drawing Software Program: The Contract Drawings are available in Revit (Architect’s current version).
c. Contractor shall execute Architects" Liability release form prior to receiving electronic files.

B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.

1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.

2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
4. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.

    a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.

1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
3. Resubmittal Review: Allow 15 days for review of each resubmittal.

D. Identification & Information: Place a permanent label or title block on each submittal item for identification.

1. Indicate name of firm or entity that prepared each submittal on label or title block.
2. Provide a space approximately 6 by 8 inches (150 by 200 mm) on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
3. Include the following information for processing and recording action taken:

    a. Project name.
    b. Date.
    c. Name of Architect.
    d. Name of Contractor.
    e. Name of subcontractor.
    f. Name of supplier.
    g. Name of manufacturer.
    h. Submittal number or other unique identifier, including revision identifier.

        1) Submittal number shall use Specification Section number followed by a decimal point and then a sequential number (e.g., 061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., 061000.01.A).

    i. Number and title of appropriate Specification Section.
    j. Drawing number and detail references, as appropriate.

k. Location(s) where product is to be installed, as appropriate.
l. Other necessary identification.

4. Additional Paper Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.

   a. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.

5. Transmittal: Assemble each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will discard submittals received from sources other than Contractor.

   a. Transmittal Form for Paper Submittals: Use AIA Document G810.

E. Options: Identify options requiring selection by Architect.

F. Deviations and Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same identification information as related submittal.

G. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.

1. Note date and content of previous submittal.
2. Note date and content of revision in label or title block and clearly indicate extent of revision.
3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.

H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.

I. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

A. General Submittal Procedure Requirements: Prepare and submit submittals required by individual Specification Sections. Provide a submittal for each product section and division. PDF File format is acceptable in lieu of paper copies.

1. Action Submittals: Submit three paper copies of each submittal unless otherwise indicated. Architect will return two copies.
2. Informational Submittals: Submit two paper copies of each submittal unless otherwise indicated. Architect will not return copies.
3. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.

    a. Provide a digital signature with digital certificate on electronically submitted certificates and certifications where indicated.
    b. Provide a notarized statement on original paper copy certificates and certifications where indicated.

B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each copy of each submittal to show which products and options are applicable.
3. Include the following information, as applicable:

    a. Manufacturer's catalog cuts.
    b. Manufacturer's product specifications.
    c. Standard color charts.
    d. Statement of compliance with specified referenced standards.
    e. Testing by recognized testing agency.
    f. Application of testing agency labels and seals.
    g. Notation of coordination requirements.
    h. Availability and delivery time information.

4. For equipment, include the following in addition to the above, as applicable:

    a. Wiring diagrams showing factory-installed wiring.
    b. Printed performance curves.
    c. Operational range diagrams.
    d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before or concurrent with Samples.
6. Submit Product Data in the following format:
    a. Three paper copies of Product Data unless otherwise indicated. Architect will return two copies.

C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard

printed data, unless submittal based on Architect's digital data drawing files is otherwise permitted.

1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:

    a. Identification of products.
    b. Schedules.
    c. Compliance with specified standards.
    d. Notation of coordination requirements.
    e. Notation of dimensions established by field measurement.
    f. Relationship and attachment to adjoining construction clearly indicated.
    g. Seal and signature of professional engineer if specified.

2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches (215 by 280 mm), but no larger than 30 by 42 inches (750 by 1067 mm).
3. Submit Shop Drawings in the following format:

    a. Two opaque (bond) copies of each submittal. Architect will return one copy(ies).
    b. Three opaque copies of each submittal. Architect will retain two copies; remainder will be returned.

D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.

1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
2. Identification: Attach label on unexposed side of Samples that includes the following:

    a. Generic description of Sample.
    b. Product name and name of manufacturer.
    c. Sample source.
    d. Number and title of applicable Specification Section.
    e. Specification paragraph number and generic name of each item.

3. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.

    a. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.

E. Application for Payment and Schedule of Values: Comply with requirements specified in Division 01 Section "Payment Procedures."

F. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Submit copies to Owner, Architect, and Jurisdictions Having Authority for review.

G. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Division 01 Section "Closeout Procedures."

H. Maintenance Data: Comply with requirements specified in Division 01 Section "Operation and Maintenance Data."

I. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.

J. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.

K. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.

L. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.

M. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.

N. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.

O. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.

P. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note

corrections and field dimensions. Mark with approval stamp before submitting to Architect.

B. Project Closeout and Maintenance Material Submittals: See requirements in Division 01 Section "Closeout Procedures."

C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.

B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.

C. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.

D. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.

E. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

F. Submittals not required by the Contract Documents may be returned by the Architect without action.

END OF SECTION 013300

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for quality assurance and quality control.

B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.

1. Specific quality-assurance and -control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
2. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
3. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.

C. Related Requirements:

1. Divisions 02 through 33 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.

B. Quality-Control Services: I'Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.

C. Mockups: Full-size physical assemblies that are constructed on-site. Mockups are constructed to verify selections made under Sample submittals; to demonstrate

aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.

1. Laboratory Mockups: Full-size physical assemblies constructed at testing facility to verify performance characteristics.
2. Integrated Exterior Mockups: Mockups of the exterior envelope erected separately from the building but on Project site, consisting of multiple products, assemblies, and subassemblies.
3. Room Mockups: Mockups of typical interior spaces complete with wall, floor, and ceiling finishes, doors, windows, millwork, casework, specialties, furnishings and equipment, and lighting.

D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.

E. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.

F. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.

G. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.

I. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.

1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).

J. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.4 CONFLICTING REQUIREMENTS

A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.

B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 ACTION SUBMITTALS

A. Shop Drawings: For integrated exterior mockups, provide plans, sections, and elevations, indicating materials and size of mockup construction.

1. Indicate manufacturer and model number of individual components.
2. Provide axonometric drawings for conditions difficult to illustrate in two dimensions.

1.6 INFORMATIONAL SUBMITTALS

A. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.

B. Qualification Data: For Contractor's quality-control personnel.

C. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

D. Schedule of Tests and Inspections: Prepare in tabular form and include the following:

1. Specification Section number and title.
2. Entity responsible for performing tests and inspections.
3. Description of test and inspection.
4. Identification of applicable standards.
5. Identification of test and inspection methods.
6. Number of tests and inspections required.
7. Time schedule or time span for tests and inspections.
8. Requirements for obtaining samples.
9. Unique characteristics of each quality-control service.

1.7 CONTRACTOR'S QUALITY-CONTROL PLAN

A. Quality-Control Plan, General: Submit quality-control plan within 10 days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Architect. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's construction schedule.

B. Quality-Control Personnel Qualifications: Engage qualified full-time personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.

1. Project quality-control manager may also serve as Project superintendent.

C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.

D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:

1. Contractor-performed tests and inspections including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections.
2. Special inspections required by authorities having jurisdiction and indicated on the "Statement of Special Inspections."

1.8 REPORTS AND DOCUMENTS

A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:

1. Date of issue.
2. Project title and number.
3. Name, address, and telephone number of testing agency.
4. Dates and locations of samples and tests or inspections.
5. Names of individuals making tests and inspections.
6. Description of the Work and test and inspection method.
7. Identification of product and Specification Section.
8. Complete test or inspection data.
9. Test and inspection results and an interpretation of test results.
10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and reinspecting.

B. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:

1. Name, address, and telephone number of technical representative making report.
2. Statement on condition of substrates and their acceptability for installation of product.
3. Statement that products at Project site comply with requirements.
4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
6. Statement whether conditions, products, and installation will affect warranty.
7. Other required items indicated in individual Specification Sections.

C. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:

1. Name, address, and telephone number of factory-authorized service representative making report.
2. Statement that equipment complies with requirements.
3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
4. Statement whether conditions, products, and installation will affect warranty.
5. Other required items indicated in individual Specification Sections.

D. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.9 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project,

whose work has resulted in construction with a record of successful in-service performance.

E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.

F. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:

1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
3. Employ supervisory personnel who will oversee mockup construction. Employ workers that will be employed during the construction at Project.
4. Demonstrate the proposed range of aesthetic effects and workmanship.
5. Obtain Architect's approval of mockups before starting work, fabrication, or construction.

    a. Allow seven days for initial review and each re-review of each mockup.

6. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
7. Demolish and remove mockups when directed unless otherwise indicated.

1.10 QUALITY CONTROL

A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.

1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
2. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.

B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.

1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.

2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.

    a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.

3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.

C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Division 01 Section "Submittal Procedures."

D. Manufacturer's Technical Services: Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.

E. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.

F. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.

1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
6. Do not perform any duties of Contractor.

G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.
3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
4. Facilities for storage and field curing of test samples.
5. Delivery of samples to testing agencies.
6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
7. Security and protection for samples and for testing and inspecting equipment at Project site.

H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

I. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents as a component of Contractor's quality-control plan. Coordinate and submit concurrently with Contractor's construction schedule. Update as the Work progresses.

1. Distribution: Distribute schedule to Owner, Architect, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

1.11 SPECIAL TESTS AND INSPECTIONS

A. Special Tests and Inspections: Owner will engage a qualified special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner, and as follows:

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 ACCEPTABLE TESTING AGENCIES

A. As provided by Owner.

3.2 TEST AND INSPECTION LOG

A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
2. Description of the Work tested or inspected.
3. Date test or inspection results were transmitted to Architect.
4. Identification of testing agency or special inspector conducting test or inspection.

B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.3 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Division 01 Section "Execution."

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

B. Related Requirements:

1. Division 01 Section "Summary" for work restrictions and limitations on utility interruptions.

1.3 USE CHARGES

A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.

B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

PART 2 - PRODUCTS

2.1 Not Used

PART 3 - EXECUTION

3.1 TEMPORARY UTILITY INSTALLATION

A. Water Service: Connect to Owner's existing water service facilities.

B. Heating: Existing systems may be used.

C. Ventilation and Humidity Control: Existing HVAC systems may be used.

D. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.

E. Lighting: Existing systems may be used.

3.2 SUPPORT FACILITIES INSTALLATION

A. Parking: Use designated areas of Owner's existing parking areas for construction personnel.

3.3 SECURITY AND PROTECTION FACILITIES INSTALLATION

A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.

B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

C. Security Enclosure and Lockup: Maintain lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.

D. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.

3.4 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities to minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

END OF SECTION 015000

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.

B. Related Requirements:
   1. Division 01 Section "Substitution Procedures" for requests for substitutions.
   2. Division 01 Section "References" for applicable industry standards for products specified.

1.3 DEFINITIONS

A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.

   1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
   2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
   3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

1.4 ACTION SUBMITTALS

A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.

1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

    a. Form of Approval: As specified in Division 01 Section "Submittal Procedures."
    b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

B. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 01 Section "Submittal Procedures." Show compliance with requirements.

1.5 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.

B. Delivery and Handling:

1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.

4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.

C. Storage:

1. Store products to allow for inspection and measurement of quantity or counting of units.
2. Store materials in a manner that will not endanger Project structure.
3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
6. Protect stored products from damage and liquids from freezing.
7. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.

B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.

1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
3. See Divisions 02 through 33 Sections for specific content requirements and particular requirements for submitting special warranties.

C. Submittal Time: Comply with requirements in Division 01 Section "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.

1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
4. Where products are accompanied by the term "as selected," Architect will make selection.
5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
6. Or Equal: For products specified by name and accompanied by the term "or equal," or "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.

B. Product Selection Procedures:

1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
3. Products:

    a. Restricted List: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.

4. Manufacturers:

    a. Restricted List: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will be considered.

C. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or

texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:

1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
3. Evidence that proposed product provides specified warranty.
4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:

1. Construction layout.
2. Installation of the Work.
3. Cutting and patching.
4. Coordination of Owner-installed products.
5. Progress cleaning.
6. Starting and adjusting.
7. Protection of installed construction.
8. Correction of the Work.

B. Related Requirements:

1. Division 01 Section "Summary" for limits on use of Project site.

1.3 DEFINITIONS

A. Cutting: Removal of in-place construction necessary to permit installation or performance of other work.

B. Patching: Fitting and repair work required to restore construction to original conditions after installation of other work.

1.4 QUALITY ASSURANCE

A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.

1. Structural Elements: When cutting and patching structural elements, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting

and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.

2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.

3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.

4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

PART 2 - PRODUCTS

2.1 MATERIALS

A. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.

1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, mechanical and electrical systems, and other construction affecting the Work.

1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.

B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.

1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.

C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Existing Utility Information: Furnish information to local utility, or Owner that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.

B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect.

3.3 INSTALLATION

A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.

1. Make vertical work plumb and make horizontal work level.
2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
4. Maintain minimum headroom clearance of 96 inches in occupied spaces and 90 inches in unoccupied spaces.

B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.

D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.

E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.

F. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.

G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.

H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.

1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
2. Allow for building movement, including thermal expansion and contraction.
3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

I. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.

J. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.4 CUTTING AND PATCHING

A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.

1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.

C. Temporary Support: Provide temporary support of work to be cut.

D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.

E. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching according to requirements in Division 01 Section "Summary."

F. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize interruption to occupied areas.

G. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.

1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
4. Excavating and Backfilling: Comply with requirements in applicable Division 31 Sections where required by cutting and patching operations.
5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
6. Proceed with patching after construction operations requiring cutting are complete.

H. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.

1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.

    a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
    b. Restore damaged pipe covering to its original condition.

3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

    a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.

4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.
5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.

I. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.5 OWNER-INSTALLED PRODUCTS

A. Site Access: Provide access to Project site for Owner's construction personnel.

B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction personnel.

1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
2. Preinstallation Conferences: Include Owner's construction personnel at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction personnel if portions of the Work depend on Owner's construction.

3.6 PROGRESS CLEANING

A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.

1. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
2. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.

    a. Use containers intended for holding waste materials of type to be stored.

3. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.

B. Site: Maintain Project site free of waste materials and debris.

C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.

1. Remove liquid spills promptly.
2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.

D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.

E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.

G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.

J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.7 STARTING AND ADJUSTING

A. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.

B. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.

C. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

3.8 PROTECTION OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

B. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 017300

SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for the following:

1. Recycling nonhazardous construction waste.
2. Disposing of nonhazardous construction waste.

1.3 DEFINITIONS

A. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.

B. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.

1.4 PERFORMANCE REQUIREMENTS

A. General: Achieve end-of-Project rates for salvage/recycling of 75 percent by weight of total non-hazardous solid waste generated by the Work. Practice efficient waste management in the use of materials in the course of the Work. Use all reasonable means to divert construction and demolition waste from landfills and incinerators. Facilitate recycling and salvage of materials.

1.5 ACTION SUBMITTALS

A. Waste Management Plan: Submit plan within 7 days of date established for the Notice to Proceed.

1.6 INFORMATIONAL SUBMITTALS

A. Records of Donations: Indicate receipt and acceptance of salvageable waste donated to individuals and organizations. Indicate whether organization is tax exempt.

B. Records of Sales: Indicate receipt and acceptance of salvageable waste sold to individuals and organizations. Indicate whether organization is tax exempt.

C. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.

D. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

1.7 QUALITY ASSURANCE

A. Refrigerant Recovery Technician Qualifications: Certified by EPA-approved certification program.

B. Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction.

1.8 WASTE MANAGEMENT PLAN

A. General: Develop a waste management plan according to ASTM E 1609 and requirements in this Section. Plan shall consist of waste identification, waste reduction work plan, and cost/revenue analysis. Indicate quantities by weight or volume, but use same units of measure throughout waste management plan.

B. Waste Identification: Indicate anticipated types of waste generated by the Work. Use Form CWM-1 for construction waste. Include estimated quantities and assumptions for estimates.

C. Waste Reduction Work Plan: List each type of waste and whether it will be salvaged, recycled, or disposed of in landfill or incinerator. Use Form CWM-3 for construction waste. Include points of waste generation, total quantity of each type of waste, quantity for each means of recovery, and handling and transportation procedures.

1. Recycled Materials: Include list of local receivers and processors and type of recycled materials each will accept. Include names, addresses, and telephone numbers.
2. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.
3. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location where materials separation will be performed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 PLAN IMPLEMENTATION

A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.

1. Comply with operation, termination, and removal requirements in Division 01 Section "Temporary Facilities and Controls."

B. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work.

1. Distribute waste management plan to everyone concerned within three days of submittal return.
2. Distribute waste management plan to entities when they first begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.

C. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged, recycled, reused, donated, and sold.
2. Comply with Division 01 Section "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.

3.2 RECYCLING CONSTRUCTION WASTE, GENERAL

A. General: Recycle paper and beverage containers used by on-site workers.

B. Recycling Receivers and Processors: List below is provided for information only; available recycling receivers and processors include, but are not limited to, the following:

C. Preparation of Waste: Prepare and maintain recyclable waste materials according to recycling or reuse facility requirements. Maintain materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process.

D. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to the maximum extent practical according to approved construction waste management plan.

1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.

    a. Inspect containers and bins for contamination and remove contaminated materials if found.

2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
4. Store components off the ground and protect from the weather.
5. Remove recyclable waste from Owner's property and transport to recycling receiver or processor.

3.3 RECYCLING CONSTRUCTION WASTE

A. Packaging:

1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
2. Polystyrene Packaging: Separate and bag materials.
3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.

B. Wood Materials:

1. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
2. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.

    a. Comply with requirements in Division 32 Section "Planting." for use of clean sawdust as organic mulch.

C. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location.

1. Clean Gypsum Board: Grind scraps of clean gypsum board using small mobile chipper or hammer mill. Screen out paper after grinding.

a. Comply with requirements in Division 32 Section "Planting." for use of clean ground gypsum board as inorganic soil amendment.

3.4 DISPOSAL OF WASTE

A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning: Do not burn waste materials.

C. Disposal: Remove waste materials from Owner's property and legally dispose of them.

END OF SECTION 017419

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:

1. Substantial Completion procedures.
2. Final completion procedures.
3. Warranties.
4. Final cleaning.

B. Related Requirements:

1. Division 01 Section "Execution" for progress cleaning of Project site.
2. Division 01 Section "Operation and Maintenance Data" for operation and maintenance manual requirements.
3. Division 01 Section "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.3 ACTION SUBMITTALS

A. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.

B. Certified List of Incomplete Items: Final submittal at Final Completion.

1.4 CLOSEOUT SUBMITTALS

A. Certificate of Insurance: For continuing coverage.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Maintenance Material Items: Provide remaining paint in legibly marked and labeled cans.

1.6 SUBSTANTIAL COMPLETION PROCEDURES

A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.

B. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for final completion.

1.7 FINAL COMPLETION PROCEDURES

A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:

1. Submit a final Application for Payment according to Division 01 Section "Payment Procedures."
2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.

B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.8 SUBMITTAL OF PROJECT WARRANTIES

A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.

B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.

C. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.

1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

D. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.

END OF SECTION 017700

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals.

B. Related Requirements:

1. Division 01 Section "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.

1.3 CLOSEOUT SUBMITTALS

A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.

1. Architect will comment on whether content of operations and maintenance submittals are acceptable.
2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.

B. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect will return copy with comments.

1. Correct or revise each manual to comply with Architect's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's comments and prior to commencing demonstration and training.

PART 2 - PRODUCTS

2.1 REQUIREMENTS FOR OPERATION AND MAINTENANCE MANUALS

A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:

1. Title page.
2. Table of contents.
3. Manual contents.

B. Title Page: Include the following information:

1. Subject matter included in manual.
2. Name and address of Project.
3. Name and address of Owner.
4. Date of submittal.
5. Name and contact information for Contractor.
6. Name and contact information for Construction Manager.
7. Name and contact information for Architect.
8. Cross-reference to related systems in other operation and maintenance manuals.

C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.

1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.

D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.

E. Manuals, Paper Copy: Submit manuals in the form of hard copy, bound and labeled volumes.

1. Binders: Heavy-duty, three-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.

a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
b. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents. Indicate volume number for multiple-volume sets.

2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
3. Supplementary Text: Prepared on 8-1/2-by-11-inch white bond paper.
4. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.

    a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
    b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

F. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.

G. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.

H. Product Information: Include the following, as applicable:

1. Product name and model number.
2. Manufacturer's name.
3. Color, pattern, and texture.
4. Material and chemical composition.
5. Reordering information for specially manufactured products.

I. Maintenance Procedures: Include manufacturer's written recommendations and the following:

1. Inspection procedures.
2. Types of cleaning agents to be used and methods of cleaning.
3. List of cleaning agents and methods of cleaning detrimental to product.
4. Schedule for routine cleaning and maintenance.
5. Repair instructions.

J. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

K. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.

1. Include procedures to follow and required notifications for warranty claims.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

A. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.

END OF SECTION 017823

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes administrative and procedural requirements for project record documents, including the following:

1. Record Drawings.
2. Record Specifications.

B. Related Requirements:
1. Division 01 Section "Execution" for final property survey.
2. Division 01 Section "Closeout Procedures" for general closeout procedures.
3. Division 01 Section "Operation and Maintenance Data" for operation and maintenance manual requirements.
4. Divisions 02 through 33 Sections for specific requirements for project record documents of the Work in those Sections.

1.3 CLOSEOUT SUBMITTALS

A. Record Drawings: Comply with the following:

1. Number of Copies: Submit one set(s) of marked-up record prints.
2. Number of Copies: Submit copies of record Drawings as follows:

a. Final Submittal:

1) Submit two paper-copy set(s) of marked-up record prints.
2) Submit PDF electronic files of scanned record prints and two set(s) of prints.
3) Print each drawing, whether or not changes and additional information were recorded.

B. Record Specifications: Submit one paper copy and one annotated PDF electronic files of Project's Specifications, including addenda and contract modifications.

C. Record Product Data: Submit one paper copy and annotated PDF electronic files and directories of each submittal.

1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.

D. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit one paper copy and annotated PDF electronic files and directories of each submittal.

E. Reports: Submit written report weekly indicating items incorporated into project record documents concurrent with progress of the Work, including revisions, concealed conditions, field changes, product selections, and other notations incorporated.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.

1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.

    a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
    b. Accurately record information in an acceptable drawing technique.
    c. Record data as soon as possible after obtaining it.
    d. Record and check the markup before enclosing concealed installations.
    e. Cross-reference record prints to corresponding archive photographic documentation.

2. Content: Types of items requiring marking include, but are not limited to, the following:

    a. Dimensional changes to Drawings.
    b. Revisions to details shown on Drawings.
    c. Depths of foundations below first floor.
    d. Locations and depths of underground utilities.
    e. Revisions to routing of piping and conduits.
    f. Revisions to electrical circuitry.
    g. Actual equipment locations.
    h. Duct size and routing.
    i. Locations of concealed internal utilities.
    j. Changes made by Change Order or Construction Change Directive.

k. Changes made following Architect's written orders.
l. Details not on the original Contract Drawings.
m. Field records for variable and concealed conditions.
n. Record information on the Work that is shown only schematically.

3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
5. Mark important additional information that was either shown schematically or omitted from original Drawings.
6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

B. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

1. Record Prints: Organize record prints and newly prepared record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
2. Format: Annotated PDF electronic file.
3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
4. Identification: As follows:

a. Project name.
b. Date.
c. Designation "PROJECT RECORD DRAWINGS."
d. Name of Architect.
e. Name of Contractor.

2.2 RECORD SPECIFICATIONS

A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.

1. Give attention to information on concealed products and installations that cannot be readily identified and recorded later.
2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.

4. For each principal product, indicate whether record Product Data has been submitted in operation and maintenance manuals instead of submitted as record Product Data.
5. Note related Change Orders, record Product Data, and record Drawings where applicable.

B. Format: Submit record Specifications as annotated PDF electronic file and one.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.

B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 017839

SECTION 024119 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Demolition and removal of selected portions of building or structure.
2. Salvage of existing items to be reused or recycled.

B. Related Requirements:

1. Section 011000 "Summary" for restrictions on the use of the premises, Owner-occupancy requirements, and phasing requirements.
2. Section 017300 "Execution" for cutting and patching procedures.

1.3 DEFINITIONS

A. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.

B. Remove and Salvage: Carefully detach from existing construction, in a manner to prevent damage, and deliver to Owner ready for reuse.

C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.

D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 MATERIALS OWNERSHIP

A. Unless otherwise indicated, demolition waste becomes property of Contractor.

1.5 INFORMATIONAL SUBMITTALS

A. Schedule of Selective Demolition Activities: Indicate the following:

1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted.
2. Interruption of utility services. Indicate how long utility services will be interrupted.
3. Coordination for shutoff, capping, and continuation of utility services.
4. Use of stairs.
5. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.

B. Inventory: Submit a list of items to be removed and salvaged and deliver to Owner prior to start of demolition.

C. Warranties: Documentation indicated that existing warranties are still in effect after completion of selective demolition.

1.6 CLOSEOUT SUBMITTALS

A. Inventory: Submit a list of items that have been removed and salvaged.

1.7 FIELD CONDITIONS

A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.

B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

1. Before selective demolition, Owner will remove the following items:

a. Sleep Room Beds/Furniture.

b. Miscellaneous tools and equipment where noted on drawings.

C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.

D. Hazardous Materials: See Division 0 Section “Information Available to Bidders” for Limited Hazardous Materials Survey Report.

1. Do not disturb hazardous materials or items suspected of containing hazardous materials except under procedures specified elsewhere in the Contract Documents.

E. Storage or sale of removed items or materials on-site is not permitted.

F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.

1. Maintain fire-protection facilities in service during selective demolition operations.

PART 2 - PRODUCTS

2.1 PEFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ANSI/ASSE A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped before starting selective demolition operations.

B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.

C. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.

1. Comply with requirements for existing services/systems interruptions specified in Section 011000 "Summary."

B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.

1. Arrange to shut off indicated utilities with utility companies.

2. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
3. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated to be removed.

    a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
    b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material.
    c. Equipment to Be Removed: Disconnect and cap services and remove equipment.
    d. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment; when appropriate, reinstall, reconnect, and make equipment operational.
    e. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and deliver to Owner.
    f. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.
    g. Ducts to Be Abandoned in Place: Cap or plug ducts with same or compatible ductwork material.

3.3 PREPARATION

A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

    1. Comply with requirements for access and protection specified in Section 015000 "Temporary Facilities and Controls."

B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.

    1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
    2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
    3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
    4. Cover and protect furniture, furnishings, and equipment that have not been removed.
    5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Section 015000 "Temporary Facilities and Controls."

3.4 SELECTIVE DEMOLITION, GENERAL

A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
4. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
5. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
6. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
7. Dispose of demolished items and materials promptly. Comply with requirements in Section 017419 "Construction Waste Management and Disposal."

B. Removed and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse.
2. Protect items from damage during transport and storage.
3. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

C. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

3.5 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Resilient Floor Coverings: Remove floor coverings and adhesive according to recommendations in RFCI's "Recommended Work Practices for the Removal of Resilient Floor Coverings."

B. Roofing: Remove no more existing roofing than what can be covered in one day by new roofing and so that building interior remains watertight and weathertight.

1. Remove existing roofing system down to substrate.

3.6 DISPOSAL OF DEMOLISHED MATERIALS

A. General: Except for items or materials indicated to be recycled, reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site.

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
4. Comply with requirements specified in Section 017419 "Construction Waste Management and Disposal."

B. Burning: Do not burn demolished materials.

C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

3.7 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 024119

SECTION 028200 - ASBESTOS REMEDIATION

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

A. The authorized work requires the disturbance, demolition, removal, and disposal of the following asbestos-containing material (ACM) from Fire Station #63, located at 33414 21st Avenue South, Federal Way, Washington; as shown on the drawings and as specified herein:

1. ACM gray door frame caulking (around single metal door frame);
2. ACM gray duct seam sealant (on 5" outside diameter (OD) metal furnace flue);
3. ACM brown window frame caulking (around 5'x5' metal framed window);
4. Non-ACM new white seam caulking on ACM old black asphaltic caulking (on 1'x1' metal ducting associated w/ old exhaust fan);
5. Non-ACM new gray window frame caulking on ACM old gray window frame caulking (around 6'x5' metal framed window);
6. 2'x3' Electrical panels with assumed ACM internals;
7. 2'x4' Electrical panels with assumed ACM internals;
8. Small electrical switch gear panels with assumed ACM
9. Assumed ACM glue dots associated with wood wall cabinets (5'x14);
10. Assumed ACM thermal system insulation (TSI) on small bore pipe elbows and fittings on fiberglass runs (concealed in plumbing walls & ceilings);
11. Assumed ACM insulation on 12"x12" metal ducting concealed beneath slab;
12. Assumed ACM mastic associated with 4'x9' plaster wall panels on brick wall; and
13. Assumed ACM windows concealed under 4'x9' exterior plaster wall panels.

B. In accordance with Federal, State, and local regulations, a "Good Faith Asbestos Inspection" was conducted at Fire Station #63 in preparation for the Renovation Project. A copy of the report is included as an appendix to the Summary of Hazardous Materials Work Specification Section 011110.

1.2 SPECIAL PRECAUTIONS

A. Special precautions will be required to isolate the asbestos work within the impacted area from the un-impacted areas of Fire Station #63.

B. Only workers with training in accordance with WAC 296-65-010 under the supervision of a certified asbestos supervisor with training in accordance with WAC 296--65-012 are approved to do this work. They are required to use wet methods, accomplish prompt clean-up of any debris, have appropriate respiratory protection, and an exposure assessment.

C. Less than one percent (<1%) asbestos-containing pipe dope was identified.
1. The selective demolition of these materials is within the scope of this project. Based on the U.S. Environmental Protection Agency (EPA) guidance, the Puget

Sound Clean Air Agency (PSCAA) considers that these materials to be non-asbestos materials (see Limited Hazardous Materials Survey Report attached as appendix to Section 011110). Therefore, disturbance and demolition of these materials with <1% asbestos is not considered an asbestos project; however, Washington State Department of Labor and Industries Division of Occupational Safety and Health (L&I DOSH) requires special worker exposure precautions and qualifications when dealing with this detectable level of asbestos (refer to Paragraph 3.3 of this Section, L&I DOSH regulations, and WISHA Regional Directives). Note: Debris from demolition of building materials with <1% asbestos may be disposed/recycled with normal construction debris.

1.3 RELATED WORK SPECIFIED ELSEWHERE: Conform to General Conditions, Supplementary Conditions, Modifications thereto, and Division 1 – General Requirements.

A. Section 011110 Summary of Hazardous Materials Work

B. Section 028300 Lead-Containing Materials Disturbance

C. Hazardous Materials Removal Drawings

D. Architectural, Electrical, and Mechanical Design and Demolition Drawings

1.4 DEFINITIONS AND ABBREVIATIONS: Definitions and abbreviations pertaining to asbestos removal and disposal are provided in the regulations, codes and standards listed in Paragraph 1.5 of this section.

A. Hazardous Materials Consultant – The Hazardous Materials Consultant is the firm/individual responsible for review and approval of Asbestos/Hazardous Materials submittals, for technical response to asbestos/hazardous materials removal questions, for monitoring of asbestos/hazardous materials work and for final visual inspection and final air clearance monitoring as specified herein. For this project, the Hazardous Materials Consultant is EHS-International, Inc., 1011 SW Klickitat Way Suite 104, Seattle, WA, (206) 381-1128 phone, (206) 254-4279 facsimile, and dericae@ehsintl.com e-mail.

1.5 APPLICABLE PUBLICATIONS

A. General Requirements: All work shall be done in compliance with the publications listed in this section as well as all Occupational Safety and Health Standards, the Uniform Building Code, Uniform Plumbing Code, Uniform Fire Code, the National Electrical Code, and as specified herein.

B. Title 29 CFR Part 1910 - General Occupational Safety and Health Standards

1. Subpart E. Means of Egress
2. Subpart I. Personal Protective Equipment

3. Subpart Z. Toxic and Hazardous Substances

C. Title 29 CFR Part 1926 - Safety and Health Regulations for Construction

1. Subpart C. General Safety and Health Provisions
2. Subpart D. Occupational Health and Environmental Controls
3. Subpart F. Fire Protection and Prevention
4. Subpart Z. Toxic and Hazardous Substances
5. Section 1926.1101Asbestos

D. Title 40 CFR Part 61 - Environmental Protection Agency Hazardous Air Pollution

1. Subpart A. General Conditions
2. Subpart M. National Emission Standard for Asbestos

E. Title 40 CFR Part 763 - Environmental Protection Agency

1. Subpart E. Asbestos-Containing Materials in Schools
2. Subpart F. Friable Asbestos-Containing Materials in Schools
3. Subpart G. Asbestos Abatement Projects

F. Title 49 CFR 100-180 and 382 - Department of Transportation

G. Federal Standard 313B - Material Safety Data Sheets

H. American National Standard Institute (ANSI)

1. Z9.2-79 Local Exhaust Systems
2. Z87.1-89 Eye and Face Protection
3. Z88.2-80 Practices for Respiratory Protection

I. International Fire Code Institute

1. Uniform Fire Code (UFC) (2009 UFC Standards)

J. National Fire Protection Association (NFPA)

1. NFPA 701 (2010) Fire Tests for Flame-Resistant Textiles and Films

K. State of Washington Administrative Codes

1. WAC 173-303 Dangerous Waste Regulations
2. WAC 173-400 General Regulations for Air Pollution Sources
3. WAC 296-62-077 Part I-1-Asbestos, Tremolite, Anthophilite, and Actinolite
4. WAC 296-65 Safety Standards for Asbestos Removal and Encapsulation
5. WAC 296-155 Safety Standards for Construction Work
6. WAC 296-809 Confined Spaces
7. WAC 296-841 Airborne Contaminants
8. WAC 296-842 Respiratory Protection

9. WAC 296-843 Hazardous Waste Operations and Emergency Response
10. WAC 296-901 Hazard Communication, Global Harmonized System (GHS)

L. State of Washington Statutes

1. RCW 40.17 Industrial Safety and Health Act
2. RCW 70.105 Hazardous Waste Management Act

M. WISHA Regional Directives (Washington State Department of labor and Industries {L&I})

1. WRD 23.30 Asbestos-Containing Joint Compound in Wallboard Systems

N. Puget Sound Clean Air Agency (PSCAA)

1. Regulation III, Article 4

1.6 QUALITY ASSURANCE

A. On-site Observation:

1. The safety and protection of the Contractor's employees, sub-contractor's employees, the facility, and the public is the sole responsibility of the Contractor.
2. The Hazardous Materials Consultant or representatives of local, State or Federal agencies may make unannounced visits to the site during the work. The Contractor shall make two complete sets of clean, protective clothing and respirators available daily for such visitor use. It is the visitor's responsibility to insure medical qualification, training, and current "fit test" prior to using any respirator provided by the contractor.
3. If the Hazardous Materials Consultant or agency visitor determines that practices are in violation of applicable regulations, or are endangering workers or the facility, they will immediately notify the Contractor orally that operations must cease until corrective action is taken. Such notification will be followed by written confirmation within three (3) work days.
4. Contractor shall stop work after receiving such oral notification. The work may not be restarted until the Contractor receives written authorization from the Hazardous Materials Consultant.
5. All costs resulting from such stop work order will be borne by the Contractor and will not be a basis for an increase in the contract amount or an extension of time.

B. Air Monitoring and Visual Inspections:

1. Monitor employees for potential exposure to asbestos fibers as required by WAC 296-62-077.
2. Conduct personnel monitoring continuously during asbestos removal operations to determine the 8-hour time weighted exposure and 30-minute short term excursion limit exposure of workers to airborne fibers, as described in WAC 296-62-077.

3. The Hazardous Materials Consultant may perform air monitoring inside the building, inside the work areas, and on the Contractor's employees while asbestos work is underway. This additional monitoring does not reduce or replace the Contractor's required air monitoring.
4. Collect and have a certified laboratory analyze by phase contrast microscopy (PCM), using the NIOSH Analytical Procedure 7400, all air samples in accordance with WAC 296-62-077, and as specified herein.
5. The Contractor shall be responsible for all costs of cleaning, re-cleaning, re-inspection, and other costs required to meet final inspection requirements, including but not limited to laboratory fees, consultant fees and any premiums for accelerated "turn-around" times or overtime work required to meet approved schedules.
6. Direct asbestos laboratory, in writing on each Chain-of-Custody (CoC) form submitted for air sampling on this project, to forward by e-mail all project air monitoring results, and all other pertinent data and records, to the Owner's Asbestos Consultant. A sample of this written direction on a CoC form shall be submitted to the Owner along with the information required by Paragraph 1.13 (F).
7. Have asbestos laboratory archive all air samples until the successful completion of the project.
8. Perform pre-abatement PCM air monitoring in accordance with WAC 296-62-077, and as specified herein.
9. Perform PCM pre-clearance sampling, in accordance with WAC 296-62-077, and as specified herein.
10. The Owner's Hazardous Materials Consultant will perform PCM verification air clearance testing in all impacted areas in accordance with L&I DOSH phase contrast microscopy (PCM) method. Satisfactory verification visual and PCM air clearance monitoring, by the Owner's Hazardous Materials Consultant are required prior to removal of critical barriers and access of non-certified asbestos workers into the regulated areas.

C. The Contractor shall perform initial exposure assessments as required by WAC 296-62-077.

1.7 PROTECTION OF EXISTING WORK TO REMAIN: Perform asbestos removal in the project work areas without damage or contamination of adjacent work. Where existing work is damaged or contaminated, it shall be restored to its original condition at no expense to the Owner. The restorative procedures shall be approved by the Owner prior to start of restoration.

1.8 MEDICAL MONITORING AND DRUG TESTING

A. Institute a medical surveillance program for employees in accordance with WAC 296-62-077.

B. Provide random drug testing, as required by 49 CFR 382, for all drivers of vehicles transporting asbestos or hazardous materials.

1.9 TRAINING: Train and certify all workers who are required to remove, encapsulate, or barricade asbestos or to transport or dispose of asbestos as required by WAC 296-62-077, 40 CFR 763 and 49 CFR 382.

1.10 PERMITS AND NOTIFICATIONS: Make all required notifications for asbestos removal, hauling, and disposal as required by Federal, State, and local authorities.

1.11 SAFETY COMPLIANCE: Comply with laws, ordinances, rules, and regulations of federal, state, and local authorities regarding handling, storing, transporting, and disposing of hazardous materials and all other construction activities.

1.12 RESPIRATOR PROGRAM: Establish a respirator program as required by WAC 296-62-077 and WAC 296-62-071.

1.13 INITIAL SUBMITTAL

A. Submit one bound or electronic, indexed copy with the following documentation to the Hazardous Materials Consultant for review, comments and approval, at least three work days prior to scheduled commencement of work. The Contractor is responsible for delays caused by late or incomplete submittals. Organize and index submittal packages in the order provided in the checklist 1.13.A.1 through 1.13.A.12. See Sub-sections 1.13.B through 1.13.M for detailed descriptions of individual submittal requirements. Submittals not properly organized and indexed will be rejected. Following submittal approval, provide the required number of copies of the approved submittal to the Architect as identified in the general conditions for all submittals.

1. Contractor's shop drawings
2. Contractor's work and compliance plan
3. Contractor's asbestos liability insurance policy
4. Contractor's schedule
5. Contractor's testing laboratory and laboratory personnel (including air sample analysis personnel)
6. Disposal site designations
7. Waste transporter designation
8. Manufacturer’s product data sheets and safety data sheets (SDS)
9. Contractor's representations
10. Contractor's notifications
    a. L&I DOSH
    b. PSCAA
11. Contractor's Asbestos Certifications
12. Contractor’s request for substitutions

B. Shop drawings shall show:

1. Provide shop drawings at each work area throughout the contract duration to show the layout of regulated area barriers and construction barriers.
2. Location of temporary site storage facilities.

C. The work plan shall include procedures for:

1. Methods: A description of all techniques, methods, and special equipment to be used during the contract, including methods fort typical abatement work required for this project. Include typical work procedures for each unit of work identified on the bid documents.
2. The work plan shall specifically address asbestos removal and disposal procedures as required by WAC 396-62-077 and 40 CFR 61.

D. Insurance Policy: Submit copies of the Contractor's asbestos liability insurance policy, identifying South King County Fire & Rescue as additional insured. (Note: Policy must specifically identify coverage for asbestos and /or hazardous materials work.)

E. Schedule: Submit abatement schedule by work area.

F. Testing Laboratory and laboratory Personnel: Submit the name, location and phone number of proposed certified testing laboratory. Include legible, current copies of the laboratory's accreditation.

1. The Laboratory shall prove proficiency in the AIHA/NIOSH PAT Program and NVLAP program.
2. Provide a current AIHA PCM PAT Round results and NVLAP Certification for asbestos bulk analysis, if Contractor anticipates collecting and analyzing bulk samples.
3. Provide a copy of the Contractor's written direction to the Testing Laboratory requiring them to fax/email copies of all Contractor air monitoring results, data sheets and chain-of-custodies for air monitoring samples to the Hazardous Materials Consultant within twenty-four (24) hours of receipt of the sample.

G. Disposal Site:

1. Identify the proposed Ecology/EPA permitted disposal site at which any waste material generated during the project will be disposed.
2. Furnish evidence of all necessary government approvals to dispose of the waste.

H. Waste Transporter: Submit the name and address of the proposed waste transporter.

I. Safety data sheets (SDSs): Submit legible copies of manufacturer's SDSs that describe product usage and restrictions, application procedures, and safety precautions. Submit copies of all SDSs for tape, plastic sheeting, solvents, encapsulants, adhesives, and lock-down chemicals.

J. Representations: Submit statement signed by a Principal of the Contractor that records of employees' work assignments, certifications, respirator fit tests, and medical examinations are accurate, up-to-date, and available for inspection.

K. Notifications: Submit a copy of all required notifications and permits obtained by the Contractor (Washington State Department of Labor and Industries, and Puget Sound Clean Air Agency). Submit upon receipt any approved amendments to notifications or re-notification for multi-phase activities:

1. Department of Labor and Industries
   Regional Office
   950 Broadway #200
   Tacoma, WA, 98402

2. Puget Sound Clean Air Agency
   1904 Third Avenue, Suite 105
   Seattle, WA 98101

L. Submit legible, current copies of the following Contractor certifications:

1. Current L&I asbestos abatement firm certification.
2. Asbestos Supervisor/Competent Person: Name, Asbestos Supervisor Certification, and resume of experience of the assigned onsite supervisor. At a minimum, the supervisor shall be certified in accordance with WAC Chapter 296-65-012.

M. Substitutions: Submit proposals for substitutions of materials, equipment and methods to the Hazardous Materials Consultant at least seventy-two (72) hours prior to implementing the change.

1.14 PERIODIC SUBMITTALS

A. On the first day of mobilization, prior to commencing abatement, submit legible copies of the following asbestos certifications for the workers actually assigned to the project the day of mobilization:

1. Worker Certification: Current copies of L&I DOSH Asbestos Supervisor and Asbestos Worker Certifications for employees scheduled to work on the project in compliance with WAC Chapter 296-65-012.
2. Medical certification and respirator fit test: Submit a legible copy of the current asbestos medical certification and respirator fit test record (for each type of respirator to be worn) for each employee who will be working on the project.

B. Submit the following information obtained during the course of the work to the Hazardous Materials Consultant:

1. Initial Exposure Monitoring: Submit legible and completed results of the Contractor’s initial exposure monitoring within two working days of sample collection.
2. Daily Air Monitoring: Have the Contractor’s laboratory submit by email daily, to the Hazardous Materials Consultant, all results of Contractor's daily air monitoring. Submittal shall consist of legible and complete field data sheets and

the analytical laboratory's results. Daily air monitoring submittals shall be furnished to the Hazardous Materials Consultant within 24 hours of collection of samples.

3. Project Daily Logs: Submit legible and completed copies of the previous day's Daily Logs.
4. Updated Project Information: Submit changes in project schedule or personnel at least 48 hours prior to the effective time of change for the following:

    a. Updated schedules for asbestos removal;
    b. Copies of the L&I, medical and fit test certificate for additional workers;
    c. Copies of amended notifications; and
    d. Copies of amended disposal authorizations.

1.15 FINAL SUBMITTAL

A. Submit three copies of the following documents with the application within 30 days of completion of asbestos removal work.

1. Employees' daily sign-in sheets;
2. Contractor's actual "Start and Finish" Project Dates;
3. Waste Shipment Records (40 CFR 61, Figure 4);
4. Disposal Site Receipts; and
5. Statement of completion of asbestos abatement work as required by these specifications and drawings.

1.16 SANITARY: The Contractor shall provide adequate toilet facilities

1.17 MATERIAL STORAGE: Store all materials subject to damage off the ground and secure from damage by weather or vandalism.

1.18 ON-SITE DOCUMENTATION:

A. Maintain, on the job site, copies of the following data for safety, equipment, and supplies used for the work.

1. Equipment: Show the model, style, capacity, and the operation and maintenance procedures for the following, as applicable:
    a. HEPA vacuum cleaners. schedules for asbestos removal and
    b. Negative air machines.
2. Material Safety Data Sheets: Maintain a Material Safety Data Sheet for each tape, plastic sheeting, solvent, encapsulant, adhesive, and lock-down chemical proposed to be used as required by WAC 296-62-054.

B. Respiratory Protection Plan: Maintain on-site their written respirator program. The Contractor's written and approved respirator program shall meet all requirements of WAC 296-62-077. Any deficiencies identified in the Hazardous Materials Consultant's

review of the respiratory protection plan shall be corrected prior to commencement of work.

PART 2 - PRODUCTS

2.1 RESPIRATORS

A. Provide personally issued and marked respirators approved by NIOSH and MSHA, and provide sufficient replacement canisters for respirators with disposable filters.

B. Provided respirators with the protection factors required by WAC 296-62-077.

C. Respirators shall be suitable for dual (“stacked”) cartridge use whenever both asbestos hazards and other respiratory hazards exist in the work area.

2.2 PROTECTIVE CLOTHING

A. Provide approved protective outer clothing, consisting of disposable fire retardant, full body coveralls and hoods fabricated from nonwoven fabric. Personal protective equipment shall be provided and utilized to meet applicable safety regulations.

B. Cloth work clothes may be worn under disposable protective coveralls, boots and gloves for comfort as permitted by regulation, however if worn in a negative pressure enclosure, the cloth clothing must be removed and left in the equipment room as personnel exit the enclosure and must be laundered by the employer per the applicable instructions.

2.3 SEALANTS AND ENCAPSULANTS: Penetrating and bridging encapsulants for asbestos applications. "Lock-Down" encapsulants used in non-finished areas shall be tinted for identification in a color, which will not obscure residual asbestos. Encapsulants shall be compatible with replacement materials and shall not contain hazardous materials listed in 29 CFR 1910, Subpart Z.

2.4 SURFACTANT: A surfactant consisting of 50% polyoxyethylene ether and 50% polyoxyethylene ester (or an approved alternate) shall be used, and shall be mixed with water at the rate of one ounce of surfactant to 5 gallons of water or as recommended by the manufacturer.

2.5 MASTIC REMOVAL SOLVENTS: Mastic removal solvents, if used, shall be non-flammable and shall not contain halogenated compounds. Solvents shall be compatible with replacement materials. Solvents must be of the “low odor” or “no odor” variety and so indicated on the SDS. Citrus based solvents do not meet these criteria. Delay of schedule for using these type solvents will not be acceptable.

2.6 PLASTIC SHEET: A minimum 6-mil thick flame resistant polyethylene (in accordance with NFPA 701) shall be used unless otherwise specified. The poly shall be sized in length and width to minimize the frequency of joints.

2.7 TAPE: Tape shall be capable of sealing joints of adjacent sheets of polyethylene, for attachment of polyethylene sheets to finished or unfinished surfaces and of adhering under both dry and wet conditions, including during use of amended water.

2.8 ADHESIVES: Adhesives shall be capable of sealing joints of adjacent sheets of polyethylene to finished or unfinished surfaces and of adhering under both dry and wet conditions.

2.9 DISPOSAL CONTAINERS: Disposal containers shall be suitable to receive, retain, and dispose of asbestos-containing or contaminated materials. Containers shall be labeled in accordance with the applicable regulations and must be both airtight and watertight. Plastic bags shall be a minimum 6-mil polyethylene, pre-printed with approved warning labels. Plastic wrap shall be 6-mil polyethylene sheets, securely wrapped and taped. Disposal containers shall be labeled with “ASBESTOS NA 2212,” Contractor’s name and location, and a Class 9 label.

2.10 EYE PROTECTION: The Contractor shall provide goggles to personnel engaged in asbestos operations, unless worker is required to wear a full facepiece respirator. Full facepiece respirators shall meet the requirements of WAC 296-62-077.

2.11 DANGER SIGNS AND LABELS: Danger signs and labels shall be affixed to all products or containers containing asbestos. The required signs shall be used to demarcate areas where asbestos waste is temporarily stored; and areas, not accessible to the public where asbestos-containing materials are left in place. Signs and labels shall be in accordance with applicable regulations and codes. The signs posted at work area entrance, exists, decontamination areas, and waste disposal areas shall comply with WAC 296-62-077, WAC 296-62-05411 and the UFC.

2.12 OTHER MATERIALS: The Contractor shall provide standard commercial quality of all other materials, which are required to prepare and complete the work.

2.13 TOOLS AND EQUIPMENT

A. Sprayers for amended water and encapsulant application shall be airless.

B. Vacuum cleaning equipment shall be manufactured for asbestos use and shall use HEPA filters on the discharge.

C. Scaffolding hoists and protective equipment shall meet all applicable safety regulations.

D. Transportation equipment shall be suitable for loading, temporary storage, transit, and unloading of contaminated waste without exposure to persons or property. All trucks or vans used to transport asbestos shall be enclosed and sealed watertight. The driver of the truck shall have a commercial driver's license with hazardous material endorsement.

E. Provide all other tools and equipment for removal, enclosure, encapsulation, patching, and disposal activities.

F. Electrical tools and equipment shall meet all applicable codes and regulations.

PART 3 - EXECUTION

3.1 WORK AREAS

A. Regulated Work Areas: Establish regulated work areas in compliance with WAC 296-62-077.

B. Decontamination Area: Install decontamination areas in compliance with WAC 296-62-077. Decontamination areas shall meet fire exiting requirements of the UFC.

3.2 PERSONNEL PROTECTION PROCEDURES

A. Post the decontamination, safety, and work procedures to be followed by workers.

B. Provide continuous on-site supervision by the approved Certified Asbestos Supervisor.

C. Follow all worker protection procedures as described in the approved work plan.

D. Provide the highest level of respiratory protection unless approved and documented exposure assessments establish that a lower level of protection is adequate, as determined by the Certified Asbestos Supervisor, with the written concurrence of the Hazardous Materials Consultant. For asbestos removal inside a negative pressure enclosure, respiratory protection shall be in accordance with the requirements of WAC 296-62-077, regardless of the exposure assessment.

E. Maintain a daily log of all workers and visitors entering regulated work areas. The log shall contain the name of each individual, his or her organization, accurate time of entering and leaving, and purpose of visit

F. Monitor worker exposure to airborne asbestos fibers as required by WAC 296-62-077

G. Provide approved filters for other airborne contaminants (solvents, etc.), which may be present. These filters shall be used in combination with approved asbestos filters. At no time shall the permissible exposure limit (PEL) for any airborne contaminant exceed the PEL listed in 29 CFR 1910, Subpart Z.

3.3 ASBESTOS REMOVAL PROCEDURES: Asbestos removal shall be in accordance with the Contractor's Approved Work Plan, applicable regulations, and this specification.

A. Fire exits and fire lanes shall not be blocked.

B. Work hours shall be as follow:

1. Work shall commence and complete in accordance with the contract documents.
2. Work hours shall be in accordance with the contract documents.

C. The Hazardous Materials Consultant must concur in writing with the proposed Work Plan, prior to commencement of work.

3.4 AIR MONITORING

A. Airborne concentrations of asbestos fibers shall be monitored in accordance with WAC 296-62-077, current EPA and OSHA guidance, and as specified herein. The Hazardous Materials Consultant may perform independent monitoring of the work area and Contractor’s employees. All monitoring shall be performed by trained industrial hygiene technicians or equivalent. All sampling pumps shall be calibrated in the field with a secondary calibration device before and after each sample. Built-in rotometers on pumps are not acceptable.

B. The Contractor shall accomplish pre-abatement sampling in accordance with WAC 296-62-07709(3)(g) and as specified herein.

1. The Contractor shall collect PCM pre-abatement air samples and submit them to his certified laboratory for analysis prior to commencement of any asbestos removal work.
2. The Contractor shall collect a minimum of three (3) pre-abatement samples per building.
3. Contractor’s L&I final visual inspection and pre-abatement samples in conjunction with pre-clearance PCM samples will be used as the basis for requests for the Owner’s Hazardous Materials Consultant to accomplish “3rd party” final visual inspections and air clearance sampling.
4. The Owner’s Hazardous Materials Consultant will not accomplish verification inspections and air clearance sampling until notified by the Contractor that L&I DOSH final visual inspection and pre-clearance PCM sampling have been completed satisfactorily. The Owner’s Hazardous Materials Consultant will accomplish verification visual inspections and collect and have analyzed verification PCM air clearance samples. The results of the Owner’s Hazardous

Materials Consultant verification inspection and air sampling will be for the purpose of confirming compliance with contractual requirements, only.

C. The minimum number of daily samples per work area without a negative exposure assessment are as follows:

1. One (1) air sample within the regulated work areas.
2. One (1) air sample at least every other day, located outside the entrance to the work area.
3. Personnel samples (excluding excursion samples) shall be taken at least twice per eight-hour work shift at the rate of one sample for every six people performing that task in the same work area. Persons performing separate tasks or in separate work areas shall be sampled separately.
4. Excursion samples as required by WAC 296-62-077.
5. Two (2) waste load-out samples for the full duration of the operation, one taken inside the wash-down station and one taken on the clean side of the wash-down station. (No samples are necessary if no load-out operation is performed.).
6. All workers disturbing asbestos outside of a Negative Pressure Enclosure System shall be monitored continuously.
7. In addition to the samples listed in paragraphs 1 through 6 above, when employing a negative pressure enclosure, collect the following samples:

    a. Collect one (1) air sample every other day located at the entrance to the decontamination chamber.
    b. Collect one (1) air sample located at the exhaust(s) of the HEPA filtration unit(s) (if more than one unit is used, the sampling may be rotated between units, however, each unit must be sampled at least once every other day).
    c. Decontamination chamber entrance and HEPA exhaust samples are not required if negative pressure enclosures are not used.

D. Daily monitoring may be discontinued only after the Contractor's Certified Asbestos Supervisor certifies in writing that a Negative Exposure Assessment, in accordance with WAC 276-62-077, has been obtained. Written concurrence must be obtained from the Hazardous Materials Consultant prior to discontinuing daily monitoring.

3.5 DISPOSAL

A. Comply with current waste handling, storage, transportation, and disposal requirements of the waste disposal facility, U.S. Department of Transportation, and EPA regulations.

B. Label waste containers and vehicles in accordance with 40 CFR Part 61 and 49 CFR 100-180. Affix warning labels having waterproof print and permanent adhesive to all waste containers. Affix a Class 9 label with ID number 2212 on all four sides of the waste transport vehicle.

C. Waste transport vehicles shall be lined with polyethylene and be fully enclosed.

D. Waste shipping papers shall identify waste as "Asbestos 9, NA 2212 III, RQ" and list the total quantity being transported in addition to the requirements of 40 CFR 61.

E. Workers loading waste shall wear protective clothing and canister type respirators.

F. Materials containing <1% asbestos fibers may be disposed as normal construction debris.

G. Daily monitoring may be discontinued only after the Contractor's Certified Asbestos Supervisor certifies in writing that a Negative Exposure Assessment, in accordance with WAC 276-62-077, has been obtained. Written concurrence must be obtained from the Hazardous Materials Consultant prior to discontinuing daily monitoring.

3.6 CLEANING OF WORK AREA

A. Upon completion of asbestos repair or removal or of materials that contain <1% asbestos fibers within a work area, remove visible accumulations of asbestos material and debris. Wet clean and HEPA vacuum all work area surfaces.

B. Ensure that all asbestos-containing materials have been removed from concave corners and textured surfaces.

C. Notify the Hazardous Materials Consultant that asbestos work has been completed, that preliminary inspection has been accomplished by the Contractor, and that the work area is ready for final visual inspection. Include a statement that all asbestos in the work area has been removed, repaired, and/or encapsulated as required by the contract, and that all debris has been removed.

3.7 FINAL VISUAL INSPECTION AND AIR CLEARANCE MONITORING

A. The Owner will conduct verification inspection and verification air monitoring in all impacted areas. The Owner's Hazardous Materials Consultant's verification air monitoring shall be conducted in accordance with NIOSH 7400 Method A. The asbestos sub-contractor's L&I DOSH phase contrast microscopy final air clearance monitoring will be used to clear all areas prior to inviting the Owner's Materials Consultant to accomplish verification visual inspection or verification air sampling. The Owner's Hazardous Materials Consultant will use two-hour laboratory turn-around for all verification air monitoring. If the Contractor desires the results be provided sooner, he may request the Owner's Hazardous Materials Consultant use an accelerated turn-around and pay the differential cost in laboratory fees. The maximum acceptable level of airborne asbestos fibers for final work area clearance will be 0.01 fibers per cubic centimeter.

B. Prior to admitting non-certified workers into areas regulated by WAC 296-62-077, the Contractor shall conduct a visual inspection to verify the completion of removal and clean-up and will conduct L&I DOSH clearance air monitoring using phase contract microscopy (PCM). Airborne concentrations of asbestos fibers from the pre-clearance

samples must be less than 0.01 fibers per cubic centimeter using PCM. Upon receipt of satisfactory air clearance results the Contractor will notify the Owner's Hazardous Materials Consultant that the work area is ready for verification visual inspection or verification air sampling. Re-entry of non-certified asbestos worker personnel will be dependent on the asbestos sub-contractor's final L&I DOSH visual inspection and phase contrast microscopy final air clearance monitoring and the Owner's Hazardous Materials Consultant's verification visual inspection and verification air monitoring.

C. Verification air monitoring tests will not be performed until all areas and materials within the work area are fully clean, encapsulated and dry. Allow 4 hours after encapsulation prior to start of final air clearance sampling to ensure encapsulate is fully dry.

D. EHSI will only collect one set of PCMs per building/per floor; the contractor should organize his work to support the PCM clearances.

E. If either/both of the Owner's Hazardous Materials Consultant's verification visual inspection or verification air monitoring results show that the work area has failed to meet the clearance criteria, the Owner's Hazardous Materials Consultant shall notify the Contractor. The Contractor shall re-clean the work area, accomplish an additional L&I DOSH final visual inspection and collect and analyze an additional set of L&I DOSH final PCM clearance air monitoring samples whose asbestos concentration must be less than 0.01 fibers per cubic centimeter prior to requesting the Owner's Hazardous Materials Consultant accomplish another verification inspection and prior to collecting another set of verification air monitoring samples. All work specified in this paragraph shall be done at no additional expense to the Owner, including all labor and laboratory fees of the Owner.

F. Once the Contractor's final clearance air monitoring and the Owner's Hazardous Materials Consultant's verification visual inspection and verification air monitoring results meet the L&I DOSH PCM clearance criteria of WAC 296-62-077, for the work, then the HEPA filtration units may be deactivated (if applicable) and all seals, barriers, barricades, and decontamination areas shall be dismantled and removed, and the work area released to unprotected workers.

G. Work area containment's and/or critical barriers shall not be removed until final clearance results are reviewed and accepted by the Owner.

3.8 SUBSTANTIAL COMPLETION

A. After the work area barriers, plastic sheeting, decontamination area, etc., have been removed, the Contractor shall conduct an additional inspection to verify that there was no asbestos debris, contaminated water, or other residue, concealed by the work area protection installations. Any such residue shall be cleaned up using HEPA vacuum cleaners and wet wiping methods.

B. After the Contractor certifies that the work area has been cleaned of all asbestos in compliance with the contract, the Contractor shall conduct a final inspection to verify that there is no unrepaired damage to walls, ceilings, doors or surfaces or finishes

other than that called for by the scope of work. Costs of restoration of damaged finishes shall be borne by the Contractor.

END OF SECTION 028200

SECTION 028300 - LEAD-CONTAINING PAINT DISTURBANCE

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

A. The work for the Renovation Project requires the disturbance and disposal of materials coated with lead-containing paint (LCP) and other lead-containing building materials (LCM) from the Fire Station #63, located at 33414 21st Avenue South, Auburn, Washington and shall be performed in accordance with the lead regulations and these specifications. These work activities are identified as shown on the drawings and as specified herein:

B. Interior and exterior paint surface and other lead-containing materials (LCM) (e.g., ceramic tiles) tests using and X-ray fluorescence analyzer (XRF) measured lead at a variety of levels with results ranging from 0.5 milligrams per square centimeter (mg/cm2) to less than the detectable level. In addition, lead-containing paint (LCP) and LCM bulk QA sample results ranged from 0.0096 % Pb by weight to less than the lab reporting limit. The lead sampling data is included in the Hazardous Material Survey Report which is provided as an appendix to the Summary of Hazardous Materials Summary of Work Section 011110 of these Specifications.

1. Based on the specified work scope that includes cutting, grinding, sanding, select demolition, paint chip cleanup, etc., the Contractor will as a minimum:

    a. Accomplish initial exposure assessments for each category of lead work (disturbance) in accordance with WAC 296-155-176.
    b. Accomplish dust control using wet methods or as required in accordance with WAC 296-155-176.
    c. Accomplish waste stream sampling as needed for hazardous lead concentrations in accordance with WAC 173-303.

2. Based on lead concentrations and the known scope of work, it is not expected that any lead work beyond that required by sub-paragraphs a), b), and c) above, will be required. If initial exposure assessments or waste stream sampling require additional lead disturbance work, then the Contractor shall submit a change order with a Work Plan, in accordance with The Standard Form of Agreement, to the Owner for approval and work shall be accomplished in accordance with the approved Work Plan and as specified herein.
3. Pre-work submittals for work described in paragraphs 1.1.B.1-3, shall be in accordance with paragraph 1.11 of this Section. Provide the Owner's Hazardous Materials Consultant with copies of lead initial exposure assessment and waste stream sampling required by this Section, along with asbestos periodic submittals required by Section 028200.

C. Owner's Hazardous Materials Consultant: The Owner's Hazardous Materials Consultant is the firm/individual responsible for review and approval of Asbestos/Hazardous Materials submittals, for response to technical asbestos/hazardous materials removal

questions, for monitoring of asbestos/hazardous materials work and for final visual inspection and final air clearance monitoring as specified herein. For this project, the Owner's Hazardous Materials Consultant is EHS-International, Inc., 1011 SW Klickitat Way Suite 104, Seattle, WA, (206) 381-1128 phone, (206) 254-4279 facsimile, dericae@ehsintl.com e-mail.

D. FS #63 is not a "child occupied facility" as defined by US Environmental Protection Agency (USEPA) regulation 40 CFR 745 or WA State Department of Commerce (Commerce) regulation WAC 365-230, therefore, those regulations do not apply to this project.

1.2 RELATED DOCUMENTS

A. Drawings and general provisions of Contract, including General conditions and Division-1 Specification sections, apply to this work.

B. Related Sections

1. 011110 Summary of Hazardous Materials Work
2. 028200 Asbestos Remediation Specification
3. 028400 Arsenic Remediation Specification
4. Hazardous Materials Removal Drawings
5. Architectural, Electrical, and Mechanical Design and Demolition Drawings
6. Drawings and general provisions of the Contract, including Divisions 0 and 1 Specification Sections, apply to work of this section.

1.3 DEFINITIONS AND ABBREVIATIONS: Definitions and abbreviations pertaining to lead removal and disposal are provided in the regulations, codes, and standards listed in Paragraph 1.4 of this Section.

A. Lead disturbance: For the purposes of this project, lead disturbance shall be defined as, demolition, asbestos abatement, renovation or other work that will disturb materials coated with paint containing measurable concentrations of lead, other lead-containing building materials, or metallic lead materials, and that is not lead abatement.

1.4 APPLICABLE PUBLICATIONS

A. General Requirements

1. The publications listed below form a part of this specification to the extent referenced.
2. All work shall be performed in full compliance with the regulations listed in this section and the Uniform Building Code, Uniform Plumbing Code, Uniform Fire Code, Code of Federal Regulations (CFR) and the National Electrical Code, and as specified herein.

B. Title 29 CFR Part 1910 - General Occupational Safety and Health Standards

1. Subpart E. Means of Egress
2. Subpart I. Personal Protective Equipment
3. Subpart Z. Toxic and Hazardous Substances

C. Title 29 CFR Part 1926 - Safety and Health Regulations for Construction

1. Subpart C. General Safety and Health Provisions
2. Subpart D. Occupational Health and Environmental Controls
3. 29 CFR 1926.62 Lead
4. Subpart F. Fire Protection and Prevention
5. Subpart Z. Toxic and Hazardous Substances

D. Title 40 CFR - Environmental Protection Agency

1. 40 CFR 261 Identification and Listing of Hazardous Wastes
2. 40 CFR 260 Hazardous Waste Management System: General
3. 40 CFR 261 Identification and Listing of Hazardous Waste
4. 40 CFR 262 Standards Applicable to Generators of Hazardous Waste
5. 40 CFR 263 Standards Applicable to Transporters of Hazardous Waste
6. 40 CFR 270 Hazardous Waste Permit Program
7. 40 CFR 745 Requirements for Lead-Based Paint Activities in Target Housing and Child-Occupied Facilities

E. Title 49 CFR 100-180 and 382 - Department of Transportation

F. State of Washington Administrative Codes (WAC) - Washington State Department of Labor and Industries (L&I)

1. WAC 173-303 Dangerous Waste Regulations

G. Washington State Department of Labor and Industries (L&I)

1. WAC 296-155 Safety Standards for Construction Work
2. WAC 296-155-176 Lead
3. WAC 296-800 Safety and Health Core Rules
4. WAC 296-842 Respirators
5. WAC 296-843 Hazardous Waste Operations and Emergency Response
6. WAC 296-901 Hazard Communication, Globally Harmonized System (GHS)

H. Washington State Department of Commerce

1. WAC 365-230 "…Lead Based Paint Activities"

I. Washington Statutes Revised Code of Washington (RCW)

1. 49.17 RCW Washington Industrial Safety and Health Act
2. 70.105 RCW Hazardous Waste Management Act

J. American National Standards Institute (ANSI)

1. Z9.2 Local Exhaust Systems
2. Z87.1 Eye and Face Protection
3. Z88.2 Practices for Respiratory Protection (2015)

K. American Society for Testing and Materials (ASTM)

1. D 4397 Polyethylene Sheeting

L. Federal Standards

1. 313B Material Safety Data Sheets

M. International Fire Code Institute

1. Uniform Fire Code 2003 UFC Standards

N. National Fire Protection Association (NFPA)

1. Fire Tests for Flame Resistant Textiles and Films

O. National Institute of Occupational Safety and Health (NIOSH)

1. Manual of Analytical Methods, 3rd Edition

P. Underwriters Laboratories (UL)

1. UL 586 High-Efficiency, Particulate, Air Filter Units

1.5 MEDICAL REQUIREMENTS

A. MEDICAL CERTIFICATION - Medical testing, evaluations, certifications, and record-keeping requirements shall conform to WAC 296-155-176.

B. DRIVER TESTING - Provide random drug testing, as required by 49 CFR 382, for all drivers of vehicles transporting hazardous materials.

1.6 TRAINING

A. L&I TRAINING - Prior to commencement of work, each worker conducting lead disturbance work or handling lead wastes shall have successfully completed training in lead work as required by WAC-296-155-176. Training materials shall be available to all employees.

1.7 RESPIRATORY PROTECTION: The Contractor's Competent Person shall establish and implement a respiratory protection program in accordance with WAC 296-155-176.

A. RESPIRATORS - Respirators shall be supplied by the Contractor at no cost to the employees.

B. FIT TESTING - Respirator fit testing for each worker shall be conducted and administered at no cost to the employee.

1.8 HAZARD COMMUNICATION PROGRAM

A. The Contractor shall implement and maintain a hazard communication program in accordance with WAC 296-901.

1.9 SAFETY, HEALTH, AND ENVIRONMENTAL COMPLIANCE

A. The Contractor shall comply with all applicable safety, health, and environmental laws, ordinances, rules and regulations of federal, state, regional and local authorities.

1.10 PERMITS, LICENSES, NOTIFICATIONS, AND EPA IDENTIFICATION NUMBERS

A. FEES - The Contractor shall pay all fees for and obtain all necessary permits and licenses, required for lead storage, transportation and disposal. Timely notification shall be furnished as required by federal, state, regional and local authorities, and as specified herein.

B. EPA IDENTIFICATION NUMBER - The Contractor shall obtain the Owner's EPA Hazardous Waste Generator Identification Number from the Owner, if required for hazardous waste disposal, and shall use that number on all manifests for disposal of hazardous waste.

1.11 INITIAL SUBMITTALS

A. The Contractor shall submit one (1) bound or electronic, indexed copy with the following documentation to the Owner for review, approval, or rejection, at least three (3) working days prior to scheduled commencement of work. The Contractor is responsible for delays caused by late submittals. Submittal packages shall be organized and indexed in the order provided in the checklist 1.11.A.1 through 1.11.A.3.Submittals not properly organized and indexed will be rejected. Following submittal approval, provide one additional bound copy of the approved submittal to the Owner. It is the Contractor's responsibility to insure all subcontractors disturbing LCP/LCM are included in the Section 028300 pre-work submittals.

1. A general description of work practices, engineering controls, air monitoring, and decontamination involving lead-containing coatings. Describe whether the job will involve removing lead paint, or demolition of materials containing lead.

    a. Qualification / certification / training certificates and role of each contractor's personnel;
    b. Qualifications of the proposed testing laboratory (to perform analysis of air and waste characterization samples);
    c. Procedures for personnel and equipment cleanup / decontamination;

d. Lead waste management and disposal / recycling plan including: waste minimization efforts; container selection and labeling;
e. Description of anticipated worker exposure assessment(s) for the project.

2. Competent Person: Provide the name, qualifications, and training certifications for the Contractor's full-time on-site supervisor shall be designated as, and shall be qualified to be, a "competent person" experienced in the administration and supervision of lead disturbance or abatement projects, as specified in WAC 296-155-176.

3. Employee Training and Certifications:

a. Submit documentation for each employee to be engaged in lead disturbance work or that will be potentially exposed to lead that shows the employee has been trained in lead exposure in accordance with WAC 296-155-176.
b. Current respirator fit test for applicable respirator as determined by the Competent Person and certification of medical monitoring for respirator use.

1.12 PERIODIC SUBMITTALS

A. SCHEDULE CHANGES - Submit changes in project schedule or personnel at least 48 hours prior to the effective time of change. Note: For schedule changes the Contractor shall provide an updated signed acknowledgement form.

B. WORK PLAN CHANGES - Submit updated documentation for any submittal requirements that may have changed, reached expiration, and/or cancellation during the course of the project.

C. PERSONNEL AIR MONITORING RESULTS - Have Contractor's Certified Lab submit by e-mail/facsimile within 24 hours of receipt of sample analytical results of initial and periodic personnel air sampling.

D. WASTE STREAM CHARACTERIZATION - Provide TCLP analytical results for each construction debris waste stream, prior to disposal of any potentially lead-paint contaminated waste as other than "Hazardous Waste," showing the leachable lead content is less than the Washington State Department of Ecology threshold for disposal as "dangerous waste."

E. Site inspection process logs / documents if TCLP fails;

F. Qualification / certificates of lead waste transportation subcontractor, if applicable;

G. Qualification / certification of lead waste disposal / recycle facilities, if applicable;

H. Description of how final lead waste transportation and disposition will be documented. If TCLP fails; and

1.13 FINAL SUBMITTALS: The Contractor shall submit the following documents to the Owner's Hazardous Materials Consultant within thirty (30) days of completion of abatement work:

A. Project daily logs - Provide Contractor's daily logs for all "lead-paint" work, including identification of work area, individuals accomplishing "lead-paint" work, personal protective equipment, work practices, and engineering controls used to control exposure, and start and completion times for work.

B. Project "Start and Finish" dates.

C. Air Monitoring - Provide signed air monitoring data sheets and laboratory reports.

D. Worker Biological Monitoring - Provide copies of post-abatement biological monitoring for blood lead levels (if "lead action level" exceeded) for all workers who worked on the project that were exposed above the PEL. Tests shall have been taken within 10-days of worker's last lead exposure.

E. Waste Shipment Records - Provide lead hazardous waste shipment records (Manifest EPA form 8700-22) if required.

F. Clearance Records - Provide clearance submittals (as outlined in Part 3 of this Section), sampling data sheets (if required) and laboratory reports.

G. Disposal site receipts (if required)

H. TCLP Results

1.14 QUALITY ASSURANCE

A. On-site observation

1. The safety and protection of the contractor's employees, sub-contractor's employees, owner's employees, the facility, and the public is the sole responsibility of the contractor.
2. The owner's hazardous materials consultant or representatives of local, state or federal agencies may make unannounced visits to the site during the work. The contractor shall make two complete sets of clean, protective clothing and respirators available for such visitor use. It is the visitor's responsibility to ensure medical qualification, training, and current "fit test" prior to using any respirator provided by the contractor.
3. If the owner's hazardous materials consultant or agency visitor determines that practices are in violation of applicable regulations, or are endangering workers or the facility, they will immediately notify the contractor orally that operations must cease until corrective action is taken. Such notification will be followed by written confirmation within three (3) workdays.
4. Contractor shall stop work after receiving such notification. The work may not be restarted until the contractor receives written authorization from the owner's hazardous materials consultant.

5. All costs resulting from such stop work order will be borne by the contractor and will not be a basis for an increase in the contract amount or an extension of time.

1.15 LEAD DISTURBANCE WORK: For work involving lead disturbance only, the contractor shall comply with the following requirements:

A. Work Plan: The Contractor shall provide a “brief” Work Plan that identifies respiratory protection, engineering controls and work practices that will be followed until a negative exposure assessment can be produced and that will identify a plan for demolition debris waste stream sampling and characterization.

B. Training: Prior to commencement of work, each worker conducting lead disturbance work or handling lead wastes shall have successfully completed training as required by WAC-296-155-176.

C. Exposure Assessment: Prior to commencement of work, the Contractor shall accomplish an exposure assessment, based on the known scope of work, the concentration of lead in painted materials, and previous similar work. Note: If the Contractor is using air monitoring data from previous work sites for a negative exposure assessment, that data must be provided to, reviewed by, and concurred with by the Owner’s Hazardous Materials Consultant prior to reducing or eliminating respiratory protection for workers disturbing material with measurable lead concentration in the paint coating.

1. Exposure assessment shall be for the lead action level and shall be based on personal air monitoring accomplished by the Contractor of employees within the previous 12 months.
2. The previous air monitoring and sample analysis shall have been accomplished in accordance with the L&I lead standard and the data obtained shall be for work operations conducted under work place conditions “closely resembling” the processes, types of materials impacted, lead concentration in the paint, the condition of the paint, control methods used, and environmental conditions that are similar to those for the current project.
3. If a negative exposure assessment is not possible based on previous air monitoring, then the Contractor shall as a minimum.

    a. Provide appropriate respiratory protection to employees accomplishing the lead disturbance work.
    b. Accomplish initial air monitoring to determine the employee exposure.
    c. Obtain the concurrence of the Owner’s Hazardous Materials Consultant prior to determining that there is a negative exposure assessment and before downgrading or eliminating respiratory protection and decontamination requirements.
    d. In the absence of a negative exposure assessment, the Contractor shall comply with the requirements of worker protection and decontamination as specified in the L&I lead standard.

4. Waste stream testing for lead contamination.

a. Prior to disposal of any demolition debris, the Contractor shall accomplish waste stream testing for leachable lead contamination.
b. Testing shall be in accordance with the Department of Ecology Dangerous Waste Regulation, WAC 173-303, and shall comply with the U.S. Environmental Protection Agency Method No. 1311 for Toxic Characteristic Leaching Procedure (TCLP).
c. TCLP results must be less than 5.0 milligrams per liter of leachate (mg/l) for disposal of the debris as non-lead contaminated waste.

PART 2 - PRODUCTS

2.1 PERSONAL PROTECTIVE EQUIPMENT

A. RESPIRATORS - Respirators shall be selected and used in accordance with the manufacturer's recommendations, and shall be approved by NIOSH and MSHA for use in environments containing airborne lead. Approved respirators shall protect the worker as described in the Contractor's Respiratory Protection Plan. The Contractor shall provide approved respirators, personally issued to and marked for each individual worker. The Contractor shall also provide approved replacement filter canisters, for those types of respirators that utilize disposable filters.

B. PROTECTIVE CLOTHING - Personnel potentially exposed to lead dust or fumes above the PEL shall be provided with disposable whole-body protection as specified herein and such protection shall be worn properly. The Contractor shall provide personal protective equipment and clothing at no cost to the workers.

2.2 DECONTAMINATION

A. WASH STATION - For work that disturbs lead-containing paint, the contractor shall supply a wash station, as a minimum.

2.3 WARNING SIGNS AND TAPE

A. Warning signs and tape shall be posted at the boundaries and entrances to lead disturbance and abatement work areas. Signs required by other statutes, regulations, or ordinances may be posted in addition to, or in combination with, this warning sign. Warning signs and tape shall conform to the requirements of WAC 296-155-176.

2.4 WARNING LABELS

A. Warning labels shall be affixed to all hazardous waste disposal containers as described in the Contractor's approved Solid Waste Disposal Plan. Labeling shall conform to WAC 296-155-176 and 49 CFR 100-180.

2.5 TOOLS

A. Vacuum cleaners shall be equipped with HEPA filters. Power tools to remove lead-containing material shall have been approved for use by the Owner's Hazardous Materials Consultant. Open-flame and electric element heat-gun type tools with temperatures in excess of 700° F shall not be used to remove lead-containing material. All residual lead contamination shall be removed from reusable tools being removed from lead disturbance or abatement work areas. Electrical tools and equipment shall be UL listed.

2.6 EXPENDABLE SUPPLIES

A. Flame resistant 6-mil thick polyethylene sheet plastic (in accordance with NFPA 701) shall be provided in widths necessary to minimize seams.

2.7 Safety Data Sheets **(**SDSs**)**

A. SDSs shall be provided for all chemical materials brought onto the work-site.

2.8 OTHER ITEMS

A. Other items, such as consumable materials, disposable and/or reusable cleaning equipment and hand tools, or miscellaneous construction equipment and materials, shall be provided in sufficient quantity as necessary to fulfill and complete the requirements of the contract. Electrical equipment and supplies shall be UL listed.

2.9 ENCAPSULANTS

A. Encapsulants shall contain no toxic or hazardous substances. Encapsulants shall be compatible with the products to which they are applied.

PART 3 - EXECUTION

3.1 GENERAL**:** Lead disturbance work shall be performed in accordance with the Contractor's approved work plan, applicable regulations and this specification.

3.2 WORK STOPPAGE

A. The Contractor shall stop work when the Owner's Hazardous Materials Consultant, or a representative of a regulatory agency, determines that the work is not in compliance with the Contractor's approved work plan, these specifications, and applicable laws and regulations. The Contractor shall stop work and notify the Owner's Hazardous Materials Consultant whenever the measured concentrations of lead outside the work area equal 30 $\mu g/m^3$ for airborne lead (or the pre-work background levels, whichever is higher). When such work stoppage occurs, the cause of the contamination shall be corrected and

the damaged or contaminated area shall be restored to its original decontaminated condition by the Contractor at no expense to the Owner.

3.3 FURNISHINGS: The Owner will remove all furniture and equipment from the area before lead disturbance work begins.

3.4 BUILDING VENTILATION SYSTEM

A. Building ventilation systems supplying air into or returning air from lead work areas shall be shut down and isolated by airtight seals.

3.5 BUILDING ELECTRICAL SYSTEMS

A. A Certified Electrical Contractor shall de-energize, “lock-out,” and “tag-out” electrical service where necessary, and the Contractor’s Competent Person shall verify the “lock-out,” “tag-out,” prior to commencing any wet washing and/or wet removal work. Temporary electrical service, equipped with ground fault circuit interrupter (GFCI) protection, shall be provided where needed.

3.6 INITIAL DETERMINATION**:** (Note: An initial determination is required in the absence of acceptable prior exposure data.)

A. The Contractor shall establish an initial work area for each material to be disturbed and each disturbance procedure.

B. These work areas shall be isolated from the rest of the building. Personnel working in these areas shall wear respiratory protection and personal protective equipment as directed by the Competent Person.

C. Personal and work area air monitoring shall be performed as directed by the Competent Person. Operational decontamination facilities shall be available.

D. Work performed shall be representative of the work to be done during the remainder of the project.

3.7 RESPIRATOR EVALUATION

A. Upgrading, downgrading, or not requiring respirators shall be recommended by the Contractor’s Competent Person based on the measured airborne lead-containing dust concentrations and must be approved by the Hazardous Materials Consultant.

B. If the Contractor’s Competent Person determines that it is necessary to upgrade the respiratory protection, based on the measured airborne lead-containing dust concentrations, the upgrade shall be implemented immediately, followed by notification to the Owner’s Hazardous Materials Consultant.

C. Recommendations to downgrade respirator type or not require respirators shall be submitted in writing to the Owner's Hazardous Materials Consultant for review and written approval prior to implementation.

3.8 DISTURBANCE AND REMOVAL METHODS

A. Lead disturbance and removal shall be done as described in the Contractor's approved work plan and in accordance with applicable regulations.

1. Fire exits shall not be blocked.
2. The Hazardous Materials Consultant must concur in writing with the proposed Work Plan, prior to commencement of work.

3.9 SAMPLING **OF** WASTE MATERIALS

A. Project wastes shall be tested prior to transport and disposal as required by WAC 173-303.

3.10 HAZARDOUS WASTE DISPOSAL

A. Hazardous project wastes shall be disposed of as required by WAC 173-303 and the Contractor's approved work plan.

3.11 CONSTRUCTION **(**NON**-**HAZARDOUS**)** WASTE DISPOSAL

A. Dispose of solid (non-hazardous) waste, as determined by testing, as ordinary construction waste in accordance with the applicable federal, state, and local laws and regulations.

B. Burning of waste is prohibited.

3.12 SALVAGEABLE MATERIALS

A. The Contractor may salvage metallic lead and other materials to keep such materials from entering the project waste stream.

B. Such salvage shall be sold or transferred accompanied by a document of exempt status, in accordance with 40 CFR 261.

END OF SECTION 028300

SECTION 02 8400 - ARSENIC REMEDIATION

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

A. The work requires the disturbance and disposal of arsenic-containing brick masonry unit (BMU) mortar from Fire Station #63, located at 33414 21st Avenue South, Auburn, Washington; as shown on the drawings and as specified herein:

1. BMU mortar sampled from Fire Station #63 was analyzed and reported to contain 22 ppm of arsenic. The arsenic sampling data is included in the Limited Hazardous Materials Survey Report, which is provided as an appendix to the Summary of Hazardous Materials Work Section 011110 of these Specifications.

B. The work includes the following:

1. Renovation of space.

C. The Contractor will as a minimum:

1. Accomplish initial exposure assessments for each category of work (disturbance) in accordance with WAC 296-848-20060.
2. Accomplish dust control using wet methods or as required in accordance with WAC 296-848-400.
3. Accomplish waste stream sampling as needed for hazardous arsenic concentrations in accordance with WAC 173-303.

D. Provide the Hazardous Materials Consultant with copies of initial arsenic exposure monitoring and waste stream sampling required by this Section, along with asbestos periodic submittals required by Section 02 8200.

1.2 RELATED WORK SPECIFIED ELSEWHERE: Conform to General conditions, Supplementary Conditions, the Modifications thereto, and Division 1- General Requirements.

A. 011110 Summary of Hazardous Materials Work

B. 028200 Asbestos Remediation Specification

C. 028300 Lead-Containing Paint Disturbance Specification

D. Hazardous Materials Removal Drawings

E. Architectural, Electrical, and Mechanical Design and Demolition Drawings

1.3 DEFINITIONS AND ABBREVIATIONS**:** Definitions and abbreviations pertaining to arsenic-containing material removal and disposal are provided in the regulations, codes, and standards listed in Paragraph 1.4 of this Section.

A. Owner's Hazardous Materials Consultant – The Owner's Hazardous Materials Consultant is the firm/individual responsible for review and approval of Asbestos/Hazardous Materials submittals, for response technical response to asbestos/hazardous materials removal questions, for monitoring of asbestos/hazardous materials work and for final visual inspection and final air clearance monitoring as specified herein. For this project, the Hazardous Materials Consultant is EHS-International, Inc., 1011 SW Klickitat Way Suite 104, Seattle, WA, (206) 381-1128 phone or dericae@ehsintl.com e-mail.

1.4 APPLICABLE PUBLICATIONS

A. General Requirements:

1. The publications listed below form a part of this specification to the extent referenced.
2. All work shall be performed in full compliance with the regulations listed in this section and the Uniform Building Code, Uniform Plumbing Code, Uniform Fire Code, Code of Federal Regulations (CFR) and the National Electrical Code, and as specified herein.

B. Title 29 CFR Part 1910 – General Occupational Safety and Health Standards

1. Subpart E. Means of Egress
2. Subpart I. Personal Protective Equipment
3. Subpart Z. Toxic and Hazardous Substances

C. Title 29 CFR Part 1926 – Safety and Health regulations for Construction

1. Subpart C. General Safety and Health Provisions
2. Subpart D. Occupational Health and Environmental Controls

D. 29 CFR 1910.1018 - Arsenic

1. Subpart F. Fire Protection and Prevention
2. Subpart Z. Toxic and Hazardous Substances

E. Title 40 CFR - Environmental Protection Agency

1. 40 CFR 260 Hazardous Waste Management System: General
2. 40 CFR 261 Identification and Listing of Hazardous Waste
3. 40 CFR 262 Standards Applicable to Generators of Hazardous Waste
4. 40 CFR 263 Standards Applicable to Transporters of Hazardous Waste
5. 40 CFR 270 Hazardous Waste Permit Program

F. Title 49 CFR 100-180 and 382 - Department of Transportation

G. State of Washington Administrative Codes (WAC):

1. WAC 173-303 Dangerous Waste Regulations
2. WAC 296-62-054 Hazard Communication
3. WAC 296-62-300 Hazardous Waste Operations and Emergency Response
4. WAC 296-155 Safety Standards for Construction Work
5. WAC 296-800 Safety and Health Core Rules
6. WAC 296-848 Arsenic

H. Washington Statutes Revised Code of Washington (RCW)

1. 49.17 RCW Washington Industrial Safety and Health Act
2. 70.105 RCW Hazardous Waste Management Act

I. American National Standards Institute (ANSI)

1. Z9.2 Local Exhaust Systems
2. Z87.1 Eye and Face Protection
3. Z88.2 (2015) Practices for Respiratory Protection

J. American Society for Testing and Materials (ASTM)

1. D 4397 Polyethylene Sheeting

K. Federal Standards

1. 313B Material Safety Data Sheets

L. International Fire Code Institute

1. Uniform Fire Code 2009 UFC Standards

M. National Fire Protection Association (NFPA)

1. 701 Fire Tests for Flame Resistant Textiles and Films

N. National Institute of Occupational Safety and Health (NIOSH)

1. 1984 Manual of Analytical Methods, 3rd Edition

O. UL 586 High-Efficiency, Particulate, Air Filter Units

1.5 ARSENIC WORK AREAS

A. Until a “negative exposure assessment” is achieved, the Contractor shall identify each arsenic work area where exposure to arsenic above the action level (WA State Department of Labor and Industries Division of Occupational Safety and Health (L&I DOSH) Regulation WAC 296-848-40025) is possible and establish a line of demarcation for the area with posted warning signs (Regulated Work Area). A logbook shall be kept documenting personnel ingress and egress for each work area. Only personnel trained

and protected in accordance with WAC 296-848-100 shall be allowed beyond the posted warning signs and tape. In those areas where arsenic work is expected, or has been shown by testing to exceed the L&I DOSH permissible exposure limit (PEL), the Contractor shall erect a negative pressure containment (Contained Work Area).

1.6 MEDICAL REQUIREMENTS

A. If exposure exceeds the L&I DOSH Action Level, medical testing, evaluations, certifications, and record-keeping requirements shall conform to WAC 296-848-30030.

B. If, applicable, provide random drug testing, as required by 49 CFR 382, for all drivers of vehicles transporting hazardous materials.

1.7 TRAINING: Prior to commencement of work, the employer shall effectively communicate the hazards of inorganic arsenic to each worker conducting brick wall demolition, tuck pointing or disturbance work or handling arsenic-contaminated mortar wastes, according to WAC 296- 848-30005.

1.8 RESPIRATORY PROTECTION

A. The Contractor shall establish and implement a respiratory protection program in accordance with WAC 296-848-40045.

1. Respirators shall be supplied by the Contractor at no cost to the employees.
2. Respirator fit testing for each worker shall be conducted and administered prior to the use of respiratory protection.

1.9 HAZARD COMMUNICATION PROGRAM: A hazard communication program shall be established and implemented in accordance with WAC 296-62-300

1.10 SAFETY, HEALTH, AND ENVIRONMENTAL COMPLIANCE: The Contractor shall comply with all applicable safety, health, and environmental laws, ordinances, rules and regulations of federal, state, regional and local authorities.

1.11 PERMITS, LICENSES, NOTIFICATIONS, AND EPA IDENTIFICATION NUMBERS: The Contractor shall pay all fees for and obtain all necessary permits, licenses, and EPA identification numbers required for removal of arsenic-contaminated materials, storage, transportation and disposal. Timely notification shall be furnished as required by federal, state, regional and local authorities, and as specified herein.

1.12 SUBMITTALS

A. Initial Submittal: The Contractor shall submit one bound, indexed or electronic copy of the following pre-work documentation for the Owner’s Hazardous Materials Consultant’s

review, approval, or rejection, at least three working days prior to proceeding with additional work. The Contractor is responsible for delays caused by late, incomplete or improperly organized and indexed submittals. Submittal packages shall be organized and indexed in the order provided in the checklist 1.12.1 through 1.12.8. Submittals not properly organized and indexed will be rejected. **It is the Contractor's responsibility to insure all subcontractors disturbing arsenic-containing BMU mortar are included in the Section 028400 pre-work submittals.**

1. Arsenic Management Plan: An arsenic management plan shall include, but not be limited to:

    a. Description of anticipated worker exposure assessment(s) for the project.
    b. Description of personal protective equipment to be used.
    c. Description of construction and demarcation of work areas.
    d. Description of construction of decontamination units.
    e. Evidence that each employee has completed training on arsenic-contaminated materials and waste covering the requirements of WAC 296-848-300.

2. Competent Person: The Contractor's full-time on-site supervisor shall be designated as, and shall be qualified to be, a "competent person" experienced in the administration and supervision of inorganic arsenic-contaminated materials and waste, as specified in WAC 296-848-100
3. Testing Laboratories: The Contractor shall identify each testing laboratory selected to perform sample analysis and reporting. For each laboratory selected, the following information (signed by the Testing Laboratory and the Contractor) shall be submitted (not all laboratories need to have all certifications/proficiencies).

    a. The name, physical address, and telephone numbers of the laboratory and the name, title, and resume of the person responsible for arsenic analysis
    b. Evidence that the laboratory is currently judged proficient in arsenic analysis, as determined by the American Industrial Hygiene Association Industrial Hygiene Proficiency Analytical Testing Program (IHPAT).
    c. Evidence that the laboratory is currently certified by OSHA to perform blood arsenic analysis.
    d. Copies of the Contractor's letter to each of their independent testing laboratories, directing each to release all the results for this project to the Owner's Hazardous Materials Consultant, as these results become available and as specified herein.
4. Solid Waste Disposal Plan: Submit a written Solid and Hazardous Waste Disposal Plan with the following information:

    a. The name, address, operator's name, and phone number of his proposed Solid Waste Disposal Facility and of his proposed Hazardous Waste Disposal Facility.
    b. Written evidence that the proposed Waste Disposal Facilities are approved and permitted for solid and/or hazardous waste disposal by the US Environmental Protection Agency (USEPA), state, and local regulatory agencies.

c. Written procedures to characterize the project waste by the TCLP test to determine if the waste is hazardous.
d. In the event the waste is declared as hazardous waste, the Owner's USEPA Hazardous Waste Generator number shall be submitted by the Contractor. If the Owner does not have a generator number, the Contractor shall prepare and submit all documents as required to obtain one for the Owner.

5. Waste Transporter: If required, submit the qualifications of each waste transporter to be used.
6. Respiratory Protection Program: Submit a copy of the respiratory protection program to the Owner's Hazardous Materials Consultant.
7. Employee Training and Certification: Submit the following documentation for each employee to be engaged in arsenic-contaminated material disturbance and management work or that will be potentially exposed to arsenic.

   a. Evidence that each employee has completed training on arsenic-contaminated materials and waste covering the requirements of WAC 296-848-100.
   b. Certification of respirator fit-testing in accordance with regulations.
8. Substitutions: Submit proposals for substitutions of materials, equipment and methods as permitted by the Contract.

B. Periodic Submittals

1. Submit changes in project schedule or personnel at least 48 hours prior to the effective time of change. Submit updated documentation for any submittal requirements that may have changed, reached expiration, and/or cancellation during the course of the project.
2. Prior to disposal of any arsenic-contaminated waste as other than "Hazardous Waste," the Contractor shall submit TCLP test results showing the leachable arsenic content is less than the Washington State Department of Ecology threshold for disposal as "dangerous waste.

C. Final Submittals

1. The Contractor shall submit the following documents to the Owner's Hazardous Materials Consultant within thirty (30) days of completion of arsenic disturbance work.

   a. Project daily logs
   b. Contractor's actual project "Start and Finish" dates.
   c. Air monitoring data sheets and laboratory reports.
   d. Copies of post-abatement biological monitoring for blood arsenic levels for all workers who worked on the project that were exposed above the PEL. Tests shall have been taken within 10-days of worker's last arsenic exposure.
   e. Waste Shipment Records (Manifest EPA form 8700-22) if required.
   f. Copies of the analytical results for all TCLP waste characterization tests.
   g. Clearance sampling data sheets (if required) and laboratory reports.
   h. Disposal site receipts (if required).

i. Final clearance submittals as outlined in Part 3 of this specification (if required).

1.13 QUALITY ASSURANCE

A. On-site Observation:

1. The safety and protection of the Contractor's employees, sub-contractor's employees, faculty, the facility, and the public is the sole responsibility of the Contractor.
2. The Hazardous Materials Consultant or representatives of local, State or Federal agencies may make unannounced visits to the site during the work. The contractor shall make two complete sets of clean, protective clothing and respirators available for such visitor use. It is the visitor's responsibility to ensure medical qualification, training, and current "fit test" prior to using any respirator provided by the contractor.
3. If the Hazardous Materials Consultant or agency visitor determines that practices are in violation of applicable regulations, or are endangering workers or the facility, they will immediately notify the Contractor orally that operations must cease until corrective action is taken. Such notification will be followed by written confirmation within three (3) workdays
4. Contractor shall stop work after receiving such oral notification. The work may not be restarted until the Contractor receives written authorization from the Hazardous Materials Consultant.
5. All costs resulting from such stop work order will be borne by the Contractor and will not be a basis for an increase in the contract amount or an extension of time.

PART 2 - PRODUCTS

2.1 PERSONAL PROTECTIVE EQUIPMENT

A. The Contractor shall provide personal protective clothing and equipment at no cost to the employees and shall ensure that it is worn properly. Three complete sets of personal protective equipment shall be made available daily to the Owner's Hazardous Materials Consultant, and other authorized visitors, for entry to arsenic-containing material work areas.

1. Respirators: Respirators shall be selected and used in accordance with the manufacturer's recommendations, and shall be approved by NIOSH and MSHA for use in environments containing airborne arsenic. Approved respirators shall protect the worker as described in the Contractor's Respiratory Protection Plan. The Contractor shall provide approved respirators, personally issued to and marked for each individual worker. The Contractor shall also provide approved replacement filter canisters, for those types of respirators that utilize disposable filters
2. Whole Body Protection: Personnel potentially exposed to arsenic dust or fumes above the PEL shall be provided with disposable whole-body protection as

specified herein and such protection shall be worn properly. The Contractor's CIH shall select and approve the disposable whole body protection to be used. The Contractor shall provide personal protective equipment and clothing at no cost to the workers.

2.2 DECONTAMINATION UNIT

A. For work that disturbs arsenic-containing materials, the contractor shall supply a wash station, as a minimum.

B. If containment is required for arsenic work, a temporary three-stage decontamination unit, attached in a leak-tight manner to each Contained Work Area, shall be provided. Decontamination units shall consist of a clean room equipped with separate lockers for each worker, a shower room, and an equipment locker room equipped with separate lockers for each worker.

1. Shower specifications: Flow and temperature controls shall be located within the shower and be adjustable to the user. Water from the shower room shall not be allowed to wet the floor in the clean room

2.3 WASTE WATER FILTERS

A. The wastewater filters shall be installed in series, with the first stage filter having a pore-size of 20 microns, and the second stage filter having a pore-size of 5 microns. The final filtration shall be sufficient to meet discharge standard below. The wastewater pump shall be sized for 1.25 times the showerhead flow-rate at a pressure sufficient to satisfy the filters' head-loss and discharge line losses. Instantaneous water discharged to the sewer system shall contain no more than 4.0 ppm arsenic or per liter of water according to the King County Industrial Waste Local Discharge Limits, Section 6.1.7. All filters shall be disposed of as arsenic-contaminated waste.

2.4 WARNING SIGNS AND TAPE

A. Warning signs and tape shall be posted at the boundaries and entrances to arsenic work areas. Signs required by other statutes, regulations, or ordinances may be posted in addition to, or in combination with, this warning sign. Warning signs and tape shall conform to the requirements of WAC 296-848-100.

2.5 WARNING LABELS

A. Warning labels shall be affixed to all hazardous waste disposal containers as described in the Contractor's approved Solid Waste Disposal Plan. Labeling shall conform to WAC 296-848-100 and 49 CFR 100-180.

2.6 NEGATIVE PRESSURE EXHAUST SYSTEM

A. If any arsenic disturbance work is likely to result in airborne exposure greater than the L&I DOSH permissible Exposure Limit (PEL), the Contractor shall accomplish such work inside a negative pressure enclosure, using negative pressure exhaust systems. The negative pressure exhaust system shall operate continuously (24 hours a day) during work with arsenic-contaminated materials. The negative pressure exhaust system equipment shall be selected to provide a minimum of 4 air changes per hour under load within the work area. The negative pressure exhaust system shall have a minimum of two stages of pre-filtration ahead of the HEPA filter: The HEPA filter shall bear the UL-586 label. In no case shall the building ventilation system be used as the local exhaust for the contained work area. Terminate the exhaust outside of the building. The exhaust ventilation system equipment shall be equipped with lockout protection to prevent operation without the HEPA filter properly installed. The exhaust system equipment shall be equipped with the following instrumentation: a static pressure gauge with low flow alarm, an elapsed time indicator (hour meter), automatic shutdown capability in the event of a major rupture in the HEPA filter or blocked air discharge and an automatic re-start when power is restored after a power failure.

2.7 PRESSURE DIFFERENTIAL MONITORING EQUIPMENT

A. For contained areas, provide continuous monitoring of the pressure differential with an automatic recording instrument for each contained work area. The instrument shall be located in a clean area where personnel have access to it without respiratory protection. The instrument shall be fitted with an alarm should the negative pressure drop below 0.02 inches of water column relative to the air outside containment.

2.8 TOOLS

A. Vacuum cleaners shall be equipped with HEPA filters. Power tools to remove arsenic-containing material shall have been approved for use by the Hazardous Materials Consultant. Open-flame and electric element heat-gun type tools with temperatures in excess of 700° F shall not be used to remove arsenic-containing material. All residual arsenic contamination shall be removed from reusable tools being removed from arsenic disturbance or abatement work areas. Electrical tools and equipment shall be UL listed.

2.9 AIR MONITORING EQUIPMENT

A. Monitoring equipment capable of measuring airborne arsenic dust must be used for measurement of employee exposures.

2.10 EXPENDABLE SUPPLIES

A. Flame resistant 6-mil thick polyethylene sheet plastic (in accordance with NFPA 701) shall be provided in widths necessary to minimize seams.

2.11 SAFETY DATA SHEETS (SDSs)

A. SDSs shall be provided for all chemical materials brought onto the work-site.

2.12 OTHER ITEMS

A. Other items, such as consumable materials, disposable and/or reusable cleaning equipment and hand tools, or miscellaneous construction equipment and materials, shall be provided in sufficient quantity as necessary to fulfill and complete the requirements of the contract. Electrical equipment and supplies shall be UL listed.

2.13 ENCAPSULANTS

A. Encapsulants shall contain no toxic or hazardous substances. Encapsulants shall be compatible with the products to which they are applied.

PART 3 - EXECUTION

3.1 ARSENIC WORK PROCEDURES

A. Arsenic disturbance work shall be performed in accordance with the Contractor's approved work plan, applicable regulations and this specification.

B. Remove and dispose of waste mortar in accordance with the Contractor's approved work plan, applicable regulations and these specifications.

C. Test all potentially hazardous waste streams in accordance with the Contractor's approved work plan, applicable regulations and these specifications and properly dispose of all hazardous waste.

D. The Contractor will prepare "arsenic work areas" such that there will be "no visible emissions" of dust. The Hazardous Materials Consultant will inspect the work area for cleanliness simultaneous to inspection for arsenic-removal acceptance.

3.2 FURNISHINGS – not used.

3.3 BUILDING VENTILATION SYSTEM

A. Building ventilation systems supplying air into or returning air from an arsenic work area shall be shut down and isolated by airtight seals.

3.4 BUILDING ELECTRICAL SYSTEMS

A. Electrical service shall be disconnected where necessary for wet washing and/or removal. Temporary electrical service, equipped with ground fault protection, shall be provided where needed.

3.5 INITIAL DETERMINATION

A. (Note: An initial determination is required in the absence of acceptable prior exposure data.) The Contractor shall establish an initial work area for each disturbance procedure. These work areas shall be isolated from the rest of the building. Personnel working in these areas shall wear respiratory protection and personal protective equipment as determined by the Contractor and as specified in the approved Work Plan. Personal and work area air monitoring shall be performed In accordance with WAC 296-848. Operational decontamination facilities shall be available. Work performed shall be representative of the work to be done during the remainder of the project.

3.6 PRE-CLEANING

A. Surfaces shall be pre-cleaned by HEPA vacuum and wet washed and wiped prior to the establishment of a work area as required by the Contractor's approved work.

3.7 DECONTAMINATION PROCEDURES

A. Worker and material decontamination procedures shall be as described in the Contractor's approved work plan. Worker decontamination shall be as directed by the Contractor's competent person..

3.8 WASTE STORAGE

A. The Contractor shall store solid wastes as describe in the Solid and Hazardous Waste Disposal Plan.

3.9 RESPIRATOR EVALUATION

A. Upgrading, downgrading, or not requiring respirators shall be recommended by the Contractor based on the measured airborne arsenic-containing dust concentrations. Recommendations to upgrade the respiratory protection shall be implemented immediately, followed by notification to the Hazardous Materials Consultant. Recommendations to downgrade respirator type or not require respirators shall be submitted in writing to the Hazardous Materials Consultant for review and written approval prior to implementation.

3.10 DISTURBANCE AND REMOVAL METHODS

A. Arsenic-containing mortar disturbance and removal shall be done as described in the Contractor's approved work plan and in accordance with applicable regulations.

B. The Owner's Hazardous Materials Consultant shall be notified 48 hours in advance of any arsenic disturbance taking place.

C. Fire exits shall not be blocked.

D. The Contractor shall propose an appropriate method in the Work Plan, and if necessary, receive approval from L&I DOSH and/or PSCAA for any “alternate removal methods”.

E. The Owner’s Hazardous Materials Consultant must concur in writing with the proposed Work Plan, prior to commencement of work.

3.11 FINAL CLEANING AND VISUAL INSPECTION

A. Final cleaning and visual inspection of each arsenic work area shall be done as described in the Contractor’s approved work plan.

3.12 WORK AREA FINAL INSPECTION

A. The Owner’s Hazardous Materials Consultant may accomplish final visual inspection of each arsenic work area where exposure readings exceed the L&I DOSH Action Level along with the Contractor, if the Owner’s Hazardous Materials Consultant chooses not to accomplish this inspection then it is the Contractor’s responsibility.

B. The Owner’s Hazardous Materials Consultant may conduct concurrent clearance testing.

3.13 SAMPLING

A. Sampling shall be conducted in accordance with the Contractor's Sampling and Analysis Plan. The Owner’s Hazardous Materials Consultant may conduct air monitoring in the Contractor’s work areas and on the Contractor’s employees; however, this additional sampling in no way relieves the Contractor of his responsibility to conduct his own samplng.

3.14 SAMPLING OF WASTE MATERIALS

A. Project wastes shall be tested prior to transport and disposal as required by WAC 173-303.

3.15 HAZARDOUS WASTE DISPOSAL

A. Hazardous project wastes shall be disposed of as required by WAC 173-303 and the Contractor’s approved work plan.

3.16 CONSTRUCTION (NON-HAZARDOUS) WASTE DISPOSAL

A. The Contractor shall dispose of solid (non-hazardous) waste, as determined by testing, as ordinary construction waste in accordance with the applicable federal, state, and local laws and regulations. Burning of waste is prohibited.

END OF SECTION 028400

SECTION 028500 - Hg LIGHT TUBE AND THERMOSTAT REMEDIATION

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

A. The work includes the removal and recycling of Mercury (Hg)-containing light tubes and compact fluorescent light (CFL) bulbs and Hg-containing thermostats: The work requires the recycling of Hg-containing fluorescent light tubes and CFL bulbs and Hg-containing thermostats from Fire Station #63, located at 33414 21st Avenue South, Federal Way, Washington; as shown on the drawings and as specified herein, prior to renovation of the buildings on the facility site. Note: Refer to Hazardous Materials removal drawings for identification of impacted buildings on site.

B. General: Use HAZARDOUS MATERIALS SUMMARY provided in project drawings for Base Bid Quantities of Universal Waste Materials.

1.2 WORK SPECIFIED ELSEWHERE

A. 011110 Summary of Hazardous Materials Work Report

B. 028200 Asbestos Remediation Specification

C. 028300 Lead-Containing Paint Disturbance Specification

D. 028400 Arsenic Remediation Specification

E. Hazardous Materials Removal Drawings

F. Architectural, Electrical, Plumbing, Structural and Mechanical Design and Demolition Drawings

1.3 GENERAL REQUIREMENTS

A. MERCURY-CONTAINING LIGHT TUBES AND THERMOSTATS: These Technical Specifications pertain to the handling of mercury-containing light tubes,CFL bulbs and thermostats.

B. HAZARDOUS MATERIALS: Hazardous materials shall mean all toxic and hazardous substances listed in 29 CFR 1910 Subpart Z.

C. WASHINGTON UNIVERSAL WASTE: Washington State Universal Waste, as applies to this project shall refer to mercury-containing thermostats, as described in WAC 173-303-573 (3), and fluorescent lamps/CFL bulbs, as described in WAC 173-303-573 (5).

D. SAFETY AND PROTECTION: The safety and protection of the Contractor's employees, sub-contractor's employees, the facility, and the public is the sole responsibility of the Contractor.

E. OWNER'S HAZARDOUS MATERIALS CONSULTANT: The Owner's Hazardous Materials Consultant is the firm/individual responsible for review and approval of Asbestos/Hazardous Materials submittals, for response technical response to asbestos/hazardous materials removal questions, for monitoring of asbestos/hazardous materials work and for final visual inspection and final air clearance monitoring as specified herein. For this project, the Hazardous Materials Consultant is EHS-International, Inc., 1011 SW Klickitat Way, Suite 104, Seattle, WA, (206) 381-1128 phone, (206) 254-4279 facsimile, dericae@ehsintl.com e-mail.

F. REGULATIONS: All work is required to comply with the following regulations

1. Title 40 Code of Federal Regulations (CFR): Environmental Protection Agency

a.	40 CFR 260	Hazardous Waste Management System: General
b.	40 CFR 261	Identification and Listing of Hazardous Waste
c.	40 CFR 262	Standards Applicable to Generators of Hazardous Waste
d.	40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
e.	40 CFR 270	EPA Administered Permit Programs: the Hazardous Waste Permit Program
f.	40 CFR 273	Universal Waste Management

2. Title 49 CFR: Department of Transportation Regulations: 49 CFR 100-180 & 382

3. Washington Administrative Codes (WAC):

a.	WAC 173-303	Dangerous Waste Regulations
b.	WAC 296-155	Safety Standards for Construction Work
c.	WAC 296-843	Hazardous Waste Operations
d.	WAC 296-901	Hazard Communication, Globally Harmonized System (GHS)

4. Washington State Statutes Revised Code of Washington (RCW)

a.	49.17 RCW	Washington Industrial Safety and Health Act
b.	70.105 RCW	Hazardous Waste Management Act

5. American National Standards Institute (ANSI)

a.	Z9.2	Local Exhaust Systems
b.	Z87.1	Eye and Face Protection
c.	Z88.2	(2015) Practices for Respiratory Protection

6. American Society for Testing and Materials (ASTM)

a.	D 4397	Polyethylene Sheeting

7. Federal Standards

a. 313B Material Safety Data Sheets

8. International Fire Code Institute

a. Uniform Fire Code 2009 UFC Standards

9. National Fire Protection Association (NFPA)

a. Fire Tests for Flame Resistant Textiles and Films

10. National Institute of Occupational Safety and Health (NIOSH)

a. 1984 Manual of Analytical Methods, 3rd Edition

1.4 MEDICAL REQUIREMENTS

A. Provide random drug testing, as required by 49 CFR 382, for all drivers of vehicles transporting hazardous materials.

1.5 INITIAL SUBMITTAL

A. Pre-Work Submittal Documentation: Submit one (1) indexed, bound or electronic copy of the following “pre-work” submittal, in accordance with contract submittal requirements, for review, comments, and approval, at least three (3) working days prior to scheduled commencement of work. The Contractor is responsible for delays caused by late submittals. Submittal packages shall be organized and indexed in the order provided in the checklist 1.5.A.1 through 1.5.A.6. See Sub-sections 1.5.B through 1.5.F for detailed descriptions of individual submittal requirements. Submittals not properly organized and indexed will be rejected. Following submittal approval, provide the required number of copies of the approved submittal to the Hazardous Materials Consultant as identified in the general conditions for all submittals:

1. Competent Person knowledgeable in PCBs

2. Hazardous materials work plan.

3. Solid Waste Disposal Plan.

4. Fluorescent Light Tube, CFL Bulb, & Thermostat Work Plan.

5. Hazardous Waste ID Number.

B. Work Plan

1. The Work Plan shall be prepared in the form of checklists and shall include specific procedures for:
   a. Fluorescent light tube removal and packaging for shipment to recycler.
   b. Work area preparation and protection procedures, including reference to work site shop drawings.

c. Worker protection and decontamination procedures, including normal removal and “spill” response.
d. Waste handling, packaging, labeling, and manifesting procedures.
e. The Work Plan shall contain sufficient detail so that a skilled worker, by following the Plan, can perform acceptable work in a safe manner to remove mercury-containing light tubes and thermostats.

2. Safety Data Sheets (SDSs): The Contractor shall maintain on-site SDSs for each solvent and degreaser proposed to be used.

C. Solid Waste Disposal Plan: Submit a written Solid and Hazardous Waste Disposal Plan with the following information:

1. The name, address, operator's name, and phone number of his proposed Solid Waste Disposal Facility and of his proposed Hazardous Waste Disposal Facility and Mercury Tube/Lamp Recycling Facility.

2. Written evidence that the proposed Waste Disposal Facilities are approved and permitted for solid and/or hazardous waste disposal by the Environmental Protection Agency (EPA), state, and local regulatory agencies.

3. The Contractor shall submit the owner’s EPA Hazardous Waste Generator number. If the owner does not have a generator number, the Contractor shall prepare and submit all documents as required to obtain one for the owner.

4. Waste Transporter: Submit the qualifications of each waste transporter to be used.

5. Waste Carrier and Disposal Site Designation: The Contractor shall submit the name, address, and qualifications of his/her proposed waste transporter. The Contractor shall designate the EPA-approved recycling site to which he/she proposes to ship the universal waste.

D. Fluorescent Light Tubes, CFL Bulbs, & and thermostats Work Plan (General): Include a detailed plan of the procedures proposed for use in complying with the requirements, including the following:

1. Work Area: General description of the preparation of the work area, setting barriers, arrangement for temporary services. Describe procedure for removing tubes, CFL bulbs, and thermostats and how they will be packaged for transport offsite.

2. Handling of Tubes: General description of the proposed removal, handling methods, packaging for transport to recycle/disposal facility.

3. Submit name, location, and qualifications of hazardous materials transportation subcontractor.

4. Worker Protection: Description of safeguards to protect workers handling broken/leaking, tubes, bulbs and cleanup procedures.

5. PPE: Description of personal protective equipment to be worn by contractor's personnel and visitors.

6. Recordkeeping Procedures: For packaging, transportation and recycling. Labeling procedures for fluorescent tube packaging.

7. Recycling/Disposal Site: Name and location of the recycling site.

E. Hazardous Waste Identification Number: USEPA Hazardous Waste Generator identification number for the purpose of accumulating hazardous waste in accordance with 40 CFR 262 and an USEPA identification number for transporting hazardous waste, or documentation from the waste transporter and disposal site indicating the waste generator identification number is not required.

1.6 FINAL SUBMITTAL

A. The Contractor shall submit three copies of the following documents within thirty (30) days of completion of abatement work

1. A list of all employees who worked on the project, daily sign-in sheets, and copies of their current certification (if not previously submitted).

2. Contractor's actual "start and finish" project dates.

3. All hazardous waste shipping manifests for Hg-containing light tubes & Hg-containing thermostats.

PART 2 - PRODUCTS

2.1 PROTECTIVE CLOTHING

A. The Contractor shall provide approved aprons, gloves, goggles, face shields, and hard-hats for all workers engaged in mercury-containing materials removal.

PART 3 - EXECUTION

3.1 PREPARATION

A. ELECTRICAL POWER: The Contractor shall verify that the electrical power to the affected components is deactivated, disconnected, and locked-out.

B. LOADED DISPOSAL DRUMS: The Contractor shall provide handling equipment to move recycling containers loaded with discarded mercury-containing waste.

C. DECONTAMINATION PROCEDURES: All personnel involved with handling and recycling of mercury-containing light tubes and thermostats will comply with the following decontamination procedures:

1. Establish a change area where personnel will don or remove personal protection equipment (PPE).

2. The workers will utilize assembly-line decontamination stations where used equipment/gear will be removed and stored in approved drums or storage containers.

3. PPE materials shall be removed and placed in approved disposal containers.

4. The workers will proceed through decontamination stations and thoroughly clean their hands and exposed surfaces with soap and rinse with clean water.

5. All rinsates from the decontamination procedures will be stored in approved containers and properly disposed.

D. WASH-DOWN STATION: A wash-down station will be provided with "full person" capabilities for decontamination in a spill response.

E. SCHEDULE: The Contractor shall develop and provide the Hazardous Materials Consultant with a work schedule including, mobilization, identification of planned work areas, and start and completion dates, and shall update the schedule for any changes.

3.2 WORKER PROTECTION

A. APPROVED WORK PLAN PROCEDURES:

1. All personnel entering the work area shall sign the daily log and put on clean protective clothing.

2. Basic protective clothing shall consist of aprons, gloves, goggles, face shields, and hard hats--with the addition of approved full body coveralls, bib-type aprons, and respirators as conditions warrant.

3. A contaminated material disposal drum, 6 mil. plastic wrapping and tape, or appropriate bagging materials shall be available for leaking ballasts and/or oil-contaminated components.

B. REMOVAL AND RECYCLING OF MERCURY-CONTAINING LIGHT TUBES

1. REMOVAL PROCEDURES: Light tubes and CFL bulbs and thermostats shall be removed in a manner to prevent breakage. If a tube, bulb, or lamp breaks immediately clean-up debris and place in a box specified for broken tubes. Broken tubes shall also be recycled but must be separated from unbroken tubes.

2. TUBE CLEANUP:

a. Tubes shall be “wet wiped” using a damp cloth and dried prior to placing in boxes.

3. PACKAGING:

a. Tubes shall be placed in boxes with corrugated cardboard or Styrofoam dividers in a manner to prevent breakage. Tubes shall not be taped together.

4. RECYCLING:

a. Boxes of light tubes shall be labeled in accordance with DOT requirements and shall be transported by the approved transporter to the approved recycling facility in accordance with DOT regulations.

5. CLEAN-UP PROCEDURES FOR BROKEN FLUORESCENT LIGHT TUBES:

a. Contractor shall have cleanup kit on site prior to removing/dismantling fluorescent light fixtures.
b. Broken tubes shall be cleaned-up immediately.
c. Use calcium polysulfide wetting solution on spilled lamp material to inhibit vaporization.
d. Following removal of broken glass, clean the floor with diluted trisodium phosphate solution according to manufacturer’s recommendations.
e. Identify, seal, and mark all containers with broken bulbs for special handling.
f. Mark and seal all drums of collected phosphate powder.

3.3 UNIVERSAL WASTE RECYCLING

A. Project universal wastes shall be recycled as required by WAC 173-303 and the Contractor’s approved recylcing plan.

3.4 CONSTRUCTION (NON-HAZARDOUS) WASTE DISPOSAL

A. The Contractor shall dispose of solid (non-hazardous) waste, as determined by testing, as ordinary construction waste in accordance with the applicable federal, state, and local laws and regulations. Burning of waste is prohibited.

3.5 SALVAGEABLE MATERIALS

A. The Contractor may salvage non-hazardous materials to keep such materials from entering the project waste stream. Such salvage shall be sold or transferred accompanied by a document of exempt status, in accordance with WAC 173-303.

END OF SECTION 028500

SECTION 033000 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes cast-in-place concrete, including formwork, reinforcement, concrete materials, mixture design, placement procedures, and finishes, for the following:

1. Footings.
2. Slab on grade.
3. Concrete walls.

B. Related Sections:

1. See General Structural Notes on structural drawings for additional information and requirements.

1.3 DEFINITIONS

A. Cementitious Materials: Portland cement alone or in combination with one or more of the following: blended hydraulic cement, fly ash and other pozzolans, ground granulated blast-furnace slag, and silica fume; subject to compliance with requirements.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Design Mixtures: For each concrete mixture. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

1. Indicate amounts of mixing water to be withheld for later addition at Project site.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A qualified installer who employs on Project personnel qualified as ACI-certified Flatwork Technician and Finisher and a supervisor who is an ACI-certified Concrete Flatwork Technician.

B. Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C 94/C 94M requirements for production facilities and equipment.

1. Manufacturer certified according to NRMCA's "Certification of Ready Mixed Concrete Production Facilities."

C. Source Limitations: Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant, obtain aggregate from single source, and obtain admixtures from single source from single manufacturer.

D. ACI Publications: Comply with the following unless modified by requirements in the Contract Documents:

1. ACI 301, "Specifications for Structural Concrete".
2. ACI 117, "Specifications for Tolerances for Concrete Construction and Materials."

1.6 DELIVERY, STORAGE, AND HANDLING

A. Steel Reinforcement: Deliver, store, and handle steel reinforcement to prevent bending and damage.

PART 2 - PRODUCTS

2.1 FORM-FACING MATERIALS

A. Smooth-Formed Finished Concrete: Form-facing panels that will provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.

B. Forms for Cylindrical Columns, Pedestals, and Supports: Metal, glass-fiber-reinforced plastic, paper, or fiber tubes that will produce surfaces with gradual or abrupt irregularities not exceeding specified formwork surface class. Provide units with sufficient wall thickness to resist plastic concrete loads without detrimental deformation.

C. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and will not impair subsequent treatments of concrete surfaces.

1. Formulate form-release agent with rust inhibitor for steel form-facing materials.

2.2 STEEL REINFORCEMENT

A. Reinforcing Bars: ASTM A 615/A 615M, Grade 60, deformed.

2.3 CONCRETE MATERIALS

A. Cementitious Material: Use the following cementitious materials, of the same type, brand, and source, throughout Project:

1. Portland Cement: ASTM C 150, C595, Type II, gray. Supplement with the following:
   a. Fly ash: ASTM C618, Class F or C.

B. Normal-Weight Aggregates: ASTM C 33, Class 3M coarse aggregate or better, graded. Provide aggregates from a single source.

1. Maximum Coarse-Aggregate Size: 3/4 inch nominal.
2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.

C. Water: ASTM C 94/C 94M and potable.

2.4 ADMIXTURES

A. Chemical Admixtures: Provide admixtures certified by manufacturer to be compatible with other admixtures and that will not contribute water-soluble chloride ions exceeding those permitted in hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride.

1. Water-Reducing Admixture: ASTM C 494/C 494M, Type A.

2.5 CURING MATERIALS

A. Water: Potable.

B. Clear, Waterborne, Membrane-Forming Curing and Sealing Compound: ASTM C 1315, Type 1, Class A.

2.6 VAPOR BARRIERS

A. Sheet Vapor Retarder: Polyethylene sheet, ASTM D 4397, not less than 10 mils thick.

2.7 RELATED MATERIALS

A. Bonding Agent: ASTM C 1059/C 1059M, Type II, non-redispersible, acrylic emulsion or styrene butadiene.

2.8 FABRICATING REINFORCEMENT

A. Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice."

PART 3 - EXECUTION

3.1 FORMWORK

A. Design, erect, shore, brace, and maintain formwork, according to ACI 301, to support vertical, lateral, static, and dynamic loads, and construction loads that might be applied, until structure can support such loads.

B. Construct formwork so concrete members and structures are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117.

C. Limit concrete surface irregularities, designated by ACI 347 as abrupt or gradual, as follows:

1. Class A, 1/8 inch for smooth-formed finished surfaces.

D. Construct forms tight enough to prevent loss of concrete mortar.

E. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces steeper than 1.5 horizontal to 1 vertical.

1. Install keyways, reglets, recesses, and the like, for easy removal.
2. Do not use rust-stained steel form-facing material.

F. Chamfer edges of permanently exposed concrete.

G. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.

H. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.

I. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.

3.2 REMOVING AND REUSING FORMS

A. Clean and repair surfaces of forms to be reused in the Work. Split, frayed, delaminated, or otherwise damaged form-facing material will not be acceptable for exposed surfaces. Apply new form-release agent.

B. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints. Align and secure joints to avoid offsets. Do not use patched forms for exposed concrete surfaces unless approved by Architect.

3.3 STEEL REINFORCEMENT

A. General: Comply with CRSI's "Manual of Standard Practice" for placing reinforcement.

B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials that would reduce bond to concrete.

C. Accurately position, support, and secure reinforcement against displacement. Locate and support reinforcement with bar supports to maintain minimum concrete cover. Do not tack weld crossing reinforcing bars.

D. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.

3.4 CONCRETE PLACEMENT

A. Before placing concrete, verify that installation of formwork, reinforcement, and embedded items is complete and that required inspections have been performed.

B. Do not add water to concrete during delivery, at Project site, or during placement unless approved by Architect.

C. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301.

1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.

D. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete will be placed on concrete that has hardened enough to cause seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as indicated. Deposit concrete to avoid segregation.

1. Deposit concrete in horizontal layers of depth to not exceed formwork design pressures and in a manner to avoid inclined construction joints.
2. Consolidate placed concrete with mechanical vibrating equipment according to ACI 301.

3.5 FINISHING FORMED SURFACES

A. Smooth-Formed Finish: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams. Repair and patch tie holes and defects. Remove fins and other projections that exceed specified limits on formed-surface irregularities.

1. Apply to all concrete surfaces.

B. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces unless otherwise indicated.

C. Slab Finishes: Match existing adjacent slab finish at all interior and exterior patched locations.

3.6 CONCRETE PROTECTING AND CURING

A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Comply with ACI 306.1 for cold-weather protection and ACI 301 for hot-weather protection during curing.

B. Formed Surfaces: Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces. If forms remain during curing period, moist cure after loosening forms. If removing forms before end of curing period, continue curing for the remainder of the curing period.

C. Unformed Surfaces: Begin curing immediately after finishing concrete. Cure unformed surfaces, including floors and slabs, concrete floor toppings, and other surfaces.

D. Cure concrete according to ACI 308.1, by one or a combination of the following methods:

1. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Maintain continuity of coating and repair damage during curing period.

3.7 FIELD QUALITY CONTROL

A. Testing and Inspecting: Engage a qualified testing and inspecting agency to perform tests and inspections and to submit reports. See structural drawings for additional inspection requirements.

B. Inspections:

1. Steel reinforcement placement.
2. Verification of use of required design mixture.
3. Concrete placement, including conveying and depositing.
4. Curing procedures and maintenance of curing temperature.

C. Concrete Tests: Testing of composite samples of fresh concrete obtained according to ASTM C 172 shall be performed according to the following requirements:

1. Slump: ASTM C 143/C 143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture. Perform additional tests when concrete consistency appears to change.
2. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.

END OF SECTION 033000

SECTION 033713 - SHOTCRETE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes shotcrete applied by wet-mix process.

1.3 DEFINITIONS

A. Shotcrete: Mortar or concrete pneumatically projected onto a surface at high velocity.

B. Wet-Mix Shotcrete: Shotcrete with ingredients, including mixing water, mixed before introduction into delivery hose.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product including reinforcement and forming accessories, shotcrete materials, admixtures, and curing compounds.

B. Design Mixtures: For each shotcrete mixture. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

1. For predampened dry-mix mixtures, indicate amounts of mixing water to be added to the dry-mix materials before mixing and conveying through the delivery hose.

C. Shop Drawings: For shotcrete installation. Include support and anchor details; reinforcement materials and grades and details of fabricating, bending, and placing reinforcement; number and location of splices; special reinforcement required for openings through shotcrete structures; formwork materials and details of formwork fabrication, assembly, and support; and locations of proposed construction joints.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and preconstruction testing service.

B. Material Certificates: For each of the following:

1. Cementitious materials.
2. Admixtures.
3. Form materials.

C. Preconstruction Test Reports: For shotcrete.

D. Field quality-control reports.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: A qualified installer employing nozzle operators for the Project, each of whom attains mean core grades not exceeding 2.5, according to ACI 506.2, on preconstruction tests and is ACI Shotcrete Nozzleman certified in Wet-Mix Process for Vertical Position as appropriate to the required shotcrete work.

B. Testing Agency Qualifications: Qualified according to ASTM C 1077 and ASTM E 329 for testing indicated.

C. ACI Publications: Comply with ACI 506.2, "Specification for Shotcrete," unless modified by requirements in the Contract Documents.

D. Shotcrete Testing Service: Engage a qualified independent testing agency to perform material evaluation tests and to design shotcrete mixtures.

1.7 PRECONSTRUCTION TESTING

A. Preconstruction Testing Service: Engage a qualified independent testing agency to perform preconstruction testing and inspections indicated below:

1. Produce shotcrete test panels before shotcrete placement according to requirements in ACI 506.2 and ASTM C 1140 for each design mixture, shooting orientation, and nozzle operator. Produce test panels with dimensions of 24 by 24 inches minimum and of average thickness of shotcrete, but not less than 3-1/2 inches.
2. From each test panel, testing agency will obtain six test specimens: one set of three specimens unreinforced and one set of three specimens reinforced. Agency will perform the following:

    a. Strength Testing: Test each set of unreinforced specimens for compressive strength according to ASTM C 42/C 42M.
    b. Core Grading: Visually inspect each set of reinforced shotcrete cores taken from test panels and determine mean core grades according to ACI 506.2.

PART 2 - PRODUCTS

2.1 FORM MATERIALS

A. Forms: Form-facing panels that will provide continuous, straight, smooth, concrete surfaces. Furnish panels in largest practical sizes to minimize number of joints.

2.2 REINFORCING MATERIALS

A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

B. Reinforcing Bars: ASTM A 615/A 615M, Grade 60, deformed.

C. Low-Alloy-Steel Reinforcing Bars: ASTM A 706/A 706M, deformed.

D. Plain-Steel Wire: ASTM A 82/A 82M, as drawn.

E. Plain-Steel Welded Wire Reinforcement: ASTM A 185/A 185M, plain, fabricated from as-drawn steel wire into flat sheets.

F. Deformed-Steel Welded Wire Reinforcement: ASTM A 497/A 497M, flat sheet.

G. Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded-wire fabric in place; manufactured according to CRSI's "Manual of Standard Practice" and as follows:

1. For uncoated reinforcement, use CRSI Class 1, plastic-protected or CRSI Class 2, stainless-steel bar supports.

2.3 SHOTCRETE MATERIALS

A. Source Limitations for Shotcrete: Obtain each color, size, type, and variety of shotcrete material and shotcrete mixture from single manufacturer with resources to provide shotcrete of consistent quality in appearance and physical properties.

B. Portland Cement: ASTM C 150, Type I or Type III. Use only one brand and type of cement for Project.

1. Fly Ash: ASTM C 618, Class C or Class F.
2. Ground Granulated Blast-Furnace Slag: ASTM C 989, Grade 100 or Grade 120.

C. Blended Hydraulic Cement: ASTM C 595, Type IP.

D. Silica Fume: ASTM C 1240, amorphous silica.

E. Normal-Weight Aggregates: ASTM C 33, from a single source, and as follows:

1. Combined Aggregate Size: ACI 506R or ASTM C 1436, Grading No. 2 sieve analysis.

F. Water: Potable, complying with ASTM C 94/C 94M, free from deleterious materials that may affect color stability, setting, or strength of shotcrete.

G. Ground Wire: High-strength steel wire, 0.8 to 1.0 mm in diameter.

H. Joint Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber or [ASTM D 1752, cork or self-expanding cork.

2.4 ADMIXTURES

A. General: ASTM C 1141, Class A (liquid) or Class B (non-liquid), but limited to the following admixture materials. Provide admixtures for shotcrete that contain not more than 0.1 percent chloride ions. Certify compatibility of admixtures with each other and with other cementitious materials.

1. Accelerating Admixture, Conventional: ASTM C 494/C 494M, Type C or Type E.
2. Pozzolanic Admixture: Fly ash, ground granulated blast-furnace slag, and silica fume as limited in "Shotcrete Materials" Article.
3. Coloring Admixture: Coloring agent as limited in "Shotcrete Materials" Article.

2.5 CURING MATERIALS

A. Absorptive Cover: AASHTO M 182, Class 3, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. (305 g/sq. m) dry, or cotton mats.

B. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.

C. Water: Potable.

D. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B.

2.6 SHOTCRETE MIXTURES, GENERAL

A. Prepare design mixtures for each type and strength of shotcrete, proportioned on the basis of laboratory trial mixture or field test data, or both, according to ACI 506.2.

1. Use a qualified independent testing agency for preparing and reporting proposed mixture designs based laboratory trial mixture or field test data, or both.

B. Cementitious Materials: Use fly ash, pozzolan, ground granulated blast-furnace slag, and silica fume as needed to reduce the total amount of portland cement, which would otherwise be used, by not less than 40 percent.

C. Cementitious Materials: Limit use of fly ash, ground granulated blast-furnace slag, and silica fume to not exceed, in combination, 25 percent of portland cement by weight.

D. Limit water-soluble chloride ions to maximum percentage by weight of cement or cementitious materials permitted by ACI 301.

E. Admixtures: When included in shotcrete design mixtures, use admixtures according to manufacturer's written instructions.

F. Design-Mixture Adjustments: Subject to compliance with requirements, shotcrete design-mixture adjustments may be proposed when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant.

2.7 SHOTCRETE MIXTURES

A. Shotcrete Mixture: Proportion mixture to provide shotcrete with the following properties:

1. Compressive Strength (28 Days): 6000 psi .
2. Air Content: Add air-entraining admixture at manufacturer's prescribed rate to result in normal-weight wet-mix shotcrete having an air content before pumping of 8 percent with a tolerance of plus or minus 1-1/2 percent.
3. Color: As selected by Architect from manufacturer's full range.

2.8 SHOTCRETE EQUIPMENT

A. Mixing Equipment: Capable of thoroughly mixing shotcrete materials in sufficient quantities to maintain continuous placement.

B. Dry-Mix Delivery Equipment: Capable of discharging aggregate-cement mixture into delivery hose under close control and maintaining continuous stream of uniformly mixed materials at required velocity to discharge nozzle. Equip discharge nozzle with manually operated water-injection system for directing even distribution of water to aggregate-cement mixture.

1. Provide uniform, steady supply of clean, compressed air to maintain constant nozzle velocity while simultaneously operating blow pipe for cleaning away rebound.
2. Provide water supply with uniform pressure at discharge nozzle to ensure uniform mixing with aggregate-cement mix. Provide water pump to system if line water pressure is inadequate.

C. Wet-Mix Delivery Equipment: Capable of discharging aggregate-cement-water mixture accurately, uniformly, and continuously.

2.9 BATCHING AND MIXING

A. Dry-Mix Process: Measure mixture proportions by weight batching according to ASTM C 94/C 94M or by volume batching complying with ASTM C 685/C 685M requirements.

1. In volume batching, adjust fine-aggregate volume for bulking. Test fine-aggregate moisture content at least once daily to determine extent of bulking.
2. Prepackaged shotcrete materials may be used at Contractor's option. Predampen prepackaged shotcrete materials and mix before use.

B. Wet-Mix Process: Measure, batch, mix, and deliver shotcrete according to ASTM C 94/C 94 and furnish batch ticket information.

1. Comply with ASTM C 685/C 685M when shotcrete ingredients are delivered dry and proportioned and mixed on-site.

PART 3 - EXECUTION

3.1 PREPARATION

A. Concrete or Masonry: Before applying shotcrete, remove unsound or loose materials and contaminants that may inhibit shotcrete bonding. Chip or scarify areas to be repaired to extent necessary to provide sound substrate. Cut edges square and 1/2 inch (13 mm) deep at perimeter of work, tapering remaining shoulder at 1:1 slope into cavity to eliminate square shoulders. Dampen surfaces to saturated, surface-dry condition before shotcreting.

1. Abrasive blast or hydroblast existing surfaces that do not require chipping to remove paint, oil, grease, or other contaminants and to provide roughened surface for proper shotcrete bonding.

B. Steel: Clean steel surfaces by abrasive blasting according to SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."

3.2 FORMS

A. General: Design, erect, support, brace, and maintain forms, according to ACI 301, to support shotcrete and construction loads and to facilitate shotcreting. Construct forms so shotcrete members and structures are secured to prevent excessive vibration or deflection during shotcreting.

1. Fabricate forms to be readily removable without impact, shock, or damage to shotcrete surfaces and adjacent materials.
2. Construct forms to required sizes, shapes, lines, and dimensions using ground wires and depth gages to obtain accurate alignment, location, and grades in finished structures. Construct forms to prevent mortar leakage but permit escape of air and rebound during shotcreting. Provide for openings, offsets, blocking, screeds, anchorages, inserts, and other features required in the Work.

B. Form openings, chases, recesses, bulkheads, keyways, and screeds in formwork. Determine sizes and locations from trades providing such items. Accurately place and securely support items built into forms.

3.3 STEEL REINFORCEMENT

A. General: Comply with CRSI's "Manual of Standard Practice" for fabricating, placing, and supporting reinforcement.

B. Clean reinforcement of loose rust and mill scale, earth, ice, and other materials that weaken shotcrete bonding.

C. Securely embed reinforcing anchors into existing substrates, located as required.

D. Accurately position, support, and secure reinforcement against displacement. Locate and support reinforcement with bar supports, bolsters, chairs, spacers, and other devices as required to maintain minimum concrete cover.

E. Set wire ties with ends directed into shotcrete, not toward exposed shotcrete surfaces.

F. Install welded wire reinforcement in longest practical lengths on bar supports spaced to minimize sagging. Lap edges and ends of adjoining sheets at least one mesh spacing. Offset laps of adjoining sheet widths to prevent continuous laps in either direction. Lace overlaps with wire.

3.4 JOINTS

A. General: Construct joints at locations indicated or as approved by Architect.

B. Construction Joints: Locate and install construction joints tapered to a 1:1 slope where joint is not subject to compression loads and square where joint is perpendicular to main reinforcement. Continue reinforcement through construction joints unless otherwise indicated.

C. Contraction Joints: Construct contraction joints in shotcrete using saw cuts 1/8-inch- (3-mm-) wide by 1/3 slab depth or joint-filler strips 1/4-inch- (6-mm-) wide by 1/3 shotcrete depth unless otherwise indicated.

1. After shotcrete has cured, remove strip inserts and clean groove of loose debris.

2. Space joints where indicated. Joint locations shall be reviewed and approved by architect and engineer prior to shotcrete installation.
3. Tool edges round on each side of strip inserts if floated or troweled finishes are required.
4. Where shooting over an existing substrate joint, align new shotcrete joint with existing joint.

3.5 ALIGNMENT CONTROL

A. Ground Wires: Install ground wires to establish thickness and planes of shotcrete surfaces. Install ground wires at corners and offsets not established by forms. Pull ground wires taut and position adjustment devices to permit additional tightening.

3.6 EMBEDDED ITEMS

A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by shotcrete. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.

3.7 APPLICATION

A. Apply temporary protective coverings and protect adjacent surfaces against deposit of rebound and overspray or impact from nozzle stream.

B. Moisten wood forms immediately before placing shotcrete where form coatings are not used.

C. Apply shotcrete according to ACI 506.2.

D. Apply wet-mix shotcrete materials within 90 minutes after batching.

E. Deposit shotcrete continuously in multiple passes, to required thickness, without cold joints and laminations developing. Place shotcrete with nozzle held perpendicular to receiving surface. Begin shotcreting in corners and recesses.

1. Remove and dispose of rebound and overspray materials during shotcreting to maintain clean surfaces and to prevent rebound entrapment.

F. Maintain reinforcement in position during shotcreting. Place shotcrete to completely encase reinforcement and other embedded items. Maintain steel reinforcement free of overspray, and prevent buildup against front face during shotcreting.

G. Do not place subsequent lifts until previous lift of shotcrete is capable of supporting new shotcrete.

H. Do not permit shotcrete to sag, slough, or dislodge.

I. Remove hardened overspray, rebound, and laitance from shotcrete surfaces to receive additional layers of shotcrete; dampen surfaces before shotcreting.

J. Do not disturb shotcrete surfaces before beginning finishing operations.

K. Remove ground wires or other alignment-control devices after shotcrete placement.

L. Shotcrete Core Grade: Apply shotcrete to achieve mean core grades not exceeding 2.5 according to ACI 506.2, with no single core grade exceeding 3.0.

M. Installation Tolerances: Place shotcrete without exceeding installation tolerances permitted by ACI 117, increased by a factor of two.

N. Cold-Weather Shotcreting: Mix, place, and protect shotcrete according to ACI 306.1 and as follows. Protect shotcrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.

1. Discontinue shotcreting when ambient temperature is 40 deg F (4.4 deg C) and falling.
2. Uniformly heat water and aggregates before mixing to obtain a shotcrete shooting temperature of not less than 50 deg F (10 deg C) and not more than 90 deg F (32 deg C).
3. Do not use frozen materials or materials containing ice or snow.
4. Do not place shotcrete on frozen surfaces or surfaces containing frozen materials.
5. Do not use calcium chloride, salt, or other materials containing antifreeze agents.

O. Hot-Weather Shotcreting: Mix, place, and protect shotcrete according to recommendations of ACI 305R when hot-weather conditions and high temperatures would seriously impair quality and strength of shotcrete, and as follows:

1. Cool ingredients before mixing to maintain shotcrete temperature at time of placement below 90 deg F (32 deg C) for wet mix.
2. Reduce temperature of reinforcing steel and receiving surfaces below 100 deg F (38 deg C) before shotcreting.

3.8 SURFACE FINISHES

A. General: Finish shotcrete according to descriptions in ACI 506R.

B. Natural Finishes:

1. Broom Finish: Rough-textured finish obtained by screeding or cutting exposed face of shotcrete to plane with cutting rod, edge of trowel, or straightedge after initial set; followed by uniform brooming.

3.9 CURING

A. Protect freshly placed shotcrete from premature drying and excessive cold or hot temperatures.

B. Begin curing immediately after placing and finishing but not before free water, if any, has disappeared from shotcrete surface.

C. Curing Exposed Surfaces: Cure shotcrete by one of the following methods:

1. Moisture Curing: Keep surfaces continuously moist for not less than seven days with the following materials:

   a. Water.
   b. Continuous water-fog spray.
   c. Water-saturated absorptive covers or moisture-retaining covers. Lap and seal sides and ends of covers with 12-inch (300-mm) lap over adjacent covers.

2. Curing Compound: Apply uniformly in continuous operation by power spray according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.

   a. Apply curing compound to natural gun finish or flash-coat shotcrete at rate of 1 gal./100 sq. ft. (1 L/2.5 sq. m).

D. Curing Formed Surfaces: Cure formed shotcrete surfaces by moist curing with forms in place for full curing period or until forms are removed. If forms are removed, continue curing by methods specified above, as applicable.

3.10 FORM REMOVAL

A. Forms not supporting weight of shotcrete may be removed after curing for 24 consecutive hours at not less than 50 deg F (10 deg C), provided shotcrete is hard enough not to be damaged by form-removal operations and provided curing and protecting operations are maintained.

1. Leave forms supporting weight of shotcrete in place until shotcrete has attained design compressive strength. Determine compressive strength of in-place shotcrete by testing representative field-cured specimens of shotcrete.
2. Remove forms only if shores have been arranged to permit removal of forms without loosening or disturbing shores.

B. Clean and repair surfaces of forms to be reused in the Work. Split, frayed, delaminated, or otherwise damaged form-facing materials are unacceptable for exposed surfaces. Apply new form-coating compound as specified for new formwork.

3.11 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to sample materials, visually grade cores, perform tests, and submit reports during shotcreting.

B. Air Content: ASTM C 173/C 173M, volumetric method or ASTM C 231, pressure method; one test for each compressive-strength test for each mixture of air-entrained, wet-mix shotcrete measured before pumping.

C. Shotcrete Temperature: ASTM C 1064/C 1064M; one test hourly when air temperature is 40 deg F (4.4 deg C) and below and when 80 deg F (27 deg C) and above, and one test for each set of compressive-strength specimens.

D. Test Panels: Make a test panel, reinforced as in structure, for each shotcrete mixture and for each workday or for every 50 cu. yd. (38 cu. m) of shotcrete placed, whichever is less. Produce test panels with dimensions of 24 by 24 inches (600 by 600 mm) minimum and of average thickness of shotcrete, but not less than 4-1/2 inches (115 mm). Testing agency will obtain sets of test specimens from each test panel.

1. Compressive Strength Testing: One set of three unreinforced specimens. Test each set of unreinforced specimens for compressive strength according to ASTM C 1140 and construction testing requirements in ACI 506.2.
2. Visual Core Grading: One set of three reinforced specimens. Visually inspect each set of reinforced shotcrete cores taken from test panels and determine mean core grades according to ACI 506.2.

E. In-Place Shotcrete Testing: One set of three unreinforced cores for each mixture and for each workday or for every 50 cu. yd. (38 cu. m) of shotcrete placed, whichever is less. Test cores for compressive strength according to ACI 506.2 and ASTM C 42. Do not cut steel reinforcement.

F. Strength of shotcrete will be considered satisfactory according to the following:

1. Specimen Cores: Mean compressive strength of each set of three unreinforced cores equals or exceeds 85 percent of specified compressive strength, with no individual core less than 75 percent of specified compressive strength.
2. Specimen Cubes: Mean compressive strength of each set of three unreinforced cubes shall equal or exceed design compressive strength with no individual cube less than 88 percent of specified compressive strength.

3.12 REPAIRS

A. Remove and replace shotcrete that is delaminated or exhibits laminations, voids, or sand/rock pockets exceeding limits for specified core grade of shotcrete.

1. Remove unsound or loose materials and contaminants that may inhibit bond of shotcrete repairs.

2. Chip or scarify areas to be repaired to extent necessary to provide sound substrate. Cut edges square and 1/2 inch (13 mm) deep at perimeter of work, tapering remaining shoulder at 1:1 slope into cavity to eliminate square shoulders.
3. Dampen surfaces and apply new shotcrete. Match adjacent color and finish.

B. Repair core holes from in-place testing according to repair provisions in ACI 301, except do not use shotcrete. Match adjacent color and finish.

3.13 CLEANING

A. Immediately remove and dispose of rebound and overspray materials from final shotcrete surfaces and areas not intended for shotcrete placement.

END OF SECTION 033713

SECTION 051200 - STRUCTURAL STEEL FRAMING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Structural steel.

B. Related Requirements:

1. None.

1.3 DEFINITIONS

A. Structural Steel: Elements of the structural frame indicated on Drawings and as described in AISC 303, "Code of Standard Practice for Steel Buildings and Bridges."

B. Seismic-Load-Resisting System: Elements of structural-steel frame designated as "SLRS" or along grid lines designated as "SLRS" on Drawings, including columns, beams, and braces and their connections.

C. Demand Critical Welds: Those welds, the failure of which would result in significant degradation of the strength and stiffness of the Seismic-Load-Resisting System and which are indicated as "Demand Critical" or "Seismic Critical" on Drawings.

1.4 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of anchorage items to be embedded in or attached to other construction without delaying the Work. Provide setting diagrams, sheet metal templates, instructions, and directions for installation.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: Show fabrication of structural-steel components.

1. Include details of cuts, connections, splices, camber, holes, and other pertinent data.
2. Include embedment Drawings.
3. Indicate welds by standard AWS symbols, distinguishing between shop and field welds, and show size, length, and type of each weld. Show backing bars that are to be removed and supplemental fillet welds where backing bars are to remain.
4. Indicate type, size, and length of bolts, distinguishing between shop and field bolts. Identify pretensioned and slip-critical, high-strength bolted connections.
5. Identify members and connections of the Seismic-Load-Resisting System.
6. Identify demand critical welds.

C. Welding Procedure Specifications (WPSs) and Procedure Qualification Records (PQRs): Provide according to AWS D1.1/D1.1M, "Structural Welding Code - Steel," for each welded joint whether prequalified or qualified by testing, including the following:

1. Power source (constant current or constant voltage).
2. Electrode manufacturer and trade name, for demand critical welds.

1.6 INFORMATIONAL SUBMITTALS

A. Qualification Data: For fabricator.

B. Welding certificates.

C. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.

D. Mill test reports for structural steel, including chemical and physical properties.

E. Product Test Reports: For the following:

1. Bolts, nuts, and washers including mechanical properties and chemical analysis.
2. Direct-tension indicators.
3. Tension-control, high-strength, bolt-nut-washer assemblies.
4. Shear stud connectors.
5. Shop primers.
6. Nonshrink grout.

F. Survey of existing conditions.

G. Source quality-control reports.

H. Field quality-control and special inspection reports.

1.7 QUALITY ASSURANCE

A. Fabricator Qualifications: A qualified fabricator that participates in the AISC Quality Certification Program and is designated an AISC-Certified Plant, Category STD, or is accredited by the IAS Fabricator Inspection Program for Structural Steel (AC 172).

B. Installer Qualifications: A qualified installer who participates in the AISC Quality Certification Program and is designated an AISC-Certified Erector, Category CSE.

C. Shop-Painting Applicators: Qualified according to to SSPC-QP 3, "Standard Procedure for Evaluating Qualifications of Shop Painting Applicators."

D. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

1. Welders and welding operators performing work on bottom-flange, demand-critical welds shall pass the supplemental welder qualification testing, as required by AWS D1.8/D1.8M. FCAW-S and FCAW-G shall be considered separate processes for welding personnel qualification.

E. Comply with applicable provisions of the following specifications and documents:

1. AISC 303.
2. AISC 341 and AISC 341s1.
3. AISC 360.
4. RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."

1.8 DELIVERY, STORAGE, AND HANDLING

A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.

1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.

B. Store fasteners in a protected place in sealed containers with manufacturer's labels intact.

1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
2. Clean and relubricate bolts and nuts that become dry or rusty before use.

3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F 1852 fasteners and for retesting fasteners after lubrication.

PART 2 - PRODUCTS

2.1 STRUCTURAL-STEEL MATERIALS

A. Channels, Angles Shapes: ASTM A 36/A 36M.

B. Plate and Bar: ASTM A 36/A 36M.

C. Cold-Formed Hollow Structural Sections: ASTM A 500/A 500M, Grade B, structural tubing.

D. Steel Pipe: ASTM A 53/A 53M, Type E or Type S, Grade B.

2.2 BOLTS, CONNECTORS, AND ANCHORS

A. High-Strength Bolts, Nuts, and Washers: ASTM A 325 (ASTM A 325M), Type 1, heavy-hex steel structural bolts; ASTM A 563, Grade C, (ASTM A 563M, Class 8S) heavy-hex carbon-steel nuts; and ASTM F 436 (ASTM F 436M), Type 1, hardened carbon-steel washers; all with plain finish.

1. Direct-Tension Indicators: ASTM F 959, Type 325 (ASTM F 959M, Type 8.8), compressible-washer type with plain finish.

B. Tension-Control, High-Strength Bolt-Nut-Washer Assemblies: ASTM F 1852, Type 1, heavy-hex or round head assemblies consisting of steel structural bolts with splined ends, heavy-hex carbon-steel nuts, and hardened carbon-steel washers.

1. Finish: Plain.

C. Shear Connectors: ASTM A 108, Grades 1015 through 1020, headed-stud type, cold-finished carbon steel; AWS D1.1/D1.1M, Type B.

D. Unheaded Anchor Rods:ASTM F 1554, Grade 55, weldable.

1. Configuration: Straight.
2. Nuts: ASTM A 563 (ASTM A 563M) heavy- hex carbon steel.
3. Plate Washers: ASTM A 36/A 36M carbon steel.
4. Washers: ASTM F 436 (ASTM F 436M), Type 1, hardened carbon steel.
5. Finish: Hot-dip zinc coating, ASTM A 153/A 153M, Class.

E. Headed Anchor Rods: ASTM F 1554, Grade 55, weldable, straight.

1. Nuts: ASTM A 563 (ASTM A 563M) heavy-hex carbon steel.
2. Plate Washers: ASTM A 36/A 36M carbon steel.

3. Washers: ASTM F 436 (ASTM F 436M), Type 1, hardened carbon steel.
4. Finish: Hot-dip zinc coating, ASTM A 153/A 153M, Class C.

F. Threaded Rods: ASTM A 36/A 36M.

1. Nuts: ASTM A 563 (ASTM A 563M) heavy-hex carbon steel.
2. Washers: ASTM F 436 (ASTM F 436M), Type 1, hardened carbon steel
3. Plate Washers: ASTM A 36/A 36M carbon steel.
4. Finish: Plain.

G. Clevises and Turnbuckles: Made from cold-finished carbon steel bars, ASTM A 108, Grade 1035.

H. Eye Bolts and Nuts: Made from cold-finished carbon steel bars, ASTM A 108, Grade 1030.

I. Sleeve Nuts: Made from cold-finished carbon steel bars, ASTM A 108, Grade 1018.

2.3 PRIMER

A. Low-Emitting Materials: Paints and coatings shall comply with the testing and product requirements of the California Department of Public Health's (formerly, the California Department of Health Services') "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

B. Primer: Comply with Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."

C. Primer: SSPC-Paint 23, latex primer.

D. Primer: Fabricator's standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat.

2.4 GROUT

A. Metallic, Shrinkage-Resistant Grout: ASTM C 1107/C 1107M, factory-packaged, metallic aggregate grout, mixed with water to consistency suitable for application and a 30-minute working time.

B. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107/C 1107M, factory-packaged, nonmetallic aggregate grout, noncorrosive and nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

2.5 FABRICATION

A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate according to AISC 303, "Code of Standard Practice for Steel Buildings and Bridges," and to AISC 360.

1. Camber structural-steel members where indicated.
2. Fabricate beams with rolling camber up.
3. Identify high-strength structural steel according to ASTM A 6/A 6M and maintain markings until structural steel has been erected.
4. Mark and match-mark materials for field assembly.
5. Complete structural-steel assemblies, including welding of units, before starting shop-priming operations.

B. Thermal Cutting: Perform thermal cutting by machine to greatest extent possible.

1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1/D1.1M.

C. Bolt Holes: Cut, drill, or punch standard bolt holes perpendicular to metal surfaces.

D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.

E. Cleaning: Clean and prepare steel surfaces that are to remain unpainted according to SSPC-SP 2, "Hand Tool Cleaning."

F. Shear Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Use automatic end welding of headed-stud shear connectors according to AWS D1.1/D1.1M and manufacturer's written instructions.

G. Steel Wall-Opening Framing: Select true and straight members for fabricating steel wall-opening framing to be attached to structural-steel frame. Straighten as required to provide uniform, square, and true members in completed wall framing. Build up welded framing, weld exposed joints continuously, and grind smooth.

H. Welded Door Frames: Build up welded door frames attached to structural-steel frame. Weld exposed joints continuously and grind smooth. Plug-weld fixed steel bar stops to frames. Secure removable stops to frames with countersunk machine screws, uniformly spaced not more than 10 inches (250 mm) o.c. unless otherwise indicated.

I. Holes: Provide holes required for securing other work to structural steel and for other work to pass through steel members.

1. Cut, drill, or punch holes perpendicular to steel surfaces. Do not thermally cut bolt holes or enlarge holes by burning.
2. Baseplate Holes: Cut, drill, mechanically thermal cut, or punch holes perpendicular to steel surfaces.

3. Weld threaded nuts to framing and other specialty items indicated to receive other work.

2.6 SHOP CONNECTIONS

A. High-Strength Bolts: Shop install high-strength bolts according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.

1. Joint Type: As indicated on drawings.

B. Weld Connections: Comply with AWS D1.1/D1.1M and AWS D1.8/D1.8M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.

1. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in AISC 303 for mill material.

2.7 SHOP PRIMING

A. Shop prime steel surfaces except the following:

1. Surfaces embedded in concrete or mortar. Extend priming of partially embedded members to a depth of 2 inches (50 mm).
2. Surfaces to be field welded.
3. Surfaces of high-strength bolted, slip-critical connections.
4. Surfaces to receive sprayed fire-resistive materials (applied fireproofing).
5. Galvanized surfaces.
6. Surfaces enclosed in interior construction.

B. Surface Preparation: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces according to the following specifications and standards:

1. SSPC-SP 2, "Hand Tool Cleaning."
2. SSPC-SP 3, "Power Tool Cleaning."
3. SSPC-SP 7/NACE No. 4, "Brush-off Blast Cleaning."
4. SSPC-SP 11, "Power Tool Cleaning to Bare Metal."
5. SSPC-SP 14/NACE No. 8, "Industrial Blast Cleaning."
6. SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
7. SSPC-SP 10/NACE No. 2, "Near-White Blast Cleaning."
8. SSPC-SP 5/NACE No. 1, "White Metal Blast Cleaning."
9. SSPC-SP 8, "Pickling."

C. Priming: Immediately after surface preparation, apply primer according to manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils (0.038 mm). Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.

1. Stripe paint corners, crevices, bolts, welds, and sharp edges.
2. Apply two coats of shop paint to surfaces that are inaccessible after assembly or erection. Change color of second coat to distinguish it from first.

D. Painting: Prepare steel and apply a one-coat, nonasphaltic primer complying with SSPC-PS Guide 7.00, "Painting System Guide 7.00: Guide for Selecting One-Coat Shop Painting Systems," to provide a dry film thickness of not less than 1.5 mils (0.038 mm).

2.8 GALVANIZING

A. Hot-Dip Galvanized Finish: Apply zinc coating by the hot-dip process to structural steel according to ASTM A 123/A 123M.

1. Fill vent and drain holes that are exposed in the finished Work unless they function as weep holes, by plugging with zinc solder and filing off smooth.
2. Galvanize lintels and welded door frames attached to structural-steel frame and located in exterior walls.

2.9 SOURCE QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform shop tests and inspections.

1. Provide testing agency with access to places where structural-steel work is being fabricated or produced to perform tests and inspections.

B. Bolted Connections: Inspect and test shop-bolted connections according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."

C. Welded Connections: Visually inspect shop-welded connections according to AWS D1.1/D1.1M and the following inspection procedures, at testing agency's option:

1. Liquid Penetrant Inspection: ASTM E 165.
2. Magnetic Particle Inspection: ASTM E 709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not accepted.
3. Ultrasonic Inspection: ASTM E 164.
4. Radiographic Inspection: ASTM E 94.

D. In addition to visual inspection, test and inspect shop-welded shear connectors according to requirements in AWS D1.1/D1.1M for stud welding and as follows:

1. Perform bend tests if visual inspections reveal either a less-than-continuous 360-degree flash or welding repairs to any shear connector.
2. Conduct tests according to requirements in AWS D1.1/D1.1M on additional shear connectors if weld fracture occurs on shear connectors already tested.

E. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify, with certified steel erector present, elevations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.

1. Prepare a certified survey of existing conditions. Include bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural steel, connections, and bracing are in place unless otherwise indicated.

1. Do not remove temporary shoring supporting composite deck construction until cast-in-place concrete has attained its design compressive strength.

3.3 ERECTION

A. Set structural steel accurately in locations and to elevations indicated and according to AISC 303 and AISC 360.

B. Baseplates, Bearing Plates, and Leveling Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.

1. Set plates for structural members on wedges, shims, or setting nuts as required.
2. Weld plate washers to top of baseplate.
3. Snug-tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
4. Promptly pack grout solidly between bearing surfaces and plates so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure. Comply with manufacturer's written installation instructions for shrinkage-resistant grouts.

C. Maintain erection tolerances of structural steel within AISC 303, "Code of Standard Practice for Steel Buildings and Bridges."

D. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that are in permanent contact with members. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.

1. Level and plumb individual members of structure.
2. Make allowances for difference between temperature at time of erection and mean temperature when structure is completed and in service.

E. Splice members only where indicated.

F. Do not use thermal cutting during erection.

G. Do not enlarge unfair holes in members by burning or using drift pins. Ream holes that must be enlarged to admit bolts.

H. Shear Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Use automatic end welding of headed-stud shear connectors according to AWS D1.1/D1.1M and manufacturer's written instructions.

3.4 FIELD CONNECTIONS

A. High-Strength Bolts: Install high-strength bolts according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.

1. Joint Type: As indicated on the drawings.

B. Weld Connections: Comply with AWS D1.1/D1.1 and AWS D1.8/D1.8M for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.

1. Comply with AISC 303 and AISC 360 for bearing, alignment, adequacy of temporary connections, and removal of paint on surfaces adjacent to field welds.
2. Remove backing bars or runoff tabs, back gouge, and grind steel smooth.
3. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in AISC 303, "Code of Standard Practice for Steel Buildings and Bridges," for mill material.

3.5 FIELD QUALITY CONTROL

A. Special Inspections: Owner will engage a qualified special inspector to perform the following special inspections:

1. Verify structural-steel materials and inspect steel frame joint details.
2. Verify weld materials and inspect welds.
3. Verify connection materials and inspect high-strength bolted connections.

B. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

C. Bolted Connections: Inspect and test bolted connections according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."

D. Welded Connections: Visually inspect field welds according to AWS D1.1/D1.1M.

1. In addition to visual inspection, test and inspect field welds according to AWS D1.1/D1.1M and the following inspection procedures, at testing agency's option:

a. Liquid Penetrant Inspection: ASTM E 165.
b. Magnetic Particle Inspection: ASTM E 709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not accepted.
c. Ultrasonic Inspection: ASTM E 164.
d. Radiographic Inspection: ASTM E 94.

E. In addition to visual inspection, test and inspect field-welded shear connectors according to requirements in AWS D1.1/D1.1M for stud welding and as follows:

1. Perform bend tests if visual inspections reveal either a less-than-continuous 360-degree flash or welding repairs to any shear connector.
2. Conduct tests according to requirements in AWS D1.1/D1.1M on additional shear connectors if weld fracture occurs on shear connectors already tested.

3.6 REPAIRS AND PROTECTION

A. Galvanized Surfaces: Clean areas where galvanizing is damaged or missing and repair galvanizing to comply with ASTM A 780/A 780M.

B. Touchup Painting: Immediately after erection, clean exposed areas where primer is damaged or missing and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.

1. Clean and prepare surfaces by SSPC-SP 2 hand-tool cleaning or SSPC-SP 3 power-tool cleaning.

C. Touchup Painting: Cleaning and touchup painting are specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."

D. Touchup Priming: Cleaning and touchup priming are specified in Section 099600 "High-Performance Coatings."

END OF SECTION 051200

SECTION 055000 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Alternating tread stairs.

B. Related Requirements:

1. Section 055213 "Pipe and Tube Railings".

1.3 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of metal fabrications that are anchored to or that receive other work. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

1.4 ACTION SUBMITTALS

A. Shop Drawings: Show fabrication and installation details. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items. Provide Shop Drawings for the following:

1. Alternating tread devices.

B. Delegated-Design Submittal: For alternating tread devices, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For professional engineer.

B. Welding certificates.

1.6 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

B. Welding Qualifications: Qualify procedures and personnel according to the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."
2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum."
3. AWS D1.6/D1.6M, "Structural Welding Code - Stainless Steel."

1.7 FIELD CONDITIONS

A. Field Measurements: Verify actual locations of walls, floor elevations, and other construction contiguous with metal fabrications by field measurements before fabrication.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified professional engineer, as defined in Section 014000 "Quality Requirements," to design alternating tread devices.

B. Structural Performance of Alternating Tread Devices: Alternating tread devices shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated.

1. Uniform Load: 100 lbf/sq. ft.
2. Concentrated Load: 300 lbf applied on an area of 4 sq. in.
3. Uniform and concentrated loads need not be assumed to act concurrently.
4. Alternating Tread Device Framing: Capable of withstanding stresses resulting from railing loads in addition to loads specified above.

2.2 METALS

A. Metal Surfaces, General: Provide materials with smooth, flat surfaces unless otherwise indicated. For metal fabrications exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.

B. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.

C. Steel Pipe: ASTM A 53/A 53M, Standard Weight (Schedule 40) unless otherwise indicated.

2.3 FABRICATION, GENERAL

A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation.

B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.

C. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.

D. Form exposed work with accurate angles and surfaces and straight edges.

E. Weld corners and seams continuously to comply with the following:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing.

F. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Where exposed fasteners are required, use Phillips flat-head (countersunk) fasteners unless otherwise indicated. Locate joints where least conspicuous.

G. Provide for anchorage of type indicated; coordinate with supporting structure. Space anchoring devices to secure metal fabrications rigidly in place and to support indicated loads.

2.4 ALTERNATING TREAD DEVICES

A. Alternating Tread Devices: Fabricate alternating tread devices of open-type construction with channel or plate stringers and pipe and tube railings unless otherwise indicated. Provide brackets and fittings for installation.

1. Manufacturers: Subject to compliance with requirements, provide products by the following:

    a. Lapeyre Stair Inc.
    b. Duvinage LLC.
    c. Equal as approved by Architect.

2. Tread depth shall be not less than 5 inches exclusive of nosing or less than 8-1/2 inches including the nosing, tread width shall be not less than 7 inches, and riser height shall be not more than 9-1/2 inches.
3. Tread depth shall be not less than 8-1/2 inches exclusive of nosing or less than 10-1/2 inches including the nosing, tread width shall be not less than 7 inches, and riser height shall be not more than 8 inches.
4. Fabricate from steel and assemble by welding or with stainless-steel fasteners.
5. Comply with applicable railing requirements in Section 055213 "Pipe and Tube Railings."

2.5 FINISHES, GENERAL

A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Finish metal fabrications after assembly.

C. Finish exposed surfaces to remove tool and die marks and stretch lines, and to blend into surrounding surface.

2.6 FINISHES, STEEL

A. Steel: Safety Yellow Powder Coat.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment,

and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.

B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.

C. Field Welding: Comply with the following requirements:

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove welding flux immediately.
4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.

D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction. Provide threaded fasteners for use with concrete and masonry inserts, toggle bolts, through bolts, lag screws, wood screws, and other connectors.

3.2 ADJUSTING AND CLEANING

A. Touchup Painting: Immediately after erection, clean field welds, bolted connections, and abraded areas. Paint uncoated and abraded areas with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.

1. Apply by brush or spray to provide a minimum 2.0-mil dry film thickness.

END OF SECTION 055000

SECTION 055213 - PIPE AND TUBE RAILINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Steel pipe railings.

B. Related Requirements:

1. Section 055000 “Metal Fabrications”.

1.3 COORDINATION

A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.

B. Coordinate installation of anchorages for railings. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

C. Schedule installation so wall attachments are made only to completed walls. Do not support railings temporarily by any means that do not satisfy structural performance requirements.

1.4 ACTION SUBMITTALS

A. Product Data: For the following:

1. Paint Products.

B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1.5 INFORMATIONAL SUBMITTALS

A. Welding certificates.

1.6 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to the following:

1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

1.8 FIELD CONDITIONS

A. Field Measurements: Verify actual locations of walls and other construction contiguous with metal fabrications by field measurements before fabrication.

PART 2 - PRODUCTS

2.2 PERFORMANCE REQUIREMENTS

A. Structural Performance: Railings, including attachment to building construction, shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated:

1. Handrails and Top Rails of Guards:

a. Uniform load of 50 lbf/ ft. applied in any direction.
b. Concentrated load of 200 lbf applied in any direction.
c. Uniform and concentrated loads need not be assumed to act concurrently.

2.3 METALS, GENERAL

A. Metal Surfaces, General: Provide materials with smooth surfaces, without seam marks, roller marks, rolled trade names, stains, discolorations, or blemishes.

B. Brackets, Flanges, and Anchors: Cast or formed metal of same type of material and finish as supported rails unless otherwise indicated.

1. See Structural Drawings.

2.4 STEEL AND IRON

A. Pipe: ASTM A 53/A 53M, Type F or Type S, Grade A, Standard Weight (Schedule 40), unless another grade and weight are required by structural loads.

B. Plates, Shapes, and Bars: ASTM A 36/A 36M.

2.5 FASTENERS

A. General: Provide the following:

1. Ungalvanized-Steel Railings: Plated steel fasteners complying with ASTM B 633 or ASTM F 1941, Class Fe/Zn 5 for zinc coating.
2. Hot-Dip Galvanized Railings: Type 304 stainless-steel or hot-dip zinc-coated steel fasteners complying with ASTM A 153/A 153M or ASTM F 2329 for zinc coating.

B. Fasteners for Anchoring Railings to Other Construction: See Structural Drawings.

2.6 MISCELLANEOUS MATERIALS

A. Welding Rods and Bare Electrodes: Select according to AWS specifications for metal alloy welded.

B. Universal Shop Primer: Fast-curing, lead- and chromate-free, universal modified-alkyd primer complying with MPI#79 and compatible with topcoat.

1. Use primer containing pigments that make it easily distinguishable from zinc-rich primer.

C. Shop prime for field painting per Section 099123

2.7 FABRICATION

A. General: Fabricate railings to comply with requirements indicated for design, dimensions, member sizes and spacing, details, finish, and anchorage, but not less than that required to support structural loads.

B. Shop assemble railings to greatest extent possible to minimize field splicing and assembly. Disassemble units only as necessary for shipping and handling limitations. Clearly mark units for reassembly and coordinated installation. Use connections that maintain structural value of joined pieces.

C. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.

D. Form work true to line and level with accurate angles and surfaces.

E. Cut, reinforce, drill, and tap as indicated to receive finish hardware, screws, and similar items.

F. Connections: Fabricate railings with welded connections unless otherwise indicated.

G. Welded Connections: Cope components at connections to provide close fit, or use fittings designed for this purpose. Weld all around at connections, including at fittings.

1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
2. Obtain fusion without undercut or overlap.
3. Remove flux immediately.
4. At exposed connections, finish exposed surfaces smooth and blended so no roughness shows after finishing and welded surface matches contours of adjoining surfaces.

H. Nonwelded Connections: Connect members with concealed mechanical fasteners and fittings. Fabricate members and fittings to produce flush, smooth, rigid, hairline joints.

1. Fabricate splice joints for field connection using an epoxy structural adhesive if this is manufacturer's standard splicing method.

I. Form Changes in Direction as Follows:

1. As detailed.
2. By bending.

J. For changes in direction made by bending, use jigs to produce uniform curvature for each repetitive configuration required. Maintain cross section of member throughout entire bend without buckling, twisting, cracking, or otherwise deforming exposed surfaces of components.

K. Close exposed ends of railing members with prefabricated end fittings.

L. Brackets, Flanges, Fittings, and Anchors: Provide wall brackets, flanges, miscellaneous fittings, and anchors to interconnect railing members to other work unless otherwise indicated.

M. Toe Boards: Where indicated, provide toe boards at railings around openings and at edge of open-sided floors and platforms. Fabricate to dimensions and details indicated.

2.8 STEEL AND IRON FINISHES

A. Preparation for Shop Priming: Prepare uncoated ferrous-metal surfaces to comply with SSPC-SP 3, "Power Tool Cleaning."

B. Primer Application: Apply shop primer to prepared surfaces of railings unless otherwise indicated. Comply with requirements in SSPC-PA 1, "Shop, Field, and Maintenance Painting of Steel," for shop painting. Primer need not be applied to surfaces to be embedded in concrete or masonry.

1. Shop prime uncoated railings with universal shop primer.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine plaster and gypsum board assemblies, where reinforced to receive anchors, to verify that locations of concealed reinforcements are clearly marked for Installer. Locate reinforcements and mark locations if not already done.

3.2 INSTALLATION, GENERAL

A. Fit exposed connections together to form tight, hairline joints.

B. Perform cutting, drilling, and fitting required for installing railings. Set railings accurately in location, alignment, and elevation; measured from established lines and levels and free of rack.

1. Do not weld, cut, or abrade surfaces of railing components that are coated or finished after fabrication and that are intended for field connection by mechanical or other means without further cutting or fitting.
2. Set posts plumb within a tolerance of 1/16 inch in 3 feet.
3. Align rails so variations from level for horizontal members and variations from parallel with rake of steps and ramps for sloping members do not exceed 1/4 inch in 12 feet.

C. Control of Corrosion: Prevent galvanic action and other forms of corrosion by insulating metals and other materials from direct contact with incompatible materials.

1. Coat, with a heavy coat of bituminous paint, concealed surfaces of aluminum that are in contact with grout, concrete, masonry, wood, or dissimilar metals.

D. Adjust railings before anchoring to ensure matching alignment at abutting joints.

E. Fastening to In-Place Construction: Use anchorage devices and fasteners where necessary for securing railings and for properly transferring loads to in-place construction.

3.3 RAILING CONNECTIONS

A. Welded Connections: Use fully welded joints for permanently connecting railing components. Comply with requirements for welded connections in "Fabrication" Article whether welding is performed in the shop or in the field.

3.4 ADJUSTING AND CLEANING

A. Touchup Painting: Immediately after erection, clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop painting to comply with SSPC-PA 1 requirements for touching up shop-painted surfaces.

1. Apply by brush or spray to provide a minimum 2.0-mil dry film thickness.

3.5 PROTECTION

A. Protect finishes of railings from damage during construction period with temporary protective coverings approved by railing manufacturer. Remove protective coverings at time of Substantial Completion.

END OF SECTION 055213

SECTION 061000 - ROUGH CARPENTRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:
1. Wood blocking and nailers.
2. Plywood sheathing.
3. Framing with dimension lumber.
4. Framing with engineered wood products.

B. Related Requirements:

1. See general structural notes in structural drawings for additional information and requirements.

1.3 DEFINITIONS

A. Dimension Lumber: Lumber of 2 inches nominal or greater but less than 5 inches nominal in least dimension.

B. Lumber grading agencies, and the abbreviations used to reference them, include the following:

1. NLGA: National Lumber Grades Authority.
2. WCLIB: West Coast Lumber Inspection Bureau.
3. WWPA: Western Wood Products Association.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained.

2. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
3. Include copies of warranties from chemical treatment manufacturers for each type of treatment.

1.5 INFORMATIONAL SUBMITTALS

A. Material Certificates: For dimension lumber specified to comply with minimum allowable unit stresses. Indicate species and grade selected for each use and design values approved by the ALSC Board of Review.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.

1. Factory mark each piece of lumber with grade stamp of grading agency.
2. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.
3. Provide dressed lumber, S4S, unless otherwise indicated.

B. Maximum Moisture Content of Lumber: 15 percent for 2-inch nominal thickness or less, 19 percent for more than 2-inch nominal thickness unless otherwise indicated.

C. Engineered Wood Products: Provide engineered wood products acceptable to authorities having jurisdiction and for which current model code research or evaluation reports exist that show compliance with building code in effect for Project.

1. Allowable Design Stresses: Provide engineered wood products with allowable design stresses, as published by manufacturer, that meet or exceed those indicated. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC2 for interior construction not in contact with the ground, Use Category UC3b for exterior construction not in contact with the ground, and Use Category UC4a for items in contact with the ground.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or that does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

D. Application: Treat all rough carpentry unless otherwise indicated.

1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.

2.3 MISCELLANEOUS LUMBER

A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:

1. Blocking.
2. Nailers.

B. For items of dimension lumber size, provide Construction or No. 2 grade lumber and the following species unless noted otherwise in the structural notes and drawings:

1. Douglas fir-larch; WCLIB or WWPA.

C. For concealed boards, provide lumber with 15 percent maximum moisture content and any of the following species and grades unless otherwise noted in the structural notes and drawings:

1. Douglas fir-larch; Standard or No. 3 Common grade; NLGA, WCLIB, or WWPA.

D. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.

E. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.

2.4 PLYWOOD SHEATHING

1. Wall Sheathing: Refer to Structural Drawings.

2.5 DIMENSION LUMBER FRAMING

A. Non-Load-Bearing Interior Partitions: Construction, Stud, or No. 3 grade.
   1. Application: All interior partitions.
   2. Species:
      a. Douglas fir-larch; WCLIB, or WWPA.

B. Structural Framing:
   1. Application: Studs and plates for shear wall strengthening; studs and posts for holdown installation, joists for framing around new openings, blocking for diaphragm and shear wall nailing, blocking for metal strap installations.
   2. Species: Refer to structural drawings
   3. Grade: Refer to structural drawings

2.6 ENGINEERED WOOD PRODUCTS

A. Engineered Wood Products, General: Products shall contain no urea formaldehyde. Source Limitations: Obtain each type of engineered wood product from single source from a single manufacturer.

B. Parallel-Strand, Laminated-Strand, Laminated-Veneer Lumber: Refer to structural drawings.

C. Wood I-Joists: Refer to structural drawings.

D. Rim Boards: Refer to structural drawings.

2.7 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

   1. Where rough carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M.

B. Nails, Brads, and Staples: ASTM F 1667.

C. Power-Driven Fasteners: NES NER-272.

D. Wood Screws: ASME B18.6.1.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Set rough carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry to other construction; scribe and cope as needed for accurate fit. Locate furring, nailers, blocking and similar supports to comply with requirements for attaching other construction.

B. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.

C. Framing with Engineered Wood Products: Install engineered wood products to comply with manufacturer's written instructions.

D. Install plywood backing panels by fastening to studs; coordinate locations with utilities requiring backing panels.

E. Metal Framing Anchors: Install metal framing anchors to comply with manufacturer's written instructions. Install fasteners through each fastener hole.

F. Do not splice structural members between supports unless otherwise indicated.

G. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.

H. Sort and select lumber so that natural characteristics will not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.

I. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

1. Use inorganic boron for items that are continuously protected from liquid water.
2. Use copper naphthenate for items not continuously protected from liquid water.

J. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

1. NES NER-272 for power-driven fasteners.

2. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.

K. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 WOOD BLOCKING, AND NAILER INSTALLATION

A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

3.3 PROTECTION

A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

B. Protect rough carpentry from weather. If, despite protection, rough carpentry becomes sufficiently wet that moisture content exceeds that specified, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 061000

SECTION 062012-INTERIOR FINISH CARPENTRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes

1. Solid surface window sills.
2. Metal Laminate Wainscots.

B. Related Requirements:

1. Division 09 Section “Gypsum Board”.

1.3 SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings:

1. Include plans and elevations showing extent of materials.

C. Samples: For each exposed product and for each color and texture specified.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance data.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.6 WARRANTY

A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace materials that fail(s) in materials or workmanship within specified warranty period.

1. Warranty Period: Per manufactures standard warranty.

PART 2 - PRODUCTS

2.1 SHEET MATERIALS

A. Interior Solid Surface Window Sills: Size and profile as indicated on the drawings. Manufacturer and color as scheduled.

B. Metal Laminate Wainscot: Mix 4 x 8 sheets, locations per drawings. Manufacturer and color as scheduled.

2.2 FASTENERS

A. Non-corrosive or galvanized at all exterior locations and interior wet locations, including Apparatus Bay and all rooms with plumbing fixtures. Cadmium plated dry interior locations. Make fasteners of adequate size, spacing and number to resist design loads under intended use and of types appropriate for materials or conditions for which used. Comply with the following standards:

1. Nails: FF-N-105; common wire for concealed work; finish or casing for exposed work.
2. Screws: Brass for attachment of wood, where exposed; steel elsewhere, except matching metal when used to attach metal items. Use case-hardened steel for self-drilling, self-tapping screws.
3. Bolts, Nuts: FF-B-575, case hardened steel for self-tapping bolts.
4. Lag Bolts and Screws: FF-B-561.
5. Expansion Shields: FF-S-325; metal with no plastic or fiber parts.
6. Toggle Bolts: FF-B-0588; galvanized.

2.3 ANCILLARY MATERIALS

A. Metal Laminate Wainscot: NEMA LD3; General purpose high pressure laminate .030” thickness. Color as scheduled.

B. Adhesives:

1. For woodwork: Phenol-resin or resorcinol-resin.
2. For Metal Laminate: Contact Cement; Federal Specification MMM-A-130B.

C. Hardware: Furnish metal edge and seam trim for metal laminate wainscot, size and type to suit application.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify adequacy of backing and support framing.

B. Verify mechanical, electrical, and building items affecting work of this section are placed and ready to receive this work.

C. Do not install finish interior woodwork until the building has been dry for at least 10 days.

D. Verify spaces and preparation of surfaces are ready to receive finish carpentry items.

E. Broom clean spaces before beginning installation.

3.2 INSTALLATION

A. Coordinate with work under other sections to obtain a neat, workmanlike, finished result.

B. Installation of Finish Carpentry Items:

1. Finished Work: Erect plumb, level, true, square and in accordance with drawings. Do not install interior work until building is thoroughly dry. Leave work in suitable condition to receive finishes noted elsewhere in there specifications.
2. Woodwork assembled on job: Accurately cut, fit and neatly install. Install trim in lengths as long as practicable with running joints mitered and tightly fit. Locate joints only where solid fastenings can be made.
3. Scribing, Mitering and Joining: Done accurately and neatly to conform to details. Cope intersecting moulds at interior corners neatly, rather than miter, where possible.
4. Fasten by securely attaching work to metal studs or backing strips, blocking or other supports where noted or appropriate fasteners. Remove wood raised in by driven nails and screws.

3.3 ERECTION TOLERANCES

A. Maximum Variation from True Position: 1/16 inch.

B. Maximum Offset form true Alignment with Abutting Materials: 1/32 inch.

3.4 METAL LAMINATE WAINSCOT COLOR SCHEDULE

A. See drawings for locations

1. HPL-1 Formica Deco Metal M5307 Plex Umbra

3.5 SOLID SURFACE SILL COLOR SCHEDULE

A. Window sills Formica 656 River Rock Mosaic

END OF SECTION 062012

SECTION 066400 - PLASTIC PANELING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Plastic sheet paneling.

B. Related Requirements:

1. None.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.4 PROJECT CONDITIONS

A. Environmental Limitations: Do not deliver or install plastic paneling until spaces are enclosed and weathertight and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain plastic paneling and trim accessories from single manufacturer.

2.2 PLASTIC SHEET PANELING

A. Glass-Fiber-Reinforced Plastic Paneling: Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D 5319.

1. Product: Subject to compliance with requirements, provide product by one of the following:

    a. Marlite.
    b. Crane Composites, Inc.
    c. Glasteel.
    d. Equal as approved by Architect.

2. Nominal Thickness: Not less than 0.09 inch.
3. Surface Finish: As selected by Architect from manufacturer's full range.
4. Color: As selected by Architect from manufacturer's full range.

2.3 ACCESSORIES

A. Trim Accessories: Manufacturer's standard one-piece vinyl extrusions designed to retain and cover edges of panels. Provide division bars, inside corners, outside corners, and caps as needed to conceal edges.

    1. Color: Match panels.

B. Adhesive: As recommended by plastic paneling manufacturer.

C. Sealant: Mildew-resistant, single-component, neutral-curing silicone sealant recommended by plastic paneling manufacturer and complying with requirements in Section 079200 "Joint Sealants."

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove wallpaper, vinyl wall covering, loose or soluble paint, and other materials that might interfere with adhesive bond.

B. Prepare substrate by sanding high spots and filling low spots as needed to provide flat, even surface for panel installation.

C. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.

D. Condition panels by unpacking and placing in installation space before installation according to manufacturer's written recommendations.

E. Lay out paneling before installing. Locate panel joints to provide equal panels at ends of walls not less than half the width of full panels.

3.3 INSTALLATION

A. Install plastic paneling according to manufacturer's written instructions.

B. Install panels in a full spread of adhesive.

C. Install trim accessories with adhesive.

D. Fill grooves in trim accessories with sealant before installing panels, and bed inside corner trim in a bead of sealant.

E. Maintain uniform space between panels and wall fixtures. Fill space with sealant.

F. Maintain uniform space between adjacent panels and between panels and floors, ceilings, and fixtures. Fill space with sealant.

G. Remove excess sealant and smears as paneling is installed. Clean with solvent recommended by sealant manufacturer and then wipe with clean dry cloths until no residue remains.

END OF SECTION 066400

SECTION 07181 - WATER REPELLENTS

PART 1 GENERAL

1.01 WORK INCLUDED

A. Water repellent coating to exterior clay unit masonry vertical surfaces.

1.02 RELATED WORK

B. Section 079200 - Joint Sealants.

1.03 QUALITY ASSURANCE

A. Applicator: Acceptable to manufacturer.

B. Warranty: Manufacturer's Standard.

1.04 SUBMITTALS

A. Submit product data under provisions of Division 1.

B. Include details of product description, tests performed, limitations to coating, cautionary procedures required during application, and chemical properties, including percentage of solids.

C. Submit manufacturer's installation instructions under provisions of Division 1.

1.06 ENVIORNMENTAL REQUIREMENTS

A. Do not apply coating when ambient temperature is lower that 50 degrees F or higher than 100 degrees F or as required by product manufacturer.

PART 2 PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

A. Clay Masonry Surfaces.

1. Prosoco, Inc.; Siloxane PD
2. Equal approved by Architect.

2.02 MATERIALS

A. Water-based silane/siloxane water repellent.

PART 3 EXECUTION

3.01 INSPECTION

A. Verify that joint sealers are installed and cured.

B. Verify surfaces to be coated are dry, clean, and free of efflorescence, oil, or other matter detrimental to application of coating.

C. Beginning of installation means acceptance of substrate.

3.02 PREPARATION

A. Remove loose particles and foreign matter.

B. Remove oil or foreign substance with a chemical solvent which will not affect coating.

C. Scrub and rinse surfaces with water and let dry.

D. Protect adjacent surfaces not scheduled to receive coating.

E. If applied on unscheduled surfaces, remove immediately, by approved method.

F. Protect landscaping, property and vehicles.

3.03 APPLICATION

A. Seal all exterior masonry surfaces.

B. Apply coating in accordance with manufacturer’s instructions.

C. Apply in two continuous, uniform coats unless otherwise recommended by manufacturer.

D. Mask off windows and doors, light fixtures, louvers, and other non-concrete or masonry materials.

E. Application rates may vary somewhat from specified amounts. Determine optimum rate from manufacturer’s instructions and performance of field samples.

END OF SECTION

SECTION 072100 - THERMAL INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Foam-plastic board insulation.
2. Mineral-wool board insulation.

B. Related Sections:
1. Section 075419 “Thermoplastic Membrane Roofing” for insulation specified as part of roofing construction.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for each product.

1.5 QUALITY ASSURANCE

A. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Protect insulation materials from physical damage and from deterioration due to moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.

B. Protect foam-plastic board insulation as follows:

1. Do not expose to sunlight except to necessary extent for period of installation and concealment.
2. Protect against ignition at all times. Do not deliver foam-plastic board materials to Project site before installation time.
3. Quickly complete installation and concealment of foam-plastic board insulation in each area of construction.

PART 2 - PRODUCTS

2.1 FOAM-PLASTIC BOARD INSULATION

A. Foil-Faced, Polyisocyanurate Board Insulation: ASTM C 1289, Type I, Class 1, with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, per ASTM E 84.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following and acceptable to membrane manufacturer:

a. Johns Manville.
b. Dow Chemical Company (The).
c. Rmax, Inc.

2. Thermal Resistance: Achieve R-Value as indicated in the Drawings.

2.2 MINERAL-WOOL BOARD INSULATION

A. Non-combustible, lightweight, water repellant, semi-rigid insulation board.

1. Compliance and Performance: ASTM C612 – Type 4B, complies.
2. Fire Performance: ASTM E136 – passes.
3. Moisture Resistance: ASTM C1104 – Moisture sorption – 0.03%.
4. Water Vapor Pemeance: ASTM E96 – Water Vapor Transmission, Desiccant Method – 1895 ng Pa.s.m^2.
5. Dimensional Stability: ASTM C356 - <2% @ 1200°.
6. Thermal Resistance: ASTM C518 – R-Value @ 75° - 4.3/inch.
7. Corrosion Resistance: ASTM C665 – Corrosiveness to steel – passed. ASTM C795 – Stainless steel stress corrosion specification – conforms.
8. Density: ASTM C303 – 4.5 lbs/ft^3.

2.3 INSULATION FASTENERS

A. Adhesively Attached, Spindle-Type Anchors: Plate welded to projecting spindle; capable of holding insulation of specified thickness securely in position indicated with self-locking washer in place.

1. Products: Subject to compliance with requirements, provide one of the following:

a. AGM Industries, Inc.; TACTOO Insul-Hangers.
b. Gemco; Spindle Type.

2. Plate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
3. Spindle: Galvanized, low-carbon steel; fully annealed; 0.105 inch in diameter; length to suit depth of insulation indicated.

B. Insulation-Retaining Washers: Self-locking washers formed from 0.016-inch thick galvanized-steel sheet, with beveled edge for increased stiffness, sized as required to hold insulation securely in place, but not less than 1-1/2 inches square or in diameter.

1. Products: As recommended by fastener manufacturer.

C. Anchor Adhesive: Product with demonstrated capability to bond insulation anchors securely to substrates indicated without damaging insulation, fasteners, and substrates.

1. Products: As recommended by fastener manufacturer.

PART 3 - EXECUTION

3.1 PREPARATION

A. Clean substrates of substances that are harmful to insulation or vapor retarders, including removing projections capable of puncturing vapor retarders, or that interfere with insulation attachment.

3.2 INSTALLATION, GENERAL

A. Comply with insulation manufacturer's written instructions applicable to products and applications indicated.

B. Comply with roofing manufacturer’s installation requirements for installation of rigid insulation as part of the roofing assembly.

C. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.

D. Extend insulation to envelop entire area to be insulated. Cut and fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.

E. Provide sizes to fit applications indicated and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units to produce thickness indicated unless multiple layers are otherwise shown or required to make up total thickness.

3.3 INSTALLATION OF INSULATION FOR CONCRETE SUBSTRATES

A. Install board insulation on concrete substrates by adhesively attached, spindle-type insulation anchors as follows:

1. Fasten insulation anchors to concrete substrates with insulation anchor adhesive according to anchor manufacturer's written instructions. Space anchors according to insulation manufacturer's written instructions for insulation type, thickness, and application indicated.
2. Apply insulation standoffs to each spindle to create cavity width indicated between concrete substrate and insulation.
3. After adhesive has dried, install board insulation by pressing insulation into position over spindles and securing it tightly in place with insulation-retaining washers, taking care not to compress insulation below indicated thickness.
4. Where insulation will not be covered by other building materials, apply capped washers to tips of spindles.

3.4 PROTECTION

A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

END OF SECTION 072100

SECTION 072500 - WEATHER BARRIERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Building paper.
2. Building wrap.
3. Flexible flashing.

B. Related Requirements:

1. Section 061000 Rough Carpentry.

2. Section 074646 Fiber-Cement Siding.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. For building wrap, include data on air and water-vapor permeance based on testing according to referenced standards.

1.4 INFORMATIONAL SUBMITTALS

A. Evaluation Reports: For weather-resistive barrier and flexible flashing, from ICC-ES.

PART 2 - PRODUCTS

2.1 WEATHER-RESISTIVE BARRIER (WRB)

A. Provide materials and related flashing and accessories by one manufacturer.

1. WRB: Fortifiber Super JumboTex 60 minute paper or approved equal.
2. Self adhesive flexible flashing: Fortifiber, Fortiflash 40 or approved equal.

3. Jamb Flashing: Fortifiber Moistop Next or approved equal.
4. Sealant: Forifiber or approved equal.

PART 3 - EXECUTION

3.1 VERIFICATION

A. Verify condition of substrate and adjacent materials.

3.2 PREPARATION

A. Remove loose particles and foreign matter which might impair adhesion.

B. Clean and prime substrate to receive adhesive and sealants in accordance with manufacturer's instructions.

C. Brush, spray, or roller apply primer on substrates where self-adhesion is difficult or fails.

3.3 WATER-RESISTIVE BARRIER INSTALLATION

A. Install in accordance with manufacturer's instructions over exterior sheathing. Weather resistant membrane shall be free from holes, tears, and punctures

B. One layer of weather resistive barrier (WRB) shall be applied to all exterior walls. The weather resistive barrier shall be laid and weatherlapped in shingle-fashion to create a leak-free water-shedding layer behind siding or cladding.

C. All flashing through cladding shall be incorporated into the weather resistive barrier in watershedding, shingled fashion. All flashing components of the cladding system, including WRB, sheet metal flashing, and flexible membrane flashing shall be installed in weatherlapped, shingled fashion. The WRB shall lap down over the up-turned, vertical flange of window head flashing, and other flashings as applicable so that water will be directed to the outside of the wall cladding system and building—and not be directed into the interior of the wall assembly. Apply courses of WRB below windows so that they lap up, beneath window sill membrane flashing.

D. Repair any tears or punctures in weather resistant membrane immediately before concealment of other work.

3.4 INSTALLATION - SELF-ADHERING FLEXIBLE FLASHING AND ACCESSORIES

A. Apply self-adhering membrane and accessories in accordance to manufacturer's instructions to provide a weather proof installation.

B. Lap joints a minimum of 2 inches at side and end laps.

C. Roll surfaces to ensure full contact.

D. Do not place in contact with PVC or vinyl membranes.

END OF SECTION 072500

SECTION 074646 - FIBER-CEMENT SIDING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes:

1. Fiber-cement siding.
2. Accessories.

B. Related Requirements:

1. Section 061000 "Rough Carpentry" for wood furring, grounds, nailers, and blocking.
2. Section 072500 "Weather Barriers" for weather-resistive barriers.

1.3 COORDINATION

A. Coordinate siding installation with flashings and other adjoining construction to ensure proper sequencing.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

B. Samples for Verification: For each type, color, texture, and pattern required.

1. 12-inch long-by-actual-width Sample of siding.
2. 12-inch long-by-actual-width Samples of trim and accessories.

1.5 INFORMATIONAL SUBMITTALS

A. Product Certificates: For each type of fiber-cement siding.

B. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for fiber-cement siding.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of product, including related accessories, to include in maintenance manuals.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store packaged materials in original containers with labels intact until time of use.

B. Store materials on elevated platforms, under cover, and in a dry location.

1.8 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace products that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including cracking and deforming.
b. Deterioration of materials beyond normal weathering.

2. Warranty Period: Manufacturer's standard.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations: Obtain products, including related accessories, from single source from single manufacturer.

2.2 FIBER-CEMENT SIDING

A. General: ASTM C 1186, Type A, Grade II, fiber-cement board, noncombustible when tested according to ASTM E 136; with a flame-spread index of 25 or less when tested according to ASTM E 84.

1. Basis-of-Design Product: Subject to compliance with requirements, provide James Hardie, HardiePlank or comparable product by one of the following:

a. James Hardie Building Products, Inc.
b. CertainTeed Corporation.
c. GAF Materials Corporation.

B. Labeling: Provide fiber-cement siding that is tested and labeled according to ASTM C 1186 by a qualified testing agency acceptable to authorities having jurisdiction.

C. Nominal Thickness: Not less than 5/16 inch.

D. Horizontal Pattern: Boards 7-1/4 to 7-1/2 inches wide in plain style.

1. Texture: Smooth.

E. Factory Finish: Manufacturer's standard primer system for field painting.

2.3 ACCESSORIES

A. Siding Accessories, General: Provide starter strips, edge trim, outside and inside corner caps, and other items as recommended by siding manufacturer for building configuration.

1. Provide accessories matching color and texture as indicated in Drawings.

B. Flashing: Provide aluminum flashing complying with Section 076200 "Sheet Metal Flashing and Trim" at window and door heads and where indicated.

1. Finish for Aluminum Flashing: Siliconized polyester coating.

C. Fasteners:

1. For fastening to metal, fasteners are ET & F 0.100 x 1.5” x .25” HP conforming with ICC ES Report 4444.

2. Fasteners shall be stainless steel.

D. Fiberglass Thermal Spacer:
1. Basis of Design: Cascadia Windows Inc., Cascadia Clip or approved equal.
2. Thermal Spacer Depth: 2 inches nominal.
3. Spacer Fasteners: As recommended by spacer manufacturer for substrate.

E. Insect Screen: Glass-Fiber Mesh Fabric, 18-by-14 or 18-by-16 mesh of PVC-coated, glass-fiber threads; woven and fused to form a fabric mesh resistant to corrosion, shrinkage, stretch, impact damage, and weather deterioration. Comply with ASTM D 3656.

1. Mesh Color: Manufacturer's standard.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates for compliance with requirements for installation tolerances and other conditions affecting performance of fiber-cement siding and related accessories.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean substrates of projections and substances detrimental to application.

3.3 INSTALLATION

A. General: Comply with manufacturer's written installation instructions applicable to products and applications indicated unless more stringent requirements apply.

1. Do not install damaged components.
2. Install fasteners no more than 24 inches o.c.

B. Install joint sealants as specified in Section 079200 "Joint Sealants" and to produce a weathertight installation.

3.4 ADJUSTING AND CLEANING

A. Remove damaged, improperly installed, or otherwise defective materials and replace with new materials complying with specified requirements.

B. Clean finished surfaces according to manufacturer's written instructions and maintain in a clean condition during construction.

END OF SECTION 074646

SECTION 075419 - THERMOPLASTIC MEMBRANE ROOFING

PART 1 - GENERAL CONDITIONS

1.01 SECTION INCLUDES

A. Fully-adhered PVC roofing system including membrane, PVC flashings and other components.

1.02 Related Work

The work includes but is not limited to the installation of:

1. Substrate Preparation
2. Roof Drains
3. Vapor Barrier
4. Wood Blocking
5. Insulation
6. Separation Layers
7. Roof Membrane
8. Fasteners
9. Adhesive for Flashings
10. Roof Membrane Flashings
11. Walkways
12. Metal Flashings
13. Sealants

1.03 QUALITY ASSURANCE

A. This roofing system shall be applied only by a Roofing Applicator authorized by manufacturer prior to bid.

B. Upon completion of the installation and the delivery to manufacturer by the Applicator of certification that all work has been done in strict accordance with the contract specifications and manufacturer’s requirements, a manufacturer’s Technical Service Representative will review the installed roof system wherever a Standard or System warranty has been specified.

C. There shall be no deviation made from the Project Specification or the approved shop drawings without prior written approval by the Owner, the Owner's Representative and manufacturer.

D. All work pertaining to the installation of Sarnafil membrane and flashings shall only be completed by Applicator personnel trained and authorized by Sika Sarnafil in those procedures.

1.04 SUBMITTALS

Submit the following:

A. Copies of Specification.

B. Samples of each primary component to be used in the roof system and the manufacturer's current literature for each component.

C. Written approval by the insulation manufacturer (as applicable) for use and performance of the product in the proposed system.

D. Sample copy of manufacturer’s warranty.

E. Sample copy of Applicator's warranty.

F. Dimensioned shop drawings which shall include:

1. Outline of roof with roof size and elevations shown.
2. Profile details of flashing methods for penetrations.
3. Technical acceptance from manufacturer.

G. Certifications by manufacturers of roofing and insulating materials that all materials supplied comply with all requirements of the identified ASTM and other industry standards or practices.

H. Certification from the Applicator that the system specified meets all identified code and insurance requirements as required by the Specification.

I. Material Safety Data Sheets (MSDS)

1.05 CODE REQUIREMENTS

The Applicator shall submit evidence that the proposed roof system meets the requirements of the local building code and has been tested and approved or listed by the following test organizations. These requirements are minimum standards and no roofing work shall commence without written documentation of the system's compliance, as required in the "Submittals" section of this specification.

A. System shall be designed to meet a minimum wind design requirements of the most recent version of ASCE 7.

1.06 PRODUCT DELIVERY, STORAGE AND HANDLING

A. All products delivered to the job site shall be in the original unopened containers or wrappings bearing all seals and approvals.

B. Handle all materials to prevent damage. Place all materials on pallets and fully protect from moisture.

C. Membrane rolls shall be stored lying down on pallets and fully protected from the weather with clean canvas tarpaulins. Unvented polyethylene tarpaulins are not

accepted due to the accumulation of moisture beneath the tarpaulin in certain weather conditions that may affect the ease of membrane weldability.

D. As a general rule all adhesives shall be stored at temperatures between 40 degree F and 80 degree F. Read instructions contained on adhesive canister for specific storage instructions.

E. All flammable materials shall be stored in a cool, dry area away from sparks and open flames. Follow precautions outlined on containers or supplied by material manufacturer/supplier.

F. Any materials which the Owner's representative or manufacturer determine to be damaged are to be removed from the job site and replaced at no cost to the Owner.

1.07 JOB CONDITIONS

A. Materials may be installed under certain adverse weather conditions but only after consultation with manufacturer, as installation time and system integrity may be affected.

B. Only as much of the new roofing as can be made weather tight each day, including all flashing and detail work, shall be installed. All seams shall be cleaned and heat welded before leaving the job site that day.

C. All work shall be scheduled and executed without exposing the interior building areas to the effects of inclement weather. The existing building and its contents shall be protected against all risks.

D. All surfaces to receive new insulation, membrane or flashings shall be dry. Should surface moisture occur, the Applicator shall provide the necessary equipment to dry the surface prior to application.

E. All new and temporary construction, including equipment and accessories, shall be secured in such a manner as to preclude wind blow-off and subsequent roof or equipment damage.

F. Uninterrupted waterstops shall be installed at the end of each day's work and shall be completely removed before proceeding with the next day's work. Waterstops shall not emit dangerous or unsafe fumes and shall not remain in contact with the finished roof as the installation progresses. Contaminated membrane shall be replaced at no cost to the Owner.

G. The Applicator is cautioned that certain PVC membranes are incompatible with asphalt, coal tar, heavy oils, roofing cements, creosote and some preservative materials. Such materials shall not remain in contact with PVC membranes. The Applicator shall consult the manufacturer regarding compatibility, precautions and recommendations.

H. Arrange work sequence to avoid use of newly constructed roofing as a walking surface or for equipment movement and storage. Where such access is absolutely required, the Applicator shall provide all necessary protection and barriers to segregate the work area and to prevent damage to adjacent areas. A substantial protection layer consisting of

plywood over insulation board shall be provided for all new and existing roof areas that receive rooftop traffic during construction.

I. Prior to and during application, all dirt, debris and dust shall be removed from surfaces by vacuuming, sweeping, blowing with compressed air or similar methods.

J. The Applicator shall follow all safety regulations as required by OSHA and any other applicable authority having jurisdiction.

K. All roofing, insulation, flashings and metal work removed during construction shall be immediately taken off site to a legal dumping area authorized to receive such materials. Hazardous materials, such as materials containing asbestos, are to be removed and disposed of in strict accordance with applicable City, State and Federal requirements.

L. All new roofing waste material (i.e., scrap roof membrane, empty cans of adhesive) shall be immediately removed from the site by the Applicator and properly transported to a legal dumping area authorized to receive such material.

M. The Applicator shall take precautions that storage and application of materials and equipment does not overload the roof deck or building structure.

N. Flammable adhesives and deck primers shall not be stored and not be used in the vicinity of open flames, sparks and excessive heat.

O. All rooftop contamination that is anticipated or that is occurring shall be reported to manufacturer to determine the corrective steps to be taken.

P. The Applicator shall verify that all roof drain lines are functioning correctly (not clogged or blocked) before starting work. Applicator shall report any such blockages in writing (letter copy to manufacturer) to the Owner's Representative for corrective action prior to the installation of the roof system.

Q. Applicator shall immediately stop work if any unusual or concealed condition is discovered and shall immediately notify Owner of such condition in writing for correction.

R. Site cleanup, including both interior and exterior building areas that have been affected by construction, shall be completed to the Owner's satisfaction.

S. All landscaped areas damaged by construction activities shall be repaired at no cost to the Owner.

T. The Applicator shall conduct fastener pullout tests in accordance with the latest version of the SPRI/ANSI Fastener Pullout Standard to verify condition of the deck/substrate and to confirm expected pullout values.

U. The membrane shall not be installed under the following conditions without consulting manufacturer’s Technical Dept. for precautionary steps:

1. The roof assembly permits interior air to pressurize the membrane underside.

2. Any exterior wall has 10 percent or more of the surface area comprised of opening doors or windows.
3. The wall/deck intersection permits air entry into the wall flashing area.

V. Precautions shall be taken when using adhesives at or near rooftop vents or air intakes. Adhesive odors could enter the building. Coordinate the operation of vents and air intakes in such a manner as to avoid the intake of adhesive odor while ventilating the building. Keep lids on unused cans at all times.

W. Protective wear shall be worn when using solvents or adhesives or as required by job conditions.

X. Membranes are slippery when wet or covered with snow, frost, or ice. Working on surfaces under these conditions is hazardous. Appropriate safety measures must be implemented prior to working on such surfaces. Always follow OSHA and other relevant fall protection standards when working on roofs.

1.08 WARRANTIES

A. System Warranty

Upon successful completion of the work to manufacturer's satisfaction and receipt of final payment, the System Warranty shall be issued.

B. Owner Responsibility

Owner shall notify both manufacturer and the Applicator of any leaks as they occur during the time period when both warranties are in effect.

1.09 WARRANTY DURATIONS

A. Sika Sarnafil's warranty shall be in effect for a 20 year duration.

PART 2 - PRODUCTS

2.01 GENERAL

A. The components of the Sika Sarnafil Adhered roof system are to be products of Sika Sarnafil as indicated on the Detail Drawings and specified in the Contract Documents.

B. Components to be used that are other than those supplied or manufactured by Sika Sarnafil may be submitted for review and acceptance by Sika Sarnafil. Sika Sarnafil's acceptance of any other product is only for a determination of compatibility with Sika Sarnafil products and not for inclusion in the Sika Sarnafil warranty. The specifications, installation instructions, limitations, and restrictions of the respective manufacturers must be reviewed by the Owner's Representative for acceptability for the intended use with Sika Sarnafil products.

C. Manufacturer to have a minimum of two years experience recycling their membranes at the end of their service life back into new membrane products. Provide a minimum of five reference projects.

D. Condensation or moisture migration into the roof system must be controlled so that it does not compromise the performance of the insulation and other components of the assembly. Moisture vapor tends to migrate from warmer to cooler areas. Air/vapor retarders are used to inhibit or block the flow of warm moist air into the roof system. To determine if an air/vapor barrier is necessary, a design professional with experience with air handling and moisture control should be consulted.

Special consideration should be given to construction related moisture. An example is the significant amount of moisture generated when concrete floor slabs are poured after the roof has been installed. Sika Sarnafil is not responsible for damage to the insulation when exposed to construction related moisture.

2.02 MEMBRANE

A. Basis of Design:
1. Manufacturer: Sika Sarnafil
2. Product/System: Sarnafil Roof System G410 Textured membrane, fully adhered.

B. Membrane shall conform to ASTM D4434 (latest version), “Standard for Polyvinyl Chloride Sheet Roofing,” Classification: Type III.

1. G410, 60 mil, thermoplastic membrane with fiberglass reinforcement and felt backing. Textured surface.

C. Certified Polymer Thickness

1. Membrane manufacturer is to certify that the polymer thickness is of the polymer thickness specified (see 2.02, C, 1). Certification is to be signed by the membrane manufacturer’s quality control manager. ASTM +/- tolerance for membrane thickness is not accepted.

D. Color of Membrane

1. At Textured Roof Locations: Standard gray color.

E. Typical Physical Properties

2.03 FLASHING MATERIALS

A. Wall/Curb Flashing

1. Sarnafil G410-15 60 mil Membrane

A fiberglass reinforced membrane adhered to approved substrate using Sarnacol adhesive.

2. Sarnaclad

   A PVC-coated, heat-weldable sheet metal capable of being formed into a variety of shapes and profiles. Sarnaclad is a 24 gauge, G90 galvanized metal sheet with a 20 mil unsupported Sarnafil membrane laminated on one side. The dimensions of Sarnaclad are 4 ft x 8 ft and 4 ft x 10 ft.

3. Sarnaclad

   A PVC-coated, heat-weldable sheet metal capable of being formed into a variety of shapes and profiles. Sarnaclad is a 24 gauge, G90 galvanized metal sheet with a 20 mil unsupported Sarnafil membrane laminated on one side. The dimensions of Sarnaclad are 4 ft x 8 ft and 4 ft x 10 ft.

4. Non-Typical Edge

   Project-specific perimeter edge detail reviewed and accepted for one-time use by Sika Sarnafil's Technical Department. Consult Regional Technical Manager prior to job start for review and consideration for acceptance.

B. Miscellaneous Flashings and Accessories

1. Sarnastack

   A prefabricated vent pipe flashing made from 0.048 inch (48 mil) thick Sarnafil G410 membrane. Available in five different sizes.

2. Sarnadrain-RAC

   PVC-coated, heavy-duty aluminum roof drain insert that mechanically seals to the drainpipe interior. Sarnadrain-RAC is made of 0.080 inch thick 6063 aluminum with a urethane seal installed at the end of the drainpipe. The large 14 inch x 14 inch drain strainer is also made of 0.080 inch thick aluminum stock. The flange dimensions of Sarnadrain-RAC are 18 inches x 18 inches. Provide one overflow-type at each pair of existing drains. Provide custom flange sizes as needed to suit project conditions.

3. Sarnacorners - Inside

   Prefabricated inside corners made of 0.060 inch (60 mil) thick membrane that are heat-weldable to membrane or Sarnaclad base flashings.

4. Sarnacorners - Outside

   Prefabricated outside corners made of 0.060 inch (60 mil) thick membrane that are heat-weldable to membrane or Sarnaclad base flashings.

5. Open Post Flashing

Prefabricated post flashing, 0.048 inch (48 mil) thick, with an open seam used to flash obstructed rooftop conduits and pipes 1/2 to 1-1/4 inch in diameter. Available in 2 sizes; 1/2 to 3/4 inch and 3/4 to 1-1/4 inch diameter. Open Post Flashings are heat welded in place and terminated at the top of the penetration completing the pipe penetration detail.

6. Sikaflex-1a Sealant

   A proprietary sealant used at flashing terminations. Consult Product Data Sheet for additional information.

7. Sarnacol 2170 Adhesive

   A solvent-based reactivating adhesive used to attach membrane to flashing substrate.

8. Sarnacol 2170 VC Adhesive

   A solvent-based, low VOC, reactivating adhesive used to attach membrane to flashing substrate.

9. S327 Coverstrip

   9 inch wide precut flashing made from Sarnafil S327 polyester reinforced membrane. Used to coverstrip Sarnabar and Sarnadisc.

2.04 INSULATION/OVERLAYMENT/BARRIER BOARD

A. Coverboard: Georgia-Pacific DensDeck Prime roof board, ½ inch thickness, or equal approved by manufacturer.

B. Vapor Barrier: Sarnavap self-adhered vapor barrier, 32 mil thickness, suitable for use as a temporary roof membrane.

C. Thermal Insulation: Per Section 072100.

2.05 MISCELLANEOUS ACCESSORIES

A. Aluminum Tape

A 2 inch wide pressure-sensitive aluminum tape used as a separation layer between small areas of asphalt contamination and the membrane and as a bond-breaker under the coverstrip at Sarnaclad joints.

B. Multi-Purpose Tape

A high performance sealant tape used with metal flashings as a preventive measure against air and wind blown moisture entry.

2.06 SEALANTS AND PITCH POCKET FILLERS

A. Sarnafil Sikaflex-1a Sealant (for termination details).

B. Depending on substrates, the following sealants are options for temporary overnight tie-ins:

1. Type III hot asphalt conforming to ASTM D312 (latest version).
2. Sarnafiller.
3. Multiple layers of roofing cement and felt.
4. Spray-applied, water-resistant urethane foam.
5. Mechanical attachment with rigid bars and compressed sealant.

2.07 MISCELLANEOUS FASTENERS AND ANCHORS

A. All fasteners, anchors, nails, straps, bars, etc. shall be post-galvanized steel, aluminum or stainless steel. Mixing metal types and methods of contact shall be assembled in such a manner as to avoid galvanic corrosion. Fasteners for attachment of metal to masonry shall be expansion type fasteners with stainless steel pins. All concrete fasteners and anchors shall have a minimum embedment of 1-1/4 inch and shall be approved for such use by the fastener manufacturer. All miscellaneous wood fasteners and anchors used for flashings shall have a minimum embedment of 1 inch and shall be approved for such use by the fastener manufacturer.

2.08 RELATED MATERIALS

A. Wood Nailer

Treated wood nailers shall be installed into the structural purlins at the perimeter of the entire roof and around such other roof projections and penetrations as specified on Project Drawings. Thickness of nailers must match the insulation thickness to achieve a smooth transition. Wood nailers shall be treated for fire and rot resistance (wolmanized or osmose treated) and be #2 quality or better lumber. Creosote or asphalt-treated wood is not acceptable. Wood nailers shall conform to Factory Mutual Loss Prevention Data Sheet 1-49. All wood shall have a maximum moisture content of 19 percent by weight on a dry-weight basis.

2.09 SHEET METAL COPINGS AND FLASHINGS

A. Sheet Metal Copings and other flashings exposed to view: 24 gage, galvanized steel with Kynar PVF2 finish. Fabricate and install with standing seam joints. Colors as selected.

B. Coping Cleats and other sheetmetal flashing not exposed to view: 22 gage, galvanized steel or stainless steel as noted on drawings. Solder watertight where indicated.

PART 3 - EXECUTION

3.01 PRE-CONSTRUCTION CONFERENCE

A. The Applicator, Owner's Representative/Designer and Manufacturer(s) shall attend a pre-construction conference.

B. The meeting shall discuss all aspects of the project including but not limited to:

1. Safety
2. Set up
3. Construction schedule
4. Contract conditions
5. Coordination of the work

3.02 SUBSTRATE CONDITION

A. Applicator shall be responsible for acceptance or provision of proper substrate to receive new roofing materials.

B. Applicator shall verify that the work done under related sections meets the following conditions:

1. Roof drains, gutters and scuppers have been reconditioned or replaced and installed properly.
2. Roof curbs, nailers, equipment supports, vents and other roof penetrations are properly secured and prepared to receive new roofing materials.
3. All surfaces are smooth and free of dirt, debris and incompatible materials.
4. All roof surfaces shall be free of water, ice and snow.

3.03 SUBSTRATE PREPARATION

The roof deck and existing roof construction must be structurally sound to provide support for the new roof system. The Owner's Representative and Applicator shall determine the condition of the roof deck. Deteriorated decking or wet or deteriorated materials are to be removed and replaced. The Applicator shall load materials on the rooftop in such a manner as to eliminate risk of deck overload due to concentrated weight. The Owner's Representative shall ensure that the roof deck is secured to the structural framing according to local building code and in such a manner as to resist all anticipated wind loads in that location. A structural evaluation by a licensed structural engineer should be performed to determine that the combined weight of the roofs, other collateral, and live loads do not exceed the load capacity of the structure.

The existing metal roof system is to be removed and recycled or otherwise legally disposed of by the applicator. Applicator is responsible for all costs associated with removing the existing roof, hauling, and dump fees.

3.04 SUBSTRATE INSPECTION

A. A dry, clean and smooth substrate shall be prepared to receive the Sika Sarnafil fully adhered roof system.

B. The Applicator shall inspect the substrate for defects such as excessive surface roughness, contamination, structural inadequacy, or any other condition that will adversely affect the quality of work.

C. The substrate shall be clean, smooth, dry, free of flaws, sharp edges, loose and foreign material, oil and grease. Roofing shall not start until all defects have been corrected.

D. All roof surfaces shall be free of water, ice and snow.

E. Compressible fill material or spray, expanding urethane foam shall be used to minimize air infiltration under wood nailers for corrugated metal roof panels.

F. Sika Sarnafil shall be applied over compatible or acceptable substrates only.

3.05 VAPOR BARRIER/AIR BARRIER INSTALLATION

A. Sarnavap Self-Adhered

A. Primer Application

The substrate must be clean, dry and free of dust, grease or other contaminants. Shake well before using. Apply to clean and dry surfaces with a paint brush, roller or sprayer. Application rates will vary depending on substrate. Sarnavap Self-Adhered vapor barrier must be installed on the same day as the primer application. Acceptable substrates for primer application include wood, concrete, lightweight concrete, gypsum boards and decks. Drying time is typically 30 minutes to 3 hours.

Spraying equipment recommendations:
a) Spray tip size: between 20 and 25 mils.
b) Pressure: 1300 psi continuous

To Install:
a) Apply primer to prepared substrate.
b) Allow primer to dry completely.
c) Install Sarnavap Self-Adhered vapor barrier.

Notes:
a) Do not install when it is raining, snowing, or on wet/humid surfaces.
b) Install Sarnavap Self-Adhered Primer at temperatures 32 degree F (0 degree C) and above. Average coverage rate is 0.25 to 1.22 gallons per square (0.1 to 0.5 L per m²).
c) Install Sarnavap Self-Adhered Primer WB at temperatures 41 degree F (5 degree C) and above. Average coverage rate is 0.25 to 0.75 gallon per square (0.1 to 0.3 L per m²). KEEP FROM FREEZING.
d) Do not use Sarnavap Self-Adhered Primer WB to seal Sarnavap Self-Adhered vapor barrier membrane joints.
e) Sarnavap Self-Adhered Primer WB is not suitable for plastic surfaces.
f) Do not use Sarnavap Self-Adhered Primer WB on asphaltic boards.

1. Membrane Application Over Steel, Wood or Concrete Deck (New Construction or Reroofing with Removal of Existing Roofing):

Install Sarnavap Self-Adhered over a clean and dry substrate. In concrete deck applications concrete must be fully dry. Do not install when it is raining, snowing, or on wet/humid surfaces. Install in temperatures 14 degree F (-10 degree C) and above. The use of a primer is required on the following substrates: wood, concrete, lightweight concrete, gypsum boards and decks. On metal decks use a metal plate (6 x 42 inches - 15 x 106 cm) to support the membrane end lap between metal flutes ensuring a complete end lap seal.

a) Begin application at the bottom of the slope. Unroll Sarnavap Self-Adhered onto the substrate without adhering for alignment. Overlap each preceding sheet by 3 inches (75 mm) lengthwise following the reference line and by 6 inches (150 mm) at each end. Stagger end laps by at least 12 inches (300 mm). Do not immediately remove the silicone release sheet.

b) Once aligned, peel back a portion of the silicone release sheet and press the membrane onto the substrate for initial adherence. Hold Sarnavap Self-Adhered tight and peel back the release sheet by pulling diagonally.

c) Use a minimum 100 lb (45 kg) steel, membrane roller, by rolling in two directions to press Sarnavap Self-Adhered down into the substrate including the laps. Finish by aligning the edge of the roller with the lower end of the side laps and rolling up the membrane. Do not cut the membrane to remove air bubbles trapped under the laps. Squeeze out air bubbles by pushing the roller to the edge of the laps.

3.06 WOOD NAILER INSTALLATION

A. Install continuous wood nailers at the perimeter of the entire roof and around roof projections and penetrations as shown on the Detail Drawings.

B. Nailers shall be anchored to resist a minimum force of 300 pounds per lineal foot (4,500 Newtons per lineal meter) in any direction. Individual nailer lengths shall not be less than 3 feet (0.9 meter) long. Nailer fastener spacing shall be at 12 inches (0.3 m) on center or 16 inches (0.4 m) on center if necessary to match the structural framing. Fasteners shall be staggered 1/3 the nailer width and installed within 6 inches (0.15 m) of each end. Two fasteners shall be installed at ends of nailer lengths. Nailer attachment shall also meet the requirements of the current Factory Mutual Loss Prevention Data Sheet 1-49.

C. Thickness shall be as required to match substrate and insulation height to allow a smooth transition.

D. Any existing nailer woodwork which is to remain shall be firmly anchored in place to resist a minimum force of 300 pounds per lineal foot (4,500 Newtons per lineal meter) in any direction and shall be free of rot, excess moisture or deterioration. Only woodwork

shown to be reused in Detail Drawings shall be left in place. All other nailer woodwork shall be removed.

E. Stainless steel, corrosion resistant, fasteners are required when mechanically attaching any Sika Sarnafil product to wood nailers and wood products treated with ACQ (Alkaline copper Quaternary). When ACQ treated wood is used on steel roof decks or with metal edge detailing, a separation layer must be placed between the metal and ACQ treated wood.

3.07 INSULATION INSTALLATION

A. Insulation shall be installed according to insulation manufacturer's instructions.

B. Insulation shall be neatly cut to fit around penetrations and projections with gaps not exceeding 1/4 inch.

C. If applicable, install tapered insulation around drains creating a drain sump.

D. Do not install more insulation board than can be covered with Sarnafil membrane by the end of the day or the onset of inclement weather.

E. Use at least 2 layers of insulation when the total insulation thickness for the overlayment exceeds 2-1/2 inches. Stagger joints at least 12 inches between layers.

F. Mechanical Attachment

1. Insulation shall be mechanically fastened to the deck with approved fasteners and plates at a rate according to the insulation manufacturer's and Sika Sarnafil's recommendations for fastening rates and patterns, but not less than 1 fastener per 4 square feet . The quantity and locations of the fasteners and plates shall also cause the insulation boards to rest evenly on the roof deck/substrate. Each insulation board shall be installed tightly against the adjacent boards on all sides.

2. Fasteners are to be installed consistently in accordance with fastener manufacturer's recommendations. Fasteners are to have minimum penetration of 1 inch through the structural deck. Do not penetrate substrate at exposed eave locations.

3. Use fastener tools with a depth locator and torque-limiting attachment as recommended or supplied by fastener manufacturer to ensure proper installation.

3.08 INSTALLATION OF MEMBRANE

The surface of the insulation or substrate shall be inspected prior to installation of the Sarnafil roof membrane. The substrate shall be clean, dry, free from debris and smooth with no surface roughness or contamination. Broken, delaminated, wet or damaged insulation boards shall be removed and replaced.

C. Sarnacol 2170 / 2170 VC Adhesive:

1. Over the properly installed and prepared substrate surface, adhesive shall be applied using solvent-resistant 3/4 inch (19 mm) nap paint rollers. The adhesive shall be applied to the substrate at a rate according to Sika Sarnafil requirements. No adhesive is applied to the back of the G410 feltback membrane. The adhesive shall be applied in smooth, even coats with no gaps, globs, puddles or similar inconsistencies. Only an area which can be completely covered in the same day's operations shall be coated with adhesive. The first layer of adhesive shall be allowed to dry completely prior to installing a second layer of adhesive and the membrane.

2. The G410 feltback roof membrane is unrolled immediately into a second layer of wet adhesive. Adjacent to that first installed roll of membrane, another second layer of wet adhesive is applied and the second roll of membrane is immediately unrolled into it, overlapping the first roll by 3 inches (75 mm). This process is repeated throughout the roof area. Immediately after application into adhesive, each roll shall be pressed firmly in place with a minimum 100 lb (45 kg) steel, membrane roller, by rolling in two directions. Do not allow the second application of adhesive to dry at all!

3. Weld G410 coverstrips at all G410 feltback seams that do not have a factory selvage edge.

   Notes:

   a) The Applicator shall count the amount of pails of adhesive used per area per day to verify conformance to the specified adhesive rate.
   b) No adhesive shall be applied in seam areas. All membrane shall be applied in the same manner.

3.09 HOT-AIR WELDING OF SEAM OVERLAPS

A. General

1. All seams shall be hot-air welded. Seam overlaps should be 5-1/2 inches wide for Sarnadisc and Sarnadisc-XPN, and 7 inches wide for Sarnadisc-MAXLoad when automatic machine-welding and 4 inches wide when hand-welding, except for certain details.

2. Welding equipment shall be provided by or approved by Sika Sarnafil. All mechanics intending to use the equipment shall have successfully completed a training course provided by a Sika Sarnafil Technical Service Representative prior to welding.

3. All membrane to be welded shall be clean and dry.

B. Hand-Welding

Hand-welded seams shall be completed in two stages. Hot-air welding equipment shall be allowed to warm up for at least one minute prior to welding.

1. The back edge of the seam shall be welded with a narrow but continuous weld to prevent loss of hot air during the final welding.

2. The nozzle shall be inserted into the seam at a 45 degree angle to the edge of the membrane. Once the proper welding temperature has been reached and the membrane begins to "flow", the hand roller is positioned perpendicular to the nozzle and rolled lightly. For straight seams, the 1-1/2 inch wide nozzle is recommended for use. For corners and compound connections, the 3/4 inch wide nozzle shall be used.

C. Machine Welding

1. Machine welded seams are achieved by the use of Sika Sarnafil's automatic welding equipment. When using this equipment, Sika Sarnafil's instructions shall be followed and local codes for electric supply, grounding and over current protection observed. Dedicated circuit house power or a dedicated portable generator is recommended. No other equipment shall be operated simultaneously off the generator.

2. Metal tracks may be used over the deck membrane and under the machine welder to minimize or eliminate wrinkles.

D. Quality Control of Welded Seams

1. The Applicator shall check all welded seams for continuity using a rounded screwdriver. Visible evidence that welding is proceeding correctly is smoke during the welding operation, shiny membrane surfaces, and an uninterrupted flow of dark gray material from the underside of the top membrane. On-site evaluation of welded seams shall be made daily by the Applicator at locations as directed by the Owner's Representative or Sika Sarnafil's representative. One inch wide cross-section samples of welded seams shall be taken at least three times a day. Correct welds display failure from shearing of the membrane prior to separation of the weld. Each test cut shall be patched by the Applicator at no extra cost to the Owner.

3.10 MEMBRANE FLASHINGS

All flashings shall be installed concurrently with the roof membrane as the job progresses. No temporary flashings shall be allowed without the prior written approval of the Owner's Representative and Sika Sarnafil. Approval shall only be for specific locations on specific dates. If any water is allowed to enter under the newly completed roofing, the affected area shall be removed and replaced at the Applicator's expense. Flashing shall be adhered to compatible, dry, smooth, and solvent-resistant surfaces. Use caution to ensure adhesive fumes are not drawn into the building.

A. Sarnacol Adhesive for Membrane Flashings

1. Over the properly installed and prepared flashing substrate, Sarnacol adhesive shall be applied according to instructions found on the Product Data Sheet. The

Sarnacol adhesive shall be applied in smooth, even coats with no gaps, globs or similar inconsistencies. Only an area which can be completely covered in the same day's operations shall be flashed. The bonded sheet shall be pressed firmly in place with a hand roller.

2. No adhesive shall be applied in seam areas that are to be welded. All panels of membrane shall be applied in the same manner, overlapping the edges of the panels as required by welding techniques.

B. Install Sarnastop according to the Detail Drawings with approved fasteners into the structural deck at the base of parapets, walls and curbs.

C. Sika Sarnafil's requirements and recommendations and the specifications shall be followed. All material submittals shall have been accepted by Sika Sarnafil prior to installation.

D. All flashings shall extend a minimum of 8 inches above roofing level unless otherwise accepted in writing by the Owner's Representative and the Sika Sarnafil Technical Department.

E. All flashing membranes shall be consistently adhered to substrates. All interior and exterior corners and miters shall be cut and hot-air welded into place. No bitumen shall be in contact with the Sarnafil membrane.

F. All flashing membranes shall be mechanically fastened along the counter-flashed top edge with Sarnastop at 6-8 inches on center.

G. Sarnafil flashings shall be terminated according to Sika Sarnafil recommended details.

H. All adhered flashings that exceed 30 inches in height shall receive additional securement. Consult Sika Sarnafil Technical Department for securement methods.

I. All mechanically-attached flashings that exceed 18 inches in height shall receive additional securement. Consult Sika Sarnafil Technical Department for securement methods.

3.11 METAL FLASHINGS

A. Metal details, fabrication practices and installation methods shall conform to the applicable requirements of the following:

1. Factory Mutual Loss Prevention Data Sheet 1-49 (latest issue).
2. Sheet Metal and Air Conditioning Contractors National Association, Inc. (SMACNA) - latest issue.

B. Complete all metal work in conjunction with roofing and flashings so that a watertight condition exists daily.

C. Metal shall be installed to provide adequate resistance to bending to allow for normal thermal expansion and contraction.

D. Metal joints shall be watertight.

E. Metal flashings shall be securely fastened into solid wood blocking. Fasteners shall penetrate the wood nailer a minimum of 1 inch.

F. Airtight and continuous metal hook strips are required behind metal fascias. Hook strips are to be fastened 12 inches on center into the wood nailer or masonry wall.

G. Counter flashings shall overlap base flashings at least 4 inches.

H. Hook strips shall extend past wood nailers over wall surfaces by 1-1/2 inch minimum and shall be securely sealed from air entry.

3.12 SARNACLAD METAL BASE FLASHINGS/EDGE METAL

All flashings shall be installed concurrently with the roof membrane as the job progresses. No temporary flashings shall be allowed without the prior written approval of the Owner's Representative and Sika Sarnafil. Acceptance shall only be for specific locations on specific dates. If any water is allowed to enter under the newly completed roofing due to incomplete flashings, the affected area shall be removed and replaced at the Applicator's expense.

A. Sarnaclad metal flashings shall be formed and installed per the Detail Drawings.

1. All metal flashings shall be fastened into solid wood nailers with two rows of post galvanized flat head annular ring nails, 4 inches on center staggered. Fasteners shall penetrate the nailer a minimum of 1 inch.

2. Metal shall be installed to provide adequate resistance to bending and allow for normal thermal expansion and contraction.

B. Adjacent sheets of Sarnaclad shall be spaced 1/4 inch apart. The joint shall be covered with 2 inch wide aluminum tape. A 4 inch minimum wide strip of Sarnafil flashing membrane shall be hot-air welded over the joint.

3.13 EDGE METAL

All flashings shall be installed concurrently with the roof membrane as the job progresses. No temporary flashings shall be allowed without the prior written approval of the Owner's Representative and Sika Sarnafil. Acceptance shall only be for specific locations on specific dates. If any water is allowed to enter under the newly completed roofing due to incomplete flashings, the affected area shall be removed and replaced at the Applicator's expense.

3.14 TEMPORARY CUT-OFF

All flashings shall be installed concurrently with the roof membrane in order to maintain a watertight condition as the work progresses. All temporary waterstops shall be constructed to provide a 100 percent watertight seal. The stagger of the insulation joints

shall be made even by installing partial panels of insulation. The new membrane shall be carried into the waterstop. Waterstop shall be sealed to the deck and substrate so that water will not be allowed to travel under the new or existing roofing. The edge of the membrane shall be sealed in a continuous heavy application of sealant as described in Section 2.06. When work resumes, the contaminated membrane shall be cut out. All sealant, contaminated membrane, insulation fillers, etc. shall be removed from the work area and properly disposed of off site. None of these materials shall be used in the new work.

If inclement weather occurs while a temporary waterstop is in place, the Applicator shall provide the labor necessary to monitor the situation to maintain a watertight condition.

If any water is allowed to enter under the newly-completed roofing, the affected area shall be removed and replaced at the Applicator's expense.

3.15 COMPLETION

Prior to demobilization from the site, the work shall be reviewed by the Owner's Representative and the Applicator. All defects noted and non-compliances with the Specifications or the recommendations of Sika Sarnafil shall be itemized in a punch list. These items must be corrected immediately by the Applicator to the satisfaction of the Owner's Representative and Sika Sarnafil prior to demobilization.

All Warranties referenced in this Specification shall have been submitted and have been accepted at time of contract award.

END OF SECTION 075419

SECTION 076200 - SHEET METAL FLASHING AND TRIM

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Flashings and Trim.

B. Downspouts and Gutters.

C. Copings.

1.2 RELATED SECTIONS

A. Section 061000 - Rough Carpentry.

B. Section 076200 – Thermoplastic Membrane Roofing.

1.3 REFERENCES

A. ASTM A525 - Steel Sheet, Zinc Coated, (Galvanized) by the Hot-Dip Process.

B. NRCA (National Roofing Contractors Association) - Roofing Manual.

C. SMACNA - Architectural Sheet Metal Manual.

1.4 QUALITY ASSURANCE

A. Perform work in accordance with SMACNA and NRCA standards.

1.5 QUALIFICATIONS

A. Fabricator and Installer: To establish responsibility for a weathertight system, the flashing and sheetmetal work that is a part of the particular roof system shall be done by the same installer that does that roofing work. The installer must specialize in this type of work and be able to show similar installations that have been in service for 3 years minimum..

1.6 DELIVERY, STORAGE, AND HANDLING

A. Stack preformed material to prevent twisting, bending, or abrasion.

PART 2 PRODUCTS

2.1 SHEET MATERIALS

A. Pre-Coated Galvanized Steel: 24 gauge unless otherwise noted, Commercial Quality smooth, ASTM A446, Grade A, G90 zinc coating; PVF2 finish. Color as selected by Architect.

B. Stainless Steel: ASTM A167, Type 302 or 304, No. 2D, dull finish unless otherwise specified.

2.2 DOWNSPOUTS

A. General: Same metal as flashing with precoated finish as specified herein, 24 gauge thickness.

B. Downspouts: 3 inch diameter round profile. Use 1/16 inch thick by 1-inch wide downspout hanger straps, SMACNA Figure 1-35-J.

2.3 ACCESSORIES

A. Fasteners: Same material and finish as flashing metal, of sufficient length to penetrate into substrate.

B. Isolation Paint: ASTM D1187, asphalt.

C. Sealant: Polyurethane type.

D. Plastic Cement: ASTM D2822, Asphalt type with mineral fiber components, free of toxic solvents, capable of setting with 24 hours at temperatures of 75 degrees F and 50 percent RH.

E. Sealer Tape: Polyisobutylene sealer tape specifically manufactured for setting flanges.

2.4 FABRICATION OF FLASHING

A. Field measure prior to fabrication.

B. Fabricate in accordance with SMACNA Architectural Sheet Metal Manual.

C. Accurately form flashings to shapes shown and detailed, with angles and lines in true alignment.

D. Form arris and angles true to line and surfaces free of waves and buckles.

E. Form bends to 1/16th inch inside radius.

F. Hem exposed edges of flashing minimum 1/4 inch on underside.

G. Reinforcements and Supports: Provide same material as flashing unless other material is shown. Steel, where shown or required, shall be coil coated galvanized or stainless.

H. Rigid Joints and Seams: Make joints and seams mechanically strong. Solder galvanized and stainless steel metal joints. Do not use solder to transmit stress loads.

I. Fabricated sheet metal in 10-foot maximum lengths, unless otherwise indicated.

J. At exposed ends of counterflashing furnish weathertight closures.

K. Fabricate corners in one piece with legs extending 30 inches each way to field joint. Lap, rivet, and solder corner seams weathertight.

L. Solvent clean sheet metal. Concealed surfaces shall be coated with isolation paint.

2.5 FABRICATION OF DOWNSPOUTS AND GUTTERS

A. Fabricate in accordance with SMACNA Architectural Sheet Metal Manual.

B. Form downspouts and gutters in maximum lengths as practicable to sizes and shapes indicated on Drawings.

C. Telescope end joints 1-1/2 inches and lock longitudinal joints of downspouts.

D. Fit downspouts into boots or drainpipes where indicated; neatly caulk and fill joint at top of pipes with grout.

2.6 FABRICATION OF COPINGS

A. Fabricate in accordance with SMACNA Architectural Sheet Metal Manual.

B. Join coping sections with standing seam joint.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify roof openings, pipes or vents through roof are solidly set, reglets in place, and nailing strips located.

B. Verify roofing termination and base flashings are in place, sealed, and secure.

3.2 INSTALLATION

A. Conform to drawing details included in the SMACNA and NRCA manuals.

B. Secure flashings in place using concealed fasteners. Use exposed fasteners only where specifically shown on the drawings.

C. Coordinate flashing Work with roofing Work for weathertight and watertight assembly.

D. Isolate metal from wood and concrete and from dissimilar metal with two coats of specified isolation paint or tape.

E. Use only stainless steel fasteners to connect isolated dissimilar metals.

F. Joints: 10 foot maximum spacing and 2-1/2 feet from corners, butted with 3/16 inch space centered over matching 8 inch long backing plate with sealer tape in laps.

G. Set flanges of flashings and roof accessories on continuous sealer tape or in plastic roof cement on top of envelope ply of roofing. Nail flanges through sealer tape and at 3 inch maximum spacing. Touch up isolation paint on flanges.

H. Joints, Fastenings, Reinforcements, and Supports: Sized and located as required to preclude distortion or displacement due to thermal expansion and contraction.

I. Provide continuous hold-down clips at counterflashing and metal coping.

J. Install prefabricated metal copings in accordance with manufacturer's latest printed instructions. Do not penetrate fasteners through top of copings.

K. Fit flashings tight in place. Make corners square, surfaces true and straight in planes, and lines accurate to profiles.

L. Seal metal joints watertight.

M. Anchor downspouts to wall with straps of same material as downspouts.

3.3 SCHEDULE

A. Colors: As selected.

END OF SECTION

SECTION 079200 - JOINT SEALANTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Silicon joint sealants.

B. Related Sections:
1. Division 08 Section "Glazing" for glazing sealants.

1.3 SUBMITTALS

A. Provide in accordance with Section 013300 “Submittal Procedures”.

B. Product Data: For each joint-sealant product indicated.

C. Qualification Data: For qualified Installer.

D. Product Certificates: For each kind of joint sealant and accessory, from manufacturer.

E. Warranties: Sample of special warranties.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.

B. Source Limitations: Obtain each kind of joint sealant from single source from single manufacturer.

1.5 PROJECT CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.6 WARRANTY

A. Special Installer's Warranty: Manufacturer's standard form in which Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.

B. VOC Content of Interior Sealants: Provide sealants and sealant primers for use inside the weatherproofing system that comply with the following limits for VOC content when calculated according to 40 CFR 59, Part 59, Subpart D (EPA Method 24):

1. Architectural Sealants: 250 g/L.
2. Sealant Primers for Nonporous Substrates: 250 g/L.
3. Sealant Primers for Porous Substrates: 775 g/L.

C. Liquid-Applied Joint Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied joint sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.

D. Stain-Test-Response Characteristics: Where sealants are specified to be nonstaining to porous substrates, provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.

E. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range.

2.2 SILICONE JOINT SEALANTS

A. Silicone, S, NS, 100/50, NT: Single-component, nonsag, plus 100 percent and minus 50 percent movement capability, nontraffic-use, neutral-curing silicone joint sealant; ASTM C 920, Type S, Grade NS, Class 100/50, Use NT.

1. Products: Subject to compliance with requirements, provide one of the following.

a. GE Construction Sealants.
b. Sika Corporation U.S.
c. Tremco.
d. Equal approved by Architect.

2.3 FIRE-RESISTIVE JOINT SYSTEMS

A. Where penetrants pass through fire-resistive assemblies, provide fire-resistive joint systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which fire-resistive joint systems are installed. Fire-resistive joint systems shall accommodate building movements without impairing their ability to resist the passage of fire and hot gases.

B. Joints in or between Fire-Resistance-Rated Construction: Provide fire-resistive joint systems with ratings determined per ASTM E 1966 or UL 2079:

1. Fire-Resistance Rating: 1 Hour.

2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

a. Hilti, Inc.
b. 3M Fire Protection Products.
c. Equal approved by Architect.

2.4 JOINT SEALANT BACKING

A. General: Provide sealant backings of material that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

B. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.5 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Concrete.
    b. Masonry.
    c. Unglazed surfaces of ceramic tile.

3. Remove laitance and form-release agents from concrete.
4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

    a. Metal.
    b. Glass.
    c. Glazed surfaces of ceramic tile.

B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.

D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile per Figure 8A in ASTM C 1193, unless otherwise indicated.
4. Provide flush joint profile where indicated per Figure 8B in ASTM C 1193.
5. Provide recessed joint configuration of recess depth and at locations indicated per Figure 8C in ASTM C 1193.

a. Use masking tape to protect surfaces adjacent to recessed tooled joints.

3.4 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.5 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION 079200

SECTION 081113 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes:

1. Standard hollow metal doors and frames.
2. Hollow metal frames for stopped in glazing.

B. Related Requirements:

1. Section 087100 "Door Hardware" for door hardware for hollow-metal doors.
2. Section 088000 “Glazing”.

1.3 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

B. Standard Hollow Metal Work: Hollow metal work fabricated according to ANSVSDI A250.8.

1.4 COORDINATION

A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

1.5 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, core descriptions, fire-resistance ratings, and finishes.

B. Shop Drawings: Include the following:

1. Elevations of each door type.
2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
4. Locations of reinforcement and preparations for hardware.
5. Details of each different wall opening condition.
6. Details of anchorages, joints, field splices, and connections.
7. Details of accessories.
8. Details of moldings, removable stops, and glazing.
9. Details of conduit and preparations for power, signal, and control systems.

C. Schedule: Provide a schedule of hollow metal work prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with door hardware schedule.

D. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for each type of hollow metal door and frame assembly.

1.6 QUALITY ASSURANCE

A. Source Limitations: Obtain hollow metal work from single source from single manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.

1. Provide additional protection to prevent damage to factory-finished units.

B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.

C. Store hollow-metal work vertically under cover at Project site with head up. Place on minimum 4-inch- high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

1.8 PROJECT CONDITIONS

A. Field Measurements: Verify actual dimensions of openings by field measurements before fabrication.

1.9 COORDINATION

A. Coordinate installation of anchorages for hollow metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturer: Subject to compliance with requirements. Available manufacturers offering products that may be incorporated into the work but are not limited to the following:

1. Ceco Door Products; An Assa Abloy Group Company.
2. Curries Company.
3. Equal approved by Architect.

2.2 REGULATORY REQUIREMENTS

A. Fire-Rated Assemblies: Complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.

2.3 INTERIOR DOORS AND FRAMES

A. Construct interior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Hollow-Metal Doors and Frames: NAAMM-HMMA 860. At locations indicated in the Door and Frame Schedule.

1. Physical Performance: Level A according to SDI A250.4.
2. Doors:

a. Type: As indicated in the Door and Frame Schedule.
b. Thickness: 1-3/4 inches
c. Face: Metallic-coated, cold-rolled steel sheet, minimum thickness of 0.032 inch.
d. Edge Construction: Continuously welded with no visible seam.
e. Core: Steel stiffened.

f. Minimum 18 gauge steel with both lock and hinge rail edge of intermittently welded, filled and ground smooth the full height of the door.

3. Frames:

a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch for frames that receive hollow-metal doors; minimum thickness of 0.042 inch for frames that receive hollow-core wood doors.
b. Construction: Fully welded.

4. Exposed Finish: Prime.

2.4 EXTERIOR HOLLOW-METAL DOORS AND FRAMES

A. Construct exterior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Hollow-Metal Doors and Frames: NAAMM-HMMA 860. At locations indicated in the Door and Frame Schedule.

1. Physical Performance: Level A according to SDI A250.4.
2. Doors:

a. Type: As indicated in the Door and Frame Schedule.
b. Thickness: 1-3/4 inches
c. Face: Metallic-coated steel sheet, minimum thickness of 0.042 inch, with minimum G60A60 coating.
d. Edge Construction: Continuously welded with no visible seam.
e. Core: Steel stiffened, insulated at exterior locations.
f. Minimum 16 gauge steel.

3. Frames:

a. Materials: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum G60A60 coating.
b. Construction: Welded.

4. Exposed Finish: Prime.

2.5 HOLLOW-METAL PANELS

A. Provide hollow-metal panels of same materials, construction, and finish as adjacent door assemblies.

2.6 MATERIALS

A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.

B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.

C. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B.

D. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.

E. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.

F. Grout: ASTM C 476, except with a maximum slump of 4 inches, as measured according to ASTM C 143/C 143M.

G. Mineral-Fiber Insulation: ASTM C 665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E 136 for combustion characteristics.

H. Glazing: Comply with requirements in Section 088000 "Glazing."

I. Bituminous Coating: Cold-applied asphalt mastic, compounded for 15-mil dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.7 FABRICATION

A. Fabricate hollow-metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for metal thickness. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.

B. Tolerances: Fabricate hollow metal work to tolerances indicated in SDI 117.

C. Hollow- Metal Doors:

1. Exterior Doors: Provide weep-hole openings in bottom of exterior doors to permit moisture to escape. Seal joints in top edges of doors against water penetration.
2. Glazed Lites: Factory cut openings in doors.
3. Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated. Extend minimum 3/4 inch beyond edge of door on which astragal is mounted.

D. Hollow Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.

1. Welded Frames: Weld flush face joints continuously; grind, fill, dress, and make smooth, flush, and invisible.
2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
3. Grout Guards: Weld guards to frame at back of hardware mortises in frames to be grouted.
4. Floor Anchors: Weld anchors to bottom of jambs and mullions with at least four spot welds per anchor.
5. Jamb Anchors: Provide number and spacing of anchors as follows:
    a. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
        1) Three anchors per jamb up to 60 inches high.
        2) Four anchors per jamb from 60 to 90 inches high.
        3) Five anchors per jamb from 90 to 96 inches high.
        4) Five anchors per jamb plus 1 additional anchor per jamb for each 24 inches or fraction thereof above 96 inches high.
        5) Two anchors per head for frames above 42 inches wide and mounted in metal-stud partitions.
6. Door Silencers: Except on weather-stripped doors, drill stops to receive door silencers as follows. Keep holes clear during construction.
    a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
    b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.

E. Fabricate concealed stiffeners, edge channels, and hardware reinforcement from either cold- or hot-rolled steel sheet.

F. Hardware Preparation: Factory prepare hollow metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to the Door Hardware Schedule and templates furnished as specified in Division 08 Section "Door Hardware."

1. Locate hardware as indicated, or if not indicated, according to ANSI/SDI A250.8.
2. Reinforce doors and frames to receive nontemplated, mortised and surface-mounted door hardware.

3. Comply with applicable requirements in ANSI/SDI A250.6 and ANSI/DHI A115 Series specifications for preparation of hollow metal work for hardware.
4. Coordinate locations of conduit and wiring boxes for electrical connections with Division 26 Sections. Coordinate with Owner's security system vendor for additional hardware installation.

G. Stops and Moldings: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with butted or mitered hairline joints.

1. Single Glazed Lites: Provide fixed stops and moldings welded on secure side of hollow metal work.
2. Multiple Glazed Lites: Provide fixed and removable stops and moldings so that each glazed lite is capable of being removed independently.
3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames.
4. Provide loose stops and moldings on inside of hollow metal work.
5. Coordinate rabbet width between fixed and removable stops with type of glazing and type of installation indicated.

2.8 STEEL FINISHES

A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.

1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

2.9 ACCESSORIES

A. Louvers: Provide louvers for interior doors, where indicated, which comply with SDI 111C, with blades or baffles formed of 0.020-inch thick, cold-rolled steel sheet set into 0.032-inch thick steel frame.

1. Sightproof Louver: Stationary louvers constructed with inverted-V or inverted-Y blades.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for embedded and built-in anchors to verify actual locations before frame installation.

C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces.

B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

C. Prior to installation, adjust and securely brace welded hollow metal frames for squareness, alignment, twist, and plumbness to the following tolerances:

1. Squareness: Plus or minus 1/16 inch (1.6 mm), measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
2. Alignment: Plus or minus 1/16 inch (1.6 mm), measured at jambs on a horizontal line parallel to plane of wall.
3. Twist: Plus or minus 1/16 inch (1.6 mm), measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
4. Plumbness: Plus or minus 1/16 inch (1.6 mm), measured at jambs on a perpendicular line from head to floor.

3.3 INSTALLATION

A. General: Install hollow-metal work plumb, rigid, properly aligned, and securely fastened in place. Comply with Drawings and manufacturer's written instructions.

B. Hollow-Metal Frames: Install hollow-metal frames of size and profile indicated. Comply with SDI A250.11 or NAAMM-HMMA 840 as required by standards specified.

1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.

    a. At fire-rated openings, install frames according to NFPA 80.

b. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
c. Install door silencers in frames before grouting.
d. Remove temporary braces necessary for installation only after frames have been properly set and secured.
e. Check plumb, square, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
f. Field apply bituminous coating to backs of frames that will be filled with grout containing antifreezing agents.

2. Wood-Stud Partitions: Secure slip-on drywall frames in place according to manufacturer's written instructions. Solidly pack mineral-fiber insulation behind frames.
3. Installation Tolerances: Adjust hollow-metal door frames for squareness, alignment, twist, and plumb to the following tolerances:

a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.

C. Hollow-Metal Doors: Fit hollow-metal doors accurately in frames, within clearances specified below. Shim as necessary.

1. Non-Fire-Rated Steel Doors:

a. Between Door and Frame Jambs and Head: 1/8 inch plus or minus 1/32 inch.
b. Between Edges of Pairs of Doors: 1/8 inch to 1/4 inch plus or minus 1/32 inch.
c. At Bottom of Door: 5/8 inch plus or minus 1/32 inch.
d. Between Door Face and Stop: 1/16 inch to 1/8 inch plus or minus 1/32 inch.

2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.

D. Glazing: Comply with installation requirements in Section 088000 "Glazing" and with hollow-metal manufacturer's written instructions.

1. Secure stops with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

3.4 ADJUSTING AND CLEANING

A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow-metal work that is warped, bowed, or otherwise unacceptable.

B. Remove grout and other bonding material from hollow-metal work immediately after installation.

C. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

D. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.

3.5 PAINT SCHEDULE

A. Paint all hollow metal doors and frames.

B. Interior: Color to match existing interior hollow metal doors and frames.

C. Exterior: See Drawings.

END OF SECTION 081113

SECTION 081416 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Solid-core doors with wood-veneer faces.
2. Factory fitting flush wood doors to frames and factory machining for hardware.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of door. Include details of core and edge construction, and trim for openings.

B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each kind of door; construction details not covered in Product Data; and the following:

1. Dimensions and locations of cutouts.
2. Fire-protection ratings for fire-rated doors.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Comply with requirements of referenced standard and manufacturer's written instructions.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install doors until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during remainder of construction period.

1.6 WARRANTY

A. A. Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
   1. Warranty Period for Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
   1. Eggers Industries.
   2. Graham Wood Doors; an Assa Abloy Group company.
   3. VT Industries, Inc.
   4. Approved equal.

B. Source Limitations: Obtain flush wood doors from single manufacturer.

2.2 FLUSH WOOD DOORS, GENERAL

A. Quality Standard: In addition to requirements specified, comply WDMA I.S.1-A, "Architectural Wood Flush Doors."
   1. Contract Documents contain selections chosen from options in quality standard and additional requirements beyond those of quality standard. Comply with those selections and requirements in addition to quality standard.

B. Low-Emitting Materials: Fabricate doors with adhesives and composite wood products that do not contain urea formaldehyde.

C. WDMA I.S.1-A Performance Grade: Heavy Duty.

D. Fire-Rated Wood Doors: Doors complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.
   1. Temperature-Rise Limit At vertical exit enclosures and exit passageways, provide doors that have a maximum transmitted temperature end point of not more than 450 deg F (250 deg C) above ambient after 30 minutes of standard fire-test exposure.
   2. Cores: Provide core specified or mineral core as needed to provide fire-protection rating indicated.
   3. Edge Construction: Provide edge construction with intumescent seals concealed by outer stile. Comply with specified requirements for exposed edges.

E. Particleboard-Core Doors:

1. Particleboard: Straw-based particleboard complying with ANSI A208.1, Grade LD-2 or M-2, except for density.
2. Blocking: Provide wood blocking in particleboard-core doors as needed to eliminate through-bolting hardware.

F. Structural-Composite-Lumber-Core Doors:

1. Structural Composite Lumber: WDMA I.S.10.

   a. Screw Withdrawal, Face: 700 lbf (3100 N).
   b. Screw Withdrawal, Edge: 400 lbf (1780 N).

G. Mineral-Core Doors:

1. Core: Noncombustible mineral product complying with requirements of referenced quality standard and testing and inspecting agency for fire-protection rating indicated.
2. Blocking: Provide composite blocking with improved screw-holding capability approved for use in doors of fire-protection ratings indicated as needed to eliminate through-bolting hardware.

3. Edge Construction: At hinge stiles, provide laminated-edge construction with improved screw-holding capability and split resistance. Comply with specified requirements for exposed edges.

2.3 VENEER-FACED DOORS FOR TRANSPARENT FINISH

A. Interior Solid-Core Doors:

1. Grade: Premium, with Grade A faces.
2. Species: Match existing.
3. Stain: Color as selected.
4. Apply medium density overlay to standard thickness, closed grain, hardwood face veneers.
5. Hardwood faces: AHA A135.4, Class 1 (tempered) or Class 2 (standard).
6. MDF Faces: ANSI A208.2, Grade 150 or 160.
7. Exposed vertical and top edges: Any closed-grain hardwood.
8. Core: Glued wood slave or particle wood.
9. Construction: five or seven piles. Sides and rails are bonded to core, then entire unit abrasive planed before veneering. Faces are bonded to core using a hot press.
10. Construction: Seven piles, either bonded or nonbonded construction.
11. WDMA I.S 1-A Performance Grade: Standard Duty.

2.4 FABRICATION

A. Factory fit doors to suit frame-opening sizes indicated. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.

1. Comply with NFPA 80 requirements for fire-rated doors.

B. Factory machine doors for hardware that is not surface applied. Locate hardware to comply with DHI-WDHS-3. Comply with final hardware schedules, door frame Shop Drawings, BHMA-156.115-W, and hardware templates.

1. Coordinate with hardware mortises in metal frames to verify dimensions and alignment before factory machining.

2.5 FACTORY FINISHING

A. General: Comply with referenced quality standard for factory finishing. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.

1. Finish faces, all four edges, edges of cutouts, and mortises. Stains and fillers may be omitted on bottom edges, edges of cutouts, and mortises.

B. Factory finish doors.

C. Factory finish doors that are indicated to receive transparent finish.

D. Factory finish doors where indicated in schedules or on Drawings as factory finished.

E. Transparent Finish:

1. Grade: Premium.
2. Finish: AWI's, AWMAC's, and WI's "Architectural Woodwork Standards" WDMA TR-6 catalyzed polyurethane
3. Staining: Match existing colors.
4. Sheen: Match existing.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine doors and installed door frames, with Installer present, before hanging doors.

1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
2. Reject doors with defects.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Hardware: For installation, see Section 087100 "Door Hardware”.

B. Installation Instructions: Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.

1. Install fire-rated doors according to NFPA 80.

C. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.

3.3 ADJUSTING

A. Operation: Rehang or replace doors that do not swing or operate freely.

B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 081416

SECTION 085113 - ALUMINUM WINDOWS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes aluminum windows for exterior locations.

B. Related Requirements:

1. Section 088000 “Glazing”.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, glazing and fabrication methods, dimensions of individual components and profiles, hardware, and finishes for aluminum windows.

B. Shop Drawings: Include plans, elevations, sections, hardware, accessories, insect screens, operational clearances, and details of installation, including anchor, flashing, and sealant installation.

C. Samples: For each exposed product and for each color specified, 2 by 4 inches in size.

D. Samples for Initial Selection: For units with factory-applied color finishes.

1. Include similar Samples of hardware and accessories involving color selection.

E. Samples for Verification: For aluminum windows and components required, showing full range of color variations for finishes, and prepared on Samples of size indicated below:

1. Exposed Finishes: 2 by 4 inches.

F. Product Schedule: For aluminum windows. Use same designations indicated on Drawings.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For manufacturer and Installer.

B. Product Test Reports: For each type of aluminum window, for tests performed by a qualified testing agency.

C. Field quality-control reports.

D. Sample Warranties: For manufacturer's warranties.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: A manufacturer capable of fabricating aluminum windows that meet or exceed performance requirements indicated and of documenting this performance by test reports, and calculations.

B. Installer Qualifications: An installer acceptable to aluminum window manufacturer for installation of units required for this Project.

1.6 WARRANTY

A. Manufacturer's Warranty: Manufacturer agrees to repair or replace aluminum windows that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Failure to meet performance requirements.
b. Structural failures including excessive deflection, water leakage, condensation, and air infiltration.
c. Faulty operation of movable sash and hardware.
d. Deterioration of materials and finishes beyond normal weathering.
e. Failure of insulating glass.

2. Warranty Period: Manufacturer’s standard warranty.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Basis-of-Design Product: Subject to compliance with requirements, Fixed: TRACO NX-280, Projected: TRACO NX-250, or comparable product by one of the following:

1. TRACO.

2. EFCO.
3. Kawneer North America; an Alcoa company.
4. Equal as approved by Architect.

B. Source Limitations: Obtain aluminum windows from single source from single manufacturer.

2.2 WINDOW PERFORMANCE REQUIREMENTS

A. Product Standard: Comply with AAMA/WDMA/CSA 101/I.S.2/A440 for definitions and minimum standards of performance, materials, components, accessories, and fabrication unless more stringent requirements are indicated.

1. Window Certification: AMMA certified with label attached to each window.

B. Thermal Transmittance: NFRC 100 maximum whole-window U-factor of 0.28 Btu/sq. ft. x h x deg F.

C. Solar Heat-Gain Coefficient (SHGC): NFRC 200 maximum whole-window SHGC of 0.40.

2.3 ALUMINUM WINDOWS

A. Operating Types: Provide the following operating types in locations indicated on Drawings:

1. Awning: Project out.
2. Fixed.

B. Frames and Sashes: Aluminum extrusions complying with AAMA/WDMA/CSA 101/I.S.2/A440.

1. Thermally Improved Construction: Fabricate frames, sashes, and muntins with an integral, concealed, low-conductance thermal barrier located between exterior materials and window members exposed on interior side in a manner that eliminates direct metal-to-metal contact.

C. Insulating-Glass Units: See Section 088000 Glazing.

D. Hardware, General: Provide manufacturer's standard hardware fabricated from aluminum, stainless steel, carbon steel complying with AAMA 907, or other corrosion-resistant material compatible with adjacent materials; designed to smoothly operate, tightly close, and securely lock windows, and sized to accommodate sash weight and dimensions.

1. Exposed Hardware Color and Finish: As selected by Architect from manufacturer's full range.

E. Weather Stripping: Provide full-perimeter weather stripping for each operable sash unless otherwise indicated.

F. Fasteners: Noncorrosive and compatible with window members, trim, hardware, anchors, and other components.

1. Exposed Fasteners: Do not use exposed fasteners to the greatest extent possible. For application of hardware, use fasteners that match finish hardware being fastened.

2.4 ACCESSORIES

A. Subsills: Thermally broken, extruded-aluminum subsills in configurations indicated on Drawings.

B. Interior Trim: Extruded-aluminum profiles in sizes and configurations indicated on Drawings.

C. Panning Trim: Extruded-aluminum profiles in sizes and configurations indicated on Drawings.

D. Receptor System: Two-piece, snap-together, thermally broken, extruded-aluminum receptor system that anchors windows in place.

2.5 INSECT SCREENS

A. General: Fabricate insect screens to integrate with window frame. Provide screen for each operable exterior sash. Screen wickets are not permitted.

1. Type and Location: Full, inside for project-out sashes.

B. Aluminum Frames: Manufacturer's standard aluminum alloy complying with SMA 1004 or SMA 1201. Fabricate frames with mitered or coped joints or corner extrusions, concealed fasteners, and removable PVC spline/anchor concealing edge of frame.

1. Tubular Framing Sections and Cross Braces: Roll formed from aluminum sheet.

C. Glass-Fiber Mesh Fabric: 18-by-14 or 18-by-16 mesh of PVC-coated, glass-fiber threads; woven and fused to form a fabric mesh resistant to corrosion, shrinkage, stretch, impact damage, and weather deterioration. Comply with ASTM D 3656.

1. Mesh Color: Manufacturer's standard.

2.6 FABRICATION

A. Fabricate aluminum windows in sizes indicated. Include a complete system for assembling components and anchoring windows.

B. Glaze aluminum windows in the factory.

C. Weather strip each operable sash to provide weathertight installation.

D. Weep Holes: Provide weep holes and internal passages to conduct infiltrating water to exterior.

E. Provide water-shed members above side-hinged sashes and similar lines of natural water penetration.

F. Complete fabrication, assembly, finishing, hardware application, and other work in the factory to greatest extent possible. Disassemble components only as necessary for shipment and installation.

2.7 GENERAL FINISH REQUIREMENTS

A. Comply with NAAMM's "Metal Finishes Manual" for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.8 ALUMINUM FINISHES

A. Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.

B. Class II, Color Anodic Finish: AA-M12C22A32/A34 (Mechanical Finish: nonspecular as fabricated; Chemical Finish: etched, medium matte; Anodic Coating: Architectural Class II, integrally colored or electrolytically deposited color coating 0.010 mm or thicker) complying with AAMA 611.

1. Color: As selected by Architect from full range of industry colors and color densities.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine openings, substrates, structural support, anchorage, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Verify rough opening dimensions, levelness of sill plate, and operational clearances.

C. Examine wall flashings, vapor retarders, water and weather barriers, and other built-in components to ensure weathertight window installation.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Comply with manufacturer's written instructions for installing windows, hardware, accessories, and other components. For installation procedures and requirements not addressed in manufacturer's written instructions, comply with installation requirements in ASTM E 2112.

B. Install windows level, plumb, square, true to line, without distortion or impeding thermal movement, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction to produce weathertight construction.

C. Install windows and components to drain condensation, water penetrating joints, and moisture migrating within windows to the exterior.

D. Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials.

3.3 ADJUSTING, CLEANING, AND PROTECTION

A. Adjust operating sashes and hardware for a tight fit at contact points and weather stripping for smooth operation and weathertight closure.

B. Clean exposed surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances.

1. Keep protective films and coverings in place until final cleaning.

C. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

D. Protect window surfaces from contact with contaminating substances resulting from construction operations. If contaminating substances do contact window surfaces, remove contaminants immediately according to manufacturer's written instructions.

END OF SECTION 085113

SECTION 087100 – DOOR HARDWARE

PART 1 GENERAL

1.1 SUMMARY

A. This section includes the following:

1. Door hardware

B. Related Sections:

1. Section 081113 “Hollow Metal Doors and Frames”.

2. Section 081416 “Flush Wood Doors and Frames”.

1.2 QUALITY ASSURANCE

A. Product Qualification:
1. To assure a uniform high quality of materials for the project, it is intended that only specified items be furnished. Comparable products may be accepted upon prior approval of architect.
2. Hardware to be new, free of defects, blemishes and excessive play. Obtain each kind of hardware (latch and locksets, exit devices, hinges and closers) from one manufacturer except where specified.
3. Fire-Rated opening in compliance with NFPA80. Hardware UL10C/UBC-7-2 (positive pressure) compliant for given type/size opening and degree of label. Provide proper latching hardware, non-flaming door closers, approved bearing hinges and smoke seal. Furnish openings complete.

B. Supplier Qualifications
1. Hardware supplier will be a direct factory contract supplier who employs a certified architectural hardware consultant (AHC) available at all reasonable time during the course of the work for project hardware consultation to owner, architect and contractor.
2. Supplier will be responsible for detailing, scheduling and ordering of finish hardware.
3. Conduct pre-installation conference at jobsite. Initiate and conduct with supplier, installer and related trades. Coordinate materials and techniques and sequence complex hardware items and systems installation.
4. Key Conference shall be initiated and conducted with owner to determine system, keyway(s) and structure.

C. Installer Qualifications:
1. Installer to have not less than 3-year experience specializing in installation of work in this section. Company must maintain qualified personnel trained and experienced in installing hardware.

1.3 REFERENCES

A. NFPA80 – Fire Doors and Windows
B. NFPA101 – Life Safety Code
C. NFPA105 – Smoke and Draft Control Door Assemblies
D. ANSI A117.1 Specifications for making Buildings usable by physically handicapped people.

1.4 SUBMITTALS

A. Hardware schedule: Submit 6 copies of schedule. Organize vertically formatted schedule into Hardware Sets with index of doors and headings, indication complete designations of every item required for each door or opening. Include the following:

1. Type, style, function, size, quantity and finish of hardware items.
2. Name, part number and manufacture of each item.
3. Fastenings and other pertinent information.
4. Explanation of abbreviations, symbols and codes contained in schedule.
5. Door and frame sizes, materials and degrees of swing.

B. Product Data: Submit 4 copies for each product indicated.

C. Templates: Obtain and distribute templates for doors, frames, and other works specified, to be prepared for installing door hardware.

D. Wiring/Riser diagrams: as required for electric hardware indicated.

E. Maintenance Data: For each type of door hardware to include in maintenance manuals specified in Division 1.

F. Keying Schedule: Prepared by or under the supervision of supplier, after receipt of the approved finish hardware schedule, detailing Owner's final keying instructions for locks.

G. Samples: Upon request submit material samples.

1.5 DELIVERY, STORAGE AND HANDLING

A. Deliver, store, handle and protect products to project site under provisions of Division 1 and as specified herein.
B. Tag each item or package separately, with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.
C. Deliver keys to Owner by registered mail.

1.6 WARRANTY:

A. The finish hardware shall have a limited warranty against defects in workmanship and operation for a period of one year from date of substantial completions and the following items are as shown:

1.	Closers	Ten years mechanical, two years electrical.
2.	Exit Devices:	Three years mechanical, one year electrical
3.	Hinges	Life of the building.
4.	Locksets	Seven years

PART 2 PRODUCTS

2.1 MATERIAL AND FABRICATION

A. Provide all door hardware for complete work, in accordance with the drawings and as specified herein.

B. Provide items and quantities not specifically mentioned to ensure a proper and complete operational installation.

2.2 MANUFACTURERS:

A. Any item shown in the hardware schedule, but not listed below shall be supplied as shown unless otherwise approved by the Architect.

ITEM:	MANUFACTURER:	ACCEPTABLE SUB:
Hinges	(IVE) Ives	Mckinney, Bommer
Locks	(SCH) Schlage	None
Cylinders	(BES) Best	None
Exit Devices	(VON) Von Duprin	None
Electric Strikes	(VON) Von Duprin	HES
Closers	(LCN) LCN	None
Silencers	(IVE) Ives	Hager, Rockwood
Push & Pull Plates	(IVE) Ives	Hager, Rockwood
Kickplates	(IVE) Ives	Hager, Rockwood
Stops & Holders	(IVE) Ives	Hager, Rockwood
Overhead Stops	(GLY) Glynn-Johnson	None
Thresholds	(NGP) National Guard	Pemko, Zero
Seals & Bottoms	(NGP) National Guard	Pemko, Zero
Automatic Opener	(LCN) LCN	None
Prox Reader/Controllers	(SCE) Schlage Electonics	None
Pocket Set	(JOH) Johnson	Stanley

2.3 HANGING

A. Conventional Hinges: Hinge open width minimum, but of sufficient throw to permit maximum door swing. Steel or stainless steel pins.

1. Three hinges per leaf to 7 foot, 6 inch height. Add one for each additional 30 inches in height or any fraction thereof.
2. Provide 4 ½ x 4 ½ for 1 ¾" thick doors up to 36". Provide 5 x 4 ½ on doors over 36".
3. Out swinging exterior doors to have non removable (NRP) pins.
4. Pin tips, flat button, finish to match leaves

2.4 LOCKSETS, LATCHSETS, DEADBOLTS

A. Extra Heavy Duty Cylindrical Locks and Latches: as scheduled.

1. ANSI A156.2 Series 4000, Grade 1 Strength and Operational requirements.
   a. UL listed for A label and lesser class single doors up to 4ft x 8ft.
2. Meets A117.1 Accessibility Codes.
3. Latch bolts shall be steel with minimum ½" throw, deadlocking on keyed and exterior functions. ¾" throw anti-friction latch bolt on pairs of fire doors.
4. Lock case steel.
5. Lock shall incorporate one piece spring cage and spindle.
6. Locksets to be tested to exceed 3,000,000 cycles.
7. Strikes: 16 gage curved steel, bronze or brass with 1" deep box construction, lips of sufficient length to clear trim and protect clothing.
8. Provide seven year warranty.
9. Lock Series and Design: Schlage ND series, "Rhodes" design.

2.5 KEYS, KEYING, AND KEY CONTROL

A. Keying shall be established at a key conference attended by the Owner/Architect and Hardware Supplier. Provide Schlage cylinders.

B. Provide permanent key schedule in a format acceptable to the Owner. All permanent keys shall be hand delivered or sent via registered mail directly to the Owner.

C. Provide Construction cylinders for exterior doors.
Provide:
3 keys per cylinders
3 control keys
12 Master keys
6 Construction keys
1 Key Cabinet RWC25S

2.6 EXIT DEVICES/PANIC HARDWARE

A. General features:

1. Independent lab-tested 1,000,000 cycles.

2. Push-through touch pad design. No exposed touch bar fasteners, no exposed cavities when operated. Return stroke fluid dampeners and rubber bottoming dampeners, plus anti-rattle devices.
3. ¾" throw deadlocking latchbolts.
4. No exposed screws to show through glass doors.
5. Non-handed basic device design with center case interchangeable with all functions, no extra parts required to effect change of function.
6. Releasable with 32 lb. maximum pressure under 250 lb. load to the door.

B. Specific features:

1. Lever Trim: Breakaway type, forged brass or bronze escutcheon min .130" thickness, match lockset lever design.
2. Fire-Labeled Devices: UL label indicating "Fire Exit Hardware".

2.7 CLOSERS

1. Full rack-and-pinion type cylinder with removable non-ferrous cover and cast iron body. Double heat-treated pinion shaft, single piece forged piston, chrome-silicon steel spring.
2. ISO 2000 certified. Units stamped with date-of-manufacture code.
3. Independent lab-tested 5,000,000 cycles.
4. Thru-bolts at wood doors unless doors are provided with closer blocking. Non-sized, non-handed and adjustable. Place closers inside building, stairs and rooms.
5. Plates, brackets and special templating when needed for interface with particular header, door and wall conditions and neighboring hardware.
6. Opening pressure: Exterior doors 8.5 lb., interior doors 5 lb., labeled fire doors 15 lb.
7. Separate adjusting valves for closing speed, latching speed and backcheck, fourth valve for delayed action where scheduled.
8. Exterior door closers: tested to 100 hours of ASTM B117 salt spray test, furnish data on request.
9. Exterior doors do not require seasonal adjustments in temperatures from 120 degrees F to 0 degrees F, furnish data on request.
10. Non-flaming fluid will not fuel door or floor covering fires.

2.8 OTHER HARDWARE

A. Door stops: Provide stops to protect walls, casework or other hardware.
   1. Except as otherwise indicated, provide stops (wall, floor or overhead) at each leaf of every swinging door leaf.
   2. Where wall or floor stops are not appropriate, provide overhead holders.

B. Gaskets and Sweeps

1. Provide continuous weather-strip gasketing on exterior doors and provide smoke, light, or sound gasketing on interior doors where indicated or scheduled.
2. Provide non-corrosive fasteners as recommended by the manufacturer for application indicated.

C. Thresholds

1. Except as otherwise indicated, provide standard metal threshold unit of type, size and profile as detailed or scheduled.

D. Silencers

1. Interior hollow metal frames, 3 for single doors, 4 for pairs of doors.

2.9 HARDWARE FINISH

A. Provide the following finishes unless noted differently in hardware groups.

Locks, Latches 626
Push, pulls - 630
Hinges, Exterior 630 Interior 626
Closers Alum
Exit Devices 626
Other hardware 626
Thresholds Alum
Weatherstrip/sweeps Alum

PART 3 EXECUTION

3.1 ACCEPTABLE INSTALLERS:

A. Factory trained, certified, and carries a factory-issued card certifying that person as a “Certified Installer”. Alternative: can demonstrate suitably equivalent competence and experience.

3.2 PREPARATION:

A. Ensure that walls and frames are square and plumb before hardware installation.
B. Locate hardware per SDI-100 and applicable building, fire, life-safety, accessibility, and security codes. Notify Architect of any code conflicts before ordering materials.

3.3 INSTALLATION

A. Install hardware per manufacturer's instructions and recommendations. Do not install surface mounted items until finishes have been completed on substrate. Set units level, plumb and true to line and location. Adjust and reinforce attachment substrate for proper installation and operation. Locate floor stops not more than 4 inches from the wall. Drill pilot holes for fasteners in wood doors and/or frames.

3.4 ADJUSTING

A. Adjust and check for proper operation and function. Replace units which cannot be adjusted to operate freely and smoothly.

B. Hardware damaged by improper installation or adjustment methods to be repaired or replaced to Owner's satisfaction.

3.5 FOLLOW UP INSPECTION

A. Installer to provide letter of agreement to Owner that approximately 6 months after substantial completion, installer will visit project with representative of the manufacturers of the locking devices and door closers to accomplish the following:
1. Re-adjust locks and closers
2. Evaluate maintenance procedures and recommend changes or additions, and instruct Owner's personnel.
3. Identify items that have deteriorated or failed.
4. Submit written report identifying problems and likely future problems.

3.6 DEMONSTRATION

A. Demonstrate electrical, electronic and pneumatic hardware systems, including adjustment and maintenance procedures

3.7 PROTECTION/CLEANING

A. Cover installed hardware, protect from paint, cleaning agents, weathering, carts/barrows, etc. Remove covering materials and clean hardware just prior to substantial completion.
B. Clean adjacent wall, frame and door surfaces soiled from installation/reinstallation process.

3.8 DOOR HARDWARE SCHEDULE

HW SET: 01

3	EA	HINGE	5BB1 4.5 X 4.5	652 IVE

1	EA	PRIVACY SET	ND40S RHO	626	SCH
1	EA	OVERHEAD STOP	900S	630	GLY
1	EA	KICK PLATE	8400 10" X 2" LDW	630	IVE
1	EA	KICK PLATE	8400 4" X 1" LDW	630	IVE
1	SET	SEALS	5050B	BRN	NGP

HW SET: 02

3	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
1	EA	STOREROOM SET	ND10S RHO	626	SCH
1	EA	ELECTRIC STRIKE	BY OTHERS		B/O
1	EA	SURFACE CLOSER	1461 EDA	689	LCN
1	EA	OVERHEAD STOP	100S	630	GLY
1	EA	KICK PLATE	8400 10" X 2" LDW	630	IVE
1	SET	SEALS	5050B	BRN	NGP
1	EA	DOOR SWEEP	C607A	CL	NGP
1	EA	THRESHOLD	425E MS/LA	AL	NGP
1	EA	CARD READER	BY OTHERS		B/O

HW SET: 03

3	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
1	EA	OFFICE SET	ND40S RHO	626	SCH
1	EA	KICK PLATE	8400 10" X 2" LDW	630	IVE
1	EA	KICK PLATE	8400 4" X 1" LDW	630	IVE
1	EA	WALL STOP	WS401CCV	626	IVE
2	EA	SILENCER	SR65	GRY	IVE

HW SET: 04

3	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
1	EA	PASSAGE SET	ND10S RHO	626	SCH
1	EA	KICK PLATE	8400 10" X 2" LDW	630	IVE
1	EA	KICK PLATE	8400 4" X 1" LDW	630	IVE
1	EA	WALL STOP	WS401CCV	626	IVE
3	EA	SILENCER	SR65	GRY	IVE

HW SET: 05

3	EA	HINGE	5BB1 4.5 X 4.5 NRP	630	IVE
1	EA	STD COMBINATED CORE	1C7- 2	626	BES
1	EA	STOREROOM SET	ND80BDC RHO	626	SCH
1	EA	ELECTRIC STRIKE	BY OTHERS		B/O
1	EA	SURFACE CLOSER	1461 EDA	689	LCN

1	EA	KICK PLATE	8400 10" X 2" LDW	630	IVE
1	EA	FLOOR STOP	FS444	626	IVE
1	SET	SEALS	5050B	BRN	NGP
1	EA	DRIP CAP	16A	CL	NGP
1	EA	DOOR SWEEP	C607A	CL	NGP
1	EA	THRESHOLD	659 MS/LA	AL	NGP
1	EA	CARD READER	BY OTHERS		B/O
1	EA	LOCK GUARD	LG14	630	IVE

HW SET: 06

2	EA	HINGE
1	EA	GATE LATCH

END OF SECTION 087100

SECTION 088000 - GLAZING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes glazing for the following products and applications, including those specified in other Sections where glazing requirements are specified by reference to this Section:

1. Hollow Metal Door Vision Lites.
2. Hollow Metal Frame Relites.

B. Related Sections:

1. Section 081113 “Hollow Metal Doors and Frames.”
2. Section 085113 “Aluminum Windows”.

1.3 DEFINITIONS

A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.

B. Glass Thicknesses: Indicated by thickness designations in millimeters according to ASTM C 1036.

C. Interspace: Space between lites of an insulating-glass unit.

1.4 PERFORMANCE REQUIREMENTS

A. General: Installed glazing systems shall withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.

1.5 SUBMITTALS

A. Product Data: For each glass product and glazing material indicated.

B. Qualification Data: For installers.

C. Product Certificates: For glass and glazing products, from manufacturer.

D. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for insulating glass and glazing gaskets.

E. Warranties: Sample of special warranties.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: A qualified installer who employs glass installers for this Project who are certified under the National Glass Association's Certified Glass Installer Program.

B. Source Limitations for Glazing Accessories: Obtain from single source from single manufacturer for each product and installation method.

C. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.

1. GANA Publications: GANA's "Glazing Manual."
2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."

D. Safety Glazing Labeling: Where safety glazing labeling is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.

E. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of IGCC.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials according to manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

B. Comply with insulating-glass manufacturer's written recommendations for venting and sealing units to avoid hermetic seal ruptures due to altitude change.

1.8 PROJECT CONDITIONS

A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.

1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or below 40 deg F.

1.9 WARRANTY

A. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer's standard form in which coated-glass manufacturer agrees to replace coated-glass units that deteriorate within specified warranty period. Deterioration of coated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning coated glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in coating.

1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 GLASS PRODUCTS, GENERAL

A. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass lites in thicknesses as needed to comply with requirements indicated.

B. Strength: Where float glass is indicated, provide annealed float glass, Kind HS heat-treated float glass, or Kind FT heat-treated float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened glass is indicated, provide Kind HS heat-treated float glass or Kind FT heat-treated float glass as needed to comply with "Performance Requirements" Article. Where fully tempered glass is indicated, provide Kind FT heat-treated float glass.

2.2 GLASS PRODUCTS

A. Float Glass: ASTM C 1036, Type I, Quality-Q3, Class I (clear) unless otherwise indicated.

B. Heat-Treated Float Glass: ASTM C 1048; Type I; Quality-Q3; Class I (clear) unless otherwise indicated; of kind and condition indicated.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.
2. For uncoated glass, comply with requirements for Condition A.

2.3 INSULATING GLASS

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Guardian Industries Corp.
2. PPE Industries
3. Oldcastle Glass.
4. Equal as approved by Architect.

B. Insulating-Glass Units: Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified according to ASTM E 2190, and complying with other requirements specified.

1. Sealing System: Dual seal, with manufacturer's standard primary and secondary.
2. Spacer: Manufacturer's standard spacer material and construction.
3. Desiccant: Molecular sieve or silica gel, or blend of both.

2.4 INSULATED GLASS UNIT TYPES

A. Type G-1 - Sealed Insulating Glass Units: Vision glazing, low-E.
1. Application: All exterior glazing unless otherwise indicated.
2. Substitutions: Refer to Section 016000 - Product Requirements.
   a. Other products of the basis of design manufacturer and products of other manufacturers will be considered provided the overall performance is within the specified range(s) and the overall appearance is not significantly different from that of the specified product.
3. Between-lite space filled with argon.
4. Thermal Resistance (U-Value): 0.28 or better.
5. Total Solar Heat Gain Coefficient: 0.40 or better.
6. Total Visible Light Transmittance: 66% or better.
7. Basis of Design: Guardian Industries Corp: www.sunguardglass.com.
8. Outboard Lite: Annealed float glass, 1/4 inch thick, minimum.
   a. Tint and Coating: Clear with SunGuard SN 68 on #2 surface.
9. Inboard Lite: Annealed float glass, 1/4 inch thick.
   a. Tint: None (clear).
10. Total Thickness: 1 inch at windows, ½” overall thickness at exterior doors.
11. Glazing Method: Gasket glazing.

B. Type G-2 - Single Safety Glazing: Non-fire-rated.
1. Applications: Provide this type of glazing in the following locations:

a. Glazed lites in doors.
b. Other locations required by applicable federal, state, and local codes and regulations.
c. Other locations indicated on the drawings.

2. Type: Fully tempered float glass.
3. Tint: Clear.
4. Thickness: 1/4 inch.

2.5 GLAZING GASKETS

A. Dense Compression Gaskets: Molded or extruded gaskets of profile and hardness required to maintain watertight seal, made from one of the following:

1. Neoprene complying with ASTM C 864.
2. EPDM complying with ASTM C 864.
3. Silicone complying with ASTM C 1115.
4. Thermoplastic polyolefin rubber complying with ASTM C 1115.

2.6 MISCELLANEOUS GLAZING MATERIALS

A. General: Provide products of material, size, and shape complying with referenced glazing standard, requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.

B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

C. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.

D. Spacers: Elastomeric blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.

E. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).

F. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

G. Perimeter Insulation for Fire-Resistive Glazing: Product that is approved by testing agency that listed and labeled fire-resistant glazing product with which it is used for application and fire-protection rating indicated.

2.7 FABRICATION OF GLAZING UNITS

A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

B. Clean-cut or flat-grind vertical edges of butt-glazed monolithic lites to produce square edges with slight chamfers at junctions of edges and faces.

C. Grind smooth and polish exposed glass edges and corners.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:

1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
2. Presence and functioning of weep systems.
3. Minimum required face and edge clearances.
4. Effective sealing between joints of glass-framing members.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that will leave visible marks in the completed work.

3.3 GLAZING, GENERAL

A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.

B. Adjust glazing channel dimensions as required by Project conditions during installation to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.

D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

G. Provide spacers for glass lites where length plus width is larger than 50 inches.

1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
2. Provide 1/8-inch minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.

H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.

I. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

J. Set glass lites with proper orientation so that coatings face exterior or interior as specified.

K. Where wedge-shaped gaskets are driven into one side of channel to pressurize sealant or gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.

L. Square cut wedge-shaped gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away; seal corner joints and butt joints with sealant recommended by gasket manufacturer.

3.4 GASKET GLAZING (DRY)

A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

B. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.

C. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.

D. Install gaskets so they protrude past face of glazing stops.

3.5 CLEANING AND PROTECTION

A. Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended in writing by glass manufacturer.

C. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains; remove as recommended in writing by glass manufacturer.

D. Remove and replace glass that is broken, chipped, cracked, or abraded or that is damaged from natural causes, accidents, and vandalism, during construction period.

E. Wash glass on both exposed surfaces in each area of Project not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

END OF SECTION 088000

SECTION 089200 – LOUVERED EQUIPMENT ENCLOSURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Fixed, extruded-aluminum louvered roof top equipment screens

B. See Division 5 Section "Structural Metal Framing" for structural framing supporting louver sections.

1.2 PERFORMANCE REQUIREMENTS

A. Design: Design louvers, including comprehensive engineering analysis by a qualified engineer, using structural performance requirements and design criteria indicated.

B. Structural Performance: Louvers shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated without permanent deformation of louver components, noise or metal fatigue caused by louver blade rattle or flutter, or permanent damage to fasteners and anchors.

1. Wind Loads: Determine loads based on a uniform pressure of 30 lb./sq. ft. (1435 Pa), acting inward or outward.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For equipment screens and accessories. Include plans, elevations, sections, details, and attachments to other work. Show frame profiles and blade profiles, angles, and spacing.

C. Samples: For each type of metal finish required.

D. Submittal: For louvers indicated to comply with structural performance requirements and design criteria indicated.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Aluminum Extrusions: ASTM B 221M, Alloy 6063-T5.

B. Aluminum Sheet: ASTM B 209M, Alloy 3003 with temper as required for forming.

C. Fasteners: Use types and sizes to suit unit installation conditions.

1. For fastening aluminum, use aluminum or 300 series stainless-steel fasteners.

2.2 FABRICATION, GENERAL

A. Join concealed frame members to each other and to fixed louver blades with fillet welds concealed from view welds, threaded fasteners, or both, as standard with louver manufacturer unless otherwise indicated or size of louver assembly makes bolted connections between frame members necessary.

2.3 EXTRUDED-ALUMINUM ROOF TOP EQUIPMENT SCREEN

A. Horizontal Blade Louvered Roof Top Equipment Screen

1. Basis-of-Design Product: Architectural Louvers; Model V2KS. Subject to compliance with requirements, provide the specified product or comparable product by one of the following:
   a. Manufacturers of equivalent products submitted and approved in accordance with Section 012500 - Substitution Procedures.

2. Louver Blade Depth: 2 inches (100 mm)
3. Blade Profile: Plain blade with center baffle.
4. Blade Nominal Thickness: Not less than 0.063 inch (1.6 mm).
5. Framing Support Nominal Thickness: Not less than 0.125 inch (3.2 mm)
6. Louver Performance Requirements:
   a. Free Area: Not less than 8.0 sq. ft. (0.74 sq. m) for 48-inch- (1220-mm-) wide by 48-inch- (1220-mm-) high louver assembly.
   b. Horizontal Drag Coefficient: Not greater than 0.66 on a cross sectional profile, allowing for a 34% reduction in wind load imposed horizontally upon supporting structural framing.

2.4 ALUMINUM FINISHES

A. High-Performance Organic Finish: 3-coat fluoropolymer finish complying with AAMA 2605 and containing not less than 70 percent PVDF resin by weight in color coat.

Prepare, pre-treat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

1. Color and Gloss: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Locate and place equipment screens level, plumb, and at indicated alignment with adjacent work.

B. Use concealed anchorages where possible. Provide brass or lead washers fitted to screws where required to protect metal surfaces and to make a weather-tight connection.

C. Provide perimeter reveals and openings of uniform width to allow for thermal expansion, as indicated.

D. Repair damaged finishes so no evidence remains of corrective work. Return items that cannot be refinished in the field to the factory and refinish entire unit or provide new units.

END OF SECTION 089200

SECTION 092900 - GYPSUM BOARD

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Interior gypsum board.

B. Related Requirements:

1. Section 099123 – “Interior Painting"

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.4 DELIVERY, STORAGE AND HANDLING

A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written recommendations, whichever are more stringent.

B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.

C. Do not install panels that are wet, those that are moisture damaged, and those that are mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 GYPSUM BOARD, GENERAL

A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

2.2 INTERIOR GYPSUM BOARD

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. American Gypsum.
2. CertainTeed Corp.
3. Georgia-Pacific Gypsum LLC.
4. USG Corporation.
5. Equal approved by Architect.

B. Gypsum Board, Type X: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch.
2. Long Edges: Tapered.

C. Gypsum Ceiling Board, Type X: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch.
2. Long Edges: Tapered.

2.3 TRIM ACCESSORIES

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. American Gypsum.
2. CertainTeed Corp.
3. Georgia-Pacific Gypsum LLC.
4. USG Corporation.
5. Equal approved by Architect.

B. Interior Trim: ASTM C 1047.

1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized steel sheet.
2. Shapes:

    a. Cornerbead.

2.4 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C 475/C 475M.

B. Joint Tape:

1. Interior Gypsum Board: Paper.

C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas and substrates including welded hollow-metal frames and framing, with Installer present, for compliance with requirements and other conditions affecting performance.

B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLYING AND FINISHING PANELS, GENERAL

A. Comply with ASTM C 840.

B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.

C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch of open space between panels. Do not force into place.

D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite

sides of partitions. Do not make joints other than control joints at corners of framed openings.

E. Form control and expansion joints with space between edges of adjoining gypsum panels.

F. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.

G. Wood Framing: Install gypsum panels over wood framing, with floating internal corner construction. Do not attach gypsum panels across the flat grain of wide-dimension lumber, including floor joists and headers. Float gypsum panels over these members or provide control joints to counteract wood shrinkage.

3.3 APPLYING INTERIOR GYPSUM BOARD

A. Install interior gypsum board as indicated on drawings.

B. Single-Layer Application:

1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated.
2. On partitions/walls, apply gypsum panels horizontally.
3. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

3.4 INSTALLING TRIM ACCESSORIES

A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.

B. Interior Trim: Install in the following locations:

1. Cornerbead: Use at outside corners.

3.5 FINISHING GYPSUM BOARD

A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.

B. Prefill open joints and damaged surface areas.

C. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.

D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:

1. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.

a. Match finish level of adjacent surfaces as required.

b. Primer and its application to surfaces are specified in Section 099123 "Interior Painting."

3.6 PROTECTION

A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.

B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.

C. Remove and replace panels that are wet, moisture damaged, and mold damaged.

1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 092900

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Thermoplastic-rubber base.

B. Related Sections:

1. 096516 Resilient Sheet Flooring.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples: For each exposed product and for each color and texture specified.

C. Samples for Initial Selection: For each type of product indicated.

D. Samples for Verification: For each type of product indicated and for each color, texture, and pattern required in manufacturer's standard-size samples.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F .

1.5 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following time periods:

1. 48 hours before installation.
2. During installation.

3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.

C. Install resilient products after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 THERMOPLASTIC-RUBBER BASE (RB-1)

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Roppe Corporation, USA or equal

B. Product Standard: ASTM F 1861, Type TP (rubber, thermoplastic).

1. Style and Location:

a. Style B, Cove: Provide in areas with resilient flooring

1) Profile: Standard Toe Cove Base

C. Thickness: 1/8 inch

D. Height: 4 inches

E. Lengths: Coils in manufacturer's standard length or Cut lengths 48 inches long or coils in manufacturer's standard length.

F. Outside Corners: Job formed

G. Inside Corners: Job formed

H. Colors: As indicated by manufacturer's designations

a. 100 Black

2.2 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

1. Installation of resilient products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.

B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

C. Do not install resilient products until materials are the same temperature as space where they are to be installed.

1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.3 RESILIENT BASE INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient base.

B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.

C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.

D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.

E. Do not stretch resilient base during installation.

F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.

G. Preformed Corners: Install preformed corners before installing straight pieces.

H. Job-Formed Corners:

1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches.

a. Form without producing discoloration (whitening) at bends.

2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches.

a. Miter corners to minimize open joints.

3.4 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.

B. Perform the following operations immediately after completing resilient-product installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum horizontal surfaces thoroughly.
3. Damp-mop horizontal surfaces to remove marks and soil.

C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

D. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 096513

SECTION 096516 - RESILIENT SHEET FLOORING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes vinyl sheet flooring.

B. Related Sections:
   1. 096513 Resilient Base and Accessories

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Samples for Verification: In manufacturer's standard size, but not less than 6” x 9”.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of resilient sheet flooring to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: A qualified installer who employs workers for this Project who are competent in techniques required by manufacturer for resilient sheet flooring installation and seaming method indicated.

   1. Engage an installer who employs workers for this Project who are trained or certified by resilient sheet flooring manufacturer for installation techniques required.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Store resilient sheet flooring and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 55 deg F or more than 85 deg F. Store rolls upright.

1.8 FIELD CONDITIONS

A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 85 deg F, in spaces to receive resilient sheet flooring during the following time periods:

1. 48 hours before installation.
2. During installation.
3. 48 hours after installation.

B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.

C. Close spaces to traffic during resilient sheet flooring installation.

D. Close spaces to traffic for 48 hours after resilient sheet flooring installation.

E. Install resilient sheet flooring after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For resilient sheet flooring, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

B. FloorScore Compliance: Resilient sheet flooring shall comply with requirements of FloorScore certification.

2.2 VINYL SHEET FLOORING WITH BACKING (VSF-1)

A. Products: Subject to compliance with requirements, provide the following

1. Johnsonite

B. Product Standard: ASTM F 1303.

1. Type (Binder Content): Type I, minimum binder content of 90 percent
2. Wear-Layer Thickness: Grade 1.
3. Overall Thickness: 0.080” (2.0 mm)
4. Backing Class: Class B (nonfoamed plastic)

C. Sheet Width: As standard with manufacturer

D. Cove Base: See drawings for height requirement. Install metal cove cap.

E. Seamless-Installation Method: Heat welded

F. Colors and Patterns
1. Ruby Heterogeneous Vinyl Sheet Flooring
2. Color: To be selected by Architect from manufacturer’s full range

2.3 INSTALLATION MATERIALS

A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient sheet flooring manufacturer for applications indicated.

B. Adhesives: Water-resistant type recommended by flooring and adhesive manufacturers to suit resilient sheet flooring and substrate conditions indicated.

C. Seamless-Installation Accessories:

1. Heat-Welding Bead: Manufacturer's solid-strand product for heat welding seams.

a. Color: Match flooring.

D. Transition Strips: Rubber with profile and width shown, of height required to protect exposed edge of resilient floor, and of maximum lengths to minimize running joints.
1. Products: provide the following:
a. Manufacturer: Johnsonite
b. Color: as selected by Architect from manufacturer’s full range

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges,

depressions, scale, and foreign deposits that might interfere with adhesion of resilient sheet flooring.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Prepare substrates according to resilient sheet flooring manufacturer's written instructions to ensure adhesion of resilient sheet flooring.

B. Concrete Substrates: Prepare according to ASTM F 710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by resilient sheet flooring manufacturer. Do not use solvents.
3. Alkalinity and Adhesion Testing: Perform tests recommended by resilient sheet flooring manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 7 or more than 9 pH.
4. Moisture Testing: Proceed with installation only after substrates pass testing according to resilient sheet flooring manufacturer's written recommendations, but not less stringent than the following:
   a. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have a maximum 80 percent relative humidity level.

C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.

D. Do not install resilient sheet flooring until it is the same temperature as the space where it is to be installed.

1. At least 48 hours in advance of installation, move flooring and installation materials into spaces where they will be installed.

E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient sheet flooring.

3.3 RESILIENT SHEET FLOORING INSTALLATION

A. Comply with manufacturer's written instructions for installing resilient sheet flooring.

B. Unroll resilient sheet flooring and allow it to stabilize before cutting and fitting.

C. Lay out resilient sheet flooring as follows:

1. Maintain uniformity of flooring direction.

2. Minimize number of seams; place seams in inconspicuous and low-traffic areas, at least 6 inches away from parallel joints in flooring substrates.
3. Match edges of flooring for color shading at seams.
4. Avoid cross seams.

D. Scribe and cut resilient sheet flooring to butt neatly and tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, and door frames.

E. Extend resilient sheet flooring into toe spaces, door reveals, closets, and similar openings.

F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on resilient sheet flooring as marked on substrates. Use chalk or other nonpermanent marking device.

G. Install resilient sheet flooring on covers for telephone and electrical ducts and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of flooring installed on covers and adjoining flooring. Tightly adhere flooring edges to substrates that abut covers and to cover perimeters.

H. Adhere resilient sheet flooring to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

I. Seamless Installation:

1. Heat-Welded Seams: Comply with ASTM F 1516. Rout joints and heat weld with weld, and finish seams to produce surfaces flush with adjoining flooring surfaces.

3.4 CLEANING AND PROTECTION

A. Comply with manufacturer's written instructions for cleaning and protecting resilient sheet flooring.

B. Perform the following operations immediately after completing resilient sheet flooring installation:

1. Remove adhesive and other blemishes from surfaces.
2. Sweep and vacuum surfaces thoroughly.
3. Damp-mop surfaces to remove marks and soil.

C. Protect resilient sheet flooring from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

D. Cover resilient sheet flooring until Substantial Completion.

END OF SECTION 096516

SECTION 096810 -CARPET TILE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes:

1. Carpet Tile
2. Sheet Carpet

B. Related Sections include the following:

1. Section 096513 “Resilient Base and Accessories.”

1.3 SUBMITTALS

A. Provide in accordance with Section 013300 “Submittal Procedures”.

B. Product Data: For each type of product indicated. Include manufacturer's written data on physical characteristics, durability, and fade resistance. Include installation methods.

C. Shop Drawings: Show the following:
1. Columns, doorways, enclose walls or partitions, built-in cabinets, and locations where cutouts are required in carpet.
2. Carpet type, color, and dye lot.
3. Type of subfloor.
4. Type of installation.
5. Pattern of installation.
6. Pattern type, location, and direction.
7. Pile direction.
8. Type, color, and location of edge, transition, and other accessory strips.
9. Transition details to other flooring materials.

D. Samples: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.

1. Carpet Tile: Full-size Sample.
2. Sheet Carpet: 12” x 12” Sample

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An experienced installer who is certified by the Floor Covering Installation Board or who can demonstrate compliance with its certification program requirements.

B. Product Options: Products and manufacturers named in Part 2 establish requirements for product quality in terms of appearance, construction, and performance. Other manufacturers' products comparable in quality to named products and complying with requirements may be considered. Refer to Division 1 Section "Substitutions."

1.5 DELIVERY, STORAGE, AND HANDLING

A. General: Comply with CRI 104, Section 5, "Storage and Handling."

1.6 PROJECT CONDITIONS

A. General: Comply with CRI 104, Section 6.1, "Site Conditions; Temperature and Humidity."

B. Environmental Limitations: Do not install carpet until wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

C. Do not install carpet over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet manufacturer.

D. Where demountable partitions or other items are indicated for installation on top of carpet, install carpet before installing these items.

1.7 EXTRA MATERIALS

A. Furnish extra materials described below, before installation begins, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
   1. Carpet Tile: Full-size units equal to 5 percent.

1.8 CARPET TILE

A. WOM-1
   1. Manufacturer: Shaw
   2. Pattern: Portal Tile – All Access 5T035
   3. Color: Ebony 34500
   4. Size: 24x24
   5. Installation Pattern: Monolithic

1.9 SHEET CARPET

A. CPT-1
   1. Manufacturer: Shaw
   2. Pattern: Scribe 5A215
   3. Color: Bistre 15750
   4. Size: 12 ft.

1.10 INSTALLATION ACCESSORIES

A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided by or recommended by carpet manufacturer.

B. Adhesives: Water-resistant, mildew-resistant, non-staining type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet and that is recommended by carpet manufacturer.

C. Transition Strips: Rubber with profile and width shown, of height required to protect exposed edge of carpet, and of maximum lengths to minimize running joints.
   1. Products: provide the following:
      a. Manufacturer: Johnsonite
      b. Color: as selected by Architect from manufacturer's full range

PART 2 - EXECUTION

2.1 EXAMINATION

A. Examine substrates, areas, and conditions for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet performance. Verify that substrates and conditions are satisfactory for carpet installation and comply with requirements specified.

B. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710 and the following:
   1. Slab substrates are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond. Determine adhesion and dryness characteristics by performing bond and moisture tests recommended by carpet manufacturer.
   2. Subfloor finishes comply with requirements specified in Division 3 Section "Cast-in-Place Concrete" for slabs receiving carpet.
   3. Subfloors are free of cracks, ridges, depressions, scale, and foreign deposits.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

2.2 PREPARATION

A. General: Comply with CRI 104, Section 6.2, "Site Conditions; Floor Preparation," and carpet manufacturer's written installation instructions for preparing substrates indicated to receive carpet installation.

B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.

C. Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by carpet manufacturer.

D. Broom and vacuum clean substrates to be covered immediately before installing carpet. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Proceed with installation only after unsatisfactory conditions have been corrected.

2.3 INSTALLATION

A. General: Comply with CRI 104, Section 13, "Carpet Modules (Tiles)."

B. Installation Method: As recommended in writing by carpet manufacturer for material.

C. Cut and fit carpet to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet manufacturer.

D. Extend carpet into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.

E. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, non-staining marking device.

F. Install pattern parallel to walls and borders.

G. Install in monolithic pattern.

2.4 CLEANING AND PROTECTION

A. Perform the following operations immediately after installing carpet:
   1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet manufacturer.
   2. Remove yarns that protrude from carpet surface.
   3. Vacuum carpet using commercial machine with face-beater element.

B. Protect installed carpet to comply with CRI 104, Section 15, and “Protection of Indoor Installations."

C. Protect carpet against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet manufacturer.

END OF SECTION 096810

SECTION 099113 - EXTERIOR PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes surface preparation and the application of paint systems on the following exterior substrates:

1. Fiber Cement.
2. Galvanized metal.
3. Aluminum (not anodized or otherwise coated).
4. Wood.

B. Related Requirements:

1. Section 051200 "Structural Steel Framing" for shop priming of metal substrates with primers specified in this Section.
2. Section 099123 "Interior Painting" for surface preparation and the application of paint systems on interior substrates.

1.3 DEFINITIONS

A. Gloss Level 1: Not more than 5 units at 60 degrees and 10 units at 85 degrees, according to ASTM D 523.

B. Gloss Level 3: 10 to 25 units at 60 degrees and 10 to 35 units at 85 degrees, according to ASTM D 523.

C. Gloss Level 4: 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees, according to ASTM D 523.

D. Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D 523.

E. Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D 523.

F. Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D 523.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

B. Samples for Initial Selection: For each type of topcoat product.

C. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. Printout of current "MPI Approved Products List" for each product category specified, with the proposed product highlighted.
3. VOC content.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F (7 deg C).

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.6 FIELD CONDITIONS

A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F (10 and 35 deg C).

B. Do not apply paints in snow, rain, fog, or mist; when relative humidity exceeds 85 percent; at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Kelly-Moore Paints.
2. Sherwin-Williams Company (The).
3. Approved equal.

B. Products: Subject to compliance with requirements, provide product listed in other Part 2 articles for the paint category indicated.

2.2 PAINT, GENERAL

A. MPI Standards: Provide products that comply with MPI standards indicated and that are listed in its "MPI Approved Products List."

B. Material Compatibility:

1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.

C. VOC Content: Provide materials that comply with VOC limits of authorities having jurisdiction.

D. Colors: As selected by Architect from manufacturer's full range.

2.3 PRIMERS/SEALERS

A. Primer, Alkali Resistant, Water Based: MPI #3.

B. Wood-Knot Sealer: Sealer recommended in writing by topcoat manufacturer for exterior use in paint system indicated.

2.4 METAL PRIMERS

A. Primer, Galvanized, Water Based: MPI #134..

B. Primer, Quick Dry, for Aluminum: MPI #95.

2.5 WOOD PRIMERS

A. Primer, Latex for Exterior Wood: MPI #6.

2.6 WATER-BASED PAINTS

A. Latex, Exterior Semi-Gloss (Gloss Level 5): MPI #11.

2.7 SOURCE QUALITY CONTROL

A. Testing of Paint Materials: Owner reserves the right to invoke the following procedure:

1. Owner will engage the services of a qualified testing agency to sample paint materials. Contractor will be notified in advance and may be present when samples are taken. If paint materials have already been delivered to Project site,

samples may be taken at Project site. Samples will be identified, sealed, and certified by testing agency.
2. Testing agency will perform tests for compliance with product requirements.
3. Owner may direct Contractor to stop applying paints if test results show materials being used do not comply with product requirements. Contractor shall remove noncomplying paint materials from Project site, pay for testing, and repaint surfaces painted with rejected materials. Contractor will be required to remove rejected materials from previously painted surfaces if, on repainting with complying materials, the two paints are incompatible.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
1. Wood: 15 percent.

C. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.

D. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates and paint systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection.

C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

D. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.

E. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

F. Aluminum Substrates: Remove loose surface oxidation.

G. Wood Substrates:

1. Scrape and clean knots. Before applying primer, apply coat of knot sealer recommended in writing by topcoat manufacturer for exterior use in paint system indicated.
2. Sand surfaces that will be exposed to view, and dust off.
3. Prime edges, ends, faces, undersides, and backsides of wood.
4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

3.3 APPLICATION

A. Apply paints according to manufacturer's written instructions and recommendations in "MPI Manual."

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable items same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed items with prime coat only.
3. Paint both sides and edges of exterior doors and entire exposed surface of exterior door frames.
4. Paint entire exposed surface of window frames and sashes.
5. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
6. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.

B. Tint undercoats same color as topcoat, but tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.

D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

E. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:

1. Paint the following work where exposed to view:

a. Equipment, including panelboards and switch gear.
b. Uninsulated metal piping.
c. Pipe hangers and supports.
d. Metal conduit.
e. Tanks that do not have factory-applied final finishes.

3.4 FIELD QUALITY CONTROL

A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.

1. Contractor shall touch up and restore painted surfaces damaged by testing.
2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.6 EXTERIOR PAINTING SCHEDULE

A. Concrete Substrates, Nontraffic Surfaces:

1. Latex System:

a. Prime Coat: Primer, alkali resistant, water based, MPI #3.
b. Intermediate Coat: Latex, exterior, matching topcoat.
c. Topcoat: Latex, exterior semi-gloss (Gloss Level 5), MPI #11.

B. Metal Substrates:

1. Latex System:

a. Prime Coat: Primer, galvanized, water based, MPI #134.
b. Prime Coat: Primer, galvanized metal, as recommended in writing by topcoat manufacturer for exterior use on galvanized-metal substrates with topcoat indicated. (Primers not required at shop primed steel surfaces)
c. Intermediate Coat: Latex, exterior, matching topcoat.
d. Topcoat: Latex, exterior semi-gloss (Gloss Level 5), MPI #11.

C. Aluminum Substrates:

1. Latex System:

a. Prime Coat: Primer, quick dry, for aluminum, MPI #95.
b. Intermediate Coat: Latex, exterior, matching topcoat.
c. Topcoat: Latex, exterior semi-gloss (Gloss Level 5), MPI #11.

D. Wood Substrates: Including wood trim.

1. Latex System:

a. Prime Coat: Primer, latex for exterior wood, MPI #6. (Prime coat not required at pre-primed siding.)
b. Intermediate Coat: Latex, exterior, matching topcoat.
c. Topcoat: Latex, exterior semi-gloss (Gloss Level 5), MPI #11.

END OF SECTION 099113

SECTION 099123 - INTERIOR PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specifications Sections, apply to this Section.

1.2 SUMMARY

A. This Section includes surface preparation and the application of paint systems on the following interior substrates:

1. Steel.
2. Galvanized metal.
3. Wood.
4. Gypsum board.

B. Related Sections include the following:

1. Division 05 Sections for shop priming of metal substrates with primers specified in this Section.
2. Division 06 Sections for shop priming carpentry with primers specified in this Section.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Samples for verification for each color and finish specified

C. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. Printout of current "MPI Approved Products List" for each product category specified in Part 2, with the proposed product highlighted.

1.4 QUALITY ASSURANCE

A. MPI Standards:

1. Products: Complying with MPI standards indicated and listed in "MPI Approved Products List."
2. Preparation and Workmanship: Comply with requirements in "MPI Architectural Painting Specification Manual" for products and paint systems indicated.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.6 PROJECT CONDITIONS

A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.

B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

1.7 EXTRA MATERIALS

A. Furnish extra materials described below that are from same production run (batch mix) as materials applied and that are packaged for storage and identified with labels describing contents.

1. Quantity: Furnish an additional 5 percent, but not less than 1 gal. of each material and color applied.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Benjamin Moore & Co.
2. Kelly-Moore Paints.
3. Parker Paint Mfg. Co. Inc.
4. Rodda Paint Co.
5. Sherwin-Williams Company (The).

6. Miller Paint.

2.2 PAINT, GENERAL

A. Material Compatibility:

1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.

B. VOC Content of Field-Applied Interior Paints and Coatings: Provide products that comply with the following limits for VOC content, exclusive of colorants added to a tint base, when calculated according to 40 CFR 59, Subpart D (EPA Method 24); these requirements do not apply to paints and coatings that are applied in a fabrication or finishing shop:

1. Flat Paints, Coatings, and Primers: VOC content of not more than 50 g/L.
2. Nonflat Paints, Coatings, and Primers: VOC content of not more than 150 g/L.
3. Anti-Corrosive and Anti-Rust Paints Applied to Ferrous Metals: VOC not more than 250 g/L.
4. Floor Coatings: VOC not more than 100 g/L.
5. Shellacs, Clear: VOC not more than 730 g/L.
6. Shellacs, Pigmented: VOC not more than 550 g/L.
7. Flat Topcoat Paints: VOC content of not more than 50 g/L.
8. Nonflat Topcoat Paints: VOC content of not more than 150 g/L.
9. Anti-Corrosive and Anti-Rust Paints Applied to Ferrous Metals: VOC not more than 250 g/L.
10. Floor Coatings: VOC not more than 100 g/L.
11. Shellacs, Clear: VOC not more than 730 g/L.
12. Shellacs, Pigmented: VOC not more than 550 g/L.
13. Primers, Sealers, and Undercoaters: VOC content of not more than 200 g/L.
14. Dry-Fog Coatings: VOC content of not more than 400 g/L.
15. Zinc-Rich Industrial Maintenance Primers: VOC content of not more than 340 g/L.
16. Pre-Treatment Wash Primers: VOC content of not more than 420 g/L.

C. Chemical Components of Field-Applied Interior Paints and Coatings: Provide topcoat paints and anti-corrosive and anti-rust paints applied to ferrous metals that comply with the following chemical restrictions; these requirements do not apply to paints and coatings that are applied in a fabrication or finishing shop:

1. Aromatic Compounds: Paints and coatings shall not contain more than 1.0 percent by weight of total aromatic compounds (hydrocarbon compounds containing one or more benzene rings).
2. Restricted Components: Paints and coatings shall not contain any of the following:

a. Acrolein.
b. Acrylonitrile.
c. Antimony.
d. Benzene.
e. Butyl benzyl phthalate.
f. Cadmium.
g. Di (2-ethylhexyl) phthalate.
h. Di-n-butyl phthalate.
i. Di-n-octyl phthalate.
j. 1,2-dichlorobenzene.
k. Diethyl phthalate.
l. Dimethyl phthalate.
m. Ethylbenzene.
n. Formaldehyde.
o. Hexavalent chromium.
p. Isophorone.
q. Lead.
r. Mercury.
s. Methyl ethyl ketone.
t. Methyl isobutyl ketone.
u. Methylene chloride.
v. Naphthalene.
w. Toluene (methylbenzene).
x. 1,1,1-trichloroethane.
y. Vinyl chloride.

D. Colors: As indicated in a color schedule on drawings or as selected by Architect.

2.3 PRIMERS/SEALERS

A. Interior Latex Primer/Sealer: MPI #50.

B. Wood-Knot Sealer: Sealer recommended in writing by topcoat manufacturer for use in paint systems indicated.

2.4 METAL PRIMERS

A. Alkyd Anticorrosive Metal Primer: MPI #79.

B. Quick-Drying Alkyd Metal Primer: MPI #76.

C. Waterborne Galvanized-Metal Primer: MPI #134.

2.5 WOOD PRIMERS

A. Interior Latex-Based Wood Primer: MPI #39.

2.6 LATEX PAINTS

A. Institutional Low-Odor/VOC Latex (Semigloss): MPI #147 (Gloss Level 5).

B. High-Performance Architectural Latex (Semigloss): MPI #141 (Gloss Level 5).

2.7 ALKYD PAINTS

A. Interior Alkyd (Semigloss): MPI #47 (Gloss Level 5).

2.8 OIL BASED WOOD STAIN: MPI #90

A. Interior Oil Based Wood Stain.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of work.

B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
   1. Wood: 15 percent.
   2. Gypsum Board: 12 percent.

C. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.

D. Begin coating application only after unsatisfactory conditions have been corrected and surfaces are dry.

   1. Beginning coating application constitutes Contractor's acceptance of substrates and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual" applicable to substrates indicated.

B. Remove plates, machined surfaces, and similar items already in place that are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
2. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.

C. Clean substrates of substances that could impair bond of paints, including dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers as required to produce paint systems indicated.

D. Steel Substrates: Remove rust and loose mill scale. Clean using methods recommended in writing by paint manufacturer.

E. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal fabricated from coil stock by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.

F. Wood Substrates:

1. Scrape and clean knots, and apply coat of knot sealer before applying primer.
2. Sand surfaces that will be exposed to view, and dust off.
3. Prime edges, ends, faces, undersides, and backsides of wood.
4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.

G. Gypsum Board Substrates: Do not begin paint application until finishing compound is dry and sanded smooth.

3.3 APPLICATION

A. Apply paints according to manufacturer's written instructions.

1. Use applicators and techniques suited for paint and substrate indicated.
2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.

B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.

D. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.

E. Painting Mechanical and Electrical Work: Paint items exposed in equipment rooms and occupied spaces including, but not limited to, the following:

1. Mechanical Work:

a. Uninsulated metal piping.
b. Uninsulated plastic piping.
c. Pipe hangers and supports.
d. Tanks that do not have factory-applied final finishes.
e. Visible portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets.
f. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
g. Mechanical equipment that is indicated to have a factory-primed finish for field painting.

2. Electrical Work:

a. Switchgear.
b. Panelboards.
c. Electrical equipment that is indicated to have a factory-primed finish for field painting.

3.4 FIELD QUALITY CONTROL

A. Testing of Paint Materials: Owner reserves the right to invoke the following procedure at any time and as often as Owner deems necessary during the period when paints are being applied:

1. Owner will engage the services of a qualified testing agency to sample paint materials being used. Samples of material delivered to Project site will be taken, identified, sealed, and certified in presence of Contractor.
2. Testing agency will perform tests for compliance with product requirements.
3. Owner may direct Contractor to stop applying paints if test results show materials being used do not comply with product requirements. Contractor shall remove noncomplying-paint materials from Project site, pay for testing, and repaint surfaces painted with rejected materials. Contractor will be required to remove rejected materials from previously painted surfaces if, on repainting with complying materials, the two paints are incompatible.

3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

3.6 INTERIOR PAINTING SCHEDULE

A. Steel Substrates:

1. High-Performance Architectural Latex System: MPI INT 5.1R.

a. Prime Coat: Quick-drying alkyd metal primer.
b. Intermediate Coat: High-performance architectural latex matching topcoat.
c. Topcoat: High-performance architectural latex semi-gloss.

B. Galvanized-Metal Substrates:

1. High-Performance Architectural Latex System: MPI INT 5.3M.

a. Prime Coat: Waterborne galvanized-metal primer.
b. Intermediate Coat: High-performance architectural latex matching topcoat.
c. Topcoat: High-performance architectural semi-gloss.

C. Gypsum Board Substrates Standard:

1. Latex Over Latex Primer System: MPI INT 9.2A.

a. Prime Coat: Interior latex primer/sealer.
b. Intermediate Coat: Interior latex matching topcoat.
c. Topcoat: Interior latex eggshell.

D. Plywood Substrates:

1. Alkyd Over Latex Primer System: MPI INT 9.2C-G5

a. Prime Coat: Interior latex primer/sealer.
b. Intermediate Coat: Interior alkyd matching topcoat.
c. Topcoat: Interior alkyd eggshell.

3.7 INTERIOR PAINT COLORS

A. PT-1 Match Existing

END OF SECTION 099123

SECTION 102600 - WALL AND DOOR PROTECTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes Stainless Steel Corner Guards

B. Related Requirements:
   1. Division 06 Section “Interior Finish Carpentry”
   2. Division 09 Section “Gypsum Board Assemblies”

1.3 PERFORMANCE REQUIREMENTS

A. Corner Guards: Resist lateral impact force of 100 lbs at any point without damage or permanent set.

1.4 ACTION SUBMITTALS

A. Submit under provisions of Division 1.

B. Product Data: For each type of product indicating physical dimensions and features.

C. Shop Drawings: Showing locations.

D. Maintenance Data: For corner guards to include in maintenance manuals.

PART 2 - PRODUCTS

2.1 CORNER GUARDS

A. Material: 430-grade stainless steel, 16 ga. Satin finish.

B. Mounting: Adhesive

C. Size:
   1. Corner Guard: 3 ½ in x 3 ½ in. at corners (angles as shown on drawings)
   2. Corner Guard U: Custom sized “U” to cover uncased opening (90 degrees).

3. 4 foot high, typical. 8 foot high at Apparatus Bay

2.2 FABRICATION

A. Fabricate components with tight joints, corners and seams.

B. Finish sharp edges smooth.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify that walls are ready to receive work

B. Verify that rough-in for components are correctly sized and located.

3.2 INSTALLATION

A. Install components in accordance with manufacturer's instructions, level and plumb, secured rigidly in position.

B. Position corner guard as shown on drawings and adhere securely to wall surface.

END OF SECTION 102600

SECTION 102800 - TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Public-use washroom accessories.
2. Underlavatory guards.

B. Related Sections:

1. Section 061000 “Rough Carpentry” for wood blocking.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include the following:

1. Construction details and dimensions.
2. Anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
3. Material and finish descriptions.
4. Features that will be included for Project.
5. Manufacturer's warranty.

B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.

1. Identify locations using room designations indicated.
2. Identify products using designations indicated.

1.4 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For toilet and bath accessories to include in maintenance manuals.

1.6 QUALITY ASSURANCE

A. Source Limitations: For products listed together in the same Part 2 articles, obtain products from single source from single manufacturer.

1.7 COORDINATION

A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.

B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

1.8 WARRANTY

A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to replace mirrors that develop visible silver spoilage defects and that fail in materials or workmanship within specified warranty period.

1. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PUBLIC-USE WASHROOM ACCESSORIES

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Bobrick Washroom Equipment, Inc.
2. Bradley Corporation.
3. American Specialties, Inc.
4. Equal as approved by Architect.

B. Toilet Tissue (Roll) Dispenser:

1. Basis-of-Design Product: Bobrick Washroom Equipment, Inc.; Model B-2888.
2. Description: Roll-in-reserve dispenser with hinged front secured with tumbler lockset.

3. Mounting: Surface mounted.
4. Material and Finish: Stainless steel, No. 4 finish (satin).

C. Paper Towel (Folded) Dispenser:

1. Basis-of-Design Product: Bobrick Washroom Equipment, Inc.; Model B-262.
2. Mounting: Surface mounted.
3. Minimum Capacity: 400 C-fold or 525 multifold towels.
4. Material and Finish: Stainless steel, No. 4 finish (satin).
5. Lockset: Tumbler type.
6. Refill Indicators: Pierced slots at sides or front.

D. Liquid-Soap Dispenser:

1. Basis-of-Design Product: Bobrick Washroom Equipment, Inc.; Model 818615.
2. Description: Designed for dispensing soap in liquid or lotion form.
3. Mounting: Surface Mounted.
4. Capacity: 40 oz.
5. Lockset: Tumbler type.
6. Refill Indicator: Window type.

E. Grab Bar:

1. Basis-of-Design Product: Bobrick Washroom Equipment, Inc.; B5806 x 18, B5806 x 36, B5806 x 42.
2. Mounting: Flanges with concealed fasteners.
3. Material: Stainless steel.

    a. Finish: Smooth, No. 4 finish (satin).

4. Outside Diameter: 1-1/4 inches.
5. Configuration and Length: As indicated on Drawings.

F. Seat-Cover Dispenser:

1. Basis-of-Design Product: Bobrick Washroom Equipment, Inc.; Model B-221.
2. Mounting: Surface mounted.
3. Minimum Capacity: 250 seat covers.
4. Exposed Material and Finish: Stainless steel, No. 4 finish (satin).

G. Mirror Unit:

1. Basis-of-Design Product: Bobrick Washroom Equipment, Inc,; Model B-165 2436
2. Frame: Stainless-steel channel.

    a. Corners: Mitered.

3. Hangers: Produce rigid, tamper- and theft-resistant installation, using method indicated below.

a. One-piece, galvanized-steel, wall-hanger device with spring-action locking mechanism to hold mirror unit in position with no exposed screws or bolts.
b. Wall bracket of galvanized steel, equipped with concealed locking devices requiring a special tool to remove.

4. Size: 24 x 36 inches.

2.2 UNDERLAVATORY GUARDS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Plumberex Specialty Products, Inc.
2. Truebro by IPS Corporation.
3. Equal as approved by Architect.

B. Underlavatory Guard:

1. Basis-of-Design Product: Plumberex Specialty Products, Inc. Model 3011-2.
2. Description: Insulating pipe covering for supply and drain piping assemblies that prevent direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.3 FABRICATION

A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.

B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.

B. Grab Bars: Install to withstand a downward load of at least 250 lbf, when tested according to ASTM F 446.

3.2 ADJUSTING AND CLEANING

A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.

B. Remove temporary labels and protective coatings.

C. Clean and polish exposed surfaces according to manufacturer's written recommendations.

END OF SECTION 102800

SECTION 123623 - PLASTIC-LAMINATE-CLAD COUNTERTOPS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section includes plastic-laminate countertops.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product including plastic laminate countertops

B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.

1. Show locations and sizes of cutouts and holes for plumbing fixtures faucets soap dispensers electrical switches and outlets and other items installed in plastic-laminate countertops.

C. Samples for Verification:

1. Plastic laminates: Selected color.

1.4 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Do not deliver countertops until painting and similar operations that could damage countertops have been completed in installation areas. If countertops must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.6 FIELD CONDITIONS

A. Field Measurements: Where countertops are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

PART 2 - PRODUCTS

2.1 PLASTIC-LAMINATE COUNTERTOPS

A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades indicated for construction, installation, and other requirements.

1. The Contract Documents contain selections chosen from options in the quality standard and additional requirements beyond those of the quality standard. Comply with those selections and requirements in addition to the quality standard.

B. Grade: Custom.

1. Grain Direction: Parallel to cabinet fronts.

C. Edge Treatment: Same as laminate cladding on horizontal surfaces.

D. Core Material at Sinks: Plywood made with exterior glue.

E. Core Thickness: 1-1/8 inch.

F. Backer Sheet: Provide plastic-laminate backer sheet, NEMA LD 3, Grade BKL, on underside of countertop substrate.

2.2 PLASTIC-LAMINATE COUNTERTOP SCHEDULE

PLAM-1	Pionite	AG021 Sable, suede finish

2.3 MISCELLANEOUS MATERIALS

A. Adhesives: Do not use adhesives that contain urea formaldehyde.

2.4 FABRICATION

A. Sand wood lightly to remove raised grain on exposed surfaces before fabrication.

B. Fabricate countertops to dimensions, profiles, and details indicated. Ease edges to radius indicated for the following:

1. Solid-Wood (Lumber) Members: 1/16 inch unless otherwise indicated.

C. Complete fabrication, including assembly, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

D. Shop cut openings to maximum extent possible to receive appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

1. Seal edges of openings in countertops with a coat of varnish.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition countertops to average prevailing humidity conditions in installation areas.

B. Before installing countertops, examine shop-fabricated work for completion and complete work as required, including removal of packing and backpriming.

3.2 INSTALLATION

A. Grade: Install countertops to comply with same grade as item to be installed.

B. Assemble countertops and complete fabrication at Project site to the extent that it was not completed in the shop.

1. Provide cutouts for appliances, plumbing fixtures, electrical work, and similar items.
2. Seal edges of cutouts by saturating with varnish.

C. Field Jointing: Where possible, make in the same manner as shop jointing, using dowels, splines, adhesives, and fasteners recommended by manufacturer. Prepare edges to be joined in shop so Project-site processing of top and edge surfaces is not required. Locate field joints where shown on Shop Drawings.

1. Secure field joints in plastic-laminate countertops with concealed clamping devices located within 6 inches of front and back edges and at intervals not

exceeding 24 inches. Tighten according to manufacturer's written instructions to exert a constant, heavy-clamping pressure at joints.

D. Install countertops level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.

E. Scribe and cut countertops to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

F. Countertops: Anchor securely by screwing through corner blocks of base cabinets or other supports into underside of countertop.

1. Install countertops with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
2. Secure backsplashes to tops with concealed metal brackets at 16 inches o.c. and to walls with adhesive.
3. Seal junctures of tops, splashes, and walls with mildew-resistant silicone sealant or another permanently elastic sealing compound recommended by countertop material manufacturer.

3.3 ADJUSTING AND CLEANING

A. Repair damaged and defective countertops, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.

B. Clean countertops on exposed and semi-exposed surfaces. Touch up shop-applied finishes to restore damaged or soiled areas.

END OF SECTION 123623

SECTION 21 00 00

FIRE SUPPRESSION GENERAL CONDITIONS

PART 1 GENERAL

1.1 GENERAL REQUIREMENTS

A. Conform to General Conditions, Supplementary Conditions, the modifications thereto and Division 1 - General Requirements for all work.

1.2 SUMMARY

A. Design Intent:
1. Remove existing 13D type partial sprinkler system.
2. Provide new coverage for entire building.
3. Provide hydraulically designed (or pipe schedule only if acceptable by authorities having jurisdiction) system to NFPA 13 occupancy requirements.
4. Determine volume and pressure of incoming water supply from water flow test data.
5. Interface system with building fire and smoke alarm systems.
6. Piping from the site connection to the flange at the base of the sprinkler riser is specifically included in Division 21 00 00.

B. **This is a design/build specification.** Provide all required design, permits, labor, materials and installation of fire protection work, complete and operable in accordance with these specifications and drawings. Work of Division 21 includes, but is not limited to, that as delineated in conceptual information shown on the drawings and the following specification sections:

21 00 00 Fire Suppression General Conditions

21 05 00 Common Work Results for Fire Suppression

21 13 13 Wet-Pipe Sprinkler Systems

1.3 CODES AND STANDARDS

A. Conform to following code and agency requirements having jurisdictional authority over fire protection installation.
1. International Building Code (IBC) with local amendments.
2. National Electrical Code (NEC) NFPA 70.
3. Requirements of OSHA.
4. National Fire Protection Association (NFPA) Codes and Standards.
5. ASTM, ASME, ANSI and NEMA standards, as referenced in subsequent sections.
6. Local Water District Requirements.

7. Local Health Department Requirements.

1.4 SUBMITTALS

A. See Division 01 - Submittal Procedures.

B. Field Test Reports: Include results of hydrostatic and flow tests with hydraulic calculations.

C. Design Data: Submit design calculations signed and sealed by NICET Level III Certified Designer.

D. Provide one electronic copy of product data submittals for all products listed under “Part 2 Products” of Division 21 and all additional products noted on drawings or required for completion of project.

E. **Submittals shall be complete in one PDF file with bookmarks for each Division. Multi-part submittals will be returned without review.**
1. First Page: Name of Project, Owner, Location & Contracting Company.
2. Index Page: List of specification sections with contents by Tag or item.
3. Bookmarks: Electronic bookmark of each specification section corresponding to listing in index.
4. Acceptable forms of delivery are:
   a. Email (for file sizes less than 10 MB)
   b. Online File Transfer: Dropbox, Google Drive or similar
   c. FTP: Architects or General Contractors file server (if available)

F. Clearly indicate on each page the equipment schedule designation (Tag) and/or specification section, as applicable. Indicate model and all accessories intended for use.

G. Equipment vendor cover page with contact information shall precede submittal by that vendor.

H. Submitted product information shall include (as applicable) but not be limited to the following information:
1. Product description
2. Manufacturer and model
3. Dimensions
4. Performance Ratings (i.e. capacity, rpm, HP, temperature)
5. Construction Materials
6. Ratings (i.e. UL, FM, NEMA, etc)
7. Electrical data
8. Vibration Isolation
9. Controls and wiring diagrams
10. Accessories
11. Engineering technical data (i.e. pressure drops, leakage rates, pump curves)

1.5 SHOP DRAWINGS

A. Prepare Shop Drawings stamped and signed by a NICET Class III Certified designer. Develop in accordance with NFPA 13 and the State and Local Fire Marshals. Submit PDF copies of these drawings for approval prior to beginning work.

B. Submit shop drawings to Architect, Local Fire Marshal, and all other approving authorities. Drawings shall be approved by all agencies prior to fabrication or installation. **Drawings submitted for Architect's approval shall have been stamped approved by the Fire Department.**

C. The Contractor shall draw the design team's attention to any areas in which they contemplate deviations from the conceptual information shown on the contract documents (e.g., due to site conditions).

D. These drawings and diagrams shall show all pipe sizes as well as the manufacturer's name and catalog number of each piece of equipment used.

E. The Architect's review of such drawings shall not relieve the Contractor of responsibility for deviations from the Contract drawings or specifications, nor shall it relieve him from responsibility for errors or omission in such drawings.

F. Fire Sprinkler shop drawings shall indicate all relevant pipe, ceiling, and structural elevations and clearances. All elbows, offsets, and turns shall be clearly identified. All required access doors shall be shown. By submission of sheet fire sprinkler shop drawings, the Contractor acknowledges that coordination has been done to ensure that all ductwork and piping fits and no conflicts exist.

G. Indicate layout of piping and sprinkler locations coordinated with ceiling type, lighting, structural and mechanical. Conform to symmetrical spacing of heads and integrate into locations of lights and other ceiling devices. Center heads on ceiling tiles (+/- 1") and align in straight rows.

H. Indicate detailed pipe layout, hangers and supports, sprinklers, components and accessories. Include building sections and a plot plan showing location of underground supply connections, outside control valves, fire department connections and other equipment to be used.

I. Indicate pipe materials used, jointing methods, supports, floor and wall penetration seals. Indicate installation layout, mounting and support details, and piping connections.

J. Indicate layout of flexible connectors, expansion joints, expansion compensators, loops, offsets and swing joints.

K. Indicate inertia bases and locate vibration isolators, with static and dynamic load on each.

L. Indicate layout of finished ceiling areas indicating sprinkler locations coordinated with ceiling installation.

M. Indicate system controls.

1.6 FIRE SPRINKLER PERMIT

A. Fire Sprinkler contractor shall prepare all documents for permit application, submit and obtain the permit from reviewing authority. All costs and fees to obtain the permit shall be paid by the Fire Sprinkler Contractor.

1.7 QUALITY ASSURANCE

A. Perform work in accordance with NFPA 13 and Local and/ or State Fire Marshal.

B. Perform work in accordance with ASME B31.9 code for installation of piping systems and ASME Section IX for welding materials and procedures.

1.8 QUALIFICATIONS

A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years of continuous representation, a stocking distributor and service representative in the State of Washington.

B. Contractor: Licensed and regularly engaged in the specialized design and installation of automatic sprinkler equipment as listed by UL or other nationally recognized testing laboratories. Minimum three years' experience and have installed at least five systems of comparable size.

C. Bids by wholesalers, suppliers or any firm whose principal business is not that of manufacturing and/or installing fire protection systems are not acceptable.

1.9 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store valves in shipping containers, with labeling in place.

B. Furnish cast iron and steel valves with temporary protective coating with end caps and closures on piping and fittings. Maintain in place until installation.

C. Accept expansion joints on site in factory packing with shipping bars and positioning devices intact. Inspect for damage.

1.10 FIELD MEASUREMENTS

A. Where the word 'verify' is used on the documents, the contractor shall field verify the existing conditions and modify the scope of the installation as required to meet the verified conditions without additional cost to the Owner.

B. Existing systems and utility lines indicated on drawings are in accordance with information furnished to the Architect and may not be complete. Contractor is

responsible for locating, uncovering, disposing of or maintaining existing systems.

1.11 COORDINATION

A. Visit the site and become familiar with existing conditions affecting work.

B. Verify locations of any overhead or buried utilities on or near site. Determine such locations in conjunction with all public and private utility companies and with all authorities having jurisdiction.

C. Mechanical drawings are diagrammatic and do not indicate all possible site conditions. The contractor shall verify all measurements, dimensions and connections on site and coordinate between trades to preclude interferences. The contractor shall provide adjustments to piping as necessary to fit conditions including but is not limited to relocation, offsets, and transitions.

D. In the event of a conflict with other trades of work, the following priority from highest to lowest shall be followed: Structural, lighting, HVAC, plumbing/piping and sprinklers. Starting with the lowest priority, the HVAC, plumbing, and sprinkler contractors shall provide whatever materials, offsets, labor etc. is required to resolve the conflict.

E. When discrepancies occur between plans and specifications, the Architect will determine which takes precedence and the Contractor shall perform the selected requirement at no additional cost.

F. Prior to ordering equipment cross-check mechanical and electrical drawings and specifications to assure proper location and electrical characteristics of connections serving mechanical and electrical equipment.

G. Advise the Architect of any modifications required to suit equipment furnished. Costs for modifications due to equipment substitution will be borne by the contractor.

H. Wherever conflicts occur between different parts of the Contract Documents the greater quantity, the better quality, or larger size shall prevail unless the Architect informs the Contractor otherwise in writing.

I. The scale of each drawing is relatively accurate, but the Contractor is warned to obtain the necessary dimensions for any exact takeoffs from the Architect. No additional cost to the Owner will be considered for failure to obtain exact dimensions where not clear or in error on the drawings. Any device of fixture roughed in improperly and not positioned on implied centerlines or as required by good practice must be repositioned at no cost to the Owner.

1.12 CUTTING, FITTING, REPAIRING AND PATCHING

A. Arrange and pay for all cutting, fitting, repairing, patching and finishing of work by other trades where necessary for installation of mechanical work. Perform work only with craftsmen skilled in their respective trades.

B. Avoid cutting, where possible, by setting sleeves, frames, etc., and by coordinating for openings in advance. Assist other trades in securing correct location and placement of rough-frames, sleeves, openings, etc. for ducts and piping.

C. Cut all holes neatly and as small as possible to admit work. Perform cutting in manner so as not to weaken walls, partitions or floors. Drill holes required to be cut in floors without breaking out around holes.

1.13 SALVAGE

A. Remove excess piping and plug or cap any unused branch connections. Remove scrap pipe and all other excess materials from the site.

B. Comply with contractor’s Construction Waste Management Plan.

1.14 EXTRA MATERIALS

A. Provide extra sprinklers under provisions of NFPA 13.

B. Furnish suitable wrenches for each sprinkler type.

C. Furnish metal storage cabinet adjacent to alarm valve. Lettered "Automatic Sprinklers - Reserve Supplies."

1.15 FINAL APPROVAL

A. Completion and approval of the following is required for final approval of systems.
1. Execution of Architect's and Engineer’s final observation reports
2. Operation and maintenance instruction
3. Operation and maintenance manuals submitted
4. Equipment cleaning
5. Record drawings submitted

B. See Division 01.

1.16 OPERATING AND MAINTENANCE INSTRUCTIONS

A. General: In addition to requirements of Division 01, following initial operation of mechanical systems and prior to acceptance by the Architect, perform the following services.

B. At least two weeks prior to each instruction period, give written notification of readiness to proceed to the Architect and Owner, and obtain mutually acceptable dates.

C. Conduct demonstrations and instructions for the Owner's representatives, pointing out requirements for operating, servicing and maintaining equipment and systems. Describe general system operation and specific equipment functions. Cover all equipment calibration, setpoint adjustment, safeties and alarms.

D. Furnish qualifications of Contractor's personnel in charge of the instruction; foreman position is minimum acceptable. Where equipment startup is performed by supplier's or manufacturer's personnel, those personnel should also provide training on that equipment.

E. During demonstrations and instructions include and reference information from maintenance manuals and contract drawings.
   1. Provide documentation of all instruction which includes:
      a. Date and time of instruction
      b. Name, affiliation and qualifications of the instructor
      c. Name and affiliation of the attendees
      d. Topics, systems, and equipment covered
      e. Length of instruction

F. Minimum duration of instruction period is 1 hours.

1.17 OPERATING AND MAINTENANCE MANUALS

A. Contents: Furnish, in accord with Division 1, three (3) bound copies of operating and maintenance manuals to include the following:
   1. Manufacturers, suppliers, contractor names, addresses and phone numbers.
   2. Warranty service contractors' names, address and phone numbers (if different from above).
   3. Schedule and description of routine maintenance for each component to include oiling, lubrication and greasing data.
   4. Test data log.
   5. Manufacturer's cuts and rating tables, including brochures for all submittal items.
   6. Part numbers of all replaceable items.
   7. Control diagrams and operation sequence.
   8. Written guarantees.
   9. Record drawings corrected and completed.
   10. Completed equipment start-up forms and checklists.

B. Binders:
   1. Furnish typewritten or printed index and tabbed dividers between principal categories.
   2. Bind each manual in a hard-backed loose-leaf binder.

C. Imprint on cover:
   1. Name of project.
   2. Owner.
   3. Location of project.
   4. Architect.
   5. Contractor.
   6. Year of completion.

D. Imprint on backing:
   1. Name of project.

2. Year of completion.

E. Submittals:
1. Preliminary Copies: Prior to scheduled completion of the project, submit two copies for review by the Architect.
2. Final Copies: After approval of the preliminary copies, submit three (3) finished copies to the Owner.

1.18 EQUIPMENT AND PIPE CLEANING

A. Clean interior and exterior of all equipment. Equipment shall be free of dirt, construction debris, corrosion, etc.

B. Adequate provisions shall be made during construction to eliminate dirt, debris or other material from entering and collecting inside of pipe. Any collection of material shall be thoroughly cleaned before equipment startup and if necessary before owner occupancy.

C. Clean exterior of all exposed pipe.

D. Flush entire piping system of foreign matter.

1.19 RECORD DRAWINGS

A. See Division 1.

B. Submit one DVD or CD with all drawings in PDF and AutoCAD format.

C. Show location of equipment and size of piping. Where appropriate provide tag or label identification for all valves and similar equipment. Indicate locations and elevations of exterior pipe and utility connections. Maintain continuously updated drawings during progress of project.

1.20 TESTING

A. Provide completed start-up forms and checklists.

1.21 WARRANTIES AND CONTRACTOR'S GUARANTEE

A. Furnish one year warranty from date of substantial completion for all systems unless specifically noted otherwise.

B. All work, material and equipment shall be free of defect, complete and in perfect operating order at time of delivery to Owner.

C. Without cost to Owner, **correct all defects and failures discovered within one year from date of final acceptance**, except when in the opinion of the Architect such condition is due to neglect or carelessness of the Owner.

D. The guarantee of the Contractor is independent of shorter time limits by any manufacturer of equipment he has furnished. Submit with Operation and Maintenance Manual all guarantees which exceed one year.

E. Make all necessary adjustments during first year of operation.

F. The presence of any inspector or observer during any construction does not relieve the Contractor from responsibility for defects discovered after completion of the work.

PART 2 NOT USED

PART 3 EXECUTION

3.1 DOCUMENTATION

A. Additional plan submittals to Local Fire Marshal: If additional drawing submittals are required at any time during construction contractor shall prepare and submit drawings, review with Fire Marshal, and pick up subsequent approved drawings.

3.2 INSPECTION

A. Do not allow any work to be covered up or enclosed until inspected, tested and approved by the Architect and all authorities having jurisdiction over the work.

B. Should any work be enclosed or covered up before such inspection and test, Contractor shall at his own expense uncover work, and after it has been inspected, tested and approved, make all repairs as necessary to restore all work disturbed by him to its original condition.

3.3 INTERFACE WITH OTHER PRODUCTS

A. Verify devices are installed and connected to fire alarm system.

END OF SECTION

SECTION 21 05 00

COMMON WORK RESULTS FOR FIRE SUPPRESSION

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Pipe
   2. Valves
   3. Hangers and Support
   4. Seismic Controls
   5. Identification

1.2 EXPANSION AND SEISMIC DESIGN REQUIREMENTS

A. Provide structural work and equipment required for expansion and contraction of piping. Verify anchors, guides, and expansion joints provide and adequately protect system.

B. Expansion Compensation Design Criteria:
   1. Installation Temperature: 50 degrees F.
   2. Fire Protection System Temperature: 90 degrees F.
   3. Safety Factor: 30 percent.

C. Seismic performance: Provide seismic restraint in compliance with local jurisdiction and IBC 1613 requirements.

1.3 QUALITY ASSURANCE

A. Through penetration firestopping of fire rated assemblies: ASTM E814 with 0.10” w.g. minimum positive pressure differential. Minimum 1-hour protection.

B. Installed products shall have surface Burning Characteristics: 25/50 flame spread/smoke developed index when tested in accordance with ASTM E84.

C. Perform work in accordance with local jurisdiction’s requirements and AWS D1.1 for welding hanger and support attachments to building structure.

D. Conform to ASME A13.1 for color scheme for identification of piping systems and accessories.

PART 2 PRODUCTS

2.1 BURIED PIPING

A. Steel Pipe: ASTM A53 Grade B, ASTM A135, ASTM A795 Schedule 40 black.

1. Steel Fittings: ASME B16.9, wrought steel, butt welded; ASTM A234, wrought carbon steel and alloy steel; with half-lapped 10 mil polyethylene tape.
2. Cast Iron Fittings: ASME B16.1 flanges and flanged fittings.
3. Joints: AWS D1.1, welded.
4. Protection: ASME C105 polyethylene jacket with heat shrink sleeves or double layer, half-lapped 10 mil polyethylene tape to 6" above grade.

B. Copper Tubing: Type K annealed. ASTM B75, ASTM B88, ASTM B251.
1. Fittings: Cast copper alloy ASME B16.18; wrought copper and bronze, ASME B16.22. Pressure type solder joint.
2. Joints: Silver braze, AWS A5.8 Classification BCuP-3 or BCuP-4; Solder, ASTM B32 Grade 95TA.
3. Protection: ASME C105 polyethylene jacket with heat shrink sleeves or double layer, half-lapped 10 mil polyethylene tape to 6" above grade.

2.2 ABOVE GROUND PIPING

A. Note that piping from the combination meter to the RPBP must be in piping suitable for domestic water (i.e., stainless steel).

B. Steel Pipe: ASTM A53 Grade B, ASTM A135, ASTM A795 Schedule 40 black; Schedule 10 UL listed light wall; ASTM A-795 Type E, Grade A Eddy-Flow or Dyna-Flow UL listed thin wall flow pipe.
1. Steel Fittings: ASME 16.9, wrought steel, butt welded; ASME B16.25, butt weld; ASTM A234, wrought carbon steel and alloy steel; ASME B16.5, steel flanges and fittings; ASME B16.11, forged steel socket welded and threaded.
2. Cast Iron Fittings: ASME B16.1 flanges and flanged fittings; ASME B16.4, threaded fittings.
3. Malleable Iron Fittings: ASME B16.3, threaded.
4. Mechanical Grooved Couplings: Malleable iron housing clamps to engage and lock, "C" shaped elastomeric sealing gasket, steel bolts, nuts, and washers. Victaulic, Gruvlok or approved equal.

C. Steel Pipe: ASTM A135 Grade A, UL threadable thin wall, black.
1. Cast Iron Fittings: ASME B16.4, threaded fittings.
2. Malleable Iron Fittings: ASME B16.3 threaded type.

2.3 VALVES

A. Manufacturers: UL & FM approved by Nibco, Stockham, Milwaukee or approved equal.

B. Gate Valves:
1. Over 2 inches: Iron body, bronze trim, rising stem pre-grooved for mounting tamper switch, hand wheel, OS&Y, solid bronze or cast iron wedge, flanged or grooved ends.
2. Over 4 inches: Iron body, bronze trim, non-rising stem with bolted bonnet, solid bronze wedge, flanged ends.

C. Ball Valves:
   1. Up to and including 2 inches: Bronze two piece body, brass, chrome plated bronze, or stainless steel ball, teflon seats and stuffing box ring, lever handle, threaded or sweat fitting ends.

D. Butterfly Valves:
   1. Bronze Body: Stainless steel disc, resilient replaceable seat, threaded or grooved ends, extended neck, hand wheel and gear drive and integral indicating device, and built-in tamper proof switch where required.
   2. Cast or Ductile Iron Body: Cast or ductile iron, chrome or nickel plated ductile iron or aluminum bronze disc, resilient replaceable EPDM seat, wafer, lug, or grooved ends. With extended neck, hand wheel and gear drive and integral indicating device where required.

E. Check Valves:
   1. Up to 2 inches: Bronze body and swing disc, rubber seat, threaded ends.
   2. 2 to 4 inches: Iron body, bronze trim, swing check with rubber disc, renewable disc and seat, grooved or flanged ends.
   3. 4 inches and over: Iron body, bronze disc with stainless steel spring, resilient seal, wafer, grooved or flanged ends.

F. Drain Valves:
   1. Compression Stop: Bronze with hose thread nipple and cap.
   2. Ball Valve: Brass with cap and chain, 3/4 inch hose thread.

2.4 BACKFLOW ASSEMBLY

A. Double check valve, detector check or as jurisdiction requires. FDA approved epoxy coated cast iron check valve bodies with bronze seats. Furnish with bronze body ball valve test cocks. Suitable for supply pressures to 175 psi and water temperatures to 140 degrees. Tamper switches on gate valves for monitoring. Ames, Watts, Apollo, FEBCO, Wilkins or approved.

2.5 PIPE HANGERS AND SUPPORTS

A. Conform to NFPA 13.

B. Hangers for Pipe Sizes 1 to 6 inch: Carbon steel, adjustable swivel, band hanger. Tolco Fig 200 or equal.

C. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.

D. Wall Support for Pipe Sizes to 3 inches: Cast iron hook.

E. Wall Support for Pipe Sizes 4 inches and Over: Welded steel bracket and wrought steel clamp.

F. Vertical Support: Steel riser clamp.

G. Floor Support: Cast iron pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

2.6 FLEXIBLE PIPE CONNECTORS

A. Manufacturers: Metraflex, Mason or approved equal.

B. Steel Piping:
1. UL Listed
2. Inner Hose: Stainless Steel.
3. Exterior Sleeve: Braided stainless steel.
4. Joint: Flanged, threaded with union or welded, as specified for pipe joints.
5. Maximum offset: 3/4 inch.

2.7 FLEXIBLE SPRINKLER HOSE CONNECTIONS

A. Manufacturers: FlexHead or approved equal.

B. Performance:
1. FM Approved for its intended use pursuant to FM 1637 Approval Standard for Flexible Sprinkler Hose with Threaded End Fittings.
2. UL Listed for its intended use pursuant to UL 2443 Standard for Flexible Sprinkler Hose with Fittings for Fire Protection Service.
3. Seismically qualified for use pursuant to ICC-ES AC-156 Acceptance Criteria for Seismic Qualification by Shake-Table Testing of Nonstructural Components and Systems.

C. Flexible Hose Assemblies and End Fittings:
1. 100% Type 304 Stainless Steel.
2. Straight Hose Assembly or Elbow Hose Assembly.
3. ½ inch or ¾ inch outlet.
4. 175 psi / 300 psi maximum rated pressure.
5. Fully welded non-mechanical fittings, braided, leak-tested with minimum 1 inch true-bore internal corrugated hose diameter.

D. Ceiling Bracket:
1. Type G90 Galvanized Steel.
2. Direct attachment type, having integrated snap-on clip ends positively attached to the ceiling using tamper-resistant screws.
3. Flexible Hose Attachment: Removable hub type with set screw.

2.8 FIRESTOPPING-APPLIED

A. Manufacturers: RectorSeal, Dow Corning, 3M Fire Protection or approved equal.

B. General:
1. Fire stopping materials shall conform to Flame (F) and Temperature (T) ratings as required by applicable building codes and tested by nationally accepted test agencies per ASTM E 814 or UL 1479 fire tests for through

penetrations, and ASTM E 1966 or UL 2079 for construction joints, and UL 2307 for perimeter edge joints.

2. Fire stopping material shall be free of asbestos, PCBs, ethylene glycol, and lead.
3. Do not use any product containing solvents or that requires hazardous waste disposal.
4. Fire stopping shall be performed by a contractor trained or approved by firestop manufacturer.
5. Select products with rating not less than rating of wall or floor being penetrated.

C. Single Source Responsibility: Provide firestop systems for all conditions from a single supplier.

D. Product Description: Provide Latex caulk/sealant, Silicone caulk/sealant, Intumescent Wrap Strip, Firestop Putty, Firestop Collar or Intumescent Sleeve to meet each specific application and performance requirement.

E. Primer: Type recommended by firestopping manufacturer for specific substrate surfaces and suitable for required fire ratings.

F. Installation Accessories: Provide clips, collars, fasteners, temporary stops or dams, and other devices required to position and retain materials in place.

1. Forming/Damming Materials: Mineral fiberboard, backer rod or other type recommended by Manufacturer's tested system.

2.9 MECHANICAL SLEEVE SEALS

A. Manufacturers: Metraflex Metraseal, Thunderline Link-Seal or approved equal.

B. Product Description: Modular mechanical type, consisting of interlocking synthetic rubber links shaped to continuously fill annular space between object and sleeve, connected with bolts and pressure plates causing rubber sealing elements to expand when tightened, providing watertight seal and electrical insulation.

2.10 PIPING ACCESSORIES

A. Manufacturers: Grinnell, EMCO Wheaton, OPW or approved equal.

B. Pipe Alignment Guides: Two piece welded steel with enamel paint, bolted, with spider to fit standard pipe, frame with four mounting holes, clearance for minimum 1 inch thick insulation, minimum 3 inch travel.

C. Swivel Joints: Fabricated steel, bronze, ductile Iron or cast steel body, double ball bearing race, field lubricated, with rubber or Buna-N o-ring seals.

2.11 PIPE MARKERS

A. Color and Lettering shall conform to ASME A13.1.

B. Fire service piping labels shall be red background with white lettering. Legend shall indicate service of pipe.

C. Plastic Pipe Markers: Factory fabricated, flexible, semi-rigid plastic, preformed to fit around pipe or pipe covering. Larger sizes may have maximum sheet size with spring fastener.

D. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.

PART 3 EXECUTION

3.1 PREPARATION - PIPING

A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.

B. Remove scale and foreign material, from inside and outside, before assembly.

C. Prepare piping connections to equipment with flanges, unions or grooved couplings.

3.2 INSTALLATION - PIPING

A. Install piping in accordance with NFPA 13 for sprinkler systems.

B. Route piping in orderly manner, plumb and parallel to building structure. Maintain gradient.

C. Install piping to conserve building space, to not interfere with use of space and other work.

D. Group piping whenever practical at common elevations.

E. Install pipe sleeve at piping penetrations through footings, partitions, walls, and floors. Seal pipe and sleeve penetrations to maintain fire resistance equivalent to fire separation.

F. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

G. Pipe Hangers and Supports:
1. Install in accordance with NFPA 13.
2. Install hangers with minimum 1/2 inch space between finished covering and adjacent work.
3. Place hangers within 12 inches of each horizontal elbow.
4. Use hangers with 1-1/2 inch minimum vertical adjustment. Design hangers for pipe movement without disengagement of supported pipe.
5. Support vertical piping at every floor. Support riser piping independently of connected horizontal piping.

6. Where installing several pipes in parallel and at same elevation, provide multiple or trapeze hangers.
7. Install copper plated hangers and supports for copper piping.
8. Prime coat exposed steel hangers and supports. Hangers and supports located in crawl spaces, pipe shafts, and suspended ceiling spaces are not considered exposed.

H. Slope piping and arrange systems to drain at low points.

I. Prepare pipe, fittings, supports, and accessories for finish painting. Where pipe support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welding.

J. Do not penetrate building structural members unless indicated.

K. Where more than one piping system material is specified, install compatible system components and joints. Install flanges, union, and couplings at locations requiring servicing.

L. Die cut threaded joints with full cut standard taper pipe threads with red lead and linseed oil or other non-toxic joint compound applied to male threads only.

M. Install valves with stems upright or horizontal, not inverted. Remove protective coatings after installation.

N. Install gate, ball, or butterfly valves for shut-off or isolating service.

O. Install drain valves at main shut-off valves, low points of piping and apparatus.

3.3 INSTALLATION – HEAT TRACE

A. Provide electric heat trace and insulation on wet piping subject to freezing.

B. Heat trace failure is an alarm point in the building fire alarm system. Provide control point(s) and coordinate with the alarm system subcontractor.

3.4 INSTALLATION – SEISMIC CONTROLS

A. Provide seismic restraints and hangers in compliance with SBC 1613.

B. Seismic Bracing: Follow SBC 1613, SMACNA Seismic Restraint Manual and the following.
1. Bracing shall be bidder designed to resist seismic loading in accord with Chapter 16 of the International Building Code or the SMACNA guideline.
2. Provide seismic calculations for all equipment as required for Ip = 1.0.

3.5 INSTALLATION – FIRESTOPPING AND SEALS AT PARTITIONS

A. Install material at fire rated construction perimeters and openings containing penetrating sleeves, piping and other items requiring firestopping.

B. Apply primer where recommended by manufacturer for type of firestopping material and substrate involved, and as required for compliance with required fire ratings. Primers must comply with VOC limits per Green Seal standards GS-03 (1997), GS-11 (1993), or SCAQMD Rule #1113 (2004).

C. Place intumescent coating in sufficient coats to achieve rating required.

D. Clean adjacent surfaces of firestopping materials.

E. Fire Rated Surface:
   1. Seal opening at floor, wall, partition, ceiling, and/or roof as follows:
      a. Install sleeve through opening and extending beyond minimum of 1 inch on both sides of building element.
      b. Size sleeve allowing minimum of 1 inch void between sleeve and building element.
      c. Pack void with backing material.
      d. Seal ends of sleeve with UL listed fire resistive silicone compound to meet fire rating of structure penetrated.

F. Non-Rated Surfaces:
   1. Seal opening through non-fire rated wall, partition, floor, ceiling, and/or roof opening as follows:
      a. Install sleeve through opening and extending beyond minimum of 1 inch on both sides of building element.
      b. Size sleeve allowing minimum of 1 inch void between sleeve and building element.
   2. Install escutcheons where piping penetrates non-fire rated surfaces in occupied spaces.
   3. Exterior wall openings below grade: Assemble rubber links of mechanical sealing device to size of piping and tighten in place, in accordance with manufacturer's instructions.
   4. Interior partitions: Seal pipe penetrations air tight. Apply sealant to both sides of penetration to completely fill annular space between sleeve and conduit.

3.6 INSTALLATION - IDENTIFICATION

A. Identification is not required on sprinkler branch lines and run-outs to heads.

B. Identification is required on:
   1. Bulk mains
   2. Incoming fire service
   3. FDC piping
   4. Standpipe (not in stairwell)

C. Identify service and flow direction (and pressure where more than one pressure is used). Install in clear view and align with axis of piping. Locate identification not to exceed 20 feet on straight runs including risers and drops, adjacent to each valve and tee, at each side of penetration of structure or enclosure, and at

each obstruction. Install a minimum of one label for each story traversed by piping.

D. Install plastic nameplates with corrosive-resistant mechanical fasteners, or adhesive.

E. Install labels with sufficient adhesive for permanent adhesion.

3.7 INTERFACE WITH OTHER PRODUCTS

A. Inserts:
1. Install inserts for placement in concrete forms.
2. Install inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
3. Install hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.

3.8 MANUFACTURER'S FIELD SERVICES

A. Furnish inspection services by flexible pipe manufacturer's representative for final installation and certify installation is in accordance with manufacturer's recommendations and connectors are performing satisfactorily.

END OF SECTION

SECTION 21 13 13

WET-PIPE SPRINKLER SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

A. Section includes wet-pipe sprinkler system design, installation, and certification.

1.2 SYSTEM DESCRIPTION

A. The fire sprinkler system is to be design-build, but in conformance with conceptual information shown on the drawings.

B. This section requires design and installation of wet pipe sprinkler systems for building fire protection.

C. Provide hydraulically designed system to NFPA 13 occupancy requirements.

D. Perform work in accordance with NFPA 13, state and local municipality having jurisdiction.

E. Determine volume and pressure of incoming water supply from water flow test data. Revise design when test data become available prior to submittals.

F. Interface system with building fire and smoke alarm system.

G. Provide connection to site fire department connection.

H. Piping from the site connection(s) (up to 5 feet outside the building) to the flange at the base of the sprinkler riser and FDC connection is specifically included in Division 21.

I. Fire suppression system shall not contain ozone depleting substances such as halons, CFC’s and HCFC’s.

PART 2 PRODUCTS

2.1 SPRINKLERS

A. Manufacturers: Tyco, Reliable, Viking or approved equal.

B. Provide “quick response” heads in all residential occupancies.

C. Provide “quick response” heads in all light hazard occupancies.

D. Suspended T-bar Ceiling Type:
   1. Type: Semi-recessed pendant type with matching escutcheon plate.
   2. Sprinkler and escutcheon plate finish: Chrome plated factory finish.

3. Fusible link: Glass bulb type temperature rated for specific area hazard.

E. GWB Ceiling Type:
1. Type: Semi-recessed pendant type with matching escutcheon plate.
2. Sprinkler and escutcheon plate finish: Chrome plated factory finish.
3. Fusible link: Glass bulb type temperature rated for specific area hazard.

F. Exposed Area Type:
1. Type: Standard upright type.
2. Finish: Brass
3. Fusible Link: Glass bulb type temperature rated for specific area hazard.

G. Side wall Type:
1. Type: Standard horizontal side wall type.
2. Sprinkler and escutcheon plate finish: Brass (exterior) \ Chrome plated (interior) factory finish.
3. Fusible Link: Glass bulb type temperature rated for specific area hazard.

H. Guards: Finish matching sprinkler finish.

2.2 PIPING SPECIALTIES

A. Electric Alarm: Electrically operated red enameled gong with pressure alarm switch.

B. Water Flow Switch: Vane type switch for mounting horizontal or vertical, with two contacts.

2.3 ELECTRICAL CHARACTERISTICS AND COMPONENTS

A. Controls: Supervisory switches. Coordinate with fire alarm section of work.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with NFPA 13.

B. Install pressure gauges on each side of sprinkler alarm valve.

C. Install approved backflow assembly at sprinkler system water source connection.

D. Locate outside alarm on building exterior wall.

E. Place pipe runs to minimize obstruction to other work.

F. It shall be a specific requirement that insofar as possible, all sprinkler system mains and branches shall be installed as close as possible to the structural members, not the ceiling.

G. Install main piping in concealed spaces above finished ceilings or soffits; branch piping in joist space or other concealed space to sprinkler heads.

H. Center sprinklers in two directions in ceiling tile and install piping offsets.

I. Install guards on sprinklers exposed to potential damage.

J. Provide drains at system low points.

K. Hydrostatically test entire system.

L. Testing must be witnessed by Authorities having jurisdiction.

3.2 CLEANING

A. Flush entire piping system of foreign matter.

3.3 PROTECTION OF INSTALLED CONSTRUCTION

A. Apply masking tape or paper cover to protect concealed sprinklers, cover plates, and sprinkler escutcheons not receiving field paint finish. Remove after painting. Replace painted sprinklers with new.

END OF SECTION

SECTION 22 00 00

PLUMBING GENERAL CONDITIONS

PART 1 GENERAL

1.1 GENERAL REQUIREMENTS

A. Conform to General Conditions, Supplementary Conditions, the modifications thereto and Division 01 - General Requirements for all work in Division 22.

1.2 SUMMARY

A. Design Intent: Provide plumbing revisions; including new piping and fixtures for a remodel.

B. Provide labor, materials and appliances necessary for satisfactory installation of mechanical work ready to operate in strict accordance with these specifications and drawings. Work of Division 22 includes, but is not limited to, that as delineated in the following specification sections:

22 00 00 Plumbing General Conditions

22 05 00 Common Work Results for Plumbing

22 07 00 Plumbing Insulation

22 11 00 Facility Water Distribution

22 13 00 Facility Sanitary Sewerage

22 14 00 Facility Storm Drainage

22 15 00 General Service Compressed Air Systems

22 23 00 Natural Gas System

22 40 00 Plumbing Fixtures

1.3 CODES AND STANDARDS

A. Conform to following code and agency requirements having jurisdictional authority over mechanical installations.
1. Uniform Plumbing Code (UPC) with local amendments.
2. International Mechanical Code (IMC) with local amendments.
3. International Building Code (IBC) with local amendments.
4. International Fuel Gas Code (IFGC) with local amendments.
5. National Electrical Code (NEC) NFPA 70.

6. Requirements of OSHA and EPA.
7. National Fire Protection Association (NFPA) Codes and Standards.
8. ASME code for construction of pressure vessels.
9. American Gas Association (AGA) Standards.
10. ASTM, ANSI and NEMA standards, as referenced in subsequent sections.
11. Local Sewer District Requirements.
12. Local Water District Requirements.
13. Local Health Department Requirements.
14. Washington State Energy Code.

1.4 PERFORMANCE REQUIREMENTS

A. Firestopping: Conform to International Building Code with local amendments, FM and UL for fire resistance ratings and surface burning characteristics.

1.5 PRODUCT SUBSTITUTIONS:

A. Manufacturers and models of equipment and material indicated herein and on drawings are those upon which mechanical design is based. Other manufacturers with products considered equal in general quality may be listed without specific model designation. Manufacturers not listed must be submitted for approval.

B. Substitutions will be evaluated based on product manufacturer only. Specific product model, specifications, options and accessories will be evaluated during submittals. Approval of a manufacturer substitution does not constitute approval of the submitted product.

C. Any equipment other than the basis of design is considered a substitution.

D. In selecting substitute equipment, the Contractor is responsible for and must guarantee equal performance and fit. Cost of redesign and all additional costs incurred to accommodate the substituted equipment shall be borne by the Contractor.

E. Unless indicated otherwise, "or approved" may be assumed for all products in Division 22.

1.6 SUBMITTALS

A. Provide one electronic copy of product data submittals for all products listed under “Part 2 Products” of Division 22 and all additional products noted on drawings or required for completion of sequence of operations.

B. **Submittals shall be complete in one PDF file with bookmarks for each Division. Multi-part submittals will be returned without review.**
1. First Page: Name of Project, Owner, Location & Contracting Company.
2. Index Page: List of specification sections with contents by Tag or item.

3. Bookmarks: Electronic bookmark of each specification section corresponding to listing in index.
4. Acceptable forms of delivery are:
   a. Email (for file sizes less than 10 MB)
   b. Online File Transfer: Dropbox, Google Drive or similar
   c. FTP: Architects or General Contractors file server (if available)

C. Clearly indicate on each page the equipment schedule designation (Tag) and/or specification section, as applicable. Indicate selected model and all accessories intended for use.

D. Equipment vendor cover page with contact information shall precede submittal by that vendor.

E. Submitted product information shall include (as applicable) but not be limited to the following information:
1. Product description
2. Manufacturer and model
3. Dimensions
4. Performance Ratings (i.e. capacity, rpm, HP, temperature)
5. Construction Materials
6. Ratings (i.e. UL, ASTM, NEMA, etc)
7. Electrical data
8. Sound level data (corresponding to scheduled values)
9. Vibration Isolation
10. Controls and wiring diagrams
11. Accessories
12. Engineering technical data (i.e. pressure drops, leakage rates, pump curves)

F. If requested by Architect or Engineer, submit Manufacturer's Installation Instructions on any equipment, procedures, or certifications so requested.

G. Do no ordering, fabrication or manufacturing of products until return of approved submittals.

1.7 SHOP DRAWINGS

A. The Contractor shall submit drawings and/or diagrams for review and for job coordination in all cases where deviation from the Contract Drawings are contemplated because of job conditions, interference or substitution of equipment, or when requested by the Engineer for purposes of clarification of the Contractor’s intent. Also submit detailed drawings, rough-in sheets, etc., for all special or custom-built items or equipment. Drawings and details under the section shall include (but not be limited to) the following, where applicable to this project:
1. Electrical interlock wiring diagrams.
2. Piping layout plans and interference details.
3. Custom sink layout.

B. By submission of plumbing shop drawings, the Contractor acknowledges that coordination has been done to ensure that all piping fits and no conflicts exist.

C. The Architect's review of shop drawings shall not relieve the Contractor of responsibility for deviations from the Contract drawings or specifications, unless he has, in writing, called the attention of the Architect to such deviations at the time of the submission, nor shall it relieve him from responsibility for errors or omission in such shop drawings.

1.8 PLUMBING PERMIT

A. Plumbing contractor shall prepare all documents for plumbing permit application, submit for and obtain the permit. All costs and fees to obtain the permit shall be paid by the Plumbing Contractor.

B. Contractor shall not commence work until permit is obtained. Contractor is solely responsible to insure that the permit application and any revisions are submitted in a timely manner so as not to impact project schedule.

1.9 QUALITY ASSURANCE

A. Perform Work in accordance with ASME B31.9 – Building Services Piping for installation of piping systems and ASME Section IX – Welding and Brazing Qualifications for welding materials and procedures.

B. Perform Work in accordance with the Uniform Plumbing Code including State and local amendments.

C. Provide products requiring electrical connections listed and classified by UL as suitable for purpose specified and indicated.

D. Perform Work in accordance with Washington State Energy Code.

1.10 QUALIFICATIONS

A. Manufacturer: Company specializing in manufacturing Products specified in this section with minimum three years' experience.

B. Installer: Company specializing in performing Work of this section with minimum three years' experience.

1.11 DELIVERY, STORAGE, AND HANDLING

A. Accept materials on site in original factory packaging, labeled with manufacturer's identification.

B. Protect all equipment, materials, and insulation from weather, construction traffic, dirt, water, chemicals, and damage by storing in original packaging and under cover. Where original packaging is insufficient, provide additional protection. Maintain protection in place until installation.

C. Inspect all products and materials for damage prior to installation.

D. Protect piping from all entry of foreign materials by providing temporary end caps or closures on piping and fittings. Furnish temporary protective coating on cast iron and steel valves.

E. Protect materials and finishes during handling and installation to prevent damage.

F. Comply with manufacturer's installation instruction for rigging, unloading and transporting units.

G. Protect installed fixtures from damage by securing areas and by leaving factory packaging in place to protect fixtures and prevent use.

1.12 ENVIRONMENTAL REQUIREMENTS

A. Do not apply fire stopping materials when temperature of substrate material and ambient air is below 60 degrees F. Maintain this minimum temperature before, during, and for minimum 3 days after installation of fire stopping materials.

B. Provide ventilation in areas to receive solvent cured materials.

C. Do not install underground piping or valves when bedding is wet or frozen.

D. Install insulation only when ambient temperature and humidity conditions are within range recommended by manufacturer. Maintain temperature during and after installation for minimum period of 24 hours.

E. Do not install instruments when areas are under construction, except rough in, taps, supports and test plugs.

1.13 FIELD MEASUREMENTS

A. Verify field measurements prior to fabrication.

B. Verify by field measurements, sizes and configurations are compatible with wall construction and layout.

C. Existing systems and utility lines indicated on drawings are in accordance with information furnished to the Architect and may not be complete. Contractor is responsible for locating, uncovering, disposing of or maintaining existing systems.

1.14 COORDINATION

A. Visit the site and become familiar with existing conditions affecting work.

B. Verify locations of any overhead or buried utilities on or near site. Determine such locations in conjunction with all public and private utility companies and with all authorities having jurisdiction.

C. Existing systems and utility lines indicated on drawings are in accordance with information furnished to the Architect and may not be complete. Contractor is responsible for locating, uncovering, disposing of or maintaining existing systems.

D. Plumbing drawings are diagrammatic and do not indicate all possible site conditions. The contractor shall verify all measurements, dimensions and connections on site and coordinate between trades to preclude interferences. The contractor shall provide adjustments to piping as necessary to fit conditions including but is not limited to relocation, offsets, and transitions.

E. In the event of a conflict with other trades of work, the following priority from highest to lowest shall be followed: Structural, lighting, HVAC, plumbing/piping and sprinklers. Starting with the lowest priority, the HVAC, plumbing, and sprinkler contractors shall provide whatever materials, offsets, labor etc. is required to resolve the conflict.

F. When discrepancies occur between plans and specifications, the Architect will determine which takes precedence and the Contractor shall perform the selected requirement at no additional cost.

G. Prior to ordering equipment cross-check plumbing and electrical drawings and specifications to assure proper location and electrical characteristics of connections serving mechanical and electrical equipment.

H. Advise the Architect of any modifications required to suit equipment furnished. Costs for modifications due to equipment substitution will be borne by the contractor.

I. Wherever conflicts occur between different parts of the Contract Documents the greater quantity, the better quality, or larger size shall prevail unless the Architect informs the Contractor otherwise in writing.

J. The scale of each drawing is relatively accurate, but the Contractor is warned to obtain the necessary dimensions for any exact takeoffs from the Architect. No additional cost to the Owner will be considered for failure to obtain exact dimensions where not clear or in error on the drawings. Any device or fixture roughed in improperly and not positioned on implied centerlines or as required by good practice must be repositioned at no cost to the Owner.

K. Where the word ‘verify’ is used on the documents, the contractor shall field verify the existing conditions and modify the scope of the installation as required to meet the verified conditions without additional cost to the Owner.

L. Coordinate trenching, excavating, bedding, backfilling of buried systems with requirements of this specification.

M. Coordinate wall openings, piping rough-in locations, concrete housekeeping pads, and electrical rough-in locations to accommodate Work of this Section.

1.15 CUTTING, FITTING, REPAIRING AND PATCHING

A. Arrange and pay for all cutting, fitting, repairing, patching and finishing of work by other trades where necessary for installation of plumbing work. Perform work only with craftsmen skilled in their respective trades.

B. Avoid cutting, where possible, by setting sleeves, frames, etc., and by coordinating for openings in advance. Assist other trades in securing correct location and placement of rough-frames, sleeves, openings, etc. for piping.

C. Cut all holes neatly and as small as possible to admit work. Perform cutting in manner so as not to weaken walls, partitions or floors. Drill holes required to be cut in floors without breaking out around holes.

1.16 SALVAGE

A. Remove excess piping and plug or cap any unused branch connections. Remove scrap pipe and all other excess materials from the site.

B. Comply with contractor’s Construction Waste Management Plan

1.17 ELECTRICAL

A. Power Wiring: By Electrical Contractor.

B. Control Wiring: Responsibility of Division 22, including all line and low voltage control wiring. Owner will not entertain additional cost due to lack of coordination between Plumbing Contractor and Electrical Contractor.

1.18 PROJECT CLOSEOUT

A. Completion, submission and approval of the following is required for final project closeout.
   1. Execution of Architect's and Engineer’s final observation reports (punchlist)
   2. Operating and Maintenance Instructions
   3. Operating and Maintenance Manual
   4. Equipment and Pipe Cleaning
   5. Record Drawings
   6. Testing
   7. Commissioning
   8. Warranty

B. See Division 01 for additional requirements.

1.19 OPERATING AND MAINTENANCE INSTRUCTIONS

A. General: In addition to requirements of Division 01, following initial operation of plumbing systems and prior to acceptance by the Architect, perform the following services.

B. At least two weeks prior to each instruction period, give written notification of readiness to proceed to the Architect and Owner, and obtain mutually acceptable dates.

C. Conduct demonstrations and instructions for the Owner's representatives, pointing out requirements for operating, servicing and maintaining equipment and systems. Describe general system operation and specific equipment functions. Cover all equipment calibration, setpoint adjustment, safeties and alarms.

D. Furnish qualifications of Contractor's personnel in charge of the instruction; foreman position is minimum acceptable. Where equipment startup is performed by supplier’s or manufacturer’s personnel, those personnel should also provide training on that equipment.

E. During demonstrations and instructions include and reference information from maintenance manuals and contract drawings.
   1. Provide documentation of all instruction which includes:
      a. Date and time of instruction
      b. Name, affiliation and qualifications of the instructor
      c. Name and affiliation of the attendees
      d. Topics, systems, and equipment covered
      e. Length of instruction

F. Minimum duration of instruction periods:
   1. Plumbing Systems 2 hours

1.20 OPERATING AND MAINTENANCE MANUALS

A. Contents: Furnish, in accord with Division 1, three (3) bound copies of operating and maintenance manuals to include the following:
   1. Manufacturers, suppliers, contractor names, addresses and phone numbers.
   2. Warranty service contractors' names, address and phone numbers (if different from above).
   3. Schedule and description of routine maintenance for each component to include oiling, lubrication and greasing data.
   4. Test data log.
   5. Manufacturer's cuts and rating tables, including brochures for all submittal items.
   6. Part numbers of all replaceable items.
   7. Control diagrams and operation sequence.
   8. Written guarantees.
   9. Record drawings corrected and completed.

10. Completed equipment start-up forms and checklists.

B. Operation and Maintenance Data:
1. Submit frequency of treatment required for interceptors. Include, spare parts lists, exploded assembly views for pumps and equipment.
2. Submit fixture, trim, exploded view and replacement parts lists.
3. Submit replacement part numbers and availability, and nearest service depot location and telephone number.

C. Binders:
1. Furnish typewritten or printed index and tabbed dividers between principal categories.
2. Bind each manual in a hard-backed loose-leaf binder.

D. Imprint on cover:
1. Name of project.
2. Owner.
3. Location of project.
4. Architect.
5. Contractor.
6. Year of completion.

E. Imprint on backing:
1. Name of project.
2. Year of completion.

F. Submittals:
1. Preliminary Copies: Prior to scheduled completion of the project, submit two copies for review by the Architect.
2. Final Copies: After approval of the preliminary copies, submit three (3) finished copies to the Owner.

1.21 EQUIPMENT AND PIPE CLEANING

A. Clean interior and exterior of all equipment. Equipment shall be free of dirt, construction debris, corrosion, etc.

B. Adequate provisions shall be made during construction to eliminate dirt, debris or other material from entering and collecting inside of pipe and equipment. Any collection of material shall be thoroughly cleaned before equipment startup and if necessary again before owner occupancy.

C. Clean exterior of all exposed pipe and equipment.

1.22 RECORD DRAWINGS

A. Submit one CD or DVD with all drawings in PDF format.

B. Show location of equipment, location and size of piping. Locate all valves and similar equipment with tag or label identification. Indicate locations and elevations

of exterior pipe and utility connections. Maintain continuously updated drawings during progress of project.

C. Record actual locations of equipment, clean-outs, controlling devices, and all above grade, under-floor, and buried piping.

1.23 WARRANTIES AND CONTRACTOR'S GUARANTEE

A. All work, material and equipment shall be free of defect, complete and in perfect operating order at time of delivery to Owner.

B. Furnish one year warranty from date of substantial completion for all systems unless specifically noted otherwise.

C. Without cost to Owner, **correct all defects and failures discovered within one year from date of final acceptance**, except when in the opinion of the Architect a failure is due to neglect or carelessness of the Owner.

D. The guarantee of the Contractor is independent of shorter time limits by any manufacturer of equipment furnished. Submit with Operation and Maintenance Manual all guarantees that exceed one year (e.g.: water heaters).

E. Make all necessary balancing and control adjustments during first year of operation.

F. The presence of any inspector or observer during any construction does not relieve the Contractor from responsibility for defects discovered after completion of the work.

PART 2 NOT USED

PART 3 EXECUTION

3.1 DOCUMENTATION

A. Additional plan submittals to reviewing authority: If additional drawing submittals are required at any time during construction contractor shall submit drawings, review with authority, and pick up subsequent approved drawings. Engineer will revise and/or prepare drawings for submittal.

3.2 INSPECTION

A. Do not allow any work to be covered up or enclosed until inspected, tested and approved by the Architect and all authorities having jurisdiction over the work.

B. Should any work be enclosed or covered up before such inspection and test, Contractor shall at his own expense uncover work, and after it has been

inspected, tested and approved, make all repairs as necessary to restore all work disturbed by him to its original condition.

3.3 FIELD QUALITY CONTROL

A. Inspect installed fire stopping for compliance with specifications and submitted schedule.

B. Test domestic water piping system in accordance with applicable code and local authority having jurisdiction.

C. Test sanitary waste and vent piping system in accordance with applicable code and local authority having jurisdiction.

D. Test storm drainage piping system in accordance with applicable code and local authority having jurisdiction.

3.4 CLEANING

A. Clean adjacent surfaces of fire stopping materials.

B. Clean plumbing fixtures and equipment.

C. Use acceptable cleaning products per IAQ Management Plan.

3.5 PROTECTION OF FINISHED WORK

A. Protect adjacent surfaces from damage by material installation.

B. Do not permit use of plumbing fixtures before final acceptance.

END OF SECTION

SECTION 22 05 00

COMMON WORK RESULTS FOR PLUMBING

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. General Plumbing Valves.
2. Hangers and Supports.
3. Firestopping.
4. Access Panels
5. Tags and Identification.
6. Execution

1.2 GENERAL REQUIREMENTS

A. Comply with requirements and recommendations of Manufacturers Standardization Society of the Valve and Fittings Industry (MSS) Standards SP-58 and SP-69.

B. Comply with Federal "Reduction of Lead in Drinking Water Act" – 2011. Pipes, pipe fittings, plumbing fittings and fixtures shall be "Lead Free" meaning not more than a weighted average of 0.25% lead in wetted surfaces.

1.3 SCOPE

A. This section includes products, assemblies and methods applicable to more than one of the systems specified in the following sections of Division 22.

1.4 MATERIALS AND EQUIPMENT

A. Where two or more units of same class of equipment are required, use products of a single manufacturer. All equipment shall be new and free from damage.

B. Provide major equipment components with manufacturer's name, address, catalog number and capacity indicated on a nameplate, securely affixed in a conspicuous place.

C. Furnish standard and fabricated hangers and supports complete with necessary inserts, bolts, nuts, rods, washers and other accessories.

1.5 QUALITY ASSURANCE

A. Installed products shall have surface Burning Characteristics: 25/50 flame spread/smoke developed index when tested in accordance with ASTM E84.

B. Perform work in accordance with local jurisdiction’s requirements and AWS D1.1 for welding hanger and support attachments to building structure.

PART 2 PRODUCTS

2.1 GENERAL VALVE REQUIREMENTS

A. Bronze valves shall be made with dezincification-resistant materials. Bronze valves made with copper alloy (brass) containing more than 15 percent zinc are not permitted. Brass valves are not permitted.

B. Valve Pressure and Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.

C. Valve Sizes: Same as upstream piping unless otherwise indicated.

2.2 GATE VALVES

A. Manufacturers: NIBCO or equal by Apollo, Hammond, Milwaukee, Stockham or approved equal.

B. 4 inches and Smaller: Use ball valve or butterfly valve in lieu of gate valve.

2.3 BALL VALVES

A. Manufacturers: NIBCO or equal by Apollo, Hammond, Milwaukee, Stockham or approved equal.

B. 2 inches and Smaller: Lead-Free, NSF-61-8, UPC-IGC-157, MSS SP 110, 600 psi WOG, two piece silicon performance bronze body, bronze trim, bronze ball, full port, PTFE seats, blow-out proof stem, solder or threaded ends with union, lever handle. For insulated piping provide 2" extended handles of non-thermal conductive material. Nibco Model T/S-585-80-LF.

2.4 CHECK VALVES

A. Swing Check Valves:
   1. Manufacturers: NIBCO or equal by Apollo, Hammond, Milwaukee, Stockham or approved equal.
   2. 2 inches and Smaller: Lead-Free, NSF-61-8, MSS SP 80, 200 psi CWP, silicone performance bronze body and cap, bronze disc with PTFE seat, Y-pattern design, solder or threaded ends. Nibco Model T/S-413-Y-LF.

B. Spring Loaded Check Valves:
   1. Manufacturers: NIBCO or equal by Apollo, Hammond, Milwaukee, Stockham, Titan or approved equal.
   2. 2 inches and Smaller: Lead-Free, NSF-61-8, MSS SP 80, 250 psi CWP, silicone performance bronze body, in-line spring lift check, silent closing, PTFE disc, integral seat, solder or threaded ends. Nibco Model T/S-480-Y-LF.

2.5 PIPE HANGERS AND SUPPORTS

A. Provide hangers and supports with incompressible insulation inserts and shields for all piping to be insulated per 220700.
   1. Manufacturer: Pipe Shields, INC or approved equal.
   2. Material: Calcium Silicate or Uretherne per temperature application.
   3. Thickness: Insert thickness shall match required insulation thickness per 220700.

B. Plumbing Piping - DWV: Cast-iron or PVC
   1. Hangers for Pipe Sizes 1/2 to 1-1/2 inch: Carbon steel, adjustable swivel, split ring.
   2. Hangers for Pipe Sizes 2 inches and Larger: Carbon steel, adjustable, clevis.
   3. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.
   4. Wall Support for Pipe Sizes 3 inches and Smaller: Cast iron hook.
   5. Wall Support for Pipe Sizes 4 inches and Larger: Welded steel bracket and wrought steel clamp.
   6. Vertical Support: Steel riser clamp.
   7. Floor Support: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
   8. Copper Pipe Support: Copper-plated, carbon-steel adjustable, ring.

C. Plumbing Piping - Water: Copper
   1. Hangers for Pipe Sizes 1/2 to 1-1/2 inch: Carbon steel, adjustable swivel, split ring, with rigid insulation inserts.
   2. Hangers for Cold Pipe Sizes 2 inches and Larger: Carbon steel, adjustable, clevis, with rigid insulation inserts and saddle.
   3. Wall Support for Pipe Sizes 3 inches and Smaller: Cast iron hook.
   4. Vertical Support: Steel riser clamp.
   5. Floor Support for Cold Pipe: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
   6. Floor Support for Hot Pipe Sizes 4 inches and Smaller: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.
   7. Copper Pipe Support: Copper-plated, Carbon-steel ring.

D. Secondary Pipe Positioning and Supports:
   1. Makeshift, field devised methods of plumbing pipe support, such as with the use of scrap framing materials, are not allowed. Support and positioning of piping shall be by means of engineered methods that comply with IAPMO PS 42-96. Hubbard "HOLDRITE" support systems or approved equal.
   2. For vertical mid-span supports of piping 4” and under, use HOLDRITE Stout Brackets™ with HOLDRITE Stout Clamps or two-hole pipe clamps (MSS Type 26).
   3. For plenum applications use pipe supports that meet ASTM E-84 25/50 standards, such as the HOLDRITE Flame Fighter™ or approved equal.

2.6 HANGER ACCESSORIES

A. Hanger Rods: Mild steel threaded both ends, threaded on one end, or continuous threaded.

2.7 INSERTS

A. Malleable iron case of galvanized steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

2.8 ACCESS PANELS

A. Milcor or approved equal.

B. Include an allowance for a minimum of 16 access panels.

C. Architectural grade, 14 guage frame and door, painted steel or stainless steel based on application.

2.9 UNIONS AND FLANGES

A. Unions for Pipe 2 inches and Smaller:
1. Ferrous Piping: Class 150, 300 psi CWP, malleable iron, threaded.
2. Copper Piping: Class 150, 300 psi CWP, bronze unions.
3. Dielectric Connections: Union with galvanized or plated steel threaded end, copper solder end, water impervious isolation barrier.
4. PVC Piping: PVC.
5. CPVC Piping: CPVC.

2.10 FLEXIBLE PIPE CONNECTORS

A. Manufacturers: Metraflex, Mason or approved equal.

B. Victaulic Style flexible couplings may be used in lieu of flexible connectors for vibration isolation at equipment connections. Three (3) couplings, for each connector, shall be placed in close proximity to the source of vibration.

2.11 FLASHING

A. Metal Flashing: 26 gage galvanized steel.

B. Metal Counterflashing: 22 gage galvanized steel.

C. Lead Flashing:
1. Waterproofing: 5 lb./sq. ft sheet lead.
2. Soundproofing: 1 lb./sq. ft sheet lead.

D. Flexible Flashing: 47 mil thick sheet butyl; compatible with roofing.

E. Caps: Steel, 22 gage minimum; 16 gage at fire resistant elements.

2.12 SLEEVES

A. Sleeves for Pipes Through Non-fire Rated Floors: 18 gage galvanized steel.

B. Sleeves for Pipes Through Non-fire Rated Beams, Walls, Footings, and Potentially Wet Floors: Steel pipe or 18 gage galvanized steel.

C. Sealant: Acrylic

D. Size large enough to allow for movement due to expansion and to provide for continuous insulation or installation of fire sealant at fire-rated walls. Note that insulation is discontinuous at fire walls.

2.13 MECHANICAL SLEEVE SEALS

A. Manufacturers: Metraflex Metraseal, Thunderline Link-Seal or approved equal.

B. Product Description: Modular mechanical type, consisting of interlocking synthetic rubber links shaped to continuously fill annular space between object and sleeve, connected with bolts and pressure plates causing rubber sealing elements to expand when tightened, providing watertight seal and electrical insulation.

2.14 FORMED STEEL CHANNEL

A. Manufacturers: Allied Tube & Conduit, B-Line Systems, Unistrut or approved equal.

B. Product Description: Galvanized 12 gage steel with holes 1-1/2 inches on center.

2.15 FIRESTOPPING-APPLIED

A. Manufacturers: RectorSeal, Dow Corning, 3M Fire Protection or approved equal.

B. General:
1. Fire stopping materials shall conform to Flame (F) and Temperature (T) ratings as required by applicable building codes and tested by nationally accepted test agencies per ASTM E 814 or UL 1479 fire tests for through penetrations, and ASTM E 1966 or UL 2079 for construction joints, and UL 2307 for perimeter edge joints.
2. Fire stopping material shall be free of asbestos, PCBs, ethylene glycol, and lead.
3. Do not use any product containing solvents or that requires hazardous waste disposal.
4. Fire stopping shall be performed by a contractor trained or approved by firestop manufacturer.
5. Select products with rating not less than rating of wall or floor being penetrated.

C. Single Source Responsibility: Provide firestop systems for all conditions from a single supplier.

D. Product Description: Provide Latex caulk/sealant, Silicone caulk/sealant, Intumescent Wrap Strip, Firestop Putty, Firestop Collar or Intumescent Sleeve to meet each specific application and performance requirement.

E. Primer: Type recommended by firestopping manufacturer for specific substrate surfaces and suitable for required fire ratings.

F. Installation Accessories: Provide clips, collars, fasteners, temporary stops or dams, and other devices required to position and retain materials in place.
1. Forming/Damming Materials: Mineral fiberboard, backer rod or other type recommended by Manufacturer's tested system.

2.16 TAGS

A. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inches high.

B. Metal Tags: Brass, Aluminum or Stainless Steel with stamped letters; tag size minimum 1-1/2 inches diameter with finished edges. Plain English designations.

C. Information Tags: Clear plastic with printed "Danger," "Caution," or "Warning" and message; size 3-1/4 x 5-5/8 inches with grommet and self-locking nylon ties.

D. Tag Chart: Plain English designations so no chart or index is required.

2.17 PIPE MARKERS

A. Color and Lettering shall conform to ASME A13.1 and UPC. Specific examples are noted in the table below.

Service	Background Color	Letter Color	Legend
Domestic Cold Water	Green	White	DOMESTIC COLD WATER
Domestic Hot Water	Green	White	DOMESTIC HOT WATER
Waste	Black	White	SANITARY SEWER
Vent	Black	White	SANITARY VENT
Condensate Drain	Black	White	CONDENSATE
Storm Drainage	Black	White	STORM
Compressed Air	Blue	White	COMPRESSED AIR

B. Plastic Pipe Markers: Factory fabricated, flexible, semi-rigid plastic, preformed to fit around pipe or pipe covering. Larger sizes may have maximum sheet size with spring fastener.

C. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.

D. Underground Pipe Markers: Bright colored continuously printed plastic ribbon tape, minimum 6 inches wide by 4 mil thick, imprinted with service type in large letters, manufactured for direct burial service.

E. Underground Trace Wire: Magnetic detectable conductor, brightly colored plastic covering, imprinted with service type in large letters.

2.18 CEILING TACKS

A. Description: Steel with 3/4 inch diameter color-coded head.

B. Color code plumbing valves green.

2.19 LOCKOUT DEVICES

A. Lockout Hasps: Anodized aluminum hasp with erasable label surface; size minimum 7-1/4 x 3 inches.

B. Valve Lockout Devices: Nylon device preventing access to valve operator, accepting lock shackle.

PART 3 EXECUTION

3.1 EXISTING WORK

A. Provide access to existing piping and equipment and other installations remaining active and requiring access.

B. Extend existing piping installations using materials and methods compatible with existing installations.

3.2 SURFACE PREPARATION

A. Clean substrate surfaces of dirt, dust, grease, oil, loose material, or other matter affecting bond of firestopping material.

B. Remove incompatible materials affecting bond of adhesives or firestopping.

C. Install backing or damming materials to arrest liquid material leakage.

D. Obtain permission from Architect/Engineer before drilling or cutting structural members.

E. Degrease and clean surfaces to receive adhesive for identification materials.

3.3 INSTALLATION-CLEARANCE

A. Appliances and equipment shall be accessible for inspection, service, repair and replacement.

B. A minimum of 36” of clearance shall be provided in front of the control side of appliances and equipment. Provide additional space when required by NEC.

3.4 INSTALLATION – ACCESS PANELS

A. Furnish access panels for installation at all concealed equipment which requires service, maintenance or adjustment to include but not limited to equipment, valves, open drains, control valves and controls.

B. Provide location layout and required size for all access panels to general contractor. Layout shall be regular and consistent, maintain a uniform wall panel height of 24” centerline above finished floor, unless noted otherwise.

C. Provide fire rated access panels where installed in fire rated assembly.

D. Provide stainless steel access panels where installed in tile surfaces.

E. Furnish access panels to general contractor for installation.

F. Paint installed access panels to match wall or ceiling. Verify that panels are not painted shut.

3.5 INSTALLATION - VALVES

A. Install valves with stems upright or horizontal, not inverted.

B. Install brass male adapters each side of valves in copper piped system. Solder adapters to pipe.

C. Install 3/4 inch ball valves with cap for drains at main shut-off valves, low points of piping, bases of vertical risers, and at equipment.

D. Install valves with clearance for installation of insulation and allowing access.

E. Provide access panels where valves and fittings are not accessible.

F. Insulate valves according to application in Section 22 07 00.

G. For installation of valves in domestic water systems refer to Section 22 11 00.

3.6 VALVE APPLICATIONS

A. Install ball or butterfly valves for shut-off and to isolate equipment, part of systems, or vertical risers.

B. Install globe valves for throttling, bypass, or manual flow control services.

3.7 INSTALLATION - PIPE HANGERS AND SUPPORTS

A. Support horizontal piping as scheduled.

B. Install hangers with minimum 1/2 inch space between finished covering and adjacent work.

C. Place hangers within 12 inches of each horizontal elbow.

D. Use hangers with 1-1/2 inch minimum vertical adjustment.

E. Support vertical piping at every floor. Support vertical cast iron pipe at each floor at hub.

F. Where piping is parallel and at same elevation, provide multiple pipe or trapeze hangers.

G. Adjust hangers and supports as required to bring system to proper line and grade. Piping shall be plumb with floor and parallel/perpendicular to building structure.

H. Support riser piping independently of connected horizontal piping.

I. Provide copper plated hangers and supports for copper piping, or sheet lead packing between pipe and hanger.

J. Design hangers for pipe movement without disengagement of supported pipe.

K. Prime coat exposed steel hangers and supports. Hangers and supports located in crawl spaces, pipe shafts, and suspended ceiling spaces are not considered exposed.

L. Provide clearance in hangers and from structure and other equipment for installation of insulation. Insulated piping shall have insulation run continuous through hangers and supports with use of rigid inserts. Insulation shall be glued to both sides of insert at hangers and supports, no insulation gaps are allowed. Refer to Section 22 07 00.

M. Support of pipe, tubing and equipment shall be accomplished by means of engineered products, specific to each application. Makeshift, field devised methods shall not be allowed.

N. Support horizontal cast iron pipe adjacent to each hub, with 5 feet maximum spacing between hangers.

3.8 INSTALLATION-PIPING PROTECTION

A. Provide protective shield plates in concealed locations where piping, other than cast-iron or steel, is installed in studs, joists or rafters. Plates shall be 16 gage steel and cover the pipe area plus 2”. Shields may be omitted if piping is more than 1-1/2” from nearest edge of structural member.

B. Prevent contact between dissimilar metals, such as copper tubing and steel, by use of copper-plated, plastic coated, or flexible materials. All supports which contact copper tubing shall be copper plated.

3.9 INSTALLATION - FLASHING

A. Provide flexible flashing and metal counterflashing where piping penetrates weather or waterproofed walls, floors, and roofs.

B. Provide acoustical lead flashing around pipes penetrating equipment rooms for sound control.

C. Flash vent and soil pipes projecting 3 inches minimum above finished roof surface with lead worked 1 inch minimum into hub, 8 inches minimum clear on sides with 24 x 24 inches sheet size. For pipes through outside walls, turn flanges back into wall and caulk, metal counter-flash, and seal.

D. Flash floor drains in floors with topping over finished areas with lead, 10 inches clear on sides with minimum 36 x 36 inch sheet size. Fasten flashing to drain clamp device.

E. Seal drains watertight to adjacent materials.

F. Adjust storm collars tight to pipe with bolts; caulk around top edge. Use storm collars above roof jacks. Screw vertical flange section to face of curb.

3.10 INSTALLATION - SLEEVES

A. Exterior watertight entries: Seal with mechanical sleeve seals.

B. Set sleeves in position in forms. Provide reinforcing around sleeves.

C. Size sleeves large enough to allow for movement due to expansion and contraction. Provide for continuous insulation wrapping.

D. Extend sleeves through floors 1 inch above finished floor level. Caulk sleeves.

E. Where piping penetrates floor, ceiling, or wall, close off space between pipe and adjacent work with insulation and caulk or fireproof airtight. Provide close fitting metal collar or escutcheon covers at both sides of penetration.

3.11 INSTALLATION – FIRESTOPPING AND SEALS AT PARTITIONS

A. Install material at fire rated construction perimeters and openings containing penetrating sleeves, piping and other items requiring firestopping.

B. Apply primer where recommended by manufacturer for type of firestopping material and substrate involved, and as required for compliance with required fire ratings.

C. Apply firestopping material in sufficient thickness to achieve required fire and smoke rating and to uniform density and texture. Remove dam material after firestopping material has cured.

D. Place foamed material in layers to ensure homogenous density, filling cavities and spaces. Place sealant to completely seal junctions with adjacent dissimilar materials.

E. Place intumescent coating in sufficient coats to achieve rating required.

F. Clean adjacent surfaces of firestopping materials.

G. Fire Rated Surface:
   1. Seal opening at floor, wall, partition, ceiling, and/or roof as follows:
      a. Install sleeve through opening and extending beyond minimum of 1 inch on both sides of building element.
      b. Size sleeve allowing minimum of 1 inch void between sleeve and building element.
      c. Pack void with backing material.
      d. Seal ends of sleeve with UL listed fire resistive silicone compound to meet fire rating of structure penetrated.

H. Non-Rated Surfaces:
   1. Seal opening through non-fire rated wall, partition, floor, ceiling, and/or roof opening as follows:
      a. Install sleeve through opening and extending beyond minimum of 1 inch on both sides of building element.
      b. Size sleeve allowing minimum of 1 inch void between sleeve and building element.
   2. Install escutcheons where piping penetrates non-fire rated surfaces in occupied spaces.
   3. Exterior wall openings below grade: Assemble rubber links of mechanical sealing device to size of piping and tighten in place, in accordance with manufacturer's instructions.
   4. Interior partitions: Seal pipe penetrations air tight. Apply sealant to both sides of penetration to completely fill annular space between sleeve and conduit.

3.12 INSTALLATION - IDENTIFICATION

A. Install identifying devices after completion of coverings and painting.

B. Install plastic nameplates with corrosive-resistant mechanical fasteners, or adhesive.

C. Install labels with sufficient adhesive for permanent adhesion and seal with clear lacquer. For unfinished canvas covering, apply paint primer before applying labels.

D. Nameplates: Identify plumbing equipment (water heaters, pumps, heat transfer equipment, tanks, and water treatment devices) with plastic nameplates.
   1. Identify in-line pumps and other small devices with name tags.
   2. Identify control panels and major control components outside panels with plastic nameplates.
   3. Identity description should be as numbered on drawings or plain English description. i.e. “WH-1” or “Rain Water Storage Tank”.
   4. Label automatic controls, instruments, and relays. Key to control schematic.
   5. Label wall controls and switches with associated equipment designation and control function, i.e. “DCP, Timer”.

E. Valve Tags: Identify valves in main and branch piping with tags.
   1. Do not provide numbered tags.
   2. Provide tags with plain English description of service and function. i.e. “Domestic Hot Water, Kitchen”

F. Pipe Labels: Identify piping, concealed or exposed, with plastic tape pipe markers.
   1. Identify service, flow direction, and pressure.
   2. Install in clear view and align with axis of piping.
   3. Locate identification on straight runs including risers and drops with spacing not to exceed 20 feet.
   4. Locate adjacent to each valve and tee, at each side of penetration of structure or enclosure, and at each obstruction.

G. Provide ceiling tacks to locate valves above T-bar type panel ceilings. Locate in corner of panel closest to equipment.

H. Equipment and Valve Tag Index: Plain English designations so no chart or index is required.

3.13 PROTECTION OF FINISHED WORK

A. Protect adjacent surfaces from damage by firestoppping material installation.

3.14 SCHEDULES

A. Pipe Hanger Spacing

PIPE MATERIAL	MAXIMUM HANGER SPACING (Feet)	HANGER ROD DIAMETER (Inches)
Cast Iron (All Sizes)	5	3/8
Cast Iron (All Sizes) with 10 foot length of pipe	10	3/8
CPVC, 1 inch and smaller	3	1/2
CPVC, 1-1/4 inches and larger	4	1/2

Copper Tube, 1-1/4 inches and smaller	6	1/2
Copper Tube, 1-1/2 inches and larger	10	1/2
PVC (All Sizes)	4	3/8
Steel, 3 inches and smaller	6	1/2
Steel, 4 inches and larger	12	3/8

B. Pipe Isolation Schedule:

Pipe Size Inch	Isolated Distance from Equipment
1	120 diameters
2	90 diameters
3	80 diameters
4	75 diameters

END OF SECTION

SECTION 22 07 00

PLUMBING INSULATION

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Piping system insulation.
2. Pipe insulation jackets.
3. Insulation accessories including vapor retarders and accessories.

1.2 QUALITY ASSURANCE

A. Provide insulation tested for maximum flame spread index of 25 and maximum smoke developed index of not exceeding 50 in accordance with ASTM E84.

B. All systems components subject to heat loss or gain, such as, piping, valves etc. shall be insulated to conform with the Washington State Energy Code (as a minimum).

1.3 IDENTIFICATION

A. Insulation shall bear a manufacturer's mark indicating the product R-value or K-value and thickness. This mark shall be visible after installation and shall be repeated at an interval of no more than 10 feet.

PART 2 PRODUCTS

2.1 GLASS FIBER, RIGID

A. Manufacturers: Johns Manville Micro-Lok AP-T Plus or equal by Owens-Corning, Knauf or approved equal.

B. Insulation: Rigid, noncombustible. ASTM C547.
1. 'K' factor: 0.23 at 75 degrees F.
2. Fiberglass or Earthwool with ECOSE
3. Maximum Service Temperature: 850 degrees F.
4. Maximum Moisture Absorption: 0.2 percent by volume.
5. Density: 3.0 lb/cu ft.

C. Vapor Retarder Jacket: ASJ+ or Type I, reinforced facing, paintable. Longitudinal acrylic adhesive closure system with factory supplied butt strips. ASTM C1136.

D. Rigid clamp/hanger insert: Preformed, incompressible (Calcium Silicate or similar), matching pipe size and insulation thickness.

2.2 GLASS FIBER, BLANKET

A. Manufacturers: Johns Manville Micro-Flex or equal by Owens-Corning, Knauf or approved equal.

B. Insulation: Semi-rigid, shot-free, continuous fiber, noncombustible. ASTM C1393.
1. 'K' factor: 0.24 at 75 degrees F.
2. Maximum Service Temperature: 850 degrees F.
3. Maximum Moisture Absorption: 0.2 percent by volume.
4. Density: 2.5 lb/cu ft.

C. Vapor Retarder Jacket: Type I, reinforced facing, will accept paint. Seal with pressure sensitive tape. ASTM C1136.

2.3 POLYOLEFIN INSULATION

A. Manufacturers: IMCOA or similar.

B. Polyolefin or Polyethylene pipe insulation is **NOT ACCEPTABLE** for any application.

2.4 PIPE INSULATION AND EQUIPMENT JACKETS

A. PVC Plastic Pipe Jacket:
1. Product Description: One piece molded type fitting covers and sheet material, off-white color. ASTM D1784.
2. Thickness: 15 mil indoor, 30 mil outdoor.
3. Connections: Brush on welding adhesive.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify piping and equipment has been tested before applying insulation materials.

B. Verify surfaces are clean and dry, with foreign material removed.

3.2 INSTALLATION

A. Apply insulation when building is thoroughly dry to prevent shrinkage.

B. Exposed Piping: Locate insulation and cover seams in least visible locations.

C. Insulate entire piping system including fittings, valves, unions, flanges, strainers, flexible connections, pump fittings, connections to equipment and expansion joints. Use canvas jackets for valves and other irregular shapes.

D. Piping Inserts and Shields:

1. Insulation shall be continuous through supports and hangers with incompressible inserts and shields. Do not directly clamp/support pipe scheduled to be insulated.
2. Shields: Galvanized steel saddle between pipe clevis hangers or pipe rollers and insulation. Minimum 6 inches long, of contour matching adjoining insulation; may be factory fabricated.
3. Inserts: Between pipe clamps, hangers or rollers and piping.
4. Insert material: Compression resistant insulating material suitable for insulation type and planned temperature range and service.
5. Glue insulation to both sides of insert.
6. Shields without inserts may be used at clevis hangers on refrigerant piping 5/8” and smaller with continuous insulation.

E. Continue insulation through penetrations of building assemblies or portions of assemblies having fire resistance rating of one hour or less. Provide intumescent firestopping when continuing insulation through assembly. Finish at supports, protrusions, and interruptions.

F. Heat Traced Piping: Insulate fittings, joints, and valves with insulation of like material, thickness, and finish as adjoining pipe. Size insulation large enough to enclose pipe and heat tracer.

G. Pipe Exposed in Mechanical Equipment Rooms or Finished Spaces: Finish with PVC jacket and fitting covers.

H. Apply insulation close to equipment by grooving, scoring, and beveling insulation. Fasten insulation to equipment with studs, pins, clips, adhesive, wires, or bands.

I. Finish insulation at supports, protrusions, and interruptions.

3.3 SCHEDULES

A. Piping: Provide on piping as listed below.

		PIPE SIZE			
Service	**Insulation Type**	**<1”**	**1" to 1-1/4”**	**1-1/2" to 4"**	**4" to 8”**
Domestic Cold Water	Glass Fiber RIGID	1/2"	1/2"	1/2"	1/2"
Domestic Hot Water	Glass Fiber RIGID	1"	1"	1-1/2"	1-1/2"
Domestic water H/C/R/T outside conditioned space	Glass Fiber RIGID	1-1/2”	1-1/2”	2”	2”
Condensate Drains	RIGID / FOAM	1/2"	1/2"	1/2"	1/2"
Roof Drain & Overflow Bowls in conditioned area	Glass Fiber RIGID	1/2"	1/2"	1/2"	1/2"

END OF SECTION

SECTION 22 11 00

FACILITY WATER DISTRIBUTION

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Domestic water piping.
2. Piping Accessories.
3. Reduce pressure backflow assembly.
4. Pressure balanced mixing valves.

1.2 SCOPE

A. This section includes hot and cold water supply, equipment and accessories.

B. This section includes domestic hot and/or cold water consumption metering with data collection and billing software.

1.3 GENERAL REQUIREMENTS

A. Comply with Federal "Reduction of Lead in Drinking Water Act" – 2011. Pipes, pipe fittings, plumbing fittings and fixtures shall be "Lead Free" meaning not more than a weighted average of 0.25% lead in wetted surfaces.

1.4 QUALITY ASSURANCE

A. The mechanical press fitting manufacturer’s factory trained representative shall provide on-site training for contractor’s field personnel in the use of press fittings and crimping tools. The representative shall periodically visit the jobsite and review installation. (A distributor’s representative is not considered qualified to conduct the training or jobsite visit(s).)

PART 2 PRODUCTS

2.1 DOMESTIC WATER PIPING, ABOVE GRADE

A. Copper Tubing: Type L hard drawn seamless. ASTM B88.
1. Fittings:
a. Wrought copper and bronze. ASME B16.22, ASTM B75.
b. Copper press with EPDM O-ring, ASME B16.22, 200 psi.
2. Joints:
a. Solder, lead free, 95-5 tin-antimony, or tin and silver. ASTM B32.
b. Press connection, Viega ProPress or approved equal.

2.2 STRAINERS

A. Manufacturers: Apollo/Conbraco, Metraflex, Titan, Nibco or approved equal.

B. 4 inch and Smaller: Threaded or Solder, 400 PSI CWP, lead-free bronze body, Y-pattern with 20 mesh stainless steel perforated screen. Apollo 59LF.

2.3 REDUCED PRESSURE BACKFLOW PREVENTERS (RPBA)

A. Manufacturers: Watts or equal by Apollo/Conbraco, Wilkens or approved equal. Must be listed as acceptable by the State of Washington Cross Connection Manual.

B. 2 inches and Smaller: Lead-Free. Comply with ASSE 1013. Cast copper silicone body with internal pressure differential relief valve located between two positive seating captured spring check valves, inlet Y-strainer, inlet and outlet shutoff ball valves, ball valve test cocks, replaceable polymer seats and silicone seat discs, air gap drain fitting, 175 psi working pressure, 33-180 F operating temperature range. Watts model LF919.

2.4 WATER HAMMER ARRESTORS

A. Manufacturers: Wade, PPP or approved equal.

B. ASSE 1010; stainless steel or copper construction, pre-charged, bellows or piston type sized in accordance with PDI WH-201.

2.5 ELECTRIC TEMPERATURE MAINTENANCE TAPE (Hot Water)

A. Manufacturers: Raychem HWAT or approved equal.

B. General: Provide a complete UL listed system of heating cables, components and control for maintaining water temperature in hot water or tempered water piping.

C. Cable: Self-regulating cable with nickel-copper bus wires embedded in conductive polymer core with dielectric polyolefin jacket, braided tinned copper ground and outer jacket of polyolefin. Cable shall vary power output in response to temperature with a self-regulating factor of at least 90%.

D. Components: Control enclosures shall be NEMA 4X rated. Connection system shall not require stripping of wires.

E. Controller: Adjustable temperature between 105 F and 140 F.

F. Installation:
1. Apply "Electric Traced" labels to outside of insulated pipe.
2. Attached cable to metal pipe with glass cloth tape and plastic pipe with aluminum tape.
3. Adjust pipe insulation size to accommodate maintenance tape.
4. Follow manufacturer's installation instructions.

2.6 TEMPERING VALVE (EMERGENCY)

A. Manufacturers: Haws, Lawler, Powers or approved equal.

B. General: Prepackaged, fully engineered and tested system for providing tempered water to emergency showers and/or eyewashes. Mixing valve to close on cold water failure and bypass cold water on hot water failure. Haws TWBS.EWE, TWBS.SHE

C. Construction: NSF 61 Lead-Free brass

D. Assembly: Valve and piping assembly with wall bracket, thermostatic mixing valve, high temperature limit valve, bypass valve, outlet temperature gauge with stainless steel stem, pipe unions. Certified to ASSE 1071 standard.

E. Accessories:
1. Cabinet

2.7 TEMPERING VALVE (PUBLIC LAV)

A. Manufacturers: Symmons, Leonard, Powers or approved equal.

B. General: Lead-Free brass and bronze body with brass and stainless steel flow control components with check stops, vandal resistant lockable handle, rough bronze finish. Certified to ASSE 1070 standard.

C. Accessories:
1. Cabinet

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs. Bevel or groove plain end ferrous pipe.

B. Remove scale and dirt, on inside and outside, before assembly.

C. Prepare piping connections to equipment with groove couplings, flanges or unions.

D. Keep open ends of pipe free from scale and dirt. Protect open ends with temporary plugs or caps.

3.2 INSTALLATION - ABOVE GROUND PIPING

A. Route piping in orderly manner and maintain gradient. Route parallel and perpendicular to walls.

B. Install piping to maintain headroom without interfering with use of space or taking more space than necessary.

C. Group piping whenever practical at common elevations.

D. Install piping on interior side of building insulation.

E. Sleeve pipe passing through partitions, walls and floors.

F. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

G. Protection: Where piping, other than cast iron or steel, is installed in a concealed location through holes or notches in framing (i.e. studs, joists, rafters, etc.), less than 1-1/2 from framing edge, provide shield plates. Shield plates shall be 16 gauge steel and cover the piping area within framing plus 2” on each side along framing.

H. Provide clearance in hangers and from structure and other equipment for installation of insulation and access to valves and fittings. Refer to Section 22 07 00.

I. Provide access panel where valves and fittings are not accessible.

J. Install non-conducting dielectric connections wherever jointing dissimilar metals.

K. Slope piping and arrange systems to drain at low points. Provide hose bibb if low point is not at a plumbing fixture.

L. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the Work, and isolating parts of completed system.

M. Insulate piping. Refer to Section 22 07 00.

N. Install pipe identification in accordance with Section 22 05 00.

3.3 INSTALLATION - DOMESTIC WATER PIPING SYSTEMS

A. Install domestic water piping system in accordance with ASME B31.9.

B. Grade piping to drain at low points. Provide hose bibb if low point is not at plumbing fixture.

C. Install water piping on interior side of building insulation. Provide heat tape for all piping in unheated areas.

D. Install water hammer arrestors on hot and cold water of each fixture group (e.g.: one arrestor may serve each service to a toilet). Select unit sizes and install in accord with PDI Standard WH-201.

3.4 VALVES

A. Use ball valves for up to 4” piping. Gate valves are not approved for use up to 4” piping. Gate valves are for 6” piping and larger only.

B. Gate valves which are part of a valve assembly are acceptable.

3.5 FIELD QUALITY CONTROL

A. Test domestic water piping system at 100 psig minimum for a period of not less than 4 hours.

3.6 CLEANING

A. Flush system with water for minimum of 60 minutes to remove all dirt and foreign materials. Use minimum of 80 psi flushing pressure.

B. Inject disinfectant, free chlorine in liquid, powder, tablet or gas form, throughout system to obtain residual from 50 to 80 mg/L.

C. Bleed water from outlets to obtain distribution and test for disinfectant residual at a minimum of 15 percent of outlets.

D. Maintain disinfectant in system for 24 hours.

E. Flush disinfectant from system until residual concentration is equal to incoming water or 1.0 mg/L.

END OF SECTION

SECTION 22 13 00

FACILITY SANITARY SEWERAGE

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Sanitary sewer piping, buried within 5 feet of building.
2. Sanitary sewer piping, above grade.
3. Condensate drains
4. Floor drains.
5. Trench drains.
6. Cleanouts.

PART 2 PRODUCTS

2.1 SANITARY SEWER PIPING, BURIED WITHIN 5 FEET OF BUILDING

A. Cast Iron Pipe & Fittings: ASTM A888, CISPI 301, hub-less. Made in USA by AB&I, Charlotte or Tyler marked with collective trademark of the Cast Iron Soil Pipe Institute (CISPI) and listed by NSF International.
1. Fittings: Long pattern cast iron.
2. Joints: Neoprene gasket ASTM C-564, all type 304 stainless steel clamp and shield assemblies, 80 in/lbs worm drive. FM-1680, Class 1, CISPI 310 and certified by NSF international. Minimum 4 clamps up to 4”, 6 clamps for 5” and larger. Husky SD 4000, Mission Heavy Weight, Clamp-All or approved equal.

B. PVC Pipe: Schedule 40 solid wall PVC, bell and spigot solvent sealed ends. NSF Standard 14, ASTM D1785, ASTM D1784.
1. Fittings: Schedule 40, PVC, ASTM D2665.
2. Joints: Solvent weld with ASTM D2564 solvent cement.

2.2 SANITARY SEWER PIPING, ABOVE GRADE

A. Cast Iron Pipe & Fittings: ASTM A888, CISPI 301, hub-less. Made in USA by AB&I, Charlotte or Tyler marked with collective trademark of the Cast Iron Soil Pipe Institute (CISPI) and listed by NSF International.
1. Fittings: Long pattern cast iron.
2. Joints: Neoprene gasket ASTM C-564, all type 304 stainless steel clamp and shield assemblies, 80 in/lbs worm drive. FM-1680, Class 1. Husky, Mission, Clamp-All or approved equal.

B. Copper Tube (Use only for short piping sections where dimensional constraints require thin wall pipe): ASTM B306 DWV.
1. Fittings: Long Pattern, ASME B16.23, cast bronze, or ASME B16.29, wrought copper.

2. Joints: Solder, lead free, ASTM B32, 95-5 tin-antimony, or tin and silver.

C. Steel Pipe (water closet connections only): Schedule 40, galvanized. ASTM A53.
1. Fittings: Cast Iron, ASME B16.4, threaded fittings.
2. Joints: Threaded.

D. **[VENT ONLY]** PVC Pipe: Schedule 40 solid wall PVC, bell and spigot solvent sealed ends (If approved by local authorities). NSF Standard 14, ASTM D1785, ASTM D1784. **Not for use in air plenum.**
1. Fittings: Schedule 40, PVC, ASTM D2665.
2. Joints: Solvent weld with ASTM D2564 solvent cement.

2.3 EQUIPMENT DRAINS (CONDENSATE)

A. Copper Tubing: Type L, hard drawn. ASTM B88.
1. Fittings: ASME B16.18, cast brass, or ASME B16.22 solder wrought copper.
2. Joints: Solder, lead free, ASTM B32, 95-5 tin-antimony, or tin and silver, with melting range 430 to 535 degrees F.

B. CPVC Pipe: Schedule 40. ASTM D2846. **Not for use in air plenum.**
1. Fittings: Schedule 40 CPVC. ASTM D2846.
2. Joints: Solvent weld with ASTM F493 solvent cement. ASTM D2846.

2.4 FLOOR DRAINS

A. Manufacturers: Zurn, Josam, J.R. Smith, Wade or approved equal.

B. General Service: Cast iron body, membrane clamp, adjustable collar, polished nickel bronze strainer, trap primer connection. Provide funnel where scheduled.

2.5 TRENCH DRAIN

A. Manufacturers: Zurn, J.R. Smith or approved equal.

B. 12” wide throat trench drain system. HDPE, extra heavy duty frame with anchor studs, ¾ ductile iron slotted grate – Class C. Bottom dome strainer.

2.6 CLEANOUTS

A. Manufacturers: Zurn, J.R. Smith, Josam, Wade or approved equal.

B. Exterior or interior vehicle areas: Heavy-Duty round coated cast iron body and cover with bronze plug.

C. Interior Finished Floor Areas: Type of ferrule, top and cover as required for the type of floor construction, finish surface and traffic conditions. Cleanout construction material to match waste piping with anchor flange, threaded top assembly, and round scored cover with gasket in service areas and round depressed cover with gasket to accept floor finish in finished floor areas. For

carpet provide marker. For cast iron construction provide bronze gasket threaded plug.

D. Interior Finished Wall Areas: Cleanout construction material to match waste piping, line type with round gasket threaded plug, and round stainless steel access cover secured with machine screw. For cast iron construction provide bronze gasket threaded plug.

E. Interior Unfinished Accessible Areas: Threaded type. Provide bolted stack cleanouts on vertical waste stacks.

2.7 FLASHING AND COUNTERFLASHING

A. 3lb. lead soldered joints and seams, 24 x 24 base pad and counterflashed into pipe.

2.8 TRAP SEAL MAINTENANCE DEVICE

A. Manufacturers: Sure-Seal, Jay R Smith or approved equal.

B. Inline floor drain trap sealer, commercial grade, neoprene rubber diaphragm and rubber sealing gaskets.

2.9 AIR GAP FITTING

A. Manufacturers: Zurn Z-1025 or equal by J.R. Smith or approved equal.

B. Construction: Inline, fixed air gap, coated cast iron.

PART 3 EXECUTION

3.1 PREPARATION

A. Remove scale and dirt, on inside and outside, before assembly.

B. Prepare piping connections to equipment with flanges or unions.

C. Verify and provide required extensions, clamps and drain styles to match floor construction and finish.

3.2 INSTALLATION

A. Coordinate location of floor drains in mechanical spaces with mechanical contractor equipment layout.

B. Protect floor drain strainer during construction.

C. TRAPS: Install trap seal maintenance devices.

D. Align square floor drains with floor tiles or parallel with walls.

3.3 CONDENSATE PIPING

A. Provide condensate piping for air-conditioning and high-efficiency gas fired equipment. Coordinate quantity required with mechanical contractor. Provide minimum 3” deep p-trap at equipment.

B. Determine best routing to nearest indirect waste using minimum 3/4” piping with minimum 1/8” per foot slope. Acceptable indirect waste locations are service sink, laundry sink, floor drain or air gap fitting into waste pipe. Provide open drain box or access panel for air gap fitting as approved by local authority. Discharge onto roof or at grade is acceptable if allowed by local code, provide splash block.

C. If proper slope cannot be achieved advise Mechanical Contractor to provide condensate pump.

3.4 INSTALLATION - BURIED PIPING SYSTEMS

A. Verify connection to existing piping system size, location, and invert are as indicated on Drawings.

B. Provide connections to site mains as indicated on drawings.

C. Grade piping at 1/4” per foot where possible, but in no case less than 1/8” per foot. Install all main vertical soil and waste stacks with provisions for expansion and extend full size to roof line as vents.

D. Backfill trenching with pea-gravel if available at site for other purposes. If pea-gravel is unavailable, native soil may be used for backfill if all the following conditions are met.
   1. All broken concrete and sharp stones (+1” dia.) to be removed from backfill soil.
   2. All large stones (3’ dia. or bigger) to be removed from backfill soil.
   3. Piping shall be bedded on min. 2” thickness of replaced “rock free” soil and then checked for grade.

E. Establish minimum separation from other services piping in accordance with Code.

F. Provide piping layout to satisfy the UPC requirements for suds relief.

G. Route pipe in straight line.

H. Install pipe to allow for expansion and contraction without stressing pipe or joints.

I. Install plastic ribbon tape continuous over top of pipe.

J. Install trace wire continuous over top of pipe.

3.5 INSTALLATION - ABOVE GROUND PIPING

A. Route piping in orderly manner and maintain gradient at 1/4” per foot where possible, but in no case less than 1/8” per foot. Route parallel and perpendicular to walls.

B. Install piping to maintain headroom without interfering with use of space or taking more space than necessary.

C. Group piping whenever practical at common elevations.

D. Install piping on interior side of building insulation.

E. Sleeve pipe passing through partitions, walls and floors.

F. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

G. Protection: Where piping, other than cast iron or steel, is installed in a concealed location through holes or notches in framing (i.e. studs, joists, rafters, etc.), less than 1-1/2 from framing edge, provide shield plates. Shield plates shall be 16 gauge steel and cover the piping area within framing plus 2” on each side along framing.

H. Provide clearance in hangers and from structure and other equipment for installation of insulation and access to valves and fittings.

I. Establish invert elevations, slopes for drainage to 1/4 inch per foot minimum. Provide 1/8 inch per foot only where necessary and allowed by local jurisdiction. Maintain gradients.

J. Provide piping layout to satisfy the UPC requirements for suds relief.

K. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the Work, and isolating parts of completed system.

L. Install piping penetrating roofed areas to maintain integrity of roof assembly.

M. Install pipe identification in accordance with Section 22 05 00.

3.6 INSTALLATION - SANITARY WASTE AND VENT SYSTEMS

A. Install sanitary waste and vent piping systems in accordance with ASME B31.9 and local plumbing code.

B. Support cast iron drainage piping at every joint.

C. Flash and counterflash. Install vents passing through roof with roof flashing and counterflashing assemblies. 3lb. lead soldered joints and seams, 24 x 24 base pad and counterflashed into pipe.

D. Provide piping layout to satisfy the UPC requirements for suds relief.

E. Provide cleanouts every 50 feet and install at all locations required by code and to permit cleaning of all waste piping. Provide cleanouts full size of pipe, but no larger than 4". Coordinate with Architect when cleanouts are located in finished rooms. Install cleanout threads with graphite. Locate cleanouts to clear cabinet work and to be easily accessible.

3.7 FIELD QUALITY CONTROL

A. Obtain written approval of local Plumbing Authority prior to covering or concealing any work.

B. Test sanitary waste and vent piping system to hydrostatic test of 10 feet head of water.

END OF SECTION

SECTION 22 14 00

FACILITY STORM DRAINAGE

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Storm water piping, above grade.
2. Roof drains.
3. Cleanouts.

PART 2 PRODUCTS

2.1 STORM WATER PIPING, ABOVE GRADE

A. Cast Iron Pipe: ASTM A888, CISPI 301, hub-less. Made in USA by AB&I, Charlotte or Tyler marked with collective trademark of the Cast Iron Soil Pipe Institute (CISPI) and listed by NSF International.
1. Fittings: Long pattern cast iron.
2. Joints: Neoprene gasket ASTM C-564, all type 304 stainless steel clamp and shield assemblies, 80 in/lbs worm drive. FM-1680, Class 1. Husky, Mission, Clamp-All or approved equal.

2.2 ROOF DRAINS

A. Manufacturers: Zurn, Josam, J.R. Smith, Wade or approved equal.

B. Coated cast iron body with aluminum dome, membrane flange and clamp, underdeck clamp, roof sump receiver, waterproofing flange, adjustable extension sleeve for roof insulation. On overflow drains provide 2” internal water dam.

2.3 CLEANOUTS

A. Manufacturers: Zurn, J.R. Smith, Josam, Wade or approved equal.

B. Exterior Surfaced Areas: Round cast nickel bronze access frame with bronze gasket threaded plug and non-skid cover.

C. Exterior Unsurfaced Areas: Line type with lacquered cast iron body and bronze gasket threaded plug.

PART 3 EXECUTION

3.1 PREPARATION

A. Verify and provide required extensions, clamps and drain styles to match deck or roof construction and finish.

3.2 INSTALLATION - ABOVE GROUND PIPING

A. Route piping in orderly manner and maintain gradient. Route parallel and perpendicular to walls.

B. Install piping to maintain headroom without interfering with use of space or taking more space than necessary.

C. Group piping whenever practical at common elevations.

D. Sleeve pipe passing through partitions, walls and floors.

E. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

F. Protection: Where piping, other than cast iron or steel, is installed in a concealed location through holes or notches in framing (i.e. studs, joists, rafters, etc.), less than 1-1/2 from framing edge, provide shield plates. Shield plates shall be 16 gauge steel and cover the piping area within framing plus 2” on each side along framing.

G. Provide clearance in hangers and from structure and other equipment for installation of insulation and access to valves and fittings.

H. Establish invert elevations, slopes for drainage to 1/4 inch per foot minimum. Provide 1/8 inch per foot only where necessary and allowed by local jurisdiction. Maintain gradients.

I. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the Work, and isolating parts of completed system.

J. Install piping penetrating roofed areas to maintain integrity of roof assembly.

K. Insulate piping. Refer to Section 22 07 00.

L. Install pipe identification in accordance with Section 22 05 00.

3.3 INSTALLATION - STORM DRAINAGE PIPING SYSTEMS

A. Install storm drainage piping systems in accordance with ASME B31.9 and local plumbing code.

B. Support cast iron drainage piping at every joint.

C. Provide cleanouts every 50 feet and install at all locations required by code and to permit cleaning of all waste piping. Provide cleanouts full size of pipe, but no larger that 4”. Coordinate with Architect when cleanouts are located in finished rooms. Install cleanout threads with graphite. Locate cleanouts to clear cabinet work and to be easily accessible.

3.4 FIELD QUALITY CONTROL

A. Obtain written approval of local Plumbing Authority prior to covering or concealing any work.

B. Test storm piping system to hydrostatic test of 10 feet head of water.

END OF SECTION

SECTION 22 15 00

GENERAL SERVICE COMPRESSED AIR SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Compressed air piping and accessories.
2. Compressed air outlets.
3. Air pressure reducing valve.
4. Pressure regulators.
5. Hose connectors.

1.2 SCOPE

A. Furnish and install piping and accessories for a complete compressed air system.

PART 2 PRODUCTS

2.1 COMPRESSED AIR PIPING

A. Steel Pipe: ASTM A53, Schedule 40 black, seamless. Manufactured in the USA.
1. Fittings: ASME B16.3, malleable iron Class 150, or ASTM A234, forged steel welding type, Class 150.
2. Joints: Threaded for pipe 2 inch and smaller; welded for pipe 2-1/2 inches and larger.

2.2 UNIONS AND FLANGES

A. Unions for Pipe 2 inches and Smaller:
1. Ferrous Piping: Class 150, 300 psi CWP, malleable iron, threaded.
2. Copper Piping: Class 150, 300 psi CWP, bronze unions with brazed joints.
3. Dielectric Connections: Union with galvanized or plated steel threaded end, copper solder end, water impervious isolation barrier.

2.3 BALL VALVES

A. Manufacturers: NIBCO or equal by Apollo, Hammond, Milwaukee, Stockham or approved equal.

B. 2 inches and Smaller: MSS SP 110, 600 psi CWP, bronze, two piece body, type 316 stainless steel ball, full port, Teflon (TFE) seats, blow-out proof stem, solder or threaded ends with union, lever handle. Nibco Model 585-70-66.

2.4 COMPRESSED AIR OUTLETS

A. Manufacturers: Lincoln #815 or approved equal.

B. Compressed Air Outlets: Quick Connector: Brass, snap on connector with self closing valve.

2.5 HOSE REELS

A. Manufacturers: Graco XD, Reelcraft or approved equal.

B. Heavy duty type, steel construction, dual pedestal frame, powder coat finish, spring retractable, ½" inlet, ½" outlet, 300 psi rated.

C. Hose: ½", 250 psi rated.

D. Accessories:
1. Mounting bracket and stainless steel hardware.
2. Hose ball stop kit.
3. Hose inlet kit.

2.6 PRESSURE REGULATORS

A. Manufacturers: Parker, Norgren or approved equal.

B. Pressure Regulators: Diaphragm \ Pilot operated, bronze body, direct acting, spring loaded, manual pressure setting adjustment, rated for 250 psig inlet pressure.

C. Pressure Regulators: Aluminum alloy or plastic body, diaphragm operated, direct acting, spring loaded, manual pressure setting adjustment, and rated for 250 psig inlet pressure.

2.7 PRESSURE GAUGE

A. Manufacturers: Marsh, Trerice, Weiss or approved equal.

B. Gauge: ASME B40.1, with bourdon tube, rotary brass movement, brass socket, front calibration adjustment, black scale on white background.
1. Case: Cast aluminum.
2. Bourdon Tube: Phosphor bronze or Type 316 stainless steel.
3. Dial Size: 4-1/2 inch diameter within 7' of floor, 6 inch diameter over 7'.
4. Mid-Scale Accuracy: 1/2 percent.
5. Scale: 0-200 Psi.

2.8 COMBINATION FILTER/REGULATOR/LUBRICATOR

A. Manufacturers: Parker, Norgren or approved equal.

B. Lubro-psig control unit, ¾" port, auto-drain filter with guard, 5 to 125 psig regulator with pressure gauge. Micro-Fog lubricator with ½ pint bowl with guard.

2.9 COMPRESSED AIR FILTERS

A. Manufacturers: Parker Finite H, Norgren or approved equal.

B. Size filter housing using manufacturer's sizing chart base on total compressor SCFM plus 25% and scheduled pressure. Aluminum housing, chromate heads and bowls, powder painted exterior, 500 PSIG rated, nitrile seals.

C. Provide housing with differential pressure gauge and automatic drain valve.

D. Outlet Filter: Coalescing Grade 6C, epoxy saturated, borosilicate glass micro-fiber media.

2.10 FLEXIBLE HOSE CONNECTORS

A. Hose Connectors: Corrugated stainless steel tubing with stainless steel wire braid covering and ends welded to inner tubing.

B. Working Pressure: 250 psig minimum.

C. End Connections:
1. 2 inches and Smaller: Threaded steel pipe nipple.

2.11 ISOLATORS

A. Mason industries ND-C Green 140-160 pounds 0.50" maximum static deflection.

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.

B. Remove scale and dirt on inside and outside before assembly.

C. Prepare piping connections to equipment with flanges or unions.

D. Keep open ends of pipe free from scale and dirt. Protect open ends with temporary plugs or caps.

3.2 INSTALLATION - ABOVE GROUND PIPING - COMPRESSED AIR SYSTEMS

A. Slope main piping to compressor or additional system low points at 0.5-1.0% grade.

B. Install drip legs at low points of piping system with drain valves. Locate drain values in accessible locations.

C. Install take-off to outlets from top of main, with shut off valve after take off. Slope take-off piping to outlets.

D. Install compressed air couplings, female quick connectors, and pressure gauges where outlets are indicated.

E. Install tees instead of elbows at changes in direction of piping. Fit open end of each tee with plug.

F. Cut pipe and tubing accurately and install without springing or forcing.

G. Install pipe sleeves where pipes and tubing pass through walls, floors, roofs, and partitions.

H. Protection: Where piping, other than cast iron or steel, is installed in a concealed location through holes or notches in framing (i.e. studs, joists, rafters, etc.), less than 1-1/2 from framing edge, provide shield plates. Shield plates shall be 16 gauge steel and cover the piping area within framing plus 2” on each side along framing.

I. Install firestopping at fire rated construction perimeters and openings containing penetrating sleeves and piping.

J. Install pipe identification.

K. Except where indicated, install manual shut off valves with stem vertical and accessible for operation and maintenance.

3.3 INSTALLATION - EQUIPMENT

A. Install system in accord with manufacturer’s requirements and recommendations.

B. Install air compressor unit on vibration isolators and bolt in place.

C. Install line size shut-off valve on compressor discharge.

3.4 FIELD QUALITY CONTROL

A. Compressed Air Piping Leak Test: Prior to initial operation, clean and test compressed air piping in accordance with ASME B31.1 or ASME B31.9.

B. Test entire system with dry compressed air or dry nitrogen at 150 psig for a minimum duration of 2 hours, prove tight. If loss of pressure occurs, determine cause and remake joints. Caulking or patching not permitted.

3.5 CLEANING

A. Blow systems clear of free moisture and foreign matter.

END OF SECTION

SECTION 22 23 00

NATURAL GAS SYSTEMS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Natural gas piping above grade.
   2. Valves & Strainers.

1.2 SYSTEM DESCRIPTION

A. Where more than one piping system material is specified, provide compatible system components and joints. Use non-conducting dielectric connections when joining dissimilar metals in systems.

B. Provide flanges, unions, or couplings at locations requiring servicing. Use unions, flanges, or couplings downstream of valves and at equipment connections. Do not use direct welded or threaded connections to valves, equipment.

C. Use ball valves for shut-off and to isolate equipment, part of systems, or vertical risers.

1.3 QUALITY ASSURANCE

A. Comply with requirements and recommendations of NFPA 54 and the International Fuel Gas Code.

B. Perform work in accordance with applicable code and local gas company requirements.

C. Furnish shutoff valves complying with ASME B16.33 or ANSI Z21.15.

PART 2 PRODUCTS

2.1 NATURAL GAS PIPING, ABOVE GRADE

A. Steel Pipe: ASTM A53, Schedule 40 black, seamless. Manufactured in the USA.
   1. Fittings: ASME B16.3, malleable iron, or ASTM A234, forged steel welding type.
   2. Joints: 2 inch and smaller pipe - Threaded.

B. Steel Pipe: ASTM A53, Schedule 40 black, seamless. Manufactured in the USA.
   1. Fittings: Compression type, Viega MegaPress G, ANSI LC4-2012, zinc and nickel coating, HNBR sealing element, 420 stainless steel grip ring, 304 stainless steel separator ring and smart connect feature.
   2. Joints: 2 inch and smaller pipe - Viega MegaPress G Ridgid tool press.

C. Copper Tubing: Type L hard drawn. ASTM B88.
   1. Fittings: Compression type, Viega ProPress G, copper alloy.
   2. Joints: 2 inch and smaller pipe – Viega ProPress G Ridgid tool press.

2.2 BALL VALVES

A. Manufacturers: Nibco, Stockham, Milwaukee, or approved equal.

B. 1/2 inch to 3/4 inch (appliance shutoff valve): 1/2 psi rated for indoor appliance connections per ANSI Z21.15. Forged brass body, chrome plated brass ball, fluorocarbon o-rings, brass stem, painted aluminum lever handle. (Nibco G10)

C. 1/4 inch to 1 inch: MSS SP 110, Class 125, two piece, threaded ends, bronze body, chrome plated bronze ball, reinforced teflon seats, blow-out proof stem, lever handle, UL 842 listed for flammable liquids and LPG, full port. (Nibco T585-70-UL)

2.3 FLEXIBLE PIPE CONNECTIONS

A. Tubing: Annealed, 304 stainless steel, ASTM A240

B. Fittings: Brass or stainless steel.

C. Coating: Yellow polymer.

2.4 EXTERIOR WALL OUTLET

A. Manufacturer: Burnaby #GR0101-SS or approved equal.

B. Recessed stainless steel gas outlet box with brushed finish, 1/2" NPT pipe connection, shutoff valve, 3/8” quick disconnect plug, lockable access door.

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs. Bevel plain end ferrous pipe.

B. Remove scale and dirt, on inside and outside of pipe, before assembly.

C. Prepare piping connections to equipment with flanges or unions.

3.2 INSTALLATION - ABOVE GROUND PIPING SYSTEMS

A. Install natural gas piping in accordance with NFPA 54 and the International Fuel Gas Code.

B. Provide non-conducting dielectric connections wherever jointing dissimilar metals.

C. Grade horizontal pipe not less than ¼” in 15 feet.

D. Route piping in orderly manner and to conserve building space and not interfere with use of space.

E. Group piping whenever practical at common elevations.

F. Provide 6” long drip leg at bottom of vertical pipe.

G. Take from top or side of horizontal pipe.

H. Sleeve pipe passing through partitions, walls and floors.

I. Install firestopping at fire rated construction perimeters and openings containing penetrating sleeves and piping.

J. Provide clearance for access to valves and fittings.

K. Do not embed any building service low pressure pipe in concrete, in masonry, or below grade. Install such pipe in Schedule 40 welded pipe sleeves and vent to roof.

L. Prepare pipe, fittings, supports, and accessories not pre-finished, ready for finish painting.

M. Install identification on piping systems.

N. Install valves with stems upright or horizontal, not inverted.

O. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the Work, and isolating parts of completed system.

3.3 FIELD QUALITY CONTROL

A. Pressure test natural gas piping in accordance with NFPA 54 and the International Fuel Gas Code.

B. Subject pipe to air pressure of 60 psig for 30 minutes with no perceptible drop in pressure.

C. When pressure tests do not meet specified requirements, remove defective work, replace and retest.

END OF SECTION

SECTION 22 40 00

PLUMBING FIXTURES

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. General Plumbing Fixtures: Water closets, Lavatories, and Sinks.
2. Faucets and valves
3. Emergency Fixtures: Emergency Eye and Face Wash.
4. Hose bibbs & Hydrants.
5. Accessories.

1.2 SCOPE

A. This section includes all plumbing fixtures, trim and installation, to include owner furnished equipment.

1.3 REQUIREMENTS

A. All china fixtures shall be white or manufacturer's standard unless otherwise indicated.

B. Ensure that that all china fixtures install in a room or area are the exact same color and hue, especially if from different manufacturers.

C. Fixtures by type and material shall be of the same manufacturer except when scheduled or approved otherwise.

D. Tank type water closets shall have a minimum MaP (Maximum Performance) of 500 g.

E. Fixtures shall be designed or equipped to meet the following water use efficiency standards:

1.	Water closets (tank or flush valve)	1.6 GPF
2.	Lavatory faucets (Public)	0.5 GPM
3.	Service faucets	2.0 GPM

PART 2 PRODUCTS

2.1 TANK TYPE WATER CLOSETS

A. Manufacturers: Kohler, Toto, Eljer, American Standard or approved equal

B. Gravity: white, vitreous china, floor mount, 12" rough-in, 15" rim height, gravity feed flush with 3" valve, elongated bowl, close-coupled closet combination,

insulated vitreous china closet tank with fittings and lever flushing valve, siphon jet, 2-1/8" passageway, chrome plated bolt caps.

C. Gravity (ADA): white, vitreous china, floor mount, 12" rough-in, 16-1/2" rim height, ADA compliant, gravity feed flush with 3" valve, elongated bowl, close-coupled closet combination, insulated vitreous china closet tank with fittings and lever flushing valve, siphon jet, 2-1/8" passageway, chrome plated bolt caps.

2.2 WATER CLOSET SEATS

A. Manufacturers: Bemis, Olsonite or approved equal.

B. Open Front: Heavy duty solid plastic, white, large molded-in bumpers, external check hinges with stainless steel posts, without cover.

2.3 LAVATORIES

A. Manufacturers: Kohler, Eljer, American Standard or approved equal.

B. Counter Top: white, vitreous china, self-rimming, overflow, ADA compliant.

2.4 SINKS

A. Manufacturers: Elkay, Just, Acorn or approved equal.

B. Scullery: 14 gauge stainless steel, welded construction ground smooth, 1/4" radius corners, wall and floor mounted with tubular stainless steel legs, 8" high full length backsplash with 45 deg. slope top, 1-1/2" wide inward slopping top channel rims, integral drainboards sloped to drain, drilled for faucet and drain outlets, satin finish.

2.5 FAUCET, LAVATORY

A. Manufacturers: Chicago, Geberit, Delta HDF, Symmons or approved equal and as specifically noted below.

B. Centerset:
1. Single Handle: Polished chrome plated cast brass, deck mount, metal lever handle, ceramic mixing cartridge, temperature limit stop, 2.2 gpm aerator. Spout length, drain and hole spacing as scheduled.

2.6 FAUCET, DECON

A. Manufacturers: T&S or approved equal.

B. Polished chrome plated brass, backsplash mount, lever handles with spring checks & color coded indexes, 14" swing spout, pre-rise spray riser with wall bracket, finger hook, spray valve and stainless spring wound rubber hose.

2.7 EMERGENCY EYE AND FACE WASH

A. Manufacturers: Haws, Bradley, Guardian, Speakman, Acorn or approved equal.

B. Wall mounted eye/face wash with 11” stainless steel bowl, wall bracket, twin soft anti-surge eyewash heads, stainless steel face spray ring, hand flag control, chrome plated waste tailpiece and trap, dust cover, brass stay-open ball valve, in-line 50x50 mesh brass strainer, CSA certified to meet ANSI Z358.1. Include universal emergency signage 8”x11”.

2.8 HOSE STATION

A. Manufacturers: Leonard or approved equal.

B. Hot & Cold: Panel-type recessed stainless steel cabinet with stainless steel cover, inlets with stops, check valves and color coded handles, outlet dial thermometer, vacuum breaker hose connection, stainless steel hose rack, [10] feet of 3/4" heavy duty EPDM hose with industrial rubber coated bronze nozzle.

2.9 FIXTURE SUPPLIES

A. Manufacturers: Brass Craft or approved equal.

B. Chrome plated brass angle stops with fixed key metal handle and chrome plated escutcheon. Chrome plated copper flexible supplies for exposed connections, braided supplies acceptable where concealed. Provide stop and supply type as applicable to specific fixtures.

2.10 TRAPS

A. Manufacturers: Brass Craft, Dearborn Brass or approved equal.

B. Adjustable type, polished chrome plated brass with escutcheon. Provide type as applicable to specific fixture installation. PVC acceptable only where concealed.

2.11 LAVATORY INSULATION KIT

A. Manufacturers: Truebro, Plumberex, or approved equal.

B. Where lavatories or sinks have exposed traps or supplies furnish the following for ADA compliance: Safety Covers conforming to ANSI A177.1 and consisting of insulation kit of molded closed cell vinyl construction, 3/16 inch thick, white color, for insulating tailpiece, P-trap, valves, and supply piping. Furnish with weep hole and angle valve access covers, antimicrobial, with flush reusable fasteners.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify walls and floor finishes are prepared and ready for installation of fixtures.

B. Verify electric power is available and of correct characteristics.

C. For all lavatories and sinks verify required number of holes and hole spacing before ordering.

3.2 PREPARATION

A. Rough-in fixture piping connections in accordance with minimum sizes indicated in fixture rough-in schedule for particular fixtures and in accordance with manufacturer's details.

B. Locate fixtures in accordance with architectural drawings, details on structural drawings and/or Engineer's direction in field. Mount ADA fixtures according to dimensions on architectural drawings.

C. If drain, tailpiece, strainer or other accessories are not furnished by fixture manufacturer then provide accessories by Brass Craft or approved equal.

D. Provide vandal proof features on faucets, aerators, bubblers and pop-up waste assemblies on fixtures in public areas.

3.3 INSTALLATION

A. Install shut-off valves on water lines servicing a fixture group.

B. Support piping at stop, valve or flush valve.

C. Align fixtures and equipment installed in accord with architectural drawings.

D. Seal fixtures to wall and floor surfaces with silicon sealant, color to match fixture.

E. Solidly attach water closets to floor with lag screws. Lead flashing is not intended hold fixture in place.

F. For ADA accessible water closets, install flush valve with handle to wide side of stall.

3.4 INTERFACE WITH OTHER PRODUCTS

A. Review millwork shop-drawings. Confirm location and size of fixtures and openings before rough in and ordering.

3.5 ADJUSTING

A. Adjust stops or valves for intended water flow rate to fixtures without splashing, noise, or overflow.

B. Adjust flush lever or valve for intended flow rate and operation.

END OF SECTION

SECTION 224223 - COMMERCIAL SHOWERS, RECEPTORS, AND BASINS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Shower basins.

2. Shower wall panels.

B. Related Requirements:

1. Division 22 – “Plumbing”.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for basins.
2. Include rated capacities, operating characteristics, and furnished specialties and accessories.

PART 2 - PRODUCTS

2.1 SHOWER BASINS

A. Solid Surface Shower Basins:
1. Basis-of-Design Product: Subject to compliance with requirements, provide Swan Corporation; SS-4242 or comparable product by one of the following:

a. Swan Corporation.
b. Kohler Corporation.
c. Equal approved by Architect.

2. Color: Selected by Architect from Manufacturer’s full range.

2.2 SHOWER WALL PANELS

A. Solid Surface Shower Wall Panel:
   1. Basis-of-Design Product: Subject to compliance with requirements, provide Swan Corporation; XXXXXX or comparable product by one of the following:

      a. Swan Corporation.
      b. Kohler Corporation.
      c. Equal approved by Architect.

   2. Thickness: ¼”
   3. Color: Selected by Architect from Manufacturer’s full range.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine roughing-in of water-supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before shower installation.

B. Examine walls and floors for suitable conditions where showers will be installed.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Assemble shower components according to manufacturers' written instructions.

B. Install showers level and plumb according to roughing-in drawings.

C. Install water-supply piping with stop on each supply to each shower faucet.

   1. Exception: Use ball, gate, or globe valves if supply stops are not specified with shower. Comply with valve requirements specified in Section 220523 "General-Duty Valves for Plumbing Piping."
   2. Install stops in locations where they can be easily reached for operation.

D. Install shower flow-control fittings with specified maximum flow rates in shower arms.

E. Set shower basins in leveling bed of cement grout.

F. Install wall flanges or escutcheons at piping wall penetrations in exposed, finished locations. Use deep-pattern escutcheons if required to conceal protruding fittings. Comply with escutcheons requirements specified in Section 220518 "Escutcheons for Plumbing Piping."

G. Seal joints between showers and floors and walls using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Comply with sealant requirements specified in Section 079200 "Joint Sealants."

3.3 CONNECTIONS

A. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.

B. Comply with water piping requirements specified in Section 221116 "Domestic Water Piping."

C. Comply with traps and soil and waste piping requirements specified in Section 221316 "Sanitary Waste and Vent Piping."

3.4 ADJUSTING

A. Operate and adjust showers and controls. Replace damaged and malfunctioning showers, fittings, and controls.

B. Adjust water pressure at faucets to produce proper flow.

3.5 CLEANING AND PROTECTION

A. After completing installation of showers and basins, inspect and repair damaged finishes.

B. Clean showers and basins, faucets, and other fittings with manufacturers' recommended cleaning methods and materials.

C. Provide protective covering for installed fixtures and fittings.

D. Do not allow use of showers and basins for temporary facilities unless approved in writing by Owner.

END OF SECTION 224223

SECTION 23 00 00

HVAC GENERAL CONDITIONS

PART 1 GENERAL

1.1 GENERAL REQUIREMENTS

A. Conform to General Conditions, Supplementary Conditions, the modifications thereto and Division 01 - General Requirements for all work in Division 23.

1.2 SUMMARY

A. Design Intent: Provide new HVAC systems for an existing Fire Station.

B. Provide labor, materials and appliances necessary for satisfactory installation of mechanical work ready to operate in strict accordance with these specifications and drawings. Work of Division 23 includes, but is not limited to, that as delineated in the following specification sections:

23 00 00 HVAC General Conditions

23 05 00 Common Work Results for HVAC

23 05 93 Testing, Adjusting and Balancing

23 07 00 HVAC Insulation

23 08 00 Project Commissioning

23 09 00 Instrumentation and Control for HVAC

23 23 00 Refrigerant Piping

23 31 00 HVAC Ducts and Casings

23 33 00 Air Duct Accessories

23 34 00 HVAC Fans

23 37 00 Air Outlets and Inlets

23 40 00 HVAC Filters

23 72 00 Energy Recovery Units

23 81 43 Variable Refrigerant Flow, Heat Pump System

23 82 00 Terminal Heating Units

1.3 CODES AND STANDARDS

A. Conform to following code and agency requirements having jurisdictional authority over mechanical installation.
   1. Uniform Plumbing Code (UPC) with local amendments.
   2. International Mechanical Code (IMC) with local amendments.
   3. International Building Code (IBC) with local amendments.
   4. International Fuel Gas Code (IFGC) with local amendments.
   5. National Electrical Code (NEC) NFPA 70.
   6. Requirements of OSHA and EPA.
   7. National Fire Protection Association (NFPA) Codes and Standards.
   8. ASME code for construction of pressure vessels.
   9. American Gas Association (AGA) Standards.
   10. ASTM, ANSI and NEMA standards, as referenced in subsequent sections.
   11. Local Sewer District Requirements.
   12. Local Water District Requirements.
   13. Local Health Department Requirements.
   14. Washington State Energy Code.

1.4 PERFORMANCE REQUIREMENTS

A. Firestopping: Conform to International Building Code with local amendments, FM, and UL for fire resistance ratings and surface burning characteristics.

B. Provide vibration isolation on motor driven equipment.

1.5 PRODUCT SUBSTITUTIONS

A. Manufacturers and models of equipment and material indicated herein and on drawings are those upon which mechanical design is based. Other manufacturers with products considered equal in general quality may be listed without specific model designation. Manufacturers not listed shall be submitted for approval, see Division 01.

B. Substitutions will be evaluated based on product manufacturer only. Specific product model, specifications, options and accessories will be evaluated during submittals. Approval of a manufacturer substitution does not constitute approval of the submitted product.

C. Any equipment other than the basis of design is considered a substitution.

D. In selecting substitute equipment, the Contractor is responsible for and shall guarantee equal performance and fit. Cost of redesign and all additional costs incurred to accommodate the substituted equipment shall be borne by the Contractor.

E. Unless indicated otherwise, “or approved” may be assumed for all products in Division 23.

1.6 SUBMITTALS

A. Provide one electronic copy of product data submittals for all products listed under “Part 2 Products” of Division 23 and all additional products noted on drawings or required for completion of sequence of operations.

B. Electronic: **Submittals shall be complete in one PDF file with bookmarks for each Division. Multi-part submittals will be returned without review.**
   1. First Page: Name of Project, Owner, Location & Contracting Company.
   2. Index Page: List of specification sections with contents by Tag or item.
   3. Bookmarks: Electronic bookmark of each specification section corresponding to listing in index.
   4. Acceptable forms of delivery are:
      a. Email (for file sizes less than 10 MB)
      b. Online File Transfer: Dropbox, Google Drive or similar
      c. FTP: Architects or General Contractors file server (if available)

C. Clearly indicate on each page the equipment schedule designation (Tag) and/or specification section, as applicable. Indicate selected model and all accessories intended for use.

D. Equipment vendor cover page with contact information shall precede submittal by that vendor.

E. Submitted product information shall include (as applicable) but not be limited to the following information:
   1. Product description
   2. Manufacturer and model
   3. Dimensions
   4. Performance Ratings (i.e. capacity, rpm, HP, temperature)
   5. Construction Materials
   6. Ratings (i.e. UL, ASTM, NEMA, etc)
   7. Electrical data
   8. Sound level data (corresponding to scheduled values)
   9. Vibration Isolation
   10. Controls and wiring diagrams
   11. Accessories
   12. Engineering technical data (i.e. pressure drops, leakage rates, pump curves, fan curves)

F. If requested by Architect or Engineer, submit Manufacturer's Installation Instructions on any equipment, procedures, or certifications so requested.

G. Do no ordering, fabrication or manufacturing of products until return of approved submittals.

1.7 SHOP DRAWINGS

A. The Contractor shall submit drawings and/or diagrams for review and for job coordination in all cases where deviation from the Contract Drawings are

contemplated because of job conditions, interference or substitution of equipment, or when requested by the Engineer for purposes of clarification of the Contractor's intent.

B. Submit detailed drawings, rough-in sheets, etc., for all special or custom-built items or equipment. Drawings and details under the section shall include (but not be limited to) the following, where applicable to this project:
   1. Electrical interlock wiring diagrams.
   2. Piping layout plans and interference details.

C. By submission of piping and ductwork shop drawings, the Contractor acknowledges that coordination has been done to ensure that all piping and ductwork fits and that no conflicts exist.

D. The Architect's review of shop drawings shall not relieve the Contractor of responsibility for deviations from the Contract drawings or specifications, unless he has, in writing, called the attention of the Architect to such deviations at the time of the submission, nor shall it relieve him from responsibility for errors or omission in such shop drawings.

1.8 COMMISSIONING

A. See Division 01 and Section 23 08 00 for roles and responsibilities of commissioning.

B. Provide all necessary commissioning assistance, equipment and documentation as required by the Commissioning Plan.

C. The duty and responsibility for mechanical commissioning work shall be assigned to a specific individual. Inform the General Contractor and Commissioning Agent (CA) of the contact information for the person so assigned.

D. Perform corrective actions needed to resolve deficiencies identified during commissioning. Record action taken on commissioning deficiency log.

1.9 COMMISSIONING PLAN

A. The Commissioning Plan shall be submitted with other mechanical submittals.

B. Approval of commissioning plan is required before commencement of work.

1.10 HVAC PERMIT

A. HVAC contractor shall prepare all documents for mechanical permit application, submit for, and obtain the permit. HVAC Contractor shall pay all costs and fees to obtain the permit.

B. Contractor shall not commence work until permit is obtained. Contractor is solely responsible to insure that the permit application and any revisions are submitted in a timely manner so as not to impact project schedule.

C. Contractor shall retain services of a third party structural engineer to provide support, anchoring and seismic calculations for all applicable equipment.

1.11 QUALITY ASSURANCE

A. Perform Work in accordance with ASME B31.9 – Building Services Piping for installation of piping systems and ASME Section IX – Welding and Brazing Qualifications for welding materials and procedures.

B. Perform Work in accordance with the International Mechanical Code including State and local amendments.

C. Provide products requiring electrical connections listed and classified by UL as suitable for purpose specified and indicated.

D. Perform Work in accordance with Washington State Energy Code.

1.12 QUALIFICATIONS

A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years' experience.

B. Installer: Company specializing in performing Work of this section with minimum three years' experience.

1.13 SEQUENCING

A. Sequence balancing between completion of systems tested and Date of Substantial Completion.

1.14 DELIVERY, STORAGE, AND HANDLING

A. Accept materials on site in original factory packaging, labeled with manufacturer's identification.

B. Protect all equipment, materials, and insulation from weather, construction traffic, dirt, water, chemicals, and damage by storing in original packaging and under cover. Where original packaging is insufficient, provide additional protection. Maintain protection in place until installation.

C. Inspect all products and materials for damage prior to installation.

D. Protect piping from all entry of foreign materials by providing temporary end caps or closures on piping and fittings. Furnish temporary protective coating on cast iron and steel valves.

E. Protect dampers from damage to operating linkages and blades.

F. Protect materials and finishes during handling and installation to prevent damage.

G. Protect coil fins from crushing and bending by leaving in shipping cases until installation, and by storing indoors. Protect coils from entry of dirt and debris with pipe caps or plugs.

H. Comply with manufacturer's installation instruction for rigging, unloading and transporting units.

I. Comply with contractor’s construction Indoor Air Quality (IAQ) Plan.

1.15 ENVIRONMENTAL REQUIREMENTS

A. Do not apply fire stopping materials when temperature of substrate material and ambient air is below 60 degrees F. Maintain this minimum temperature before, during, and for minimum 3 days after installation of fire stopping materials.

B. Provide ventilation in areas to receive solvent cured materials.

C. Install insulation only when ambient temperature and humidity conditions are within range recommended by manufacturer. Maintain temperature during and after installation for minimum period of 24 hours.

D. Do not install instruments when areas are under construction, except rough in, taps, supports and test plugs.

E. Do not install duct sealant when temperatures are less than those recommended by sealant manufacturers. Maintain temperatures during and after installation of duct sealant.

F. Maintain water integrity of roof during and after installation of chimney or vent.

G. Do not install condensing unit foundation pad when ground is frozen or muddy.

1.16 FIELD MEASUREMENTS

A. Verify field measurements prior to fabrication.

B. Verify by field measurements, sizes and configurations are compatible with wall construction and layout.

C. Existing systems and utility lines indicated on drawings are in accordance with information furnished to the Architect and may not be complete. Contractor is responsible for locating, uncovering, disposing of or maintaining existing systems.

1.17 COORDINATION

A. Visit the site and become familiar with existing conditions affecting work.

B. Verify locations of any overhead or buried utilities on or near site. Determine such locations in conjunction with all public and private utility companies and with all authorities having jurisdiction.

C. Existing systems and utility lines indicated on drawings are in accordance with information furnished to the Architect and may not be complete. Contractor is responsible for locating, uncovering, disposing of or maintaining existing systems.

D. HVAC drawings are diagrammatic and do not indicate all possible site conditions. The contractor shall verify all measurements, dimensions and connections on site and coordinate between trades to preclude interferences. The contractor shall provide adjustments to piping or ductwork as necessary to fit conditions including but is not limited to relocation, offsets, and transitions.

E. In the event of a conflict with other trades of work, the following priority from highest to lowest shall be followed: Structural, lighting, HVAC, plumbing/piping and sprinklers. Starting with the lowest priority, the HVAC, plumbing, and sprinkler contractors shall provide whatever materials, offsets, labor etc. is required to resolve the conflict.

F. When discrepancies occur between plans and specifications, the Architect will determine which takes precedence and the Contractor shall perform the selected requirement at no additional cost.

G. Prior to ordering equipment cross-check mechanical and electrical drawings and specifications to assure proper location and electrical characteristics of connections serving mechanical and electrical equipment.

H. Advise the Architect of any modifications required to suit equipment furnished. Costs for modifications due to equipment substitution will be borne by the contractor.

I. Wherever conflicts occur between different parts of the Contract Documents the greater quantity, the better quality, or larger size shall prevail unless the Architect informs the Contractor otherwise in writing.

J. The scale of each drawing is relatively accurate, but the Contractor is warned to obtain the necessary dimensions for any exact takeoffs from the Architect. No additional cost to the Owner will be considered for failure to obtain exact dimensions where not clear or in error on the drawings. Any device or equipment roughed in improperly and not positioned on implied centerlines or as required by good practice shall be repositioned at no cost to the Owner.

K. Where the word ‘verify’ is used on the documents, the contractor shall field verify the existing conditions and modify the scope of the installation as required to meet the verified conditions without additional cost to the Owner.

L. Coordinate trenching, excavating, bedding, backfilling of buried systems with requirements of this specification.

M. Coordinate wall openings, piping rough-in locations, concrete housekeeping pads, and electrical rough-in locations to accommodate Work of this Section.

N. Coordinate all equipment with building control work.

O. Coordinate installation of
1. Condensing units with concrete pad and roof structure.
2. Air handling units with building structure.
3. Unit installation with roof structure, piping systems, and ceiling for unit access.
4. Roof curbs with roof structure, roof deck and roof membrane installation.

1.18 CUTTING, FITTING, REPAIRING AND PATCHING

A. Arrange and pay for all cutting, fitting, repairing, patching and finishing of work by other trades where necessary for installation of mechanical work. Perform work only with craftsmen skilled in their respective trades.

B. Avoid cutting, where possible, by setting sleeves, frames, etc., and by coordinating for openings in advance. Assist other trades in securing correct location and placement of rough-frames, sleeves, openings, etc. for ducts and piping.

C. Cut all holes neatly and as small as possible to admit work. Perform cutting in manner so as not to weaken walls, partitions or floors. Drill holes required to be cut in floors without breaking out around holes.

1.19 SALVAGE

A. Remove excess piping and ductwork, plug or cap any unused branch connections. Remove scrap pipe and all other excess materials from the site.

B. Comply with contractor's Construction Waste Management Plan. Retain and submit all trip and tip tickets for all construction debris and waste hauling, indicating material content, tonnage, date hauled and facility to where materials were hauled.

1.20 ELECTRICAL

A. Short-Circuit Current Rating (SCCR): All HVAC and refrigeration equipment with multi-motor or combination electrical loads shall comply with NEC 110.10 & 440.4 and must include a SCCR greater than the Available Interrupting Current (AIC) of the electrical circuit serving the equipment. See electrical drawings for required AIC kA rating. Equipment SCCR may be presented in writing from the manufacturer or shown on the unit nameplate. Refrigeration or air-conditioning equipment over 60 Amps MOCP must list the SCCR on the unit nameplate. If the AIC rating is unavailable or cannot be determined provide equipment with a minimum SCCR of 10kA.

B. Motors:
1. Temperature Rating: Rated for 40 degree C environment with maximum 50 degree C temperature rise for continuous duty at full load.
2. Starting Capability: Not less than 12 starts per hour.

3. Phase Characteristics: Squirrel-cage induction poly-phase motors for 3/4 HP and larger, and capacitor-start single-phase motors for 1/2 HP and smaller. At equipment manufacturer's option, 1/6 HP and smaller may be split-phase type.
4. Service Factor: 1.15 for polyphase motors and 1.35 for single-phase motors.
5. Enclosure Type: Open drip-proof motors for indoor use where satisfactorily housed or remotely located during operation, and guarded drip-proof motors where exposed to contact by employees or building occupants. Weather-protected Type I for outdoor use, Type II, where not housed.
6. Overload Protection: Built-in thermal overload protection.
7. Name Plate: Indicate full identification of manufacturer, ratings, characteristics, construction, special features and similar information.
8. All motor efficiencies shall conform to Washington State Energy Code and NEMA MG-1.

C. Motor Starters: By mechanical equipment manufacturer where factory mounted controls are provided. Variable frequency drives by Division 23, all other starters provided by Electrical Contractor.

D. Power Wiring: By Electrical Contractor.

E. Control Wiring: Responsibility of Division 23, including all line and low voltage control wiring. Owner will not entertain additional cost due to lack of coordination between HVAC Contractor and Electrical Contractor.

1.21 EXTRA MATERIALS

A. Furnish
1. Two refrigerant oil test kits each containing everything required for conducting one test.
2. Three sets of disposable filters for each unit.
3. One set of fan belts for each unit.

1.22 PROJECT CLOSEOUT

A. Completion, submission and approval of the following is required for final project closeout.
1. Execution of Architect's and Engineer’s final observation reports (punchlist)
2. Operating and Maintenance Instructions
3. Operating and Maintenance Manual
4. Equipment and Pipe Cleaning
5. Record Drawings
6. Testing
7. Commissioning
8. Warranty

B. See Division 01 for additional requirements.

1.23 OPERATING AND MAINTENANCE INSTRUCTIONS

A. General: In addition to requirements of Division 01, following initial operation of HVAC systems and prior to acceptance by the Architect, perform the following services.

B. At least two weeks prior to each instruction period, give written notification of readiness to proceed to the Architect and Owner, and obtain mutually acceptable dates.

C. Conduct demonstrations and instructions for the Owner's representatives, pointing out requirements for operating, servicing and maintaining equipment and systems. Describe general system operation and specific equipment functions. Cover all equipment calibration, setpoint adjustment, safeties and alarms.

D. Furnish qualifications of Contractor's personnel in charge of the instruction; foreman position is minimum acceptable. Where equipment startup is performed by supplier’s or manufacturer’s personnel, those personnel should also provide training on that equipment.

E. During demonstrations and instructions include and reference information from maintenance manuals and contract drawings.
   1. Provide documentation of all instruction which includes:
      a. Date and time of instruction
      b. Name, affiliation and qualifications of the instructor
      c. Name and affiliation of the attendees
      d. Topics, systems, and equipment covered
      e. Length of instruction

F. Minimum duration of instruction periods:

1.	HVAC Systems	8 hours
2.	Control Systems	8 hours

1.24 OPERATING AND MAINTENANCE MANUALS

A. Contents: Furnish, in accord with Division 1, three (3) bound copies of operating and maintenance manuals to include the following:
   1. Manufacturers, suppliers, contractor names, addresses and phone numbers.
   2. Warranty service contractors' names, address and phone numbers (if different from above).
   3. Schedule and description of routine maintenance for each component to include oiling, lubrication and greasing data.
   4. Manufacturer's cuts and rating tables, including brochures for all submittal items.
   5. Part numbers of all replaceable items.
   6. Control diagrams and operation sequence.
   7. Written guarantees.
   8. Record drawings corrected and completed.
   9. Completed equipment start-up forms and checklists.

10. Final copy of testing, adjusting, and balancing report.

B. Operation and Maintenance Data:
1. Include, spare parts list, exploded assembly views for all equipment.
2. Submit installation instructions, adjustment instructions, spare parts list, exploded assembly views for all equipment.
3. Submit inspection period, cleaning methods, recommended cleaning materials, and calibration tolerances.
4. Submit manufacturer's descriptive literature, operating instructions, and maintenance and repair data. Include directions for resetting constant volume regulators.

C. Filters: Operation and Maintenance Data: Submit instructions for operation, changing, and periodic cleaning.
1.
2. Submit replacement part numbers and availability, and nearest service depot location and telephone number.

D. Binders:
1. Furnish typewritten or printed index and tabbed dividers between principal categories.
2. Bind each manual in a hard-backed loose-leaf binder.

E. Imprint on cover:
1. Name of project.
2. Owner.
3. Location of project.
4. Architect.
5. Contractor.
6. Year of completion.

F. Imprint on backing:
1. Name of project.
2. Year of completion.

G. Submittals:
1. Preliminary Copies: Prior to scheduled completion of the project, submit two copies for review by the Architect.
2. Final Copies: After approval of the preliminary copies, submit three (3) finished copies to the Owner.

1.25 EQUIPMENT AND PIPE CLEANING

A. Clean interior and exterior of all equipment. Equipment shall be free of dirt, construction debris, corrosion, etc.

B. Adequate provisions shall be made during construction to eliminate dirt, debris or other material from entering and collecting inside of pipe, ductwork and equipment. Any collection of material shall be thoroughly cleaned before equipment startup and if necessary again before owner occupancy.

C. Clean exterior of all exposed pipe and ductwork.

1.26 RECORD DRAWINGS

A. Submit one CD or DVD with all drawings in PDF format.

B. Make all notes and revisions on PDF set in red.

C. Show location of equipment, location and size of piping, location and size of ductwork. Locate all valves, control dampers and similar equipment with tag or label identification. Indicate locations and elevations of exterior pipe and utility connections. Maintain continuously updated drawings during progress of project.

D. Record actual locations of tagged valves and control dampers; include valve tag numbers. Record actual locations of flexible connectors and expansion joints.

E. Record actual locations of equipment, clean-outs, controlling devices, and all above grade, under-floor, and buried piping and ductwork. Provide dimensions from gridline or walls to indicate specific locations.

1.27 TESTING

A. Provide completed start-up forms and checklists.

B. Perform testing and balancing of HVAC systems as described in this Division and as required by applicable codes and ordinances.

C. Provide changes in sheaves, belts, and dampers as required for correct balance.

D. Provide commissioning of Control System, and all mechanical components in compliance with the applicable Energy Code, the commissioning notes on the drawings and commissioning specifications of this Division. Written verification of test to be signed by Owner's Representative

1.28 COMMISSIONING REPORT

A. Submit three (3) copies of the preliminary commissioning report as required by 230800, as outlined on drawing commissioning notes and specifications of this Division. This report is an execution and fulfillment of the commissioning plan. This report shall be completed before the final mechanical permit inspection. At a minimum this report shall include:
   1. Test and balance report
   2. Complete equipment startup checklists
   3. Functional test reports
   4. Sequence of Operation test reports
   5. O&M materials
   6. Record drawings
   7. Owner training documentation
   8. Note any discrepancies observed during testing and any corrective actions taken or date when corrective action will be taken.
   9. Note any tests which could not be performed due to weather conditions.

B. After receiving review comments from the preliminary commissioning plan make corrections indicated and submit three (3) copies of the final commissioning report. At a minimum this report shall include the information from the preliminary commissioning report and the following:
   1. Corrective measures taken in response to preliminary report or field observation report.

1.29 WARRANTIES AND CONTRACTOR'S GUARANTEE

A. All work, material and equipment shall be free of defect, complete and in perfect operating order at time of delivery to Owner.

B. Furnish one year warranty from date of substantial completion for all systems unless specifically noted otherwise.

C. Without cost to Owner, **correct all defects and failures discovered within one year from date of final acceptance**, except when in the opinion of the Architect a failure is due to neglect or carelessness of the Owner.

D. The guarantee of the Contractor is independent of shorter time limits by any manufacturer of equipment furnished. Submit with Operation and Maintenance Manual all guarantees which exceed one year.

E. Make all necessary balancing and control adjustments during first year of operation.

F. The presence of any inspector or observer during any construction does not relieve the Contractor from responsibility for defects discovered after completion of the work.

PART 2 NOT USED

PART 3 EXECUTION

3.1 DOCUMENTATION

A. Additional plan submittals to reviewing authority: If additional drawing submittals are required at any time during construction contractor shall submit drawings, review with authority, and pick up subsequent approved drawings. Engineer will revise and/or prepare drawings for submittal.

3.2 INSPECTION

A. Do not allow any work to be covered up or enclosed until inspected, tested and approved by the Architect and all authorities having jurisdiction over the work.

B. Should any work be enclosed or covered up before such inspection and test, Contractor shall at his own expense uncover work, and after it has been

inspected, tested and approved, make all repairs as necessary to restore all work disturbed by him to its original condition.

C. Energy Code C104 specifically requires the following inspections.
1. Mechanical Equipment Efficiency and Economizer: To be made after all equipment and controls required by the Energy Code and this specification are installed and prior to the concealment of such equipment or controls.
2. Mechanical Pipe and Duct Insulation: To be made after all pipe and duct insulation is in place, but before concealment.
3. Motor Inspections: To be made after installation of all equipment covered by the Energy Code and this specification but before concealment.

3.3 FIELD QUALITY CONTROL

A. Inspect isolated equipment after installation for proper movement clearance.

3.4 CLEANING

A. Clean adjacent surfaces of fire stopping materials.

B. Clean ductwork and equipment.

3.5 PROTECTION OF FINISHED WORK

A. Protect adjacent surfaces from damage by material installation.

END OF SECTION

SECTION 23 05 00

COMMON WORK RESULTS FOR HVAC

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Hangers and Supports.
2. Vibration and Seismic Controls.
3. Firestopping.
4. Condensate Pumps
5. Access Panels
6. Tags and Identification.
7. Execution

1.2 GENERAL REQUIREMENTS

A. Comply with requirements and recommendations of Manufacturers Standardization Society of the Valve and Fittings Industry (MSS) Standards SP-58 and SP-69.

B. Comply with requirements and recommendations of Sheetmetal and Air Conditioning Contractors National Association (SMACNA) HVAC Duct Construction Standards.

C. Conform to requirements of IBC 1613 and SMACNA "Seismic Restraint Manual Guidelines for Mechanical Systems".

1.3 MATERIALS AND EQUIPMENT

A. Where two or more units of same class of equipment are required, use products of a single manufacturer. All equipment shall be new and free from damage.

B. Protect stored material and equipment against weather, corrosion and dirt. Protect installed mechanical components, including but not limited to piping, ductwork, and equipment against weather damage, corrosion, dirt and construction dust. Seal equipment and ductwork where and when necessary to be kept clean.

C. Provide major equipment components with manufacturer's name, address, catalog number and capacity indicated on a nameplate, securely affixed in a conspicuous place.

D. Furnish standard and fabricated hangers and supports complete with necessary inserts, bolts, nuts, rods, washers and other accessories.

1.4 REQUIREMENTS

A. Provide incompressible inserts and shields at all piping supports on pipe to be insulated per 23 07 00.

B. Provide vibration isolation on motor driven equipment, plus connected piping.

C. Firestopping Materials: Provide to achieve fire ratings as noted on architect's drawings for adjacent construction, but not less than 1 hour fire rating. ASTM and UL.
1. Ratings may be 3-hours for firestopping in through-penetrations of 4-hour fire rated assemblies unless otherwise required by applicable codes.
2. Surface Burning: UL 723 with maximum flame spread / smoke developed rating of 25/50.
3. Firestop interruptions to fire rated assemblies, materials, and components.

D. Prevent contact between dissimilar metals, such as copper tubing and steel, by use of copper-plated, plastic coated, or flexible materials. All supports which contact copper tubing shall be copper plated.

E. Firestop interruptions to fire rated assemblies, materials and components.

1.5 QUALITY ASSURANCE

A. Installed products shall have surface Burning Characteristics: 25/50 flame spread/smoke developed index when tested in accordance with ASTM E84.

B. Perform work in accordance with local jurisdiction's requirements and AWS D1.1 for welding hanger and support attachments to building structure.

C. Conform to ASME A13.1 for color scheme for identification of piping systems and accessories.

PART 2 PRODUCTS

2.1 DUCT HANGERS AND SUPPORTS

A. Hanger straps and rods shall be in accord with SMACNA Duct Construction Standards.

B. Fasten bracing to ductwork, including riveting, bolting, and tack welding per SMACNA.

C. Provide galvanized steel band or fabricated angle iron brackets for wall supports.

D. Exposed ducts shall be supported/anchored to structure at closer spacing and using heavier materials, wherever so indicated on drawings.

E. Hanger Rods: Carbon Steel, with hex nuts and flat washers.

F. Concrete Inserts:
   1. Continuous channel - Unistrut or approved.
   2. Universal, malleable iron - Type 18, FS WW-H-171.

G. Beam Clamps and Attachments as required.

2.2 PIPE HANGERS AND SUPPORTS

A. Provide hangers and supports with incompressible insulation inserts and shields for all piping to be insulated per 230700.
   1. Manufacturer: Pipe Shields, INC or approved equal.
   2. Material: Calcium Silicate or Uretherne per temperature application.
   3. Thickness: Insert thickness shall match required insulation thickness per 230700.

B. Refrigerant Piping:
   1. Hangers for rigid pipe: Carbon steel, adjustable swivel, split ring with Armacell Armafix insulated rigid insert.
   2. Hangers for flexible pipe: Carbon steel, adjustable, clevis with Armacell Armafix insulated rigid insert and saddle.
   3. Hangers for paired flexible pipe: Carbon steel, adjustable, clevis with 1” wide overlapping steel band and saddle.

2.3 HANGER ACCESSORIES

A. Hanger Rods: Mild steel threaded both ends, threaded on one end, or continuous threaded.

2.4 INSERTS

A. Malleable iron case of steel shell and expander plug for threaded connection with lateral adjustment, top slot for reinforcing rods, lugs for attaching to forms; size inserts to suit threaded hanger rods.

2.5 ACCESS PANELS

A. Milcor or approved equal.

B. Include an allowance for a minimum of 6 access panels.

C. Architectural grade, 14 guage frame and door, painted steel or stainless steel based on application.

2.6 FLEXIBLE PIPE CONNECTORS

A. Manufacturers: Metraflex, Mason or approved equal.

B. Braided Refrigeration Piping Connection
   1. Bronze flexible hose and bronze braided outer covering.
   2. Copper sweat connections, cleaned de-greased, and bagged.
   3. UL listed

2.7 FLASHING

A. Metal Flashing: 26 gage thick galvanized steel.

B. Metal Counterflashing: 22 gage thick galvanized steel.

C. Lead Flashing:
1. Waterproofing: 5 lb./sq. ft sheet lead.
2. Soundproofing: 1 lb./sq. ft sheet lead.

D. Flexible Flashing: 47 mil thick sheet butyl; compatible with roofing.

E. Caps: Steel, 22 gage minimum; 16 gage at fire resistant elements.

2.8 EQUIPMENT CURBS

A. Manufacturers' curbs where indicated on drawings.

B. Fabricated: Welded 18 gage galvanized steel shell and base, mitered 3 inch cant, variable step to match roof insulation, 1-1/2 inch thick insulation, wood nailer.

2.9 SLEEVES

A. Sleeves for Pipes Through Non-fire Rated Floors: 18 gage thick galvanized steel.

B. Sleeves for Pipes Through Non-fire Rated Beams, Walls, Footings, and Potentially Wet Floors: Steel pipe or 18 gage thick galvanized steel.

C. Sleeves for Ductwork: 18 gage thick galvanized steel.

D. Sealant: Acrylic

E. Size large enough to allow for movement due to expansion and to provide for continuous insulation or installation of fire sealant at fire-rated walls. Note that insulation is discontinuous at fire walls.

2.10 MECHANICAL SLEEVE SEALS

A. Manufacturers: Metraflex Metraseal, Thunderline Link-Seal or approved equal.

B. Product Description: Modular mechanical type, consisting of interlocking synthetic rubber links shaped to continuously fill annular space between object and sleeve, connected with bolts and pressure plates causing rubber sealing elements to expand when tightened, providing watertight seal and electrical insulation.

2.11 FORMED STEEL CHANNEL

A. Manufacturers: Allied Tube & Conduit, B-Line Systems, Unistrut or approved equal.

B. Product Description: Galvanized 12 gage thick steel, with holes 1-1/2 inches on center.

2.12 FIRESTOPPING-APPLIED

A. Manufacturers: RectorSeal, Dow Corning, 3M Fire Protection or approved equal.

B. General:
1. Fire stopping materials shall conform to Flame (F) and Temperature (T) ratings as required by applicable building codes and tested by nationally accepted test agencies per ASTM E 814 or UL 1479 fire tests for through penetrations, and ASTM E 1966 or UL 2079 for construction joints, and UL 2307 for perimeter edge joints.
2. Fire stopping material shall be free of asbestos, PCBs, ethylene glycol, and lead.
3. Do not use any product containing solvents or that requires hazardous waste disposal.
4. Fire stopping shall be performed by a contractor trained or approved by firestop manufacturer.
5. Select products with rating not less than rating of wall or floor being penetrated.

C. Single Source Responsibility: Provide firestop systems for all conditions from a single supplier.

D. Product Description: Provide Latex caulk/sealant, Silicone caulk/sealant, Intumescent Wrap Strip, Firestop Putty, Firestop Collar or Intumescent Sleeve to meet each specific application and performance requirement.

E. Primer: Type recommended by firestopping manufacturer for specific substrate surfaces and suitable for required fire ratings.

F. Installation Accessories: Provide clips, collars, fasteners, temporary stops or dams, and other devices required to position and retain materials in place.
1. Forming/Damming Materials: Mineral fiberboard, backer rod or other type recommended by Manufacturer’s tested system.

2.13 PENETRATIONS OF NON-RATED SURFACES

A. Stamped steel, chrome plated, hinged, split ring escutcheons or floor plates or ceiling plates for covering openings in occupied areas where piping is exposed.

B. For exterior wall openings below grade, furnish mechanical sealing device to continuously fill annular space between piping and cored opening or water-stop type wall sleeve.

2.14 CONDENSATE OVERFLOW SWITCH

A. Manufacturer: Rectorseal Safe-T-Switch or approved equal.

B. Sealed, waterproof reed/magnet float switch installed on the overflow outlet of drain pans or on an auxiliary drain pan. UL 508, 24 volt AC.

2.15 VIBRATION ISOLATORS

A. Manufacturers: Metraflex, Mason, Amber Booth or approved equal.

B. Restrained Closed Spring Isolators:
1. Spring Isolators:
a. For Exterior and Humid Areas: Furnish hot dipped galvanized housings and neoprene coated springs.
b. Code: Color code springs for load carrying capacity.
2. Type: Closed spring mount with top and bottom housing separated with neoprene rubber stabilizers.
3. Springs: Minimum horizontal stiffness equal to 75 percent vertical stiffness, with working deflection between 0.3 and 0.6 of maximum deflection.
4. Housings: Incorporate neoprene isolation pad meeting requirements for neoprene pad isolators, and neoprene side stabilizers with minimum 0.25 inch clearance and limit stops.

C. Rubber Mount or Hanger: Molded rubber designed for 0.5 inches deflection with threaded insert.

2.16 SPRING ISOLATION ROOF CURBS

A. Manufacturers: Mason Type RSC, Amber Booth, Vibro-Acoustics or approved.

B. Spring isolation type with rectangular steel tube lower member, continuous upper frame within "captive: guides, adjustable and removable rust-resistant steel springs mounted on 1/2" neoprene pads and having minimum deflection of 1-1/2", plated or galvanized hardware, flexible aluminum seal weatherproofing, waterproof, waterproof access ports and 2" insulation on lower curb.

2.17 TAGS

A. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inches high.

B. Metal Tags: Brass, Aluminum or Stainless Steel with stamped letters; tag size minimum 1-1/2 inches diameter with finished edges. Plain English designations.

C. Information Tags: Clear plastic with printed "Danger," "Caution," or "Warning" and message; size 3-1/4 x 5-5/8 inches with grommet and self-locking nylon ties.

D. Tag Chart: Plain English designations so no tag or valve chart is required.

2.18 PIPE MARKERS

A. Color and Lettering: Conform to ASME A13.1. Specific examples are noted in the table below.

Service	Background Color	Letter Color	Legend
Refrigerant	Purple	White	R-{TYPE} REFRIGERANT (EXAMPLE: R-410A REFRIGERANT)
Condensate	Black	White	CONDENSATE

B. Plastic Pipe Markers: Factory fabricated, flexible, semi-rigid plastic, preformed to fit around pipe or pipe covering. Larger sizes may have maximum sheet size with spring fastener.

C. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.

2.19 CEILING TACKS

A. Description: Steel with 3/4 inch diameter color-coded head.

B. Color code as follows:
1. HVAC equipment: Yellow.
2. Fire dampers/smoke dampers: Red.
3. Heating/cooling valves: Blue.

2.20 LOCKOUT DEVICES

A. Lockout Hasps: Anodized aluminum hasp with erasable label surface; size minimum 7-1/4 x 3 inches.

B. Valve Lockout Devices: Nylon device preventing access to valve operator, accepting lock shackle.

2.21 PAINT

A. Factory Finished Equipment: See individual equipment specification.

B. Ductwork: Paint interior of ductwork visible through grilles and diffusers with a flat black paint. Prepare and paint surfaces in accord with Division 9.

2.22 SEISMIC SUPPORTS

A. Provide seismic support as required by IBC 1613 and local authorities.

B. Sway bracing for ductwork, piping, and equipment shall consist of steel angles, rods or pipes. Shapes, lengths and methods of attachment shall be in accord with SMACNA “Guidelines for Seismic Restraints of Mechanical Systems”.

PART 3 EXECUTION

3.1 EXISTING WORK

A. Provide access to existing piping, ductwork, equipment and other installations remaining active and requiring access.

B. Extend existing piping and ductwork installations using materials and methods compatible with existing installations.

3.2 SURFACE PREPARATION

A. Clean substrate surfaces of dirt, dust, grease, oil, loose material, or other matter affecting bond of firestopping material.

B. Remove incompatible materials affecting bond of adhesives or firestopping.

C. Install backing or damming materials to arrest liquid material leakage.

D. Obtain permission from Architect/Engineer before drilling or cutting structural members.

E. Degrease and clean surfaces to receive adhesive for identification materials.

3.3 INSTALLATION-CLEARANCE

A. Appliances and equipment shall be accessible for inspection, service, repair and replacement.

B. Clearance shall be provided for the replacement of filters.

C. A minimum of 30” of clearance shall be provided in front of the control side of appliances and equipment. Provide additional space when required by NEC.

D. All control components shall be accessible for inspection and replacement.

3.4 INSTALLATION - INSERTS

A. Install inserts for placement in concrete forms.

3.5 INSTALLATION - VALVES

A. Install valves with stems upright or horizontal, not inverted.

B. Install brass male adapters each side of valves in copper piped system. Solder adapters to pipe.

C. Install valves with clearance for installation of insulation and allowing access.

D. Provide access panels where valves and fittings are not accessible.

E. Insulate valves according to application in Section 23 07 00.

3.6 INSTALLATION - PIPE HANGERS AND SUPPORTS

A. Support horizontal piping as scheduled.

B. Install hangers with minimum 1/2 inch space between finished covering and adjacent work.

C. Place hangers within 12 inches of each horizontal elbow.

D. Use hangers with 1-1/2 inch minimum vertical adjustment.

E. Support vertical piping at every floor.

F. Where piping is parallel and at same elevation, provide multiple pipe or trapeze hangers.

G. Support riser piping independently of connected horizontal piping.

H. Provide copper plated hangers and supports for copper piping.

I. Design hangers for pipe movement without disengagement of supported pipe.

J. Adjust hangers and supports as required to bring system to proper line and grade. Piping shall be plumb with floor and parallel/perpendicular to building structure.

K. Prime coat exposed steel hangers and supports. Hangers and supports located in crawl spaces, pipe shafts, and suspended ceiling spaces are not considered exposed.

L. Provide clearance in hangers and from structure and other equipment for installation of insulation. Insulated piping shall have insulation run continuous through hangers and supports with use of rigid inserts. Insulation shall be glued to both sides of insert at hangers and supports, no insulation gaps are allowed. Refer to Section 23 07 00.

M. Support of pipe, tubing and equipment shall be accomplished by means of engineered products, specific to each application. Makeshift, field devised methods shall not be allowed.

3.7 INSTALLATION-PIPING PROTECTION

A. Provide protective shield plates in concealed locations where piping, other than cast-iron or steel, is installed in studs, joists or rafters. Plates shall be 16 gage steel and cover the pipe area plus 2”. Shields may be omitted if piping is more than 1-1/2” from nearest edge of structural member.

3.8 INSTALLATION – DUCTWORK

A. Locate hangers, supports and accessories to handle loads imposed by ductwork, and air distribution devices and with maximum spacing noted.

B. Support all ductwork to prevent sag, undue play and swing.

C. Maximum support spacing per SMACNA standards. Spacing shall not exceed 10 feet.

D. Assemble and install hangers and supports on ductwork.

E. All supports and attachments for exposed ducts shall have non-removable fasteners.

F. Adjust hangers and supports as required to bring system to proper line and grade. Ductwork shall be plumb with floor and parallel/perpendicular to building structure.

3.9 INSTALLATION – SEISMIC CONTROLS

A. Provide seismic restraints and hangers in compliance with SBC 1613.

B. Seismic Bracing is required for:
1. All smoke control ductwork.
2. All ductwork associated with life safety systems (Including stair and elevator pressurization.
3. All ductwork with a cross sectional area of 6 square feet or a diameter of 34 inches or greater.

C. Follow SBC/IBC 1613, SMACNA Seismic Restraint Manual and the following.
1. Bracing shall be bidder designed to resist seismic loading in accord with Chapter 16 of the International Building Code or the SMACNA guideline.
2. Provide seismic calculations for all equipment as required for Ip = 1.0.
3. Transverse bracing shall occur at a maximum interval of 30 feet, at each duct turn and at the end of a duct run.
4. Longitudinal bracing shall occur at a maximum interval of 60 feet.
5. Bracing may be omitted where duct hangers are less than 12 inches in length.

3.10 INSTALLATION - EQUIPMENT BASES AND SUPPORTS

A. Provide housekeeping pads of concrete, minimum 4 inches thick and extending 6 inches beyond supported equipment.

B. Using templates furnished with equipment, install anchor bolts, and accessories for mounting and anchoring equipment.

C. Construct supports of formed steel channel or steel pipe and fittings. Brace and fasten with flanges bolted to structure.

D. Provide rigid anchors for pipes after vibration isolation components are installed.

3.11 INSTALLATION - FLASHING

A. Provide flexible flashing and metal Counterflashing where piping and ductwork penetrate weather or waterproofed walls, floors, and roofs.

B. Provide acoustical lead flashing around ducts and pipes penetrating equipment rooms for sound control.

C. Provide curbs for roof installations 14 inches minimum high above roofing surface. Flash and counter-flash with sheet metal; seal watertight. Attach Counterflashing to equipment and lap base flashing on roof curbs. Flatten and solder joints.

D. Adjust storm collars tight to pipe with bolts; caulk around top edge. Use storm collars above roof jacks. Screw vertical flange section to face of curb.

3.12 INSTALLATION - SLEEVES

A. Exterior watertight entries: Seal with mechanical sleeve seals.

B. Set sleeves in position in forms. Provide reinforcing around sleeves.

C. Size sleeves large enough to allow for movement due to expansion and contraction. Provide for continuous insulation wrapping.

D. Extend sleeves through floors 1 inch above finished floor level. Caulk sleeves.

E. Where piping or ductwork penetrates floor, ceiling, or wall, close off space between pipe or duct and adjacent work with insulation and caulk or fireproof airtight. Provide close fitting metal collar or escutcheon covers at both sides of penetration.

3.13 INSTALLATION – ACCESS PANELS

A. Furnish access panels for installation at all concealed equipment which requires service, maintenance or adjustment to include but not limited to equipment, dampers, control valves, filters and controls.

B. Provide location layout and required size for all access panels to general contractor. Layout shall be regular and consistent.

C. Furnish fire rated access panels where installed in fire rated assembly.

D. Furnish access panels to general contractor for installation

E. Paint installed access panels to match wall or ceiling. Verify that panels are not painted shut.

3.14 INSTALLATION – FIRESTOPPING AND SEALS AT PARTITIONS

A. Installation of Firestop shall be performed by either a specialty contractor specializing in firestop application (FM G 4991 or UL Qualified Firestop Contractor), or general or sub-contractors with experience in similar applications and projects with installers qualified, trained, and certified by the firestop manufacturer. Installation shall be performed in strict accordance with manufacturer's detailed installation procedures.

B. Install material at fire rated construction perimeters and openings containing penetrating sleeves, piping, ductwork, and other items, requiring firestopping.

C. Apply primer where recommended by manufacturer for type of firestopping material and substrate involved, and as required for compliance with required fire ratings.

D. Apply firestopping material in sufficient thickness to achieve required fire and smoke rating, to uniform density and texture.

E. Install dams when required to properly contain Fire stopping materials within openings and as required to achieve required fire resistance rating. Combustible damming material must be removed after appropriate curing. Incombustible damming materials may be left as a permanent component of the Firestop system.

F. Place foamed material in layers to ensure homogenous density, filling cavities and spaces. Place sealant to completely seal junctions with adjacent dissimilar materials.

G. Place intumescent coating in sufficient coats to achieve rating required.

H. Clean adjacent surfaces of firestopping materials.

I. Seal openings at surface as follows:
   1. Install sleeve through opening and extending beyond minimum of 1 inch on both sides of building element.
   2. Size sleeve allowing minimum of 1 inch void between sleeve and building element.
   3. Pack void with backing material.
   4. Seal ends of sleeve with UL listed fire resistive silicone compound to meet fire rating of structure penetrated.

3.15 INSTALLATION - PENETRATIONS OF NON-RATED SURFACES

A. Seal opening through non-fire rated wall, partition, floor, ceiling, and/or roof opening as follows:
   1. Install sleeve through opening and extending beyond minimum of 1 inch on both sides of building element.
   2. Size sleeve allowing minimum of 1 inch void between sleeve and building element.

B. Install escutcheons where piping penetrates non-fire rated surfaces in occupied spaces.

C. Exterior wall openings below grade: Assemble rubber links of mechanical sealing device to size of piping and tighten in place, in accordance with manufacturer's instructions.

D. Interior partitions: Seal pipe penetrations air tight. Apply sealant to both sides of penetration to completely fill annular space between sleeve and conduit.

3.16 INSTALLATION-VIBRATION ISOLATION

A. Install isolation for motor driven equipment.

B. Adjust equipment level.

3.17 INSTALLATION – CONDENSATE

A. For all cooling coils, high efficiency gas burners and other equipment requiring condensate drainage, provide appropriately sized condensate pumps where gravity drainage is not possible or where scheduled.

B. Coordinate number and type of condensate pumps required with Plumbing Contractor.

C. Provide condensate overflow switches on cooling coils where damage to building components could occur as a result of overflow as required by IMC.

3.18 INSTALLATION-IDENTIFICATION

A. Install identifying devices after completion of coverings and painting.

B. Install plastic nameplates with corrosive-resistant mechanical fasteners, or adhesive.

C. Install labels with sufficient adhesive for permanent adhesion and seal with clear lacquer. For unfinished canvas covering, apply paint primer before applying labels.

D. Install tags using corrosion resistant chain. Use plain English designations so no index or chart is required.

E. Nameplates: Identify mechanical equipment (air handling units, air terminal units, pumps, heat transfer equipment, tanks, and water treatment devices) with plastic nameplates.
   1. Identify in-line pumps and other small devices with name tags.
   2. Identify control panels and major control components outside panels with plastic nameplates.
   3. Identity description should be as numbered on drawings or plain English description. i.e. “EF-1” or “Boiler Controls”.

4. Label automatic controls, instruments, and relays. Key to control schematic.
5. Label wall controls and switches with associated equipment designation and control function, i.e. “EF-1 Switch”.

F. Pipe Labels: Identify piping, concealed or exposed, with plastic tape pipe markers.
1. Identify service, flow direction, and pressure.
2. Install in clear view and align with axis of piping.
3. Locate identification on straight runs including risers and drops with spacing not to exceed 20 feet.
4. Locate adjacent to each valve and tee, at each side of penetration of structure or enclosure, and at each obstruction.

G. Provide ceiling tacks to locate valves or dampers above T-bar type panel ceilings. Locate in corner of panel closest to equipment.

3.19 CLEANING

A. Contractor shall make all mechanical components free of dust and dirt prior to startup.

3.20 PROTECTION OF FINISHED WORK

A. Protect adjacent surfaces from damage by material installation.

3.21 SCHEDULES

A. Copper and Steel Pipe Hanger Spacing:

PIPE SIZE Inches	COPPER TUBING MAXIMUM HANGER SPACING Feet	STEEL PIPE MAXIMUM HANGER SPACING Feet	COPPER TUBING HANGER ROD DIAMETER Inches	STEEL PIPE HANGER ROD DIAMETER Inches
1/2	5	7	3/8	3/8
3/4	5	7	3/8	3/8
1	6	7	3/8	3/8
1-1/4	7	7	3/8	3/8
1-1/2	8	9	3/8	3/8
2	8	10	3/8	3/8

END OF SECTION

SECTION 23 05 93

TESTING, ADJUSTING, AND BALANCING

PART 1 GENERAL

1.1 SCOPE

A. Testing, adjusting and balancing of air systems.

B. Testing, adjusting and balancing of refrigerant systems.

C. Measurement of final operating conditions of above systems.

D. Duct pressure (leakage) testing as required by 23 31 00.

E. Preparation of formal report.

1.2 PERFORMANCE CRITERIA

A. Work shall be performed by approved independent testing and balancing agency.

B. Perform testing and balancing in accordance with Associated Air Balance Council (AABC) or National Environmental Balancing Bureau (NEBB). All work shall be supervised.

C. Calibrate instruments used for testing and balancing within a period of six months of start of work.

D. Mechanical contractor shall assist Balancing Agency in testing and balancing of mechanical system.

1.3 SUBMITTAL

A. Provide three (3) copies of typed and bound report to be included in Preliminary Commissioning Report.

B. Provide three (3) additional copies of updated and/or corrected report for Final Commissioning Report.

1.4 FORMAT

A. Report shall consist of test sheets similar to AABC Standard Forms for Diffusers and Grilles, Air Handling Equipment, Exhaust Fans, and Pumps (i.e., Form 12666 for Diffusers and Grilles).

B. Report shall include the following.
1. Preface suggesting abnormalities and problems encountered.
2. Instrumentation List including type, model, manufacturer, serial number, and calibration dates.

3. System Identification reporting location of equipment, zones, supply, return, and exhaust openings.
4. Record following for each piece of air handling equipment.
   a. Manufacturer, model number, and serial number.
   b. Design and manufacturer rated data.
   c. Actual CFM
   d. Suction and discharge static pressure of each fan.
   e. Outside-air and return-air total CFM.
   f. Actual operating current, voltage, and brake horsepower of each fan motor.
   g. Final RPM of each motor.
   h. Fan and motor sheave manufacturer, model, size, number of grooves and center distance.
   i. Belt size and quantity.
   j. Static-pressure controls final operating set points.

1.5 QUALIFICATIONS

A. Work of this section shall be performed by independent Air Testing and Balance Agency specializing in testing and balancing of heating, ventilating, and cooling systems to balance, adjust, and test air moving equipment, air distribution, and exhaust systems.

B. Agency shall provide proof of having successfully completed at least five years of specialized experience in air and hydronic system balancing. Work by this Agency shall be done under direct supervision of qualified heating and ventilating engineer employed by Agency.

C. Agency shall be approved in writing by Architect.

D. Neither Architect's engineering consultant nor anyone performing work on this Project under Division 23 shall be permitted to do this work.

1.6 ACCEPTABLE TEST AND BALANCE COMPANIES

A.	AIRTEST Co., Inc.	425-313-0172
B.	Neudorfer Engineers, Inc.	206-621-1810
C.	Hardin & Sons	253-862-6645
D.	American Air Measurement	425-788-4036

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify systems are complete and in good working order before commencing work. Then, put all systems and equipment into operation and continue operation until all adjusting, balancing, testing, demonstrations, instructions and cleaning of systems have been completed. Verify the following:
   1. Systems are started and operating in safe and normal condition.
   2. Temperature control systems are installed complete and operable.
   3. Proper thermal overload protection is in place for electrical equipment.
   4. Final filters are clean and in place.
   5. Duct systems are clean of debris.
   6. Fans are rotating correctly.
   7. Fire and volume dampers are in place and open.
   8. Air coil fins are cleaned and combed.
   9. Access doors are closed and duct end caps are in place.
   10. Air outlets are installed and connected.
   11. Duct system leakage is minimized.
   12. Service and balancing valves are open.

3.2 PREPARATION

A. If requested, conduct tests in presence of Architect.

B. Instruments used by Agency shall be accurately calibrated and maintained in good working order.

C. Furnish instruments required for testing, adjusting, and balancing operations including ladders, scaffolding, additional dampers and clean filters.

D. Make instruments available to Architect/Engineer to facilitate spot checks during testing.

E. During balancing technician's initial test of air handling systems, the Mechanical Contractor shall have his sheetmetal foreman present to assist in any drive changes or dampers necessary.

3.3 INSTALLATION TOLERANCES

A. Diffuser, register and grille air flow rates shall be measured and adjusted to deliver final flow rates within 10% and within 50 cfm of design rates.

B. Fan air flow rates shall be measured and adjusted to deliver final flow rates within 10% and within 50 cfm of design rates.

C. Water flow rates shall be measured and adjusted to deliver final flow rates within 10% and within 5 gpm of design rates.

D. Pump flow rates shall be measured and adjusted to deliver final flow rates within 10% and within 25 gpm of design rates.

3.4 ADJUSTING

A. Ensure that clean filters, of the type specified, are installed prior to air balancing.

B. Provide additional volume dampers as necessary to accomplish design balances.

C. Record setting and corresponding flowrate of Pressure Independent Volume Dampers (PIVD). Verify actual flowrate.

D. Set minimum position of motorized dampers for scheduled minimum outside air.

E. Check motors for proper rotation, coupling and drive alignment, belt tension and freedom from vibration, etc.

F. Provide belt drive/sheave changes to adjust fan rpm as necessary to accomplish design balances.

G. Verify recorded data represents actual measured or observed conditions.

H. Permanently mark settings of valves, dampers, and other adjustment devices allowing settings to be restored. Set and lock memory stops.

I. After adjustment, take measurements to verify balance has not been disrupted. If disrupted, verify correcting adjustments have been made.

J. Report defects and deficiencies noted during performance of services, preventing system balance.

K. Leave systems in proper working order, replacing belt guards, closing access doors, closing doors to electrical switch boxes, and restoring thermostats to specified settings.

L. After completion of testing and balancing, operate systems under normal conditions for at least two days of 8 hours each to demonstrate specified performance.

3.5 AIR SYSTEM PROCEDURE

A. Perform soloing testing and balancing functions in accordance with Associates Air Balance Council National Standards.

B. Adjust air handling and air distribution systems to obtain design supply, return, and/or exhaust air quantities.
   1. Test and adjust total system CFM by adjustment of fan speeds. Provide sheave drive changes as necessary.
   2. Perform tests at high and low speeds of variable speed systems.
   3. Adjust branch air quantities by damper regulation. Multi-diffuser branch ducts shall have at least one outlet or inlet volume damper completely open to minimize throttling losses.
   4. Make air quantity measurements in main ducts and for outside air by Pitot tube traverse of entire cross sectional area of duct.

5. Measure air quantities at air inlets and outlets.

C. Diffusers, Registers and Grilles:
1. Adjust air distribution to obtain uniform space temperatures free from objectionable drafts.
2. Use volume control devices to regulate air quantities only to the extent that the adjustments do not create objectionable air motion or sound levels.
3. Effect volume control by using volume dampers located in ducts.

D. Provide system schematic:
1. Identify the location and area of each grille, diffuser, register, and terminal box.
2. Record the required and actual air quantities at each outlet or inlet.
3. Record size, type, and manufacturer of each diffuser, grille, and register on air outlet data sheets.

E. Air Temperature:
1. Measure wet and dry bulb air temperatures on entering and leaving side of each cooling coil and unit in cooling mode.
2. Measure dry bulb temperatures on entering and leaving side of each heating coil and unit in heating mode.

F. Pressure:
1. Measure static pressure conditions on air units, including filter and coil pressure drops, and total pressure across fan with suction and discharge pressures.
2. Make air balancing allowances for 50 percent loading of filters.
3. Measure building static pressure.

G. Electrical:
1. Record nameplate motor current and voltage.
2. Measure actual motor current and voltage at balanced condition.

H. Dampers:
1. Adjust outside air, return air, and exhaust dampers for design conditions.
2. At modulating damper locations, take measurements and balance at extreme conditions.

I. Permanently mark all outside air, supply air, and return air damper positions after balancing has been completed.

J. Smoke testing, or some other approved means, may be required to determine leak locations if air balance report indicated that any system’s CFM total is less than 10 percent of design CFM. Prior to test, verify that system’s duct joints have been sealed as specified and that air moving device in question is supplying required design system air flow. Architect will approve test method required. If smoke test is selected, use following procedure. Provide necessary precautions to protect those performing or observing test from being exposed to smoke.

1. Use zinc chloride smoke candles, titanium tetrachloride ampules or sticks, or other devices acceptable to Architect to generate smoke.
2. Close openings in duct except for one opening at farthest end of duct run.
3. If re-balancing is required, submit revised air test and balance reports to Architect before Substantial Completion.
4. Spot balance and rebalance shall be performed at no additional cost to Owner.

3.6 FINAL INSPECTION AND ADJUSTMENTS

A. System shall be balanced and reports submitted before substantial completion inspection.

B. Balancing Agency shall be represented at inspection meeting(s) by qualified testing personnel with balancing equipment and two copies of current air balancing test report.
1. Architect will choose and direct spot balancing. Differences greater than specified tolerance between the spot balance and test report will be justification for requiring repeat of testing and balancing for entire building and submission of a new test report. In such case a new inspection will be made.
2. Perform rebalancing in presence of Architect/Engineer and subject to their approval.
3. If re-balancing is required, submit revised air test and balance reports to Architect before Substantial Completion.
4. Spot balance and rebalance shall be performed at no additional cost to Owner.

C. Where systems provides over 5 percent more air than schedule requirements, rooms supplied by that system shall have their supply air quantities increased by ratio of actual total air quantity supplied to minimum air quantity required by system schedule.

3.7 SUPPLEMENTAL WARRANTY

A. Test and balance agency shall include an extended warranty of 90 days, after occupancy, during which the Owner's representative, at his discretion, may request a recheck or resetting of any outlet, supply air or exhaust fan, as listed in test report.

END OF SECTION

SECTION 23 07 00

HVAC INSULATION

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Piping system insulation.
2. Pipe insulation jackets.
3. Ductwork insulation.
4. Duct liner.

1.2 QUALITY ASSURANCE

A. Insulation must have maximum flame spread index of 25 and maximum smoke developed index of not exceeding 50 in accordance with ASTM E84.

B. All systems components subject to heat loss or gain, such as, piping, storage tanks, vessels, valves etc. shall be insulated to conform with the Washington State Energy Code (as minimum) and this section.

1.3 IDENTIFICATION

A. Insulation shall bear a manufacturer's mark indicating the product R-value or K-value and thickness. This mark shall be visible after installation and shall be repeated at an interval of no more than 10 feet.

B. External duct insulation shall be legibly printed or indentified at intervals not greater than 36 inches with name of manufacturer, R-value, thickness, flame spread and smoke-developed index.

C. R-values shall be based on insulation only at 75 F mean temperature difference.

D. For rigid or spray foam the aged R-value per inch shall be provided in submittals.

PART 2 PRODUCTS

2.1 POLYOLEFIN INSULATION

A. Manufacturers: IMCOA or similar.

B. Polyolefin or Polyethylene pipe insulation is **NOT ACCEPTABLE** for any application.

2.2 ELASTOMERIC CELLULAR FOAM (PIPE)

A. Manufacturers: Armacell AP/Armaflex, Aeroflex Aerocel or approved equal.

B. Preformed flexible, closed-cell, elastomeric thermal insulation: Type I, Tubular form, self-seal or continuous, 25/50-rated, CFC free, low VOC, 'K' factor: 0.27 at 75 degrees F. ASTM C534.

C. Rigid clamp/hanger insert: Armacell Armafix, polyurethane insert and aluminum jacket, single piece with self-adhering closure.

2.3 FLEXIBLE GLASS FIBER DUCT LINER (SOUND LINER)

A. Manufacturers: Johns Manville Linacoustic RC or equal by Knauf or approved equal.

B. Description: Flexible duct liner, glass fiber bonded with thermosetting resin, airstream surface protected with reinforced coating.
1. ASTM E84, UL 723
2. Installed R Value: 1" R-4.2, 2” R-8.0
3. Maximum service temperature: 250 degrees F.
4. Maximum Velocity on Coated Air Side: 6,000 fpm.
5. Acrylic polymer coating to prevent dust incursion and biological growth.

C. Liner Fasteners: Galvanized steel, impact applied or welded with integral head.

D. Field coat edges with Superseal edge treatment.

2.4 ELASTOMERIC CELLULAR FOAM DUCT LINER (SOUND LINER)

A. Manufacturers: Armacell AP/Coilflex or approved equal.

B. Description: Fiber-free, non-particulating, formaldehyde-free, low VOC elastomeric form roll which conforms to duct corners without compression. Microban antimicrobial protection inhibits mold and mildew.
1. ASTM E84, UL 723
2. Installed R Value: 1” R-4.2, 1-1/2” R-6.0
3. Maximum service temperature: 180 degrees F
4. Maximum velocity: 10,000 fpm.

C. Install as a cross-section single piece fitting around corners.

D. Apply with water based adhesive.

2.5 POLYESTER DUCT LINER (SOUND LINER)

A. Manufacturers: Ductmate PolyArmor or approved equal.

B. Description: Fiberglass free, hypoallergenic polyester blanket with FSK facing.
1. ASTM E84, UL 723
2. Installed R Value: 1” R-4.2, 1-1/4” R-5, 1-1/2” R-6.0, 2” R-8.0
3. Maximum service temperature: 250 degrees F
4. Maximum velocity: 4,000 fpm.

C. Provide metal nosing and water based edge coating.

D. Apply with water based adhesive and pins.

2.6 GLASS FIBER ROUND DUCT LINER (SOUND LINER)

A. Manufacturers: Johns Manville Spiracoustic Plus or equal by Knauf or approved equal.

B. Description: High-density fiber glass board with kerfs; acrylic polymer meeting ASTM G21 impregnated surface coat. ASTM C1071.
1. 'K' factor: 0.23 at 75 degrees F.
2. Installed R Value: 1" R-4.3, 2" R-8.4
3. Maximum service temperature: 250 degrees F.
4. Maximum Velocity on Coated Air Side: 4,000 fpm.

2.7 ELASTOMERIC CELLULAR FOAM ROUND DUCT LINER (SOUND LINER)

A. Manufacturers: Armacell AP/Spiralflex or approved equal.

B. Description: Fiber-free, non-particulating, formaldehyde-free, low VOC elastomeric form roll which is self-supporting and conformable to round duct. Microban antimicrobial protection inhibits mold and mildew.
1. ASTM E84, UL 723
2. 'K' factor: 0.28 at 75 degrees F
3. Installed R Value: 1" R-4.2
4. Maximum service temperature: 180 degrees F
5. Maximum velocity: 10,000 fpm.

2.8 GLASS FIBER DUCT WRAP

A. Manufacturers: Johns Manville Microlite XG 75 or equal by Owens-Corning, Knauf or approved equal.

B. Description: Formaldehyde-free, flame-attenuated glass fibers bonded with thermosetting acrylic resin, FSK facing.
1. 'ASTM E84, UL 723
2. Installed R Value: 1-1/2" R-4.2, 2" R-5.6, 3" R-8.3.
3. Maximum Service Temperature: 250 degrees F.
4. Density: 0.75 lb/cu ft

C. Vapor Retarder Jacket: Reinforced FSK facing. Seal with pressure sensitive 2" tape.

D. Identification: At intervals not greater than 36" print the name of manufacturer, the thermal resistance R-value at insulation thickness, the flame spread and smoke developed indexes.

2.9 PIPE INSULATION AND EQUIPMENT JACKETS

A. PVC Plastic Pipe Jacket:
   1. Product Description: One piece molded type fitting covers and sheet material, white color. ASTM D1784.
   2. Thickness: 15 mil indoor, 30 mil outdoor.
   3. Connections: Brush on welding adhesive.

B. Aluminum Pipe Jacket:
   1. Thickness: 0.016 inch thick sheet. ASTM B209.
   2. Finish: Embossed
   3. Joining: Longitudinal slip joints and 2 inch laps.
   4. Fittings: 0.016 inch thick die shaped fitting covers with factory attached protective liner.
   5. Metal Jacket Bands: 3/8 inch wide; 0.015 inch thick aluminum.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify piping and equipment has been tested before applying insulation materials.

B. Verify surfaces are clean and dry, with foreign material removed.

3.2 INSTALLATION

A. Apply insulation when building is thoroughly dry to prevent shrinkage.

B. Exposed Piping: Locate insulation and cover seams in least visible locations.

C. Insulate entire piping system including fittings, valves, unions, flanges, strainers, flexible connections, pump fittings, connections to equipment and expansion joints. Use canvas jackets for valves and other irregular shapes.

D. Insulate flanges and unions with removable sections and jackets.

E. Piping Inserts and Shields:
   1. Insulation shall be continuous through supports and hangers with incompressible inserts and shields. Do not directly clamp/support pipe scheduled to be insulated.
   2. Shields: Galvanized steel saddle between pipe clevis hangers or pipe rollers and insulation. Minimum 6 inches long, of contour matching adjoining insulation; may be factory fabricated.
   3. Inserts: Between pipe clamps, hangers or rollers and piping.
   4. Insert material: Compression resistant insulating material suitable for insulation type and planned temperature range and service.
   5. Glue insulation to both sides of insert.

6. Shields without inserts may be used at clevis hangers on refrigerant piping 5/8” and smaller with continuous insulation.

F. Continue insulation through penetrations of building assemblies or portions of assemblies having fire resistance rating of one hour or less. Provide intumescent firestopping when continuing insulation through assembly. Finish at supports, protrusions, and interruptions.

G. Pipe Exposed in Mechanical Equipment Rooms or Finished Spaces: Finish with PVC jacket and fitting covers.

H. Exterior Piping Applications: Use only elastomeric closed-cell foam insulation. Insulate fittings, joints, and valves with insulation of like material and thickness as adjoining pipe, and finish with sealant. Cover with aluminum jacket with seams located at 3 or 9 o’clock position on side of horizontal piping with overlap facing down to shed water or on bottom side of horizontal equipment.

I. Apply insulation close to equipment by grooving, scoring, and beveling insulation. Fasten insulation to equipment with studs, pins, clips, adhesive, wires, or bands.

J. Fill joints, cracks, seams, and depressions with bedding compound to form smooth surface. On cold equipment, use vapor retarder cement.

K. Finish insulation at supports, protrusions, and interruptions.

L. Nameplates and ASME Stamps: Bevel and seal insulation around; do not insulate over.

M. Insulate exhaust air ductwork where it is outside the insulated building envelope to prevent condensation.

N. For all insulated ductwork:
1. Provide insulation with vapor retarder jackets.
2. Finish with tape and vapor retarder jacket.
3. Continue insulation through walls, sleeves, hangers, and other duct penetrations.
4. Insulate entire system including fittings, joints, flanges, fire dampers, flexible connections, and expansion joints.

O. Duct and Plenum Liner Application:
1. Adhere insulation with adhesive for 100 percent coverage.
2. Secure insulation with mechanical liner fasteners. Comply with SMACNA Standards for spacing.
3. Seal and smooth joints. Seal and coat transverse joints.
4. Seal liner surface penetrations with adhesive.
5. Duct dimensions indicated are net inside dimensions required for airflow. Increase duct size to allow for insulation thickness.

3.3 SCHEDULES

A. Piping: Provide on piping as listed below.

		PIPE SIZE			
Service	**Insulation Type**	**<1”**	**1” to <1-1/2"**	**1-1/2 to < 4"**	**4" to < 8”**
Refrigerant Suction(1)	Elastomeric Cellular FOAM	1"	1"	1-1/2"	-
Refrigerant Hot Gas	Elastomeric Cellular FOAM	1"	1"	1-1/2"	-

1. Note: Insulate Refrigerant Liquid lines same as Suction lines on all Mitsubishi brand equipment, where noted by manufacturer or called for on plans.
2. For all exterior piping applications use only Elastomeric Cellular Foam with Aluminum jacket.

B. Ductwork: Provide on ductwork as listed below. Insulation thickness is provided as reference; each application must meet minimum installed R-Value.

Service	**Location**	**Insulation Type**	**Approx. Thickness**	**Min. Installed R-Value**	**Jacket**
Supply, Return, Exhaust	Unconditioned Space Inside Bldg.	Glass Fiber Duct Wrap	2"	R-6	FSK
Supply	Concealed Space (3)	Glass Fiber Duct Wrap	1-1/2"	R-3.3	FSK
Supply	Exposed (4) in Space With Supply Air Temp ≤55 F or ≥105 F	Glass Fiber Duct Wrap / Duct Liner	1-1/2"	R-3.3	FSK
Supply	Exposed in Space With Supply Air Temp Between 56-104F	None, Except Duct Liner shown on Plans.			
Outside Air	Within Building <2800 cfm (4)	Glass Fiber Duct Wrap / Duct Liner	3"	R-7	FSK
Exhaust Air	Outside the Insulated Building Envelope	Glass Fiber Duct Wrap	2"	R-6	FSK

Exhaust Air	Between backdraft damper & building exterior.	Glass Fiber Duct Wrap	3"	R-7	FSK

1. Secure duct wrap with mechanical fasteners spaced 12” on center, minimum. For horizontal ducts 24” or more in width, duct wrap shall also be secured with mechanical fasteners spaced 18” on center, on centerline of bottom of duct.
2. Insulation is not required on sound lined ductwork with sufficient insulating value.
3. Concealed space: Any space within the insulated building envelope that is concealed from view, i.e. behind ceiling, wall, shaft, soffit, etc.
4. For exposed ductwork in finished spaces which is required to be insulated provide internal liner with equivalent R-value.
5. Insulation required from exterior to shutoff damper or equipment. After damper provide R-7 insulation.

END OF SECTION

SECTION 23 08 00

PROJECT COMMISSIONING

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Project commissioning description.
2. Project commissioning responsibilities.
3. Project commissioning documentation.

1.2 GENERAL

A. The goal of the commissioning process is to verify the proper operation, functionality and control of building systems and equipment. The by-product of this process is the commissioning plan and report which provides a confirmation record of procedures used and results obtained. The effort and goal is focused on having all systems operating efficiently and correctly.

B. The mechanical contractor shall retain a Commissioning Agent (CA) and commissioning services from one of the following companies or approved equal.

1.	AIRTEST Co., Inc.	425-313-0172
2.	Neudorfer Engineers, Inc.	206-621-1810
3.	American Air Measurement	425-788-4036

C. The mechanical contractor is responsible for the commissioning process with required documentation and shall furnish labor and material directly or through the Commissioning Agent to accomplish building commissioning as specified herein.

D. The mechanical contractor is responsible to correct deficiencies discovered during the commissioning process.

1.3 COMMISSIONING DESCRIPTION

A. The purpose of the commissioning process is to provide Owner assurance that the systems have been installed in the prescribed manner and will operate within the performance guidelines. Commissioning is intended to enhance the quality of system start-up and aid in the orderly transfer of systems to beneficial use by the Owner.

B. Commissioning includes complete and thorough investigations of mechanical systems to ensure proper installation and operation of all components and systems. It consists of but is not limited to the following elements:
1. The Commissioning Plan
2. Testing and startup of HVAC equipment and systems.
3. Testing and startup of any appropriate plumbing systems, such as water heating plants, circulation pumps and sewage ejectors.
4. Equipment control and system verification checks.
5. Air balancing.
6. Functional performance testing.

7. Sequence of operations testing.
8. Completion of record drawings.
9. Owner training.
10. Operation & Maintenance materials.
11. Preliminary Commissioning Report with deficiencies noted.
12. Final Commissioning Report with corrective actions taken.

1.4 COMMISSIONING AGENT

A. The Commissioning Agent (CA) is the person who manages the commissioning process, prepares the Commissioning Plan, schedules and coordinates commissioning activities in execution of the Commissioning Plan and compiles the Commissioning Report.

B. The CA may directly perform commissioning functions and documentation or may observe tasks assigned to others.

C. The CA provides the Owner an unbiased, objective view of the system's installation, documentation, operation, and performance.

D. The CA will observe the Commissioning procedures and results performed by the Contractor. The Contractor is expected to verify the functional readiness of systems to be tested prior to performing the tests in the presence of the Commissioning Agent.

1.5 COMMISSIONING SUBMITTALS

A. See 23 00 00.

B. Commissioning Plan: Submit copies with mechanical submittals.
1. Narrative description of activities.
2. Start-up test procedure and checklists
3. Functional performance test checklists.
4. Commissioning schedule

C. Preliminary Commissioning Report: Submit three (3) copies at substantial completion.
1. Complete start-up checklists
2. Complete functional test reports
3. Test & Balance report
4. Deficiency report

D. Final Commissioning Report: Submit three (3) copies at project close out.
1. Preliminary Commissioning Report contents
2. Record drawings
3. Owner training report
4. Deficiency & corrective action report
5. O&M manuals

1.6 QUALITY ASSURANCE

A. Perform Work in accordance with NEBB or AABC.

B. Perform Work in accordance with ASHRAE Guideline 1.

C. Perform Work in accordance with Commercial Energy Code Section C408.

1.7 COMMISSIONING MEETINGS

A. The CA shall schedule a preliminary commissioning meeting to review the commissioning plan and schedule approximately two weeks prior to the start of commissioning work. The General Contractor, Mechanical Contractor, Electrical Contractor and Electrical Commissioning Agent, applicable sub-contractors and the Engineer shall be invited.

B. The CA shall schedule additional commissioning meetings as necessary for coordination or information with the required participants.

C. The General Contractor, Mechanical Contractor and Mechanical Sub-Contractors are required to attend commissioning meetings when requested by the CA or Engineer.

1.8 SCHEDULING

A. The CA shall prepare a schedule indicating anticipated start dates for the following:
1. Piping systems pressure testing (domestic, gas, hydronic, refrigerant).
2. Piping system flushing and cleaning.
3. Ductwork cleaning.
4. Ductwork pressure testing.
5. Equipment and system startups.
6. Automatic temperature control system checkout.
7. Testing, adjusting, and balancing.
8. Functional performance tests
9. System orientation and training.
10. Operation and maintenance manual submittals.

B. Schedule seasonal tests of equipment and systems during peak weather conditions (actual or simulated) to observe full-load performance.

C. Schedule occupancy sensitive tests during conditions of both minimum and maximum occupancy use.

D. Schedule such that the Preliminary Commissioning Report can be submitted to the Owner for review with written acceptance obtained prior to the final mechanical inspection and the building certificate of occupancy.

E. Within 90 days of receipt of the building certificate of occupancy, the Record Drawings, O&M Manuals, Final Balancing Report, Final Commissioning Report and documentation of completed Owner Training shall be submitted for review.

1.9 COORDINATION

A. The mechanical contractor shall verify the commissioning schedule and notify the Commissioning Agent a minimum of two weeks in advance of the following:
1. Scheduled equipment and system startups.
2. Scheduled automatic temperature control system checkout.
3. Scheduled start of testing, adjusting, and balancing work.
4. Commissioning schedule changes.

B. Coordinate programming of automatic temperature control system with construction and commissioning schedules.

C. Coordinate commissioning of this section with Electrical commissioning.

D. Provide overall coordination and management of the commissioning program as specified herein. The commissioning process will require cooperation of the Contractor, subcontractors, vendors, Architect, Commissioning Agent, and Owner. The commissioning team shall be comprised of the following:
1. Contractor
2. Project Manager
3. Test & Balance Engineer
4. Subcontractors
5. Commissioning Agent
6. Project Engineers
7. Owner Representative(s)
8. Architect
9. Mechanical Consultant
10. Electrical Consultant

PART 2 DOCUMENTATION

2.1 COMMISSIONING PLAN

A. The Commissioning Plan shall be prepared and executed by the Commissioning Agent and at a minimum contain the following.

B. The Commissioning Plan shall be in a hard-backed loose-leaf binder with typewritten or printed index and tabbed dividers between principal categories.
1. Spine: Name of Project
2. Cover: Name of Project, Owner, Location & Commissioning Agent
3. Project Directory: Owner, Architect, Engineer, Commissioning Agent, General Contractor, Mechanical Contractor(s), Plumbing Contractor, Electrical Contractor, Test & Balance Contractor, Controls Contractor.
4. Responsible Party: Include responsible party for each contractor.

C. Narrative:
1. Describe building size, type of use and occupancy.
2. Provide an overview of the building equipment, systems, controls and their functionality.
3. Describe the activities involved in each phase of the commissioning process, including the personnel intended to accomplish each task.

D. Roles and Responsibilities:
1. Define the tasks necessary to complete the commissioning process and assign responsibility for each to a member of the commissioning team.

E. Commissioning Schedule:
1. Provide timeline of commissioning process tasks and information submittals with milestones for general scopes of work.
2. Include task for sub-contractors, contractors, vendors and CA.
3. Include owner training schedule.

F. Start-up Test Procedure and Checklists:

1. Include a list of all equipment and systems to be tested.
2. Intent: To test individual equipment for standalone function and operation.
3. Use manufacturer's startup checklist when available.
4. Utilize vendor startup and checklists for specific equipment when available.

G. Functional Performance Test checklists:
1. Intent: To test system performance and operation including controls, relays and sequences.
2. Include tests for all functions noted in Sequence of Operations.
3. Indicate conditions under which the test needs to be performed.
4. Indicate the measured criteria required to meet the performance.
5. Include space on forms to note deficiencies.

2.2 FUNCTIONAL PERFORMANCE TESTING

A. Demonstrate the correct installation and operation of each component, system, and system-to-system intertie relationship. Control systems shall be tested to ensure that control devices, components, equipment and systems are calibrated, adjusted and operate in accordance with the sequence of operation.

B. Test all system modes and all functions describe in the Sequence of Operations.

C. Test systems under full-load, part-load (if applicable) and emergency conditions (if applicable).

D. Test any redundant or automatic back-up mode.

E. Test performance of all alarms and safeties.

F. Test mode of operation upon loss of power and power restoration.

G. Independently test all similar systems. Sampling reference systems is not acceptable.

H. Physically verify by visual inspection or calibrated meter reading the operation being tested. Control system displays shall not be used as proof of function.

2.3 PRELIMINARY COMMISSIONING REPORT

A. The Preliminary Commissioning Report shall be assembled and produced by the Commissioning Agent with information obtained from the Mechanical Contractor, Controls Contractor and Test & Balance Contractor. The report shall contain the following.

B. The Commissioning Report shall be in hard-backed loose-leaf binder(s) with typewritten or printed index and tabbed dividers between principal categories.
1. Spine: Name of Project
2. Cover: Name of Project, Owner, Location & Commissioning Agent
3. Project Directory: Owner, Architect, Engineer, Commissioning Agent, General Contractor, Mechanical Contractor(s), Test & Balance Contractor, Controls Contractor.

C. System Description: Describe building systems and their intended function(s). Include equipment associated with each system.

D. Test & Balance Report: See 23 05 93

E. Start-up Test Checklists: Include completed start-up checklists.

F. Functional Performance Test Checklists:
1. Include completed functional performance checklists.
2. Include sequence of operations checklists.
3. Record conditions under which the tests were performed.
4. Record the measured criteria.

G. Deferred tests: Indicate any tests not performed due to climatic conditions with anticipated date of completion.

H. Deficiency Report: Compile any deficiencies noted on start-up or functional performance tests on to a single report.

I. Owner Training: Include documentation of owner operating and maintenance instruction completed to date. See section 23 00 00.

2.4 FINAL COMMISSIONING REPORT

A. The Final Commissioning Report shall be assembled and produced by the Commissioning Agent with information obtained from the Mechanical Contractor, Controls Contractor and Test & Balance Contractor. The Final Commissioning Report shall contain all the information provided in the Preliminary Commissioning Report and the following.

B. The Commissioning Report shall be in hard-backed loose-leaf binder(s) with typewritten or printed index and tabbed dividers between principal categories.
1. Spine: Name of Project
2. Cover: Name of Project, Owner, Location & Commissioning Agent
3. Project Directory: Owner, Architect, Engineer, Commissioning Agent, General Contractor, Mechanical Contractor(s), Test & Balance Contractor, Controls Contractor.

C. Test & Balance Report: Provide updated and/or corrected report if required.

D. Deficiency and Corrective Action Report: Include the deficiency report from the Preliminary Commissioning Report with the corrective action taken noted for each entry.

E. Owner Training: Include documentation of completed owner operating and maintenance instruction. See section 23 00 00.

F. Record Drawings: Include contractor's record drawings in each copy of the commissioning report. See section 23 00 00.

G. Operating and Maintenance Manuals: Include contractor's O&M manuals with each copy of the commissioning report. (Separate binders are OK) See section 23 00 00.

PART 3 EXECUTION

3.1 GENERAL

A. Contractor shall provide an individual to accompany the Commissioning Agent to assist, operate and/or make adjustments as necessary.

B. Contractor shall provide ladders, scaffolding, additional dampers and clean filters as required.

C. Contractor shall put all systems and equipment into operation and shall continue operation until all adjusting, balancing, testing, demonstrations, and instructions have been completed.

D. Commissioning shall not begin until systems are completed, in good working order and have been cleaned.

E. Check motors for proper rotation, coupling and drive alignment, belt tension and freedom from vibration, etc.

3.2 INSTALLATION

A. Contractor shall provide additional balancing dampers, balancing valves, access doors, test ports, and pressure and temperature taps required by Commissioning Agent or to address Commissioning deficiency.

B. Contractor shall provide replacement sheaves and belts to obtain system performance.

C. Contractor shall install test holes in ductwork and plenums as requested by Commissioning Agent for taking air measurements. Seal test holes after measurements.

D. Prior to start of functional performance testing, Contractor shall install clean filters in equipment.

3.3 DEFICIENCIES

A. The Commissioning Agent shall report all observed system deficiencies to the Architect and General Contractor and shall include them in the Preliminary Commissioning Report.

B. The Contractor shall rectify all deficiencies, detail the corrective action(s) taken on each item, initial each item of the report as "corrected" and return the deficiency report.

C. Upon receipt of the return report, the Commissioning Agent will visit the site and inspect the corrected deficiencies. The Commissioning Agent will also initial the items of the report as "checked" and include them in the Final Commissioning Report.

D. Further site visits by the Commissioning Agent to check deficiencies not corrected in back check, will be at the Contractor’s expense.

END OF SECTION

SECTION 23 09 00

INSTRUMENTATION AND CONTROL FOR HVAC

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Thermostats.
2. Timers
3. Electric damper actuators.
4. Gas sensors

1.2 SCOPE

A. The mechanical contractor shall install a complete, properly adjusted and effective temperature control system.

B. This section includes field assembled instrumentation and temperature controls for air conditioning, heating, ventilation and exhaust systems.

C. See drawings for Sequence of Operation.

D. See Equipment Schedules and associated specification sections for controls integral to HVAC equipment.

E. Controls shall be electric/electronic systems.

F. Manufacturers of components shall be equipment manufacturer, Honeywell or approved.

G. Any additional parts necessary to or incidental for a complete and operating system shall be the responsibility of the contractor.

1.3 MAINTENANCE SERVICE

A. Furnish service and maintenance of control system for one year from Date of Substantial Completion.

B. Furnish complete service of controls systems, including callbacks and service calls.

C. Furnish two complete inspections per year, one in each season, to inspect, calibrate, and adjust controls. Submit written report after each inspection.

D. Include systematic examination, adjustment, and lubrication of unit, and controls checkout and adjustments. Repair or replace parts in accordance with manufacturer's operating and maintenance data. Use parts produced by manufacturer of original equipment.

E. Perform work without removing units from service during building normal occupied hours.

F. Provide emergency call back service during working hours for this maintenance period.

G. Maintain locally, near Place of the Work, adequate stock of parts for replacement or emergency purposes. Have personnel available to ensure fulfillment of this maintenance service, without unreasonable loss of time.

H. Perform maintenance work using competent and qualified personnel under supervision and in direct employ of manufacturer or original installer.

1.4 QUALITY ASSURANCE

A. Control Air Damper Performance: Test in accordance with AMCA 500.

1.5 SUBMITTALS

A. Provide submittal to include six sets of control components, control diagrams and operational sequences.

PART 2 PRODUCTS

2.1 THERMOSTATS

A. Manufacturers: Honeywell (or as noted below) or approved equal.

B. Bi-metal thermostats are not allowed for any application.

C. Line Voltage Heating Thermostat (Programmable Electronic): King ESP230, Honeywell TL8230A or equal.
1. Integral manual On/Off switch, single-pole.
2. Accuracy: +/- 1.5 degrees F.
3. Load / Motor capacity rating of 22 amps, 208/240 volt.
4. Electronic thermistor temperature sensor with 40 F to 95 F range.
5. 7 day independent programmable schedules with 4 daily setpoints.
6. LCD display showing day, time, room temperature and setpoint, Green LED backlight, Red LED heat on Indicator, temperature adjustment buttons.
7. Positive off position/function to serve as NEC required disconnect.

D. Room Thermostat Accessories:
1. Insulating Bases: For thermostats located on exterior walls.
2. Thermostat Guards: Locking transparent plastic mounted on separate base.
3. Adjusting Key: Matching device.

E. Electric Low Limit Duct Thermostat:

1. Snap acting, single pole, single throw, manual reset switch tripping when temperature sensed across any 12 inches of bulb length is equal to or below setpoint.
2. Bulb length: Minimum 20 feet.
3. Furnish one thermostat for every 20 sq. ft of coil surface.

F. Electric High Limit Duct Thermostat:
1. Snap acting, single pole, single throw, manual reset switch tripping when temperature sensed across any 12 inches of bulb length is equal to or above setpoint.
2. Bulb length: Minimum 20 feet.
3. Furnish one thermostat for every 20 sq. ft of coil surface.

2.2 TIMERS

A. Manufacturers: Intermatic or approved equal.

B. Spring wound twist timer, 120 volt, 1 HP (20 amp inductive) rated. 'Brushed metal' gray polycarbonate faceplate. Select time range and hold as scheduled or noted in sequence.

2.3 CONTROL AIR DAMPERS

A. See Section 23 33 00.

2.4 ELECTRIC DAMPER ACTUATORS

A. Manufacturers: Belimo or approved equal.

B. Operation: Two-position or proportional as required for application, spring-return.

C. Enclosure Rating: NEMA 250 Type 2 Enclosure.

D. Mounting: Direct mount.

E. Stroke: 30 seconds end to end full stroke, 15 seconds return to normal for spring return.

F. Protection: Electronic stall protection.

G. Control Input: 0-10 VDC or 0-20 mA DC.

H. Power: Nominal 24 \ 120 volt AC.

I. Torque: Size for minimum 150 percent of required duty.

J. Duty cycle: rated for 65,000 cycles.

K. Accessories:
1. Cover mounted transformer.
2. Auxiliary potentiometer.

3. Damper linkage.
4. Direct drive feedback potentiometer.
5. Output position feedback.
6. Field selectable rotational, spring return direction, field adjustable zero and span.
7. End switch.

2.5 CO/NO2 SENSOR

A. Manufacturer: AirTest or approved equal.

B. Controller (CT2100): Integrated dual sensing capability for two gases with two sets of relays for fan/alarm activation. LED indication of power, fault and 2 threshold indicators for each gas channel. 2 minute low on delay, 10 min low off delay and 5 minute high on delay. NEMA 4X enclosure.

C. Integrated electrochemical CO sensor head (TR2000).

D. Remote NO2 Sensor: Electrochemical diffusion sensor in NEMA 4X enclosure, 0-10 ppm range, +/- 5% accuracy. (TR3210)

2.6 ENCLOSURES

A. All enclosures to be UL listed and all metal construction. All controls and instruments logically assembled at one or more panels.

2.7 CONTROL RELAYS

A. Shall be rated for the application, with a minimum of two sets of Form C contacts, enclosed in a dust proof enclosure. Relays shall be rated for a minimum life of one million operations. Operating time shall be 20 milliseconds or less, with release time of 10 milliseconds or less. Relays should be equipped with coil transient suppression devices to limit transients to 150% of rated coil voltage.

2.8 WIRING

A. Electric wiring and wiring connections required for the installation of the temperature control system as herein specified, shall be provided by the temperature control contractor. All wiring shall comply with the requirements of local and national electrical codes, and with applicable requirements of Electrical Division. Install all wiring in conduit.

B. Line voltage wiring type and size shall be per NEC.

C. Low voltage wiring type and size shall be per control manufacturer’s recommendations based on application and length of run.

2.9 CONTROL POWER

A. Provide transformers to supply power for control equipment operating at less than normal lighting circuit voltage. Do not connect wiring to lighting circuits.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify building systems to be controlled are ready to operate.

B. Verify air handling units and ductwork have been accepted and air filters are in place before installing sensors in air streams.

C. Verify location of thermostats, humidistats and other exposed control sensors with Drawings before installation.

3.2 COORDINATION

A. Furnish all control products to accomplish the specified sequence of operation, except those products specifically furnished under other sections.

B. Install all control products and connections, except where already installed by the equipment manufacturer.

3.3 INSTALLATION

A. General:
1. Install controls by mechanics skilled in erection of control systems employed by and under direct supervision of control manufacturer's representative.
2. Mount control equipment and devices as recommended by manufacturers and as shown on drawings; in case of conflicts between manufacturer's instructions and the drawings, consult the Project Manager for direction.
3. Fasten all equipment securely to structure. Install equipment and exposed piping and conduit runs parallel to building lines, plumb and level.

B. Wiring:
1. Provide line voltage and/or low voltage wiring as required to serve the complete system; conform to code.
2. Provide EMT or rigid conduit for exposed control wiring outside of cabinets or enclosures. Concealed low voltage wiring need not be in conduit, except in walls (see “3”).
3. Provide rigid conduit for control wiring concealed in partition walls, until conduit emerges from wall above ceilings.
4. Run low voltage control wiring separate from line voltage wiring and segregate from other systems to avoid Electromagnetic Interference (EMI).
5. All low voltage control wiring shall be home runs between components without splices.

C. Install thermostats, humidistat, space temperature sensors, and other exposed control sensors after locations are coordinated with other Work.

D. Provide separable sockets for liquids and flanges for air bulb elements.

E. Install control panels adjacent to associated equipment on vibration free walls or freestanding supports. Install engraved plastic nameplates for instruments and controls inside cabinet and engraved plastic nameplates on cabinet face.

3.4 THERMOSTATS AND SENSORS

A. Mount thermostats and other human interface devises at 48” centerline above finished floor to comply with ADA accessibility per ANSI A117.1. Align thermostats and devises with light switches and other controls.

B. Coordinate wall location of thermostats and other wall mount devises with light switches and controls provided by others. All devises in the same vicinity should be grouped at a common elevation with regular horizontal spacing intervals.

C. Mount CO/NO2 sensor controllers at 54” centerline above finished floor, CO sensor at 48” centerline above finished floor and NO2 sensor at 18” centerline above finished floor.

3.5 FIELD QUALITY CONTROL

A. After completion of installation, start-up, test and adjust each system. Submit data showing set points, final adjustments of controls and compliance with sequence of operations.

B. Conduct functional tests on complete systems, or individual portions as approved.

C. Conduct operational tests; set controls to operating conditions, record settings and readings of each control device.

D. Work in close coordination with testing and balancing Agency to set up control devices, set damper flow rates, and provide control system in perfect operating order. See Section 23 05 93.

3.6 DEMONSTRATION AND TRAINING

A. Demonstrate complete operation of systems, including sequence of operation prior to Date of Substantial Completion.

B. Not less than 60 days after beneficial occupancy by the Owner, recheck entire control system for compliance with Sequence of Operation.

C. Recheck controls for proper operation at the start of the heating season, if other than above timing, and again during the first warm weather period following winter operation.

END OF SECTION

SECTION 23 23 00

REFRIGERANT PIPING

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Refrigerant piping.
2. Valves.
3. Refrigerant piping accessories.

1.2 SYSTEM DESCRIPTION

A. Where more than one piping system material is specified, provide compatible system components and joints. Use non-conducting dielectric connections when joining dissimilar metals in systems.

B. Size piping in accord with equipment manufacturer's refrigerant piping design guidelines based on actual piping installation lengths. Use long line calculations when applicable.

1.3 QUALITY ASSURANCE

A. Perform Work in accordance with ASME B31.5 code for installation of refrigerant piping systems.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Dehydrate and charge refrigeration components including piping and receivers, seal prior to shipment. Maintain seal until connected into system.

B. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

C. Protect piping systems from entry of foreign materials by temporary covers, completing sections of the Work, and isolating parts of completed system.

PART 2 PRODUCTS

2.1 REFRIGERANT PIPING

A. Copper Tubing: ASTM B280, Type ACR hard drawn or annealed.
1. Fittings: ASME B16.22 wrought copper.
2. Joints: Braze, AWS A5.8 BCuP silver/phosphorus/copper alloy.

2.2 UNIONS, FLANGES, AND COUPLINGS

A. Copper Pipe: Bronze, soldered joints.

2.3 REFRIGERANT MOISTURE AND LIQUID INDICATORS

A. Manufacturers: Alco Controls, Parker Hannifin, Sporlan Valve or approved equal.

B. Indicators:
1. Port: Single, UL listed.
2. Body: Copper or brass, flared or solder ends.
3. Sight glass: Color-coded paper moisture indicator and plastic cap.
4. Maximum working pressure: 500 psig
5. Maximum working temperature: 200 degrees F.

2.4 VALVES

A. Manufacturers: Alco Controls, Parker Hannifin, Sporlan Valve or approved equal.

B. Ball Valves:
1. Two piece forged brass body with teflon ball seals and copper tube extensions, brass bonnet and seal cap, chrome plated ball, stem with neoprene ring stem seals.
2. Maximum working pressure: 500 psig.
3. Maximum working temperature: 300 degrees F.

C. Service Valve:
1. Forged brass body with copper stubs, brass caps, removable valve core, integral ball check valve.
2. Maximum working pressure: 500 psig.
3. Maximum working temperature: 300 degrees F.

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs.

B. Remove scale and dirt on inside and outside before assembly.

C. Prepare piping connections to equipment with flanges or unions.

D. Keep open ends of pipe free from scale and dirt. Protect open ends with temporary plugs or caps.

3.2 INSTALLATION PIPING SYSTEMS

A. Route piping parallel to building structure and maintain gradient.

B. Install piping to conserve building space, and not interfere with use of space.

C. Group piping whenever practical at common elevations.

D. Sleeve pipe passing through partitions, walls and floors.

E. Protection: Where piping, other than cast iron or steel, is installed in a concealed location through holes or notches in framing (i.e. studs, joists, rafters, etc.), less than 1-1/2 from framing edge, provide shield plates. Shield plates shall be 16 gauge steel and cover the piping area within framing plus 2” on each side along framing.

F. Use rigid Armacell Armafix pipe clamp assembly at all supports.

G. Determine equivalent line length and size piping per manufacturer’s installation instructions. Provide solenoid valve and other required piping accessories for long line installation.

H. Refrigerant piping shall not be installed in elevators, public stairways, stair landing or means of egress spaces.

I. Install pipe identification.

J. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

K. Provide access where valves and fittings are not exposed.

L. Flood refrigerant piping system with nitrogen during brazing. Keep piping open with nitrogen flow for zero pressure while brazing.

M. Install valves with stems upright or horizontal, not inverted.

N. Fully charge completed system with refrigerant after testing.

O. Follow ASHRAE 15 procedures for charging and purging of systems and for disposal of refrigerant.

P. Install refrigerant piping in accordance with ASME B31.5.

3.3 INSTALLATION-EXTERIOR PIPING

A. Protect exterior piping with application specific piping protection cover system or field fabricated GSM cover with steel angle supports.

B. Provide waterproof pipe entry into building with trim and flashing.

C. Protect exposed insulated pipe with aluminum jacket.

3.4 INSTALLATION - REFRIGERANT SPECIALTIES

A. Refrigerant Liquid Indicators: Install line size liquid indicators in main liquid line downstream of condenser.

B. Refrigerant Valves: Install service valves on compressor suction and discharge.

3.5 FIELD QUALITY CONTROL

A. Test refrigeration system in accordance with ASME B31.5.

B. Pressure test refrigeration system with dry nitrogen to 400 psig. Perform final tests at 27 inches vacuum and 400 psig using halide torch or electronic leak detector.

C. Repair leaks.

D. Retest until no leaks are detected.

END OF SECTION

SECTION 23 31 00

HVAC DUCTS AND CASINGS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Ductwork
2. Duct Sealant
3. Fabrication
4. Duct Pressure Testing

1.2 PERFORMANCE REQUIREMENTS

A. Variation of duct configuration or sizes other than those of equivalent or lower loss coefficient is not permitted except by written permission. Size round ducts installed in place of rectangular ducts in accordance with ASHRAE table of equivalent rectangular and round ducts.

B. Standards: Comply with most stringent requirements and recommendations of International Mechanical Code or SMACNA (Sheet Metal and Air Conditioning Contractors National Association) Duct Construction Standards for fabrication, construction and sealant of duct, fittings, and accessories.

C. Construct ductwork to NFPA 90A.

1.3 ENVIRONMENTAL REQUIREMENTS

A. Do not install duct sealant when temperatures are less than those recommended by sealant manufacturers.

B. Maintain temperatures during and after installation of duct sealant.

PART 2 PRODUCTS

2.1 DUCT MATERIALS

A. Galvanized Steel Ducts: ASTM A653 galvanized steel sheet, lock-forming quality, having G60 zinc coating of in conformance with ASTM A90.

B. Aluminum Ducts: ASTM B209; aluminum sheet, alloy 3003-H14. Aluminum Connectors and Bar Stock: Alloy 6061-T6 or of equivalent strength.

C. Fasteners: Rivets, bolts, or sheet metal screws.

D. Hanger Rod: ASTM A36; steel, galvanized; threaded both ends, threaded one end, or continuously threaded.

2.2 INSULATED FLEXIBLE DUCTS

A. Manufacturers: Thermaflex M-KC or approved equal.

B. Product Description: Insulated assembly with inner duct of woven and coated fiberglass permanently bonded to coated steel wire helix, 1" fiberglass insulation and vapor barrier jacket of fiberglass reinforced metallized film laminate, UL 181 Class 1 complying with NFPA 90A & 90B.
1. Pressure Rating: 10 inches wg positive and 2 inches wg negative.
2. Maximum Velocity: 6000 fpm.
3. Temperature Range: -20 degrees F to 250 degrees F.
4. Thermal Resistance: R-4.2

C. Accessories:
1. Hanger Strap: Thermaflex FlexTie – 1-1/2” wide, adjustable, plenum rated.
2. Elbow: Thermaflex FlexFlow Elbow – One piece adjustable design installs over flex duct.

2.3 SINGLE WALL SPIRAL ROUND DUCTS

A. Manufacturers: McGill AirFlow, Semco or approved equal.

B. Product Description: UL 181, Class 1, round spiral lockseam duct constructed of galvanized steel.

C. Joints: x” and larger flange with gasket material.

D. Elbows: Smooth radius or 5 section, 1.5D.

E. Application: Required for all exposed round ductwork; all round ductwork 12” dia. and larger; all round ductwork with static pressure over 1” w.g.. Optional for all round ductwork.

F. Construct duct with the following minimum gages:

Diameter	Gauge
3 inches to 14 inches	26
15 inches to 26 inches	24

G. Construct fittings with the following minimum gages:

Diameter	Gauge
3 inches to 14 inches	24
15 inches to 26 inches	22

2.4 SINGLE WALL ROUND DUCTS

A. Manufacturers: Ductmate GreenSeam+ or approved equal.

B. Product Description: Snap lock round duct with self-sealing butyl rubber longitudinal seam and polyurethane gasket transverse seam. No external sealant. No VOCs.

C. Joints: Male/Female with integral gasket.

D. Elbows: Smooth radius, 1.5D.

E. Application: Only allowed for low pressure ductwork with static pressure of 1" w.g. or less, less than 10" diameter and concealed. Not for use exposed.

F. Construct duct with the following minimum gages:

Diameter	Gauge
4 inches to 10 inches	26

G. Construct fittings with the following minimum gages:

Diameter	Gauge
4 inches to 10 inches	24

2.5 SINGLE WALL ROUND DUCTS (SNAP-LOCK)

A. Product Description: Product not acceptable for use.

2.6 DUCT SEALANT

A. Manufacturer: Design Polymerics, United McGill or approved equal.

B. Sealant shall be water based and formulated to withstand working temperatures of -25°F to +200°F. All sealants shall exceed 500 hours under ASTM C 732 (artificial weathering) and pass ASTM C 734 (low temperature flexibility after artificial weathering). All sealants shall be of an elastomeric nature, have a weight per gallon not to exceed 12.5, have solids by weight of 66% ± 2%, pass UL 723 with a flame spread of 5 and smoke developed of 5.

2.7 DUCTWORK FABRICATION

A. Fabricate and support rectangular and round ducts in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible. Provide duct material, gages, reinforcing, and sealing for operating pressures corresponding to the ESP (external static pressure) of the fan system. i.e. Ductwork for a fan with and ESP of 0.75" w.g. should be constructed per SMACNA 1" w.g. pressure standard.

B. Construct T's, bends, and elbows with minimum radius 1-1/2 times centerline duct width. Where not possible and where rectangular elbows are used, provide airfoil turning vanes. Where acoustical lining is indicated, furnish turning vanes of perforated metal with glass fiber insulation.

C. Indicated dimensions on drawings are net inside. Allow for thickness of duct lining where indicated.

D. Increase duct sizes gradually, not exceeding 15 degrees divergence wherever possible; maximum 30 degrees divergence upstream of equipment and 45 degrees convergence downstream.

E. Fabricate continuously welded round and oval duct fittings two gages heavier than duct gages indicated in SMACNA Standard. Minimum 4 inch cemented slip joint, brazed or electric welded. Prime coat welded joints.

F. Provide standard 45-degree lateral wye takeoffs. When space does not allow 45-degree lateral wye takeoff, use 90-degree conical tee connections.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify sizes of equipment connections before fabricating transitions.

3.2 INSTALLATION

A. Make field measurements to establish locations of hangers and supports where installation will not damage building construction.

B. During construction, install temporary closures of metal or taped polyethylene on open ductwork to prevent construction dust from entering ductwork system.

C. Where ducts pass through partitions, ceilings or floors. Provide 1" clearance and insulate from structure with insulation material. Provide flanged sheet metal closure.

D. Where ducts pass through rated walls or assemblies without fire dampers, provide ¼” to 1” annular space and fill with firestop sealant. Ductwork shall be minimum 26 gauge metal.

E. Isolate joints between dissimilar metals with fiber gasket.

F. Drawings do not attempt to show all offsets in ductwork. Make such offsets as necessary for installation of work without additional cost to Owner. 15 degree maximum angle of offset.

G. Exposed ductwork shall be Appearance Grade. Ductwork located in crawl spaces, shafts, and suspended ceiling spaces are not considered exposed.
1. All round ductwork shall be spiral seam (no snap-lock joints).
2. All joints clean and workmanlike.
3. Ductwork entirely free of dents.
4. Ductwork subject to denting due to space function construct one gauge heavier than SMACNA standard for size indicated.
5. All hangers trimmed of excess metal.
6. Plumb, level, parallel or perpendicular to building structure.
7. Sealed with transparent, paintable sealant to avoid streaking.

H. Flexible Duct:
1. Install insulated flexible duct in full extended condition free of sags and kinks.
2. Use minimum length required to make connection.
3. Length shall not exceed 10 feet.
4. Supported on 36" centers with minimum 1-1/2” wide strap. Do not crush.
5. Connect flexible ducts to metal ducts with draw bands.

I. Install duct hangers and supports in accordance with Section 23 05 00.

J. Use double nuts and lock washers on threaded rod supports.

3.3 SEISMIC BRACING

A. See 23 05 00.

3.4 DUCT SEALING

A. Install and seal ducts in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible. Ductwork shall be sealed using welds, gaskets, or mastic. Duct tape is not permitted as a sealant on any ducts with the exception of that on fiberglass ducts specifically made for such use.

B. For all ductwork seal all transverse joints and longitudinal seams. For 2” w.g. and higher pressure class ductwork also seal all duct wall penetrations (i.e. screw, fastener, rod or wire).

C. Low pressure ductwork (less than 3” w.g.) shall be sealed to a leakage rate not to exceed 6 percent of the system airflow. All deficient ductwork shall be re-sealed until compliant.

3.5 PRESSURE (DUCT LEAKAGE) TESTING

A. All ductwork found deficient by testing shall be resealed and retested until leakage compliance is reached.

B. Provide written documentation of testing to be included with the Test and Balance report, see 23 05 93. Include drawing(s) indicating where test measurements were taken.

3.6 INTERFACE WITH OTHER PRODUCTS

A. Install openings in ductwork where required to accommodate thermometers and controllers. Install pitot tube openings for testing of systems. Install pitot tube complete with metal can with spring device or screw to prevent air leakage. Where openings are provided in insulated ductwork, install insulation material inside metal ring.

B. Connect diffusers or light troffer boots to low pressure ducts with 5 feet maximum length of flexible duct held in place with strap or clamp.

C. Connect air outlets and inlets to supply ducts with five foot maximum length of flexible duct. Do not use flexible duct to change direction.

3.7 CLEANING

A. Clean duct system and force air at high velocity through duct to remove accumulated dust. To obtain sufficient air flow, clean one half of system completely before proceeding to other half. Protect equipment with potential to be harmed by excessive dirt with temporary filters, or bypass during cleaning.

3.8 SCHEDULES

A. Ductwork Material Schedule:

AIR SYSTEM	MATERIAL
Supply, Return, Exhaust, Relief	Galvanized Steel
Outside Air Intake	Galvanized Steel
Combustion Air	Galvanized Steel
Exterior	Aluminum

B. Ductwork Pressure Class Schedule: Install higher pressure class than indicated where corresponding fan system ESP (external static pressure) is higher.

AIR SYSTEM	PRESSURE CLASS
Constant Volume Low Pressure Supply	Minimum 1 inch wg.
Return, Exhaust	Minimum 1 inch wg

END OF SECTION

SECTION 23 33 00

AIR DUCT ACCESSORIES

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Dampers
2. Duct access doors
3. Flexible duct connections

1.2 COORDINATION

A. Verify locations for access panels with Architect.

B. Coordinate damper power, control and fire alarm interface with other trades.

C. See 23 09 00 for Electric Damper Actuators.

1.3 QUALITY ASSURANCE

A. Dampers tested, rated and labeled in accordance with the latest UL requirements.

B. Damper pressure drop ratings based on tests and procedures performed in accordance with AMCA 500.

PART 2 PRODUCTS

2.1 MANUAL BALANCING DAMPERS

A. Manufacturers: Ruskin, Greenheck or approved equal

B. Frames: Galvanized steel, minimum 20 gage.

C. Blades: Galvanized steel, minimum 20 gage, attached to minimum 3/8 inch shafts with locking handle quadrant. Provide 2” standoff for insulated ductwork applications.

D. Maximum Velocity: 1500 fpm.

E. Rectangular: 24” and under on a side Ruskin MD25; over 24” on a side Ruskin MD35 or equal.

F. Round: Ruskin MDRS25 or equal.

2.2 CONTROL DAMPERS

A. Manufacturers: Tamco, Ruskin, Greenheck or approved equal

B. Frame: Extruded aluminum (6063T5) channel of minimum 0.080” thickness with mounting flanges on both sides.

C. Blades: Extruded aluminum (6063T5) airfoil. Maximum blade size 6 inches wide, 48 inches long, attached to minimum 7/16 inch hex shafts.

D. Bearings: Celcon inner bearing fixed to blade pin, rotating within a polycarbonate outer bearing inserted in the frame.

E. Seals: EPDM blade seals and silicone frame seals.

F. Damper Leakage: AMCA Pressure Class 1A, maximum leakage rate of 3.0 cfm/ft^2 at 1.0 inch w.g. pressure differential.

G. Maximum Pressure Differential: 6 inches w.g.

H. Rectangular: Tamco 1000, Ruskin CD50 or equal.

I. Round: Ruskin CDRS25 or equal up to 12” diameter, for larger sizes use rectangular damper with manufacturer’s square-to-round transitions.

J. Options:
1. For dampers with a dimension over 48” provide multiple sections with jack shafts.
2. Provide parallel blade action for two position (open/closed) applications.
3. Provide opposed blade action for modulation or control applications.

2.3 INSULATED CONTROL DAMPERS

A. Manufacturers: Tamco, Ruskin, Greenheck or approved equal

B. Frame: Insulated extruded aluminum (6063T5) channel of minimum 0.080” thickness with mounting flanges on both sides.

C. Blades: Extruded aluminum (6063T5) airfoil internally insulated with expanded polyurethane foam and thermally broken. Maximum blade size 6 inches wide, 48 inches long, attached to minimum 7/16 inch hex shafts.

D. Bearings: Celcon inner bearing fixed to blade pin, rotating within a polycarbonate outer bearing inserted in the frame.

E. Seals: EPDM blade seals and silicone frame seals.

F. Damper Leakage: AMCA Pressure Class 1A, maximum leakage rate of 3.0 cfm/ft^2 at 1.0 inch w.g. pressure differential.

G. Maximum Pressure Differential: 6 inches w.g.

H. Rectangular Insulated: Tamco 9000, Ruskin CDTI-50 or equal.

I. Round: Provide rectangular damper with manufacturer's square-to-round transitions.

J. Options:
1. For dampers with a dimension over 48" provide multiple sections with jack shafts.
2. Provide parallel blade action for two position (open/closed) applications.
3. Provide opposed blade action for modulation or control applications.

2.4 REMOTE OPERATED BALANCING DAMPERS (MANUAL)

A. Manufacturers: Young, MAT or approved equal.

B. Damper:
1. Round butterfly or radial damper with external control hardware, 5020-CC, RT-250.
2. Round butterfly or radial damper with internal control hardware, 5020-CC-2, RT-150.
3. Rectangular opposed blade damper with external control hardware, 830A-CC, RT-200.
4. Rectangular opposed blade damper with internal control hardware, 830A-CC-2, RT-100.

C. Remote Damper Operator:
1. External cable control, 3" cover plate, 270-301
2. Internal cable control, 270-275
3. Remote cable wall control, 700 (where indicated).

2.5 PRESSURE INDEPENDENT VOLUME DAMPER (DUCT INSERT)

A. Manufacturer: Trox VFL

B. Circular air volume flow limiter with casing and damper blade made of high-quality plastic, UL 94. Ready-to-commission unit consists of the casing with volume flow rate setting scale and the control mechanism with stainless steel leaf spring and low-friction, silicone-free, polyurethane bellows. Easy insertion into circular ducts; secure fit ensured by a lip seal.

C. Features:
1. Mechanical self-powered
2. Aerodynamically tested and factory set to a reference volume flow rate
3. Sticker showing volume flow rates (in cfm) on each unit

D. Technical data:
1. Nominal sizes: 4 – 10 in
2. Volume flow rate range: 11-450 cfm

3. Volume flow rate control range: < 20 to 100 % of the nominal volume flow rate
4. Volume flow rate accuracy: approx. ± 10 % of the nominal volume flow rate
5. Minimum differential pressure: 0.12 in. w.g.
6. Maximum acceptable differential pressure: 1.2 in. w.g.

2.6 PRESSURE INDEPENDENT VOLUME CONTROLLER (MANUAL CONTROL)

A. Manufacturer: Trox VFC

B. Circular adjustable volume flow controller for constant flow independent of duct system pressure. Galvanized steel casing with high-quality plastic damper blade, low-friction bearings, polyurethane bellows, stainless steel leaf spring and external rotary volume flow rate setpoint knob.

C. Features:
1. Mechanical self-powered, without external power supply.
2. Volume set from external scale; no tools required.

D. Technical data:
1. Nominal sizes: 4 – 10 in
2. Volume flow rate range: 13-784 cfm
3. Volume flow rate control range: 10 to 100 % of the nominal volume flow rate
4. Volume flow rate accuracy: approx. ± 10 % of the nominal volume flow rate
5. Minimum differential pressure: 0.12 in. w.g.
6. Maximum acceptable differential pressure: 2.0 in. w.g.

2.7 COMBINATION FIRE AND SMOKE DAMPERS (INLINE)

A. Manufacturers: Ruskin FSD60/FSD60LP, equal by Greenheck, or approved equal.

B. Application: Provide FSD60LP (low pressure) model for dampers 14” in height and smaller. All others provide standard FSD60.

C. Fabricate in accordance with NFPA 90A, UL 555, and UL 555S.

D. Fire Resistance: 1-1/2 hours or 3 hours depending on rating of wall.

E. Leakage Rating: Class I, maximum of 8 cfm at 4 inches wg differential pressure.

F. Damper Temperature Rating: 350 degrees F.

G. Frame: 16 gage, galvanized steel.

H. Blades:
1. Style: Airfoil-shaped, single piece, double skin.

2. Action: Opposed.
3. Orientation: Horizontal.
4. Material: Minimum 16 gage equivalent thickness, galvanized steel.
5. Width: Maximum 7 inches.

I. Bearings: Stainless steel or bronze.

J. Seals: Silicone blade edge seals and flexible stainless steel jamb seals.

K. Linkage: Concealed in frame.

L. Provide with duct transition connection.

M. Release Device: Close in controlled manner and allow damper to be reset.

N. Actuator: Belimo, electric 120 volt, 60 hertz, two-position, fail close.

O. Resetable Link Release Temperature: 165 degrees F.

P. Factory installed sleeve and mounting angles. Furnish silicone caulk factory applied to sleeve at damper frame to comply with leakage rating requirements.

2.8 DUCT ACCESS DOORS

A. Fabricate in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible.

B. Fabrication: Rigid and close fitting of galvanized steel with sealing gaskets and quick fastening locking devices. For insulated ductwork, furnish minimum 1 inch thick insulation with sheet metal cover.
1. Less than 12 inches square, secure with sash locks.
2. Up to 18 inches Square: Furnish two hinges and two sash locks.
3. Up to 24 x 48 inches: Three hinges and two compression latches.
4. Larger Sizes: Furnish additional hinge.
5. Access panels with sheet metal screw fasteners are not acceptable.

2.9 FLEXIBLE DUCT CONNECTIONS

A. Manufacturers: Duro-Dyne or approved equal

B. Fabricate in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible.

C. Double fold “Grip-Loc” metal-to-fabric connection.

D. Indoor Connector: “Metal-Fab”, 24 ga, 3”metal - 3” fabric - 3” metal.
1. Fabric: UL listed fire-retardant Neoprene coated woven glass fiber fabric conforming to NFPA 90A, minimum density 30 oz per sq yd, 500 lbs tensile strength.

E. Exterior Connector: “Metal-Fab”, 24 ga, 3”metal - 3” fabric - 3” metal.
   1. Fabric: Ul listed fire-retardant Hypalon coated woven galas fiber fabric conforming to NFPA 90A, minimum density 24 oz per sq yd, 250 lbs tensile strength.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify rated walls are ready for fire damper installation.

B. Check location of air outlets and inlets and make necessary adjustments in position to conform to architectural features, symmetry, and lighting arrangement.

3.2 INSTALLATION.

A. Install in accordance with NFPA 90A, and follow SMACNA HVAC Duct Construction Standards - Metal and Flexible. Refer to Section 23 31 00 for duct construction and pressure class.

B. See Section 23 34 00, paragraph 1.4 for damper installation.

C. Provide motorized in lieu of gravity back-draft dampers per Energy Code.

D. Provide control dampers where not furnished with packaged equipment.

E. Provide insulated control dampers where:
   1. The damper is installed behind a louver.
   2. The damper is installed in a roof penthouse or gravity ventilator.
   3. The damper is unducted and open to a conditioned space.

F. Install remote operated dampers for balancing where damper is located in an inaccessible location.

G. Access Doors: Install access doors at the following locations and as indicated on Drawings:
   1. Before and after each fire damper, smoke damper and combination fire and smoke damper.
   2. Where access is required for a valve or damper.
   3. Install at locations for cleaning kitchen exhaust ductwork in accordance with NFPA 96.

H. Access Door Sizes: Install minimum 8 x 8 inch size for hand access, 18 x 18 inch size for shoulder access, and as indicated on Drawings. Review locations prior to fabrication.

I. Install temporary duct test holes as required for testing and balancing purposes. Cut or drill in ducts. Cap with neat patches, neoprene plugs, threaded plugs, or threaded or twist-on metal caps.

J. Install fire dampers, combination fire and smoke dampers and smoke dampers at locations as indicated on Drawings. Install with required perimeter mounting angles, sleeves, breakaway duct connections, corrosion resistant springs, bearings, bushings and hinges.
   1. Install smoke dampers and combination smoke and fire dampers in accordance with NFPA 92A.
   2. Install dampers square and free from racking with blades running horizontally.
   3. Do not compress or stretch damper frame into duct or opening.
   4. Handle damper using sleeve or frame. Do not lift damper using blades, actuator, or jack shaft.
   5. Install bracing for multiple section assemblies to support assembly weight and to hold against system pressure. Install bracing as needed.

3.3 INSTALLATION – PRESSURE INDEPENDENT VOLUME DAMPERS (PIVD)

A. Select devise volume setpoint closest to scheduled volume.

B. Provide devise dimension the same size as ductwork.

C. Trox VFL: Affix manufacturer’s identification sticker to duct exterior. Permanently mark set cfm on sticker.

D. Trox VFC: Mark setpoint on scale and indicate cfm.

E. Where PIVD is indicated, typically provide Trox VFL for duct sizes 4”-6” and airflow less than or equal to 100 cfm, unless noted otherwise.

F. Where PIVD is indicated, typically provide Trox VFC for duct sizes 6”-10” and airflow greater than 100 cfm, unless noted otherwise.

3.4 DEMONSTRATION

A. Demonstrate re-setting of fire dampers to Owner's representative.

END OF SECTION

SECTION 23 34 00

HVAC FANS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Fans.

1.2 QUALITY ASSURANCE

A. Performance Ratings: Conform to AMCA 210 and bear AMCA Certified Rating Seal.

B. Sound Ratings: AMCA 301, tested to AMCA 300, and bear AMCA Certified Sound Rating Seal.

C. UL Compliance: UL listed and labeled, designed, manufactured, and tested in accordance with UL 705.

D. Balance Quality: Conform to AMCA 204.

1.3 DAMPERS

A. A gravity backdraft or motorized control damper is required on every exhaust fan.

B. See 23 33 00 for motorized control dampers.

C. Provide insulated control dampers where scheduled or where required by 23 33 00.

PART 2 PRODUCTS

2.1 CENTRIFUGAL ROOF EXHAUST FANS

A. Manufacturers: Greenheck, Cook or approved equal.

B. Construction: Spun aluminum with rigid internal support and aluminum birdscreen. Backward inclined aluminum wheel and inlet, statically and dynamically balanced.

C. Direct Drive:
1. Motor: Electronic Commutation DC brushless motor with internal solid state AC/DC converter circuitry and heavy duty ball bearings. Speed controllable down to 20% of full speed. Minimum 85% efficient at all speeds.
a. Motor mounted potentiometer speed control dial.

2. Accessories:
   a. Gravity backdraft \ Motorized Control damper. (See Part I, Dampers)
   b. Insulated roof curb with liner; matched to roof slope.
   c. Curb seal.
   d. Aluminum birdscreen.
   e. NEMA disconnect switch.
   f. Speed Control

PART 3 EXECUTION

3.1 ROOF CURBS

A. Verify roof curbs are installed and dimensions are as instructed by manufacturer.

B. Provide sound attenuation material in curb where so indicated on drawings.

3.2 INSTALLATION

A. Secure roof fans with cadmium plated steel lag screws to roof curb.

B. Install gravity backdraft or motorized control dampers on discharge of exhaust fans and as indicated on Drawings.

3.3 CLEANING

A. Vacuum clean inside of fan cabinet.

3.4 DEMONSTRATION

A. Demonstrate fan operation and maintenance procedures.

3.5 PROTECTION OF FINISHED WORK

A. Do not operate fans for until ductwork is clean, filters in place, bearings lubricated, and fan has been test run under observation.

END OF SECTION

SECTION 23 37 00

AIR OUTLETS AND INLETS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Diffusers, Registers & Grilles
   2. Louvers
   3. Goosenecks

1.2 QUALITY ASSURANCE

A. Diffuser, register, and grille performance shall be tested and rated in accordance with ASHRAE 70.

B. Louver performance shall be tested and rated in accordance with AMCA 500.

PART 2 PRODUCTS

2.1 RECTANGULAR CEILING DIFFUSERS

A. Manufacturers: Titus, Price, Krueger or approved equal.

B. Type: Square, stamped, multi-core, adjustable pattern diffuser.

C. Frame: Surface mount with flat frame or T-bar lay-in.

D. Fabrication: Steel with baked enamel white finish.

2.2 LOW-FLOW RECTANGULAR CEILING DIFFUSERS

A. Manufacturers: Titus TJD or approved equal.

B. Type: Square plaque, induction nozzles.

C. Frame: Surface mount with flat frame or T-bar lay-in.

D. Fabrication: Steel with baked enamel white finish.

2.3 SWIRL CEILING DIFFUSERS

A. Manufacturers: Trox TDF-SA or approved equal.

B. Type: Ceiling swirl diffuser with square or circular face. Fixed air control blades for horizontal swirling creating high induction levels.

C. Frame: Installation frames for suspended T-bar ceilings, surface mount or freely suspended.

D. Fabrication: Galvanized steel with white powder-coated finish.

E. Accessories:
1. (H) – High-performance, side inlet plenum box, galvanized steel.
2. (O) – No damper.

2.4 SWIRL CEILING DIFFUSERS

A. Manufacturers: Trox VDW or approved equal.

B. Type: Ceiling swirl diffuser with square or circular face. Individual manually adjustable air control blades for variable direction swirling creating high induction levels.

C. Frame: Installation frames for suspended T-bar ceilings, surface mount or freely suspended.

D. Fabrication: Galvanized steel with white powder-coated finish. Black plastic adjustable air control blades.

E. Accessories:
1. (H) – High-performance, side inlet plenum box, galvanized steel.
2. (O) – No damper.

2.5 EXHAUST/ RETURN GRILLES

A. Manufacturers: Titus, Price, Krueger or approved equal.

B. Type: Fixed blades, 1/2 inch blade spacing, with blades set at 35 degrees.

C. Frame: 1-1/4 inch margin with countersunk screw mounting, welded corners.

D. Fabrication: Steel with 20 gage minimum frames and 22 gage minimum blades, with factory white enamel finish.

2.6 EGGCRATE EXHAUST AND RETURN GRILLES

A. Manufacturers: Titus, Price, Krueger or approved equal.

B. Type: Fixed grilles of 1/2 x 1/2 x 1/2 inch aluminum core.

C. Fabrication: Aluminum with factory white enamel finish.

D. Frame: 1-1/4 inch margin with countersunk screw mounting or channel lay-in frame for suspended grid ceilings.

2.7 LOUVERS

A. Manufacturers: Greenheck, Ruskin, Wonder Metal or approved equal.

B. Product Description: Stationary, drainable blade. AMCA certified.

C. Type: 4 inch deep with blades on 45 degree slope, heavy channel frame. Minimum initial point of water penetration of 900 fpm.

D. Fabrication: 12 gage thick extruded aluminum, welded assembly, with factory Kynar finish, color to be selected.

E. Mounting: Furnish with flanges, mullions, and hardware for installation.

F. Bird Screen: Aluminum bird screen with 3/4 inch square mesh.

2.8 GOOSENECKS

A. Fabricate in accordance with SMACNA HVAC Duct Construction Standards - Metal and Flexible, of minimum 18 gage aluminum. Provide termination insect screen.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify inlet and outlet locations with Architectural Plans.

B. Verify ceiling/wall type before ordering.

C. Verify diffuser air patterns are as indicated before starting air balance.

3.2 INSTALLATION

A. Install diffusers to ductwork with airtight connection.

B. Install balancing dampers on duct take-off to diffusers, grilles, and registers, whether or not dampers are furnished as part of diffuser, grille, and register assembly.

C. Paint visible portion of ductwork behind air outlets and inlets matte black

3.3 INTERFACE WITH OTHER PRODUCTS

A. Check location of outlets and inlets and make necessary adjustments in position to conform to architectural features, symmetry, and lighting arrangement.

END OF SECTION

SECTION 23 40 00

FILTERS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Disposable, pleated filters.
   2. Filter frames and housings.

1.2 PERFORMANCE REQUIREMENTS

A. Conform to ARI 850 Section 7.4.

B. Dust Spot Efficiency: Plus or minus 5 percent.

PART 2 PRODUCTS

2.1 DISPOSABLE, PLEATED FILTERS

A. Manufacturers: Camfil, Flanders, Airguard, Viledon or approved equal.

B. MERV 8: UL 900 Class 2, pleated, cotton and polyester blend, radial pleat with welded wire grid, cardboard frame. 1”, 2” & 4”. (Camfil 30/30)

C. MERV 13 (85%): UL 900 Class 2, pleated synthetic media with three layers, spunbond polyester prefilter, electrostatically spunpolycaronate microfiber middle layer and spunbond polyester downstream layer. 2” & 4” (Viledon Mini 85)

D. MERV 13 (85%): UL 900 Class 2, extended surface mini pleated, fiberglass or synthetic media, corrosion-resistant metal frame. 4” (Flanders PrecisionCell II)

2.2 FILTER FRAMES AND HOUSINGS

A. General: Fabricate filter frames and supporting structures of 16 gage galvanized steel or extruded aluminum T-section construction with necessary gaskets between frames and walls.

B. Standard Sizes: For interchange ability of filter media of other manufacturers; minimum 2 inches thick; for extended surface and high efficiency particulate air filters, provide for upstream mounting of panel filters.

C. Side Servicing Housings: Flanged for insertion into ductwork, of reinforced 16 gage galvanized steel; access doors with continuous gaskets and positive locking devices on both sides; extruded aluminum tracks or channels for filters with positive sealing gaskets.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install filters with felt, rubber, or neoprene gaskets to prevent passage of unfiltered air around filters.

B. Do not operate fan system until filters are in place. Replace filters used during construction before testing, with clean set. Provide owner with replacement set of filters.

END OF SECTION

SECTION 23 72 00

ENERGY RECOVERY UNITS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
   1. Package ERV with heat wheel.

1.2 COORDINATION

A. Coordinate size and location of all building penetrations required for installation of each unit and associated electrical systems.

B. Contractor shall coordinate with roofing contractor to ensure unit curb is properly flashed.

1.3 EXTRA MATERIALS

A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
   1. Filters: 3 sets of disposable filters for each unit.
   2. One set of fan and energy wheel belts

1.4 ELECTRICAL

A. Short-Circuit Current Rating (SCCR): All HVAC and refrigeration equipment with multi-motor or combination electrical loads shall comply with NEC 110.10 & 440.4 and must include a SCCR greater than the Available Interrupting Current (AIC) of the electrical circuit serving the equipment. See electrical drawings for required AIC kA rating. Equipment SCCR may be presented in writing from the manufacturer or shown on the unit nameplate. Refrigeration or air-conditioning equipment over 60 Amps MOCP must list the SCCR on the unit nameplate. If the AIC rating is unavailable or cannot be determined provide equipment with a minimum SCCR of 10kA.

PART 2 PRODUCTS

2.1 AIR TO AIR HEAT RECOVERY UNIT (ROOF-TOP) (ERV)

A. Manufacturers: Greenheck, Aaon or approved equal

B. General: Unit shall be fully assembled at the factory and consist of an insulated metal cabinet, weatherhood outdoor air intake with metal mesh filter assembly, Energy wheel, electric post-heater, motorized insulated low-leak dampers, sensors, curb assembly, service receptacle, vapor-tight light fixtures, filter

assembly for intake air and exhaust air, supply air blower assembly, exhaust air blower and an electrical microprocessor control center. All specified components and internal accessories factory installed and tested and prepared for single-point high voltage connection.

C. Cabinet: Formed double wall insulated metal cabinet. Outside casing: 18 gauge, galvanized steel, factory pre-painted with polyester urethane paint (permatector). Internal assemblies: 18 gauge, galvanized steel except for motor supports which shall be minimum14 gauge galvanized steel. Inner wall of double wall construction shall be minimum 24 gauge galvanized steel.
   1. Cabinet Insulation: 1" Fiberglass insulation. Full coverage of entire cabinet exterior to include walls, roof and floor of unit. Insulation shall be of semi-rigid type and installed between inner and outer shells of all cabinet exterior components.
   2. Access panels / doors: Unit shall be equipped with insulated, hinged doors. Doors shall be fabricated of 18 gauge galvanized G90 steel.
   3. Condensate drain pan: Pan shall be formed of welded austenitic stainless steel sheet material and provided with a welded drain connection at the front for connection to a P trap. Drain pan shall be sloped in two directions to provide positive draining.
   4. P trap: An engineered P trap (condensate drain) assembly shall be provided for each unit, to include cleanout ports, cleanout tool, vacuum break device and see-through reservoir.

D. Energy wheel: Energy wheel shall be of the total enthalpy, rotary air-to-air type and shall be an element of a removable energy wheel cassette. The cassette shall consist of a galvanized steel framework, an energy wheel as specified and a motor and drive assembly. The cassette shall incorporate a pre-tensioned urethane drive belt with a five year warranty. The wheel media shall be a polymer film matrix in a stainless steel framework and be comprised of individual segments that are removable for servicing. Non-segmented energy wheels are not acceptable. Silica gel desiccant shall be permanently bonded to the polymer film. The energy wheel is to have a five year warranty.

E. Supply Air and Exhaust Air Blowers: Belt drive motor and blower shall be assembled onto a 14 gauge galvanized steel platform and must have neoprene vibration isolation devices.
   1. Shall be statically and dynamically balanced and designed for continuous operation at maximum rated fan speed and horsepower.
   2. Centrifugal blower housing: Formed and reinforced steel panels to make curved scroll housing with shaped cutoff.
   3. Forward curved blower (fan) wheels: Galvanized or aluminum construction with inlet flange and shallow blades curved forward in direction of airflow. Mechanically attached to shaft with set screws.

F. Motors: Blower motors greater than ¾ horsepower shall be "NEMA Premium™" efficiency. Motors shall be heavy-duty, permanently lubricated type to match the fan load and furnished at the specified voltage, phase and enclosure. Drives shall be sized for a minimum of 150% of driven horsepower and pulleys shall be fully machined cast-type, keyed and fully secured to the fan wheel and motor shafts.

Electric motors of ten horsepower or less shall be supplied with an adjustable drive pulley.

G. Electric Post-heater: Post-heater shall be SCR control and shall include a temperature sensor with field adjustable set point, located in the supply air stream. Heat output of the post-heater shall be infinitely variable.

H. Motorized dampers: Exhaust Air and Intake Air motorized dampers of insulated low leakage type shall be factory installed.

I. Filter Section: Permanent metal filters located in the outdoor air intake and shall be accessible from the exterior of the unit. Combination of MERV 8 and MERV 13 pleated filters shall be provided in the intake air stream and MERV 8 filters in the exhaust air stream.

J. Sensors are considered to be part of various optional operational modes or device controllers and are to be factory supplied and installed.

K. Curb Assembly: 14 gauge galvanized steel factory curb. The curb assembly shall provide perimeter support of the entire unit and shall have duct adapter(s) for supply air and return air. Contractor shall provide and install appropriate insulation for the curb assembly.

L. Control panel / connections: unit shall have an electrical control center where all high and low voltage connections are made. Control center shall be constructed to permit single-point high voltage power supply connections. Optional electric post heater shall have a separate electrical control center and separate high voltage power circuit.
   1. The unit shall be constructed so that it can function as a stand-alone heating system controlled by factory-supplied controllers, thermostats and sensors.
   2. Variable Frequency Drive (VFD): Unit shall have factory installed variable frequency drives for modulation of the blower motors The VFDs shall be factory-programmed for unit-specific requirements and shall not require additional field programming to operate.
   3. Remote Interface: Contractor shall provide and install a Remote Interface that functions as a remote indicator of owner-selected operating parameters and also permits remote inputting of new operating parameters. Each remote panel shall have a large LCD user interface screen.
   4. Sensors:
      a. Dirty Filter Sensor
      b. Temperature Sensors- OA, SA, RA, EA
      c. Pressure Sensor- SA, RA
      d. Rotation Sensor

M. Accessories:
   1. Service receptacle: 120 VAC GFCI service outlet shall be factory-provided and installed. Service outlet requires a dedicated single phase electric circuit.

2. Vapor-tight light fixtures shall be factory installed in each compartment of the unit and wired to a NEMA switch on the outside of the unit. Vapor-tight lights require dedicated single phase electric service.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify roof curbs are installed and dimensions are as instructed by manufacturer.

3.2 PREPARATION

A. Furnish roof curbs for installation.

3.3 INSTALLATION

A. Secure unit with cadmium plated steel lag screws to roof curb.

B. Install flexible connections between unit and ductwork. Ensure metal bands of connectors are parallel with minimum one inch flex between ductwork and fan while running.

C. Provide sheaves required for final air balance.

3.4 MANUFACTURER'S FIELD SERVICES

A. Furnish services of factory trained representative for minimum of one day to start-up, calibrate controls, and instruct Owner on operation and maintenance.

3.5 CLEANING

A. Vacuum clean coils and inside of fan cabinet.

B. Install clean filters.

3.6 DEMONSTRATION

A. Demonstrate fan operation and maintenance procedures.

3.7 PROTECTION OF FINISHED WORK

A. Do not operate fans for until ductwork is clean, filters in place, bearings lubricated, and fan has been test run under observation.

END OF SECTION

SECTION 23 81 43

AIR-COOLED, VARIABLE REFRIGERANT FLOW, MULTI-UNIT HEAT PUMP

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. System Description
2. Outdoor unit
3. Indoor units
4. Refrigerant controller
5. Digital Controls
6. Condensate Overflow Switch

1.2 MAINTENANCE SERVICE

A. Furnish service and maintenance of equipment for one year from Date of Substantial Completion. Include maintenance items as shown in manufacturer's operating and maintenance data, including filter replacements, fan belt replacement, and controls checkout and adjustments.

B. Furnish 24-hour emergency service on breakdowns and malfunctions for this maintenance period.

1.3 ELECTRICAL

A. Short-Circuit Current Rating (SCCR): All HVAC and refrigeration equipment with multi-motor or combination electrical loads shall comply with NEC 110.10 & 440.4 and must include a SCCR greater than the Available Interrupting Current (AIC) of the electrical circuit serving the equipment. See electrical drawings for required AIC kA rating. Equipment SCCR may be presented in writing from the manufacturer or shown on the unit nameplate. Refrigeration or air-conditioning equipment over 60 Amps MOCP must list the SCCR on the unit nameplate. If the AIC rating is unavailable or cannot be determined provide equipment with a minimum SCCR of 5kA.

1.4 QUALIFICATIONS

A. The system shall be installed by a Mitsubishi authorized CITY MULTI Diamond Dealer. The contractor service and install training should be performed by the manufacturer.

1.5 WARRANTY

A. System shall obtain Diamond five (5) year warranty.

B. Warranties periods shall be from date of substantial completion.

PART 2 PRODUCTS

2.1 MANUFACTURER

A. Mitsubishi CITY MULTI or approved equal.

2.2 VARIABLE REFRIGERANT FLOW ZONING SYSTEM

A. General: Variable capacity, split heat pump heat recovery air conditioning system with Variable Refrigerant Flow Zoning (VRFZ) and simultaneous heating/cooling. The system consists of an outdoor unit, BC (Branch Circuit) Controller, multiple indoor fan coil units, interconnecting refrigerant piping and product specific DDC (Direct Digital Controls). All components factory assembled, internally piped and wired, tested and ready for field assembly.

B. Quality Assurance:
1. The units shall be listed by Electrical Laboratories (ETL) and bear the ETL label.
2. All wiring shall be in accordance with the National Electrical Code (N.E.C.).
3. The units shall be manufactured in a facility registered to ISO 9001 and ISO14001 which is a set of standards applying to environmental protection set by the International Standard Organization (ISO).
4. A full charge of R-410A for the condensing unit only shall be provided in the condensing unit.
5. Warranty:
   a. The units shall be covered by the manufacturer's limited warranty for a period of one (1) year.
   b. Systems designed by a certified CITY MULTI Diamond Designer, installed by a certified CITY MULTI Diamond Dealer, and verified with a completed commissioning report submitted to Mitsubishi Electric Service Department, shall be covered by an extended manufacturer's limited warranty for a period of five (5) years.
   c. In addition, the compressor shall have a manufacturer's limited warranty for a period of six (6) years.

2.3 OUTDOOR UNIT:

A. General: Units shall be equipped with multiple circuit boards that interface to the control system and shall perform all functions necessary for operation, be completely factory assembled, piped and wired. Each unit shall be run tested at the factory.
1. Sound rating no higher than 61 dB(A).
2. Both refrigerant lines from the outdoor unit to the BC (Branch Circuit) Controller shall be insulated.
3. Accumulator with refrigerant level sensors and controls.
4. High pressure safety switch, over-current protection and DC bus protection.
5. Capable of operating in heating down to -4°F ambient temperature without additional low ambient controls.

6. High efficiency oil separator plus additional logic controls to ensure adequate oil volume in the compressor is maintained.

B. Unit Cabinet: The casing shall be fabricated of galvanized steel, bonderized and finished with powder coated baked enamel.

C. Fan: Direct drive, variable speed propeller type fan with inherent protection, permanently lubricated bearings, mounted for quiet operation, raised guard and vertical discharge airflow.

D. Refrigerant: R410A refrigerant is required.

E. Coil: Nonferrous construction with lanced or corrugated plate fins on copper tubing with an integral metal guard. 4 circuits with two position valves for each circuit, except for the last stage.

F. Compressor: High performance, inverter driven, modulating capacity scroll compressor with a factory mounted crankcase heater, an inverter to modulate capacity variable down to 16%, internal thermal overload, mounted to avoid the transmission of vibration.

G. Electrical: The unit shall be controlled by integral microprocessors with the control circuit between the indoor units, BC Controller and the outdoor unit being 12VDC completed using a 2-conductor, twisted pair shielded cable to provide total integration of the system.

2.4 BRANCH CIRCUIT (BC) CONTROLLER:

A. General: These units shall be equipped with a circuit board that interfaces to the M-NET controls system and shall perform all functions necessary for operation. The unit shall have a galvanized steel finish. The BC Controller shall be completely factory assembled, piped and wired. Each unit shall be run tested at the factory. This unit shall be mounted indoors.

B. BC Unit Cabinet: Fabricated of galvanized steel with a liquid-gas separator, multiple refrigeration control valves and two tube-in-tube heat exchangers.

C. Refrigerant valves: Each circuit shall have one (54,000 Btu/h or smaller indoor unit section) two-position liquid line valve and a two-position suction line valve. When connecting a 54,000 Btu/h or larger indoor unit section, two branch circuits shall be joined together at the branch controller to deliver an appropriate amount of refrigerant. The two refrigerant valves shall operate simultaneously. Linear electronic expansion valves shall be used to control the variable refrigerant flow.

D. Service shut-off ball valves with Schrader port shall be field-provided/installed for each branch to allow service to any indoor unit without field interruption to overall system operation.

E. An integral condensate pan and drain shall be provided.

F. Accessories:

1. Provide with BlueDiamond MaxiBlue condensation pump complete with reservoir and accessories.

2.5 PKFY INDOOR UNIT (wall-mounted)

A. General: Wall mounted indoor unit section with a slim silhouette and a modulating linear expansion device.

B. Indoor Unit: Factory assembled, wired and run tested with all factory wiring, piping, electronic modulating linear expansion device, control circuit board, fan motor, self-diagnostic function, 3-minute time delay mechanism, an auto restart function, and a test run switch. Indoor unit and refrigerant pipes shall be charged with dehydrated air before shipment from the factory.

C. Unit Cabinet: White finish, same for all model sizes. Multi directional drain and refrigerant piping offering four (4) directions for refrigerant piping and two (2) directions for draining. Separate back plate which secures the unit firmly to the wall.

D. Fan: An assembly with one or two line-flow fan(s) direct driven by a single motor. Statically and dynamically balanced to run on a motor with permanently lubricated bearings. Multi-speed fan with two speeds selected by the room controller. Manual adjustable guide vane with the ability to change the airflow from side to side (left to right). Motorized air sweep louver with automatic change in airflow by directing the air up and down to provide uniform air distribution.

E. Filter: Factory installed MERV 4.

F. Coil: Nonferrous construction with smooth plate fins on copper tubing, inner grooves for high efficiency heat exchange, phos-copper or silver alloy brazed joints, pressure tested at the factory. A condensate pan and drain shall be provided under the coil. Both refrigerant lines to the PKFY indoor units shall be insulated.

G. Controls: Unit controls to be provided with unit as part of VFRZ system to perform functions necessary to operate the system. The unit shall be able to control external backup heat.

H. Accessories:
1. Provide with BlueDiamond condensation pump complete with reservoir and accessories. Provide model MicroBlue for units up to 15 MBH and MaxiBlue for units 18 MBH and larger.

2.6 PLFY INDOOR UNIT (4-way Cassette)

A. General: A cassette style indoor unit that recesses into the ceiling with a ceiling grille and a modulating linear expansion device.

B. Indoor Unit: Factory assembled, wired and run tested with all factory wiring, piping, electronic modulating linear expansion device, control circuit board, fan motor, self-diagnostic function, 3-minute time delay mechanism, an auto restart

function, an emergency operation function and a test run switch. Indoor unit and refrigerant pipes shall be charged with dehydrated air before shipment from the factory.

C. Unit Cabinet: Ceiling-recessed cassette with provisions for a field installed filtered outside air intake. Branch ducting shall be allowed from cabinet. Four-way grille shall be fixed to bottom of cabinet allowing two, three or four-way blow. Grille vane angles shall be individually adjustable from the controller to customize the airflow pattern for the conditioned space.

D. Fan: An assembly with a turbo fan direct driven by a single motor. Statically and dynamically balanced to run on a motor with permanently lubricated bearings. Four (4) fan speeds, two of which may be selected by the room controller. Adjustable air outlet system offering 4-way airflow, 3-way airflow, or 2-way airflow. Auto air swing vanes shall be capable of automatically swinging up and down for uniform air distribution.

E. Filter: Factory installed MERV 4.

F. Coil: Nonferrous construction with smooth plate fins on copper tubing, inner grooves for high efficiency heat exchange, phos-copper or silver alloy brazed joints, pressure tested at the factory. A condensate pan and drain shall be provided under the coil. Both refrigerant lines to the PLFY indoor units shall be insulated.

G. Controls: Unit controls to be provided with unit as part of VFRZ system to perform functions necessary to operate the system.

H. Accessories:
1. Factory installed condensate lift pump.
2. Trim Panel

2.7 PEFY-NMAU INDOOR UNIT (Ceiling-Concealed Ducted)

A. General: A ceiling concealed ducted indoor fan coil design that mounts above the ceiling with a 2-position, field adjustable return and a fixed horizontal discharge supply and a modulating linear expansion device.

B. Indoor Unit: Factory assembled, wired and run tested with all factory wiring, piping, electronic modulating linear expansion device, control circuit board, fan motor, self-diagnostic function, 3-minute time delay mechanism, and an auto restart function. Indoor unit and refrigerant pipes shall be charged with dehydrated air before shipment from the factory.

C. Unit Cabinet: Ceiling concealed, ducted with provisions for a field installed filtered outside air intake. Unit shall have a ducted air outlet system and ducted return air system.

D. Fan: An assembly with one or two Sirocco fan(s) direct driven by a single motor. Statically and dynamically balanced and run on a motor with permanently lubricated bearings. Three (3) fan speeds, plus Auto-Fan function.

E. Filter: MERV 8 (minimum) installed in factory filter box.

F. Coil: Nonferrous construction with smooth plate fins on copper tubing, inner grooves for high efficiency heat exchange, phos-copper or silver alloy brazed joints, pressure tested at the factory. A condensate pan and drain shall be provided under the coil. The condensate shall be gravity drained from the fan coil. Both refrigerant lines to the PEFY indoor units shall be insulated.

G. Controls: Unit controls to be provided with unit as part of VFRZ system to perform functions necessary to operate the system. The unit shall be able to control external backup heat.

H. Accessories:
1. Factory installed condensate lift pump.

2.8 FILTER BOX

A. Manufacturer: MicroMetl, Mitsubishi or approved equal.

B. Manufactured and constructed specifically to match fan coil and fasten directly to return inlet of unit. Box shall be 20 ga GSM construction.

C. Filter rack shall be angled and shall accept 1”, 2” or 4” filters. Access door shall be hinged and fastened with knurled nobs such that tools are not required to open. Rack and door shall have foam gasket.

2.9 TRIM PANEL

A. Manufacturer: Mitsubishi PLFY-ITP1, PLFY-ITP2 or PMFY-ITP1

B. Ceiling cassette trim panel to adapt with t-bar ceilings. High performance ABS impact resistant polymer with a smooth white finish. Black finish optional.

2.10 REFRIGERANT PIPING SERVICE VALVE

A. Manufacturer: Diamondback or approved equal.

B. Full port, forged brass ball valve with Schrader valve, flare connections, Teflon seals and gaskets. 700 psig rated, R-410A compatible, fully factory assembled and pressure tested.

C. Provide with insulation cover of polyethylene foam with PVC cover and tape.

2.11 CONTROLS

A. General: The physical controllers shall be plastic material with a neutral color. Each remote controller, at a minimum, shall have a LCD (Liquid Crystal Display) that shows room temperature, set point, and fan speed.

B. Electrical:
1. The electrical voltage from each circuit board to the controls shall be 12 volts DC.
2. Control wiring shall be installed in a daisy chain configuration from indoor unit to indoor unit then to the BC controller and outdoor unit. Control wiring shall run from the indoor unit terminal block to the controller associated with that unit.
3. Wiring shall be 2-conductor 16 AWG or 18 AWG stranded wire with a shield, as defined by control drawing.

2.12 REMOTE CONTROLLERS

A. Remote controllers shall operate indoor units. The wiring for the remote controllers shall be simple, non-polar, two-wire connections. All remote controllers shall be wall-mounted with an LCD display and contain a microprocessor that constantly monitors operation to maintain smooth indoor unit operation. Set temperature shall be adjusted in increments of 1°F or 2°F, depending on the systems and controllers. In the event of an abnormality, the remote controller shall display a four-digit error code and the indoor unit address.

B. PAR-U01MEDU-J: Smart ME Remote Controller
1. Backlit touch screen.
2. Capable of controlling up to 16 indoor units (defined as 1 group).
3. Displays: Room temperature, relative humidity, operation status, setpoint.
4. Control the following operations: On/Off, Operation Mode (cool, heat, auto, dry, and fan), temperature setting, fan speed setting, setback, hold and airflow direction setting.
5. Timer settings of on/off/temperature up to 8 times in a day in 5-minute increments with an Auto Off timer and able to limit the set temperature range.
6. Room temperature shall be sensed at the Controller.

2.13 CMCN: System Controllers

A. AE-200 Centralized Controller
1. Standalone controller shall be capable of controlling up to 50 indoor units across multiple outdoor units. Controller shall be capable of controlling up to 200 indoor units across multiple outdoor unit with expansion of up to three AE-50A controllers.
2. Power shall be provided by integrated power supply.
3. Controller shall support operation superseding that of the remote controllers, system configuration, daily/weekly scheduling, monitoring of operation status, night setback setting, free contact interlock configuration and malfunction monitoring.

4. Controller shall have five basic operation controls which can be applied to an individual indoor unit, a group of indoor units, or all indoor units. These controls shall include on/off, operation mode selection (cool, heat, auto, dry, setback and fan), temperature setting, fan speed setting, and airflow direction setting.
5. Ability to enable or disable operation of local remote controllers.
6. Allow both daily and weekly schedules with operations consisting of ON/OFF, mode selection, temperature setting, air flow (vane) direction, fan speed and permit/prohibit of remote controllers.
7. Controller shall be equipped with a RJ-45 Ethernet port to support interconnection with a network PC via a closed/direct Local Area Network (LAN), via an Ethernet Hub on a LAN.
8. 9” high resolution, back lit, color touch panel interface for direct graphical interface and control of system.
9. Memory back up via USB port.
10. Software functions shall be available so that the building manager can securely log into each AE-200 via the PC’s web browser to support operation monitoring, scheduling, error e-mail, personal browser, and maintenance diagnostics.

2.14 CONDENSATE OVERFLOW SWITCH

A. Manufacturer: Rectorseal Safe-T-Switch or approved equal.

B. Sealed, waterproof reed/magnet float switch installed on the overflow outlet of drain pans or on an auxiliary drain pan. UL 508, 24 volt AC.

2.15 CONDENSATE PUMP

A. Manufacturer: BlueDiamond MicroBlue or approved equal.

B. GyRok pump technology, 1.3 gal/hr, 16 feet hd, 6 feet lift, 17 dba. Thermistor level sensing. Capable of running dry. Provide with reservoir and ducting kit.

2.16 CONDENSATE PUMP

A. Manufacturer: BlueDiamond MaxiBlue or approved equal.

B. Rotary elastomer diaphragm technology, 3.7 gal/hr, 23 feet hd, 16.5 feet lift, 21 dba. Thermistor level sensing. Capable of running dry. Provide with reservoir and accessories.

PART 3 EXECUTION

3.1 EXAMINATION

A. Coordinate size and location of concrete pad for condensing unit. Provide inserts for mounting.

B. Coordinate size and location of sleeves or block-outs needs for refrigerant piping.

C. Determine refrigerant pipe routing to efficiently minimum run length and avoid interference.

3.2 INSTALLATION

A. Install condensate piping with trap and determine route from drain pan to nearest waste with 1/4" slope. Provide condensate pump where drain is not available or slope cannot be made.

B. Install components furnished loose for field mounting.

C. Install condensing units at grade on concrete foundations with anchors.

D. Install refrigerant piping from condensing unit(s) to branch controller(s) and from branch controller(s) to indoor units. Install refrigerant specialties furnished with unit.

E. Insulate both liquid and vapor refrigerant piping on all runs.

F. Evacuate refrigerant piping and install initial charge of refrigerant.

G. Install electrical devices furnished loose for field mounting.

H. Install control wiring between air handling unit, condensing unit, and field installed accessories.

3.3 INSTALLATION – CONTROLS

A. Set control of equipment based on room controller space temperature rather than default return air temperature.

B. Setup Ethernet access via local area network.

C. Setup output of error message via email, coordinate with owner for address.

D. Designate Fan Coils with unit tag and room/space name.

E. Setup occupied and unoccupied space temperature schedules, including second unoccupied temperature sweep. Coordinate schedules with Owner.

3.4 MANUFACTURER'S FIELD SERVICES

A. Furnish initial start-up and commissioning. During first year of operation, including routine servicing and checkout.

3.5 CLEANING

A. Vacuum clean coils and inside of unit cabinet.

B. Install new filters in indoor units at Substantial Completion.

3.6 DEMONSTRATION

A. Demonstrate system operation and maintenance.

B. Furnish services of manufacturer's technical representative for one day to instruct Owner's personnel in operation and maintenance of units. Schedule training with Owner, provide at least 7 days' notice to Architect/Engineer of training date.

3.7 PROTECTION OF FINISHED WORK

A. Do not operate indoor units during construction for temporary heat.

B. Do not operate indoor units until ductwork and room is clean, filters are in place, bearings lubricated, and fan has been test run under observation.

END OF SECTION

SECTION 23 82 00

TERMINAL HEATING UNITS

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:
1. Electric radiant heaters.

PART 2 PRODUCTS

2.1 ELECTRIC RADIANT PANEL

A. Manufacturers: Markel, Aztec or approved equal.

B. Assembly: Electric resistance graphite element imbedded between two layers of insulation, steel shell. T-bar mount or surface mount with aluminum frame . UL listed and labeled.

C. Ceiling Panels: 24x48 inch with baked enamel white finish.

2.2 ELECTRIC INFRARED HEATER

A. Manufacturers: Black Body ThermaZone or approved equal.

B. Heavy steel construction with mounting brackets, refractory panel and grid. UL approved.

PART 3 EXECUTION

3.1 EXAMINATION

A. For recessed units, verify recess dimensions are correct size.

B. Verify concealed blocking and supports are in place and connections are correctly located.

3.2 INSTALLATION

A. Install equipment exposed to finished areas after walls and ceilings are finished and painted. Avoid damage.

B. Protection: Install finished cabinet units with protective covers during remainder of construction.

C. Coordinate to assure correct recess size for recessed units.

D. Install electric heating equipment including devices furnished by manufacturer but not factory-mounted. Furnish copy of manufacturer's wiring diagram submittal. Install electrical wiring in accordance with manufacturer's submittals.

3.3 CLEANING

A. After construction is completed, including painting, clean exposed surfaces of units. Vacuum clean coils and inside of cabinets.

B. Touch-up marred or scratched surfaces of factory-finished cabinets, using finish materials furnished by manufacturer.

END OF SECTION

SECTION 260000 - ELECTRICAL GENERAL CONDITIONS

PART 1 - GENERAL

1.1 GENERAL

A. Conform to the General Conditions, Supplementary Conditions, and related work in other Divisions for all work in Division 26 and 28. See Division 1 for sequence of work.

1.2 WORK INCLUDED

A. It is the intention of this division of the specifications and the accompanying drawings to describe and provide for the furnishing, installing, testing and placing in satisfactory and successful operation all equipment, materials, devices and necessary appurtenances to provide a complete electrical system, together with such other miscellaneous installations and equipment hereinafter specified and/or shown in the plans. The work shall include all materials, appliances and apparatus not specifically mentioned herein or noted on the plans, but which are necessary to make a complete working installation of all electrical systems shown on the plans or described herein. Equipment and devices furnished and installed under other divisions of this specification (or by the Owner) shall be connected under this division. The drawings and specifications are complementary and what is called for in either is binding as if called for in both.

B. By submitting a bid, the Contractor is acknowledging that he has made a thorough examination of the Contract Documents, existing site and building conditions, and has determined that these documents do sufficiently describe the scope of construction work required under this Contract.

1.3 SCOPE OF BASIC BID

A. Included in Division 26 and 28 work is all work and related items necessary to provide all electrical installations except as specifically excluded. In general, this includes all labor, equipment, tools, etc., to complete the electrical work.

1.4 RELATED WORK

A. Temporary Power and Lighting - See Section 015100

B. Mechanical Control Wiring – See Division 23

C. Cutting and Patching - See Division 1

D. Trenching, backfill and asphalt work – See Division 2.

1.5 STANDARDS AND REGULATIONS

A. The work shall comply with the latest edition of the applicable Standards and Codes of the following:

ASTM	American Society for Testing and Materials
NBFU	National Board of Fire Underwriters
NEC	National Electrical Code
---	State Electrical Code
NESC	National Electrical Safety Code
NEMA	National Electrical Manufacturers Association
NFPA	National Fire Protection Association
U.L.	Underwriters Laboratories Inc.
IPCEA	Insulated Power Cable Engineers Associated
CBM	Certified Ballasts Manufacturers
---	Federal, State and Local Building Codes
ETL	Electrical Testing Laboratories

B. If any conflict occurs between Government adopted Code Rules and this specification, the codes are to govern. Nothing in these drawings and specifications shall be construed to permit work not conforming to governing codes. Also, this shall not be construed as relieving the Contractor from complying with any requirements of the plans and specifications which may be in excess of, but not in conflict with, requirements of the Governing Codes.

1.6 PERMITS & FEES

A. The Contractor shall obtain and pay for all licenses, permits and inspections required by laws, ordinances and rules governing work specified herein. The Contractor shall arrange for inspection of work by the inspectors and shall give the inspectors all necessary assistance in their work of inspection.

1.7 DEFINITIONS

A. When "Provide" is used, it shall be interpreted as "furnishing and installing complete in operating condition".

B. When "Drawings" is used, it shall be interpreted as "all Contract Drawings for all Disciplines".

C. When "Contractors" is used, it shall be interpreted as the Electrical Contractor.

1.8 INTENT OF DRAWINGS

A. The electrical drawings are intended to serve as working drawings for general layout. The equipment layout is diagrammatic and unless specifically dimensioned or detailed, does not indicate all fittings, hardware or appurtenances required for a complete operating installation.

B. Anything shown on the drawings but not covered in the specifications, or anything covered in the specifications but not shown on the drawings, shall be as if covered in both. In case of conflict between the drawings and specifications, the Engineer will select the method to be used. The Contractor shall be responsible for verifying all measurements before proceeding with the work.

C. Wiring diagrams are not intended to indicate the exact course of raceways or exact location of outlets. Raceway and outlet locations are approximately correct and are subject to revision as may be necessary or desirable at the time of installation. Precise location in every case shall be subject to the Engineer's approval.

D. The contractor shall review the manufacturer provided installation instructions for each piece of equipment prior to rough-in. Any conflict between the drawings, specifications and installation instructions shall be brought to the Engineer's attention immediately. The contractor will not be paid for any reinstallation required due to failing to comply with manufacturer's recommendations or requirements unless specifically directed by the engineer, in writing, after the conflict has been identified.

1.9 PROTECTION

A. The Contractor shall store and guard all equipment before installation and shall protect same, and replace any equipment that has been damaged prior to final acceptance.

1.10 HOUSEKEEPING

A. All electrical materials shall be kept stored in an orderly fashion protected from heat, cold, and the weather.

B. All marred surfaces shall be refinished and painted after installation.

C. All debris shall be removed from premises during work, as directed, and at completion of job.

1.11 TEMPORARY USE

A. Temporary or interim use of any and all portions of the electrical system shall be under the supervision of the Electrical Contractor.

1.12 AS-BUILT DRAWINGS

A. The Contractor shall maintain, in addition to any reference drawings, an as-built set of prints, on which all deviations from the original design shall be drafted in a neat, legible manner with red colored pencil. This red lined set shall identify all drawing revisions including addenda items, change orders, and Contractor revisions. The Contractor is responsible to revise panel schedules and load calculations as required.

B. Drawings shall show locations of all concealed raceway runs larger than 1", giving the number of conductors and size of raceway. Underground ducts shall be shown with cross section elevations. All pipe, raceway, manholes or lines of other trades shall be included.

C. The Contractor shall update all references to specific products to indicate products actually installed on project. This shall include, but not be limited to, lighting fixtures, baseboard heaters, etc.

D. Upon completion of the Division 26 and 28 Work, the Contractor shall deliver the red lined drawings and one set of neatly marked up as-built drawings to the Engineer for transmittal through the Engineer to the Owner.

E. Upon completion of the Division 26 and 28 Work, the Contractor shall deliver the red lined drawings and one set of neatly drafted as-built drawings on electronic media in AutoCAD R-2013 format and full size pdf to the Architect.

1.13 WARRANTY

A. Provide a written warranty that the Division 26 and 28 work is free from mechanical and electrical defects. Contractor shall replace and repair, to the satisfaction of the Engineer, any parts of the installation which may fail within a period of 12 months after the certificate of final acceptance, provided that such failure is due to defects in material or workmanship, or failure to follow the specifications and drawings.

1.14 INSTRUCTIONS AND MANUALS

A. A preliminary copy, complete, except for the bound cover, shall be submitted 60 days prior to completion of the project for checking and review. Five (5) bound, corrected copies shall be delivered to the Owner 20 days prior to scheduled instruction periods.

B. Manuals shall contain shop drawings, wiring diagrams, operating and maintenance instructions, replacement parts lists, and equipment nameplate data for all equipment and systems installed under the project. Signal equipment submittals shall contain step-by-step circuit description information designed to acquaint maintenance personnel with equipment operation in each mode of operation. Manuals shall contain original brochures supplied by manufacturers. Xerox copies of originals will not be accepted.

C. Each type of device provided shall be identified in the O & M Manual using the same identification as shown on the drawings and specifications. The information included must be the exact equipment installed not the complete "line" of the Manufacturer. Where sheets show the equipment installed and other equipment, the installed equipment shall be neatly and clearly identified on such sheets. Parts lists shall give full ordering information assigned by the original parts manufacturer. Relabeled and/or renumbered parts information as reassigned by equipment supplier is not acceptable. The following information shall be provided for each device:
   1. Manufacturer's name, address and phone number.
   2. Local supplier's name, address and phone number.
   3. Complete parts lists including quantities and manufacturer's part numbers.
   4. Installation instructions.
   5. Recommended maintenance items including maintenance procedure and recommended interval of maintenance listed in hours of operation, calendar unity or other similar time unit.

D. The O & M Manual shall be assembled in a loose leaf, 3-ring, hard cover binder and electronically on compact disc. The information contained in the manuals shall be grouped in an orderly arrangement by specification index. The manuals shall have a typewritten index and divider sheets between categories with identifying tabs. The covers shall be imprinted with the name of the job, Owner, Architect, Electrical Engineer, Division 26 and 28 Contractor, and year of completion. The back edge shall be imprinted with the name of the job, Owner, and year of completion. As a minimum, the following selection shall be broken out:
   1. Light Fixtures
   2. Lamps and Ballasts - referenced to each fixture type
   3. Panelboards
   4. Motor Controls
   5. Fire Alarm System

6. Fire Station Alerting System
7. Low Voltage Lighting Control Systems

E. Wiring Diagrams for each system shall be complete for the specific system installed under the Contract. "Typical" Line Diagrams will not be acceptable unless properly marked to indicate the exact field installation.

1.15 WORK NOT INCLUDED

A. Indicated motors, controls, and equipment as described in other divisions shall be furnished by other trades, but shall be moved, set and wired to electrical controls and power supply by the Electrical Contractor.

B. Work to be included under this Contract shall be defined on drawings and in these specifications. Any details beyond these limits are meant only to give installation clarity to that portion which is a part of this Contract.

1.16 INSTRUCTION PERIODS

A. Upon completion of the work and after all tests and final inspection of the work by the authority(s) having jurisdiction, the Contractor shall demonstrate and instruct the Owner's designated operation and maintenance personnel in the operation and maintenance of the various electrical systems. The Contractor shall arrange scheduled instruction periods with the Owner. The Contractor's representatives shall be superintendents or foremen knowledgeable in each system and suppliers representatives when so specified.

B. Scheduled Instruction periods shall be:
1. Fire Alarm System 1/2 day

C. Costs for time involved by Contractor shall be included in the bid.

1.17 COMPLETION OF WORK

A. Upon completion of the Division 26 and 28 work, the Contractor shall comply with requirements of Section 017000 for project closeout.

B. Arrange for and obtain all required inspections and certificates pertaining to the Division 26 and 28 work and deliver the certificates to the Engineer in triplicate.

C. Prior to or at the time of final inspection, the Contractor shall, as outlined in detail in the specifications, complete the delivery of all the following items:
1. Completion Letter
2. Certificate of Final Inspection, in triplicate form.
   Electrical Inspector COMPLETION OF WORK
   Fire Department 260000
3. Warranty to Owner (with SUPPLEMENTARY GENERAL CONDITIONS
   copy for Engineer 260000

4.	Marked Set, Electronic Media Set on CD in AutoCAD R-2013 Format, and Mylar Set of " As-Built" Electrical Drawings	GENERAL AS-BUILT DRAWINGS 260000
5.	Panelboard and Special Equipment Shop Drawings and Final Approved List of Materials Installed	MATERIALS, GENERAL 260000
6.	Certificate of Feeders Torque Results	WIRES AND CABLES 260519
7.	* Receipt from person to whom delivered the following: Spare Elements for Fire Detectors, Fuses for Switches, Spare Keys for Panelboards, receptacles switches, plugs, etc.	FIRE ALARM – 283100 FUSES – 262813 PANELBOARDS – 262416 SWITCHES & RECEPTACLES – 262726
8.	Wiring diagrams, Maintenance Manuals, Operation Instructions, and Brochures (5 sets minimum)	GENERAL, INSTRUCTIONS & MANUALS – 260000– 1.14

* Secure delivery instructions from Architect for delivery to Owner.

1.18 SHOP DRAWING SUBMITTALS

A. This Contractor shall submit to the Architect as described in Section 016000. When shop drawings are submitted electronically, they shall be submitted as described in Paragraph B below.
   1. Manufacturer's Catalog Data.
   2. Complete Physical and Technical Data.
   3. Wiring Diagrams.
   4. Detailed Reference (written or highlighted) noting compliance with the appropriate specification section and applicable item numbers within that section.
   5. Other Descriptive Data as required by the Architect/ Engineer.

B. The Contractor shall submit to the Architect electronic shop drawings in PDF format. Electronic Shop Drawings that are submitted without following the format as outlined below will be returned for corrections without any further review.
   1. A separate PDF file shall be submitted for each Division including All submittal items for that Division as outlined below:
      a. Division 26 – Electrical
      b. Division 28 – Electronic Safety and Security
   2. The contractor shall provide either a digital or hardware method of transporting the electronic submittal to the Architect. Files larger than 10Megabytes shall not be sent via email and shall be transferred via an FTP or similar file transfer protocol, PC compatible CD or PC compatible Thumb Drive. Divisions shall not be broken up into separate files for transfer via email.
   3. Each Specification PDF shall be submitted with the following format and salient attributes:
      a. Cover page including:
         1) Project Title as indicated on the plans
         2) Project Location including Address, City, State, Country

3) Prime Contractor name, phone number, and email address
4) Sub-Contractor name, phone number, and email address
5) Specification Division Number and Title

b. Index Page outlining each specification section included in the submittal. This list shall be linked to a corresponding Specification Section Divider for each section. This link shall enable the reviewer to jump to a specification section by clicking the item in the list.

c. Specification Section Divider: Shop Drawings shall be divided by specification section and each section shall begin with a Divider Page outlining the Specification Number, Title, and a list of Submittal Items for the section. In the upper right hand corner of the divider page, a Link shall be provided returning the reviewer to the Index Page.

d. Each Submittal Item listed on the Specification Section Divider shall be linked to the specific item being submitted. Each Submittal Item shall be hi-lighted Yellow with a Note Reference to the specific paragraph giving the submittal requirements.

e. Each page of the submittal shall be numbered in the Bottom Right corner of the page. Page numbering shall be Roman Numerals for all pages before the First Specification Section. Each Specification Section page shall be numbered with the Specification Section number, a dash, and the page number in the Specification Section.

f. Specification items shall be specifically hi-lighted as they apply to the project rather than hi-lighting an entire product family. Items that do not apply to this project shall be crossed out with a Red X.

g. The PDF file shall be not be protected to prevent printing, selecting of text within the document, or extracting of pages from the document.

C. Shop drawings shall be submitted complete, at one time and each item indexed with dividers and separated per specification section and shall be, but not limited to the items of equipment listed below:

1. All panelboards, showing breaker arrangement with circuit numbers, relays, and panel skirts.
2. Motor starters and controls designating where items are intended to be used and equipment being controlled.
3. Disconnect Switches
4. Fuses and spare fuse cabinet
5. Lighting Fixtures (Complete)
6. Wiring Devices
7. Back Boxes
8. Coverplates
9. Raceways and Connectors
10. Fire Wall Penetration Seals
11. Copper Wire
12. *Fire Alarm System
13. **All Specialty Systems not listed above**
14. Any other items requested by Engineer.

D. Within 10 working days after the date of the letter rejecting any items of equipment, lighting fixtures, or materials as not in accordance with the specifications, Contractor shall submit a new list of items he proposes to furnish and install in place of those items rejected. If the Contractor fails to submit this new list within the above specified time, or if any items on this second list are rejected as not being in accordance with these specifications, the Engineer may select the items which the Contractor shall furnish and install without change in Contract price or time of completion.

E. The acceptance of a manufacturer's name or product by the Engineer does not relieve the Contractor of the responsibility for providing materials and equipment which comply in all details with the requirements of the Contract Documents. The Contractor shall be solely responsible for submitting materials at such a time to allow a minimum of two weeks for Engineer's review.

F. Electrical Drawings for the project have been developed by the Engineer using AutoCAD™ Revision 2012 software. These drawing files will be made available to the Contractor for development of shop drawings and/or "As-Builts" with a signed waiver of responsibility.

1.19 SCHEDULE OF VALUES

A. Provide Schedule of Values per Division 1 and related project requirements.

B. Division 26 and 28 Breakdown: Provide schedule of values for the following categories (as a minimum):
1. Electrical Mobilization
2. Electrical Submittals
3. Electrical General Project Management, General Design, General Coordination
4. Branch Circuit Materials Rough-in
5. Branch Circuit Materials Rough in – Labor
6. Branch Circuit Trim – Materials
7. Branch Circuit Trim – Labor
8. Service Materials
9. Service Materials – Labor
10. Feeder Materials
11. Feeder Materials - Labor
12. Panelgear, Disconnects, Starters
13. Panelgear, Disconnects, Starters – Labor
14. Light Fixtures
15. Light Fixtures – Labor
16. Fire Alarm System
17. Systems Equipment – Labor
18. Commissioning
19. Electrical Punchlist, Closeout, and Owner Training

C. The dollar value for "Electrical Punchlist, Closeout, and Owner Training" shall in no case be less than 2% of the total dollar value of the Division 26 and 28 work (or as indicated in Division 1, whichever is higher). The dollar value for "Commissioning" shall in no case be less than 3.0% of the total dollar value of the Division 26 and 28 work (or as indicated in Division 1, whichever is higher).

D. The Contractor is advised that in addition to payments held out for retainage and project final completion (i.e. "Electrical Punchlist, Closeout, and Owner Training"), as specified above and in Division 1, the Owner reserves the right to withhold 10% of the funds for any of the above categories until the systems (of that category) have been proven to operate as specified and have been completely tested and adjusted.

PART 2 - PRODUCTS

2.1 COMPETITIVE PRODUCTS

A. Any reference in the specifications to any article, device, product, material, fixture, form or type of construction by name, make or catalog number shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition. The Contractor, in such cases, may at his option use any article, device, product, material, fixture, form or type of construction which in the judgment of the Engineer, expressed in writing, is equal to that specified. However, any manufacturer not listed as an accepted Bidder for a specific item must be submitted for acceptance in writing in accordance with Section 016000.

2.2 MANUFACTURER/EQUIPMENT PRIOR APPROVALS

A. Any manufacturer/equipment not listed as an approved substitute for a specified item must be submitted for acceptance in accordance with Section 016000, in writing, with detailed information to include:
1. Manufacturer's Catalog Data
2. Complete Physical and Technical Data
3. Wiring Diagrams
4. Detailed reference (written or highlighted) noting compliance with the appropriate Specification Section and all applicable Specification item numbers within that Section
5. Complete type written index cross referencing all proposed substitutes and specified items
6. Detailed reference to specified items (written or highlighted) noting equal quality and performance of proposed substitute equipment
7. Other descriptive data, as required by the Engineer

B. If substitute material is determined to be acceptable by the Engineer, it will be included in a subsequent Addenda prior to bidding. The acceptance of a manufacturer’s name or product by the Engineer does not relieve the Contractor of the responsibility for providing materials and equipment which comply in all details with the requirements of the Contract Documents.

C. Only materials which are specified or published in addenda as acceptable shall be used.

2.3 MATERIALS

A. All materials must be of the quality herein specified. All materials shall be new, of the best quality and free from defects. They shall be designed to ensure satisfactory operation and operational life in the environmental conditions which will prevail where they are being installed.

B. Each type of material shall be of the same make and quality. The materials furnished shall be standard products of the manufacturers regularly engaged in the production of such equipment and shall be the manufacturer's latest standard design.

C. All materials shall be U.L. or E.T.L. listed for the purpose for which they are used.

D. Equipment in compliance with U.L. standards but not bearing their label is not acceptable. If the manufacturer cannot arrange for labeling of an assembled unit at the factory the unit shall be field evaluated per the Washington State Administrative Code (WAC) and the electrical inspector’s requirements.

2.4 COMPLETE SYSTEM

A. All the systems mentioned shall be complete and operational in every detail except where specifically noted otherwise. Mention of certain materials in these specifications shall not be construed as releasing the Contractor from furnishing such additional materials and performing all labor required to provide a complete and operable system.

2.5 NAMEPLATES

A. Provide nameplates constructed of plastic (black on white) laminated material engraved through black surface material to white sublayer (attach with screws on NEMA 1 enclosures). EXCEPTION (1): Emergency distribution system component labeling - white letters on red background. Exception (2): Series rated systems shall be yellow background with white letters.
1. Panelboard Labels: Refer to Section 262416
2. Switch and Receptacle Labels: Refer to Section 262726
3. Motor Starter and Disconnect Labels: Refer to Section 262816
4. Special Equipment/Outlet Labels: Refer to Appropriate Sections.

PART 3 - EXECUTION

3.1 GENERAL

A. Careful consideration shall be given to clearances under and over beams, pipes and ducts, to provide proper headroom in all cases. Check drawings to determine heights of all suspended ceilings and size of pipe shafts where raceway and wire-ways shall run. Coordinate installation of Division 26 and 28 wiring and equipment with Division 23 and other trades. Where insufficient room for proper installation appears, obtain clarification from Engineer before any installation is begun.

B. Cutting and Patching:
1. Obtain permission from the Architect and/or Owner’s Representative prior to cutting. Locate cuttings so they will not weaken structural components. Cut carefully and only the minimum amount necessary. Cut concrete with diamond core drills except where space limitations prevent the use of such drills.
2. All construction materials damaged or cut into during the installation of this work must be repaired or replaced with materials of like kind and quality as original materials by skilled labor experienced in that particular building trade.

3.2 COORDINATION

A. The Contractor is responsible for accomplishing Division 26 and 28. The work shall coordinate with that of the other Contractors and/or other trades doing work in the building and shall examine all Drawings, including the several Divisions of Mechanical, Structural, Civil and Architectural, for Construction Details and necessary coordination. Specific locations of construction features and equipment shall be obtained from the Contract Documents, field measurements, and/or from the trade providing the material or equipment. No extra costs will be allowed for failure to obtain this information.

B. All conflicts shall be reported to the Engineer in writing before installation for decision and correction. Special attention is called to the following items:
1. Door swings to the end that switches will be located on "Strike" side of the door.

2. Location of grilles, pipes, sprinkler heads, ducts and other mechanical equipment so that all electrical outlets, lighting fixtures and other electrical outlets and equipment are clear from and in proper relation to these items.
3. Location of cabinets, counters, and doors so that electrical outlets, lighting fixtures and equipment are clear from and in proper relation to these items.
4. Type and height of ceiling.
5. All device measurements referenced on drawings or specifications are to be centered of device unless noted otherwise.

C. The Contractor will not be paid for work requiring reinstallation due to lack of coordination or interference with other Contractors or trades. This includes, but is not limited to, removing, replacing, relocating, cutting, patching, and finishing.

D. The Contractor shall review the installation manual for each device to be installed. If a conflict appears to occur between the manufacturer's recommended installation practices and the plans or specifications, notify the Engineer immediately. Final determination shall be by the Engineer. The Contractor will not be paid for reinstallation due to failure to comply with manufacturer instructions or design documents.

E. Device and fixture locations may be changed within 15 feet without extra charge if so desired by the Engineer, before installation.

3.3 REQUESTS FOR INFORMATION (RFI)

A. It is our intent to provide a timely response for RFIs regarding Division 26 and 28 Work. To further expedite this process, where a suggestion can be determined or derived at by the initiator of the RFI, it is required this suggestion be supplied with the submitted RFI. If no suggestion is given where one is possible, the RFI will be returned as incomplete.

3.4 CLEANING AND PAINTING

A. All equipment, whether exposed to the weather or stored indoors shall be covered to protect it from water, dust and dirt.

B. After installing, all metal finishes shall be cleaned and polished, cleaned of all dirt, rust, cement, plaster, grease and paint.

C. All equipment with a primer coat of paint shall be given two (2) or more coats of a finish enamel and scratched surfaces be refinished to look like new. Markings, identification and nameplates shall be replaced.

3.5 EQUIPMENT IDENTIFICATION

A. Provide identifying engraved bakelite nameplate on all equipment, including pull boxes, to clearly indicate its use, area served, circuit identification, voltage, and any other useful data.

B. Each auxiliary system, including communications, shall be clearly labeled to indicate its function.

3.6 DEVIATION

A. Deviation from the shop drawings in construction or installation of equipment shall not be made unless Shop Drawings showing proposed deviations are submitted to and approved by the Engineer. If any equipment is furnished under this or other divisions with current, voltage or phase ratings that differ from those shown on the drawings, the Contractor shall notify the Engineer in writing immediately and shall not connect said equipment until instructed as to required changes by the Architect. No extension of time will be granted as a result of such changes.

3.7 EXCAVATIONS

A. All excavations are to be so conducted so that no walls or footings shall be disturbed in any way.

B. Remove all surplus earth not needed for backfilling and dispose of same as directed.

3.8 WIRING METHODS

A. All low voltage wiring shall be in Raceway with Junction Boxes and Fittings where concealed in walls, in inaccessible ceiling space, or where exposed in finished or unfinished areas.

B. All branch circuit wiring shall be installed in raceway with junction boxes and fittings.

C. Provide access panels as needed for pull boxes and equipment located above ceiling or behind walls.

D. Multiple feeder runs shall be rod hung, using a strut type channel with individual one hole clamps, back plates and machine screws.

E. Any low voltage cables that are not terminated at both ends shall be tagged and labeled per code.

3.9 PENETRATIONS OF FIRE RATED ELEMENTS

A. Must be made such as to retain that rating.

3.10 HANGERS AND SUPPORTS

A. Provide hangers, brackets, and suspension rods and supplementary steel to support equipment.

B. Hangers provided under other divisions shall not be used for support of Division 26 and 28 equipment unless permitted by Architect/Engineer.

3.11 PAINTING

A. Painting in general will be covered under another division of this specification, except items furnished under Division 26 and 28 that are scratched, marred in shipment or installation, shall be refinished by the Division 26 and 28 Contractor.

3.12 WORKMANSHIP AND OBSERVATION

A. Workmanship shall be of the best quality and none but competent workers shall be employed under the supervision of a competent foreman. All completed work shall represent a neat and workmanship like appearance.

B. All work and materials shall be subject to observation at any and all times by representatives of the Engineer.

3.13 MISCELLANEOUS

A. Provide complete seismic anchorage and bracing for the lateral and vertical support of conduit and electrical equipment, as required by the International Building Code.

B. Conduits that cross seismic separations shall be installed with flexible connection suitable to accommodate conditions. Secure raceways on each side of a separation and provide a minimum of 36” length of flexible conduit to span separation.

3.14 CABLE AND WIRING ROUTED UNDERGROUND OR UNDERSLAB

A. All cables and conductors, both line voltage and low voltage, routed underground or underslab shall be U.L. listed for installation in wet locations per NEC and WAC codes.

END OF SECTION 260000

SECTION 260005 - ELECTRICAL – EXISTING SYSTEMS

PART 1 - GENERAL

1.1 WORK INCLUDED

A. Portions of the existing electrical lighting, power and signal systems are to be removed as detailed on the drawings.

1.2 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

PART 2 - PRODUCTS

2.1 EXISTING MATERIALS

A. Existing materials which are a part of the building shall remain the property of the Owner.

2.2 EXISTING MATERIALS RE-INSTALLED

A. Existing materials and equipment that are removed as a part of the work or stored in surplus may be re-installed as a part of the new system subject to approval of condition suitability by the Architect/Engineer. The requirements of the specifications (i.e. installation, warranty, testing, etc.) shall apply as if the materials were new, supplied by the Contractor.

2.3 EXISTING MATERIALS NOT TO BE RE-INSTALLED

A. In coordination with the Architect/Engineer, these materials shall be made available for his inspection and decision as to whether the Owner will retain possession. Items selected for retention shall be delivered to a location on the premises selected by the Owner and turned over to him. Take reasonable care to avoid damage to this material. If the Contractor fails to conform to this requirement, he shall purchase and turn over to the Owner replacement materials of like kind and quality.

B. All material not selected for retention by the Owner and debris shall be disposed of by the Contractor. This shall include, but not be limited to, removal of PCB type ballasts and fluorescent lamps which shall be disposed of in accordance with EPA requirements.

PART 3 - EXECUTION

3.1 EXISTING CONDITIONS

A. Examine the structure, building, and conditions under which Division 26 work is to be installed for conditions detrimental to proper and timely completion of the work. Do not proceed with work until deficiencies encountered in installation have been corrected. Report any delay or difficulties encountered in installation of Division 26 work which might be unsuitable to connect with work by other divisions of this specification. Failure to report conditions shall constitute acceptance of other work as being fit and proper for the installation of Division 26 work.

B. Maintain continuity of existing circuits of equipment to remain. Existing circuits of equipment shall remain energized. Circuits which are to remain but were disturbed during demolition shall have circuits, wiring, and power restored back to original condition.

3.2 DEMOLITION

A. Switchboards, panelboards, signaling systems, other electrical equipment free standing (or surface mounted), raceway (exposed) and conductors no longer in service as a result of this Contract shall be removed. Unused raceways or sleeves shall be cut flush at ceiling, floor or wall and filled with grout.

3.3 NEW DEVICES IN REMODEL AREAS

A. Provide surface mounting for devices on existing walls. Where existing boxes are indicated to be reused, extend box as necessary and provide new devices and plates.

3.4 EXISTING PANELBOARD

A. Any modifications made to existing panels must be incorporated into the existing circuit index on the panel. If more than three circuits are modified a new typewritten index incorporating the changes to the existing index shall be installed in the existing panel.

B. Listing shall match circuit breaker arrangements, typically with odd numbers on the left and even numbers on the right. Room numbers used shall be final room numbers used in the building as verified with the Owner.

END OF SECTION 260005

SECTION 260010 - EXCAVATION AND BACKFILL FOR ELECTRICAL UNDERGROUND UTILITIES

PART 1 - GENERAL

1.1 GENERAL INCLUDES

A. Excavation and Associated Grading.

B. Trenching and Trench Protection.

C. Backfilling and Compaction.

D. Verification of Existing Utilities.

E. Protection of Utilities.

1.2 RELATED SECTIONS

A. Section 260000 – General Electrical Conditions

B. Section 260533 - Raceways

C. Section 265000 - Lighting

D. Section 283100 – Fire Alarm System

1.3 QUALITY ASSURANCE

A. Inspection of Job Conditions: Prior to starting work and during work, the installer shall examine the work by others, site and job conditions under which excavation, trenching, and backfilling for underground utilities work will be performed, and notify the General Contractor in writing of unsatisfactory conditions or work. Do not proceed with work until unsatisfactory conditions have been corrected in a manner acceptable to the Installer.

B. Codes and Standards: Comply with requirements of the following codes and standards (Latest Edition) except as modified herein:

1. International Conference of Building Officials, "International Building Code".

2. Local requirements for all utility work.

3. OSHA and WISHA regulations.

4. APWA Standard Specifications.

5. National Electrical Code – NFPA 70.

1.4 RESPONSIBILITY

A. The Contractor is solely responsible for compliance with the requirements of the drawings, specifications, local codes and standards, proper construction coordination with work of other trades, and protection and worker's safety. Contractor shall advise Engineer of any discrepancy in, or disagreement with the specifications and/or drawings prior to starting work and not proceed until issue is resolved. Commencement of work shall indicate Contractor's acknowledgement of his expertise in this type of work. Any delay resulting from failure to comply with this procedure will not be basis for an extension of the completion date.

1.5 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced.

B. American Society of Testing and materials (ASTM) publications:

D 422-63	Particle Size Analysis of Soils.
D 423-66	Liquid Limit of Soils.
D 424-59	Plastic Limit and Plasticity Index of Soils.
D 1557-78	Moisture Density Relations of Soils using a 10 lb. (4.54kg) Rammer and 18 inch (457 mm) Drop.
D 2167-66	Density of Soil In-Place by the Rubber Balloon Method.
D 2217-66	Wet preparation of Soil Samples for Particle-Size Analysis and Determination of Soil Contents.
D 2487-69	Classification of Soils for Engineering Purposes.
D 2922-81	Test Methods for Density of Soil and Soil-Aggregate In Place by Nuclear Methods (Shallow Depth).
E 548-79	Generic Criteria for Use in the Evaluation of Testing and Inspection Agencies.

PART 2 - MATERIALS

2.1 SATISFACTORY MATERIALS

A. Materials classified as ASTM D2487, Unified Soil Classification System as SW, SP, GW, and GP are satisfactory for backfill use. Materials classified as SP-SM, GP-GM, GM, GC and ML are also satisfactory for backfill use provided that they contain moisture contents suitable for the intended use and are reasonably free of organic matter. Native material, not considered unsatisfactory as specified below, may comply. Except that no material shall have any object with a dimension exceeding 2 inches and no object shall be sharply angular.

2.2 UNSATISFACTORY MATERIALS

A. Materials classified in ASTM D2487, Unified Soil Classification System as PT, OH, and OL are unsatisfactory. Unsatisfactory materials also include man-made fills, refuse and all materials containing excessive organic matter or having moisture contents which are not suitable for the intended use, or having objects with dimensions exceeding 2 inches (boulders, etc.).

2.3 UNSTABLE MATERIAL

A. Unstable material shall consist of material too wet to properly support the utility conduit or appurtenance structure, and material identified as unsuitable in the National Electrical Code 300-5(F).

2.4 GRAVELLY SAND BORROW MATERIAL

A. Gravelly sand borrow material to provide backfill, or replace unsuitable soil, shall meet the requirements of SW, SP, GW, and GP materials, except that the maximum percentage passing the No. 200 sieve shall not exceed 5% based on the soil fraction passing the U.S. No. 4 sieve, and not contain discrete particles greater than 2 inches in diameter.

2.5 DEGREE OF COMPACTION

A. Degree of compaction shall be expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D1557, Method D. Minimum compaction requirements shall be as specified in PART 3.

2.6 DRAINAGE GRAVEL

A. Shall be 3/4 inch washed gravel with no more than 2% passing 1/2 inch sieve opening.

2.7 SPECIAL BEDDING AND INITIAL BACKFILL MATERIAL

A. Minus 3/8 inch washed pea gravel.

PART 3 - EXECUTION

3.1 EXCAVATION

A. If workers enter any trench or other excavation four or more feet in depth that does not meet the open pit requirements of WSDOT Section 2.09.3(3)B, it shall be shored and cribbed. The Contractor alone shall be responsible for worker safety. All trench safety systems shall meet the requirements of the Washington Industrial Safety and Health Act, Chapter 49.17 RCW.

B. Excavation of every description and of whatever substances encountered shall be performed to allow the installation of all utilities at the lines and grades as required. During excavation, material satisfactory for backfilling shall be stockpiled in an orderly manner at a distance from the banks of the trench sufficient to avoid overloading and to prevent slides or cave-ins. Adequate drainage shall be provided for the stockpiles and surrounding areas by means of ditches, dikes, or other approved methods. The stockpiles shall also be protected from contamination with unsatisfactory excavated material or other material that may destroy the quality and fitness of the suitable stockpiled material.

C. If the Contractor fails to protect the stockpiles and any material becomes unsatisfactory as a result, such material shall be removed and replaced with satisfactory on-site or imported material from approved sources at no additional cost to the Owner.

D. Excavated material not required or not satisfactory for backfill shall be removed from the site and shall be disposed of off site, at the Contractor's expense, at the Contractor's waste area. Any excess satisfactory excavated materials shall not be mixed with unsatisfactory materials. Unsatisfactory materials shall not cover available suitable materials, or be disposed of in such a manner as to interfere with subsequent borrow operations.

E. Grading shall be done as may be necessary to prevent surface water from flowing into the excavation, and any water accumulating therein shall be removed so that the stability of the bottom and sides of the excavation is maintained. Unauthorized over-excavation shall be backfilled in accordance with paragraph 3.05 BACKFILLIING at no additional cost to the Owner.

F. The Contractor shall provide dewatering as required for installation of underground work.

3.2 TRENCH EXCAVATION

A. The trench excavation shall meet the requirements of the National Electrical Code and local utility standards.

B. Bottom Preparation: The bottoms of trenches shall be accurately graded to provide uniform bearing and support for the bottom quadrant of each section of the conduit and for bedding. Stones of 2 inches or greater in any dimension, or as recommended by the conduit manufacturer, whichever is smaller, shall be removed to avoid point bearing.

C. Removal of Unsuitable Material: Where unsuitable material is encountered in the bottom of the trench, such material shall be removed to the depth directed and replaced to the proper grade with select granular material as provided in paragraph 3.05 BACKFILLING. When removal of unsuitable material is required due to the fault or neglect of the Contractor in his performance of the work, the resulting material shall be excavated and replaced by the Contractor without additional cost to the Owner.

D. Bedding: The bedding surface for the conduit shall provide a firm foundation of uniform density throughout the entire length of the conduit. The conduit shall be bedded carefully in a soil foundation accurately shaped and rounded to conform to the lowest one-fourth of the outside portion of circular conduit or to the lower curved portion of conduit arch for the entire length of pipe or arch. When necessary, the bedding shall be taped. Provide bedding using pea gravel where noted on the drawings.

3.3 EXCAVATION FOR APPURTENANCES

A. Excavation for manholes, handholes or similar structures below grade shall be sufficient to leave at least 12 inches clear between the outer structure surfaces and the face of the excavation or support members. When concrete or masonry is to be placed in an excavated area, special care shall be taken not to disturb the bottom of the excavation. Excavation to the final grade level shall not be made until just before the concrete or masonry is to be placed.

3.4 JACKING, BORING, AND TUNNELING

A. Unless otherwise indicated, excavation shall be by open cut, except that sections of a trench may be jacked, bored, or tunneled if the raceway, cable or duct can be safely and properly installed and backfill can be properly tamped in such sections.

3.5 BACKFILLING

A. Backfill material shall be compacted to 6" layers and as specified in Paragraph 3.06-Compaction.

B. Trench Backfill: Trenches shall be backfilled to finish grade.

C. Replacement of Unstable Material: Unstable material removed from the bottom of the trench of excavation shall be replaced with select granular material or gravel borrow placed in layers not exceeding 6 inches loose thickness.

D. Bedding and Initial Backfill: Bedding shall consist of satisfactory materials. Initial backfill shall be in 6 inch lift.

3.6 COMPACTION

A. Each layer of fill, or the excavated subgrade, shall be compacted to at least 95%, per ASTM D1557, of laboratory maximum density. Compaction shall be accomplished by approved tamping rollers, pneumatic-tired rollers, three-wheel power rollers, or other approved compaction equipment.

3.7 PROTECTION

A. Newly graded excavated or bedded areas shall be protected from traffic and from erosion, and any settlement or washing away that may occur from any cause, prior to acceptance, shall be repaired and grades reestablished to the required elevations and slopes.

END OF SECTION 260010

SECTION 260519 - WIRES AND CABLES

PART 1 - GENERAL

1.1 WORK INCLUDED

A. Provide all wire, cable, and terminations complete.

1.2 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

PART 2 - PRODUCTS

2.1 WIRE AND CABLE (Copper, 600-Volt)

A. Interior and Above Grade: All wires to be Type THW or RHW. Type THWN/THHN or XHHW wire may be utilized at Contractors option, subject to code requirements. Wire and cables shall be brought to project in original containers bearing the underwriters label. Provide Type AVA wire where conductors are subject to temperature above 167 Degrees F.

B. Underground: All conductors to be type USE. Increase Raceway size when necessary to accommodate conductors per code. Exception: Underground conductors completely contained in code recognized Raceway and boxes may be Type THW, THWN or XHHW.

2.2 SPLICES

A. Above Grade: Solderless type only. Preinsulated "twist-on" type (limited to size #10 and smaller). Bolt on compression type with application of preformed insulated cover, heat shrinkable tubing or plastic insulated tape acceptable for all sizes.

B. Below Grade: Splices below grade shall be in handholes and shall be made watertight with epoxy resin type splicing kits similar to Scotchcast.

2.3 TERMINATIONS

A. Compression set, bolted or screw terminal.

B. Conductors #12 and smaller shall utilize eye or forked tongue type compression set terminator when termination is to a bolted or screw set type terminal block or terminal cabinet.

2.4 PLASTIC CABLE TIES

A. Nylon or Equivalent, locking type.

PART 3 - EXECUTION

3.1 GENERAL

A. Install all wiring in Raceway unless shown or specifically authorized otherwise.

3.2 WIRE SIZE

A. No. 12 AWG minimum for power and lighting circuits.

B. Provide solid wire for No. 10 AWG and smaller, and stranded conductors for No. 8 AWG and larger (600) volts.

3.3 TESTS

A. In addition to the factory testing of all equipment and cable, the Contractor shall test all wiring connections for continuity and ground before any fixtures or other loads are connected. Tests shall be made with a 500V minimum DC "Megger" type tester. If tests indicate faulty insulation (less that 2 megohms), such defects shall be corrected and tested again. Contractor shall provide all apparatus to make tests and shall bear all expenses of required testing. Routine operation tests shall be made on all pieces of equipment to demonstrate that working parts are in operating condition. Results of all tests shall be recorded and submitted to the Architect. The Contractor shall immediately replace all parts, which fail to pass the test.

B. All circuits both in and out of the building shall test out free of grounds, short circuits and other defects.

C. Check and record catalog number and ampere size of controller overload heaters installed, nameplate full-load amperes, and actual operating amperes of each motor. IMPORTANT: Submit recorded data in triplicate to the Engineer. Check proper load balance on the electrical system, direction of rotation, lubrication, and overload protection of all motors before placing in operation.

D. The final test of all equipment shall be made on dates designated by the Architect/Engineer and all readings shall be made in his presence.

E. Feeders shall be checked to ensure all phases are energized before connecting to their respective motors. Each motor shall rotate in the proper direction for its respective load. Prior to rotation test, all bearings shall be inspected for proper lubrication.

F. Minimum megger test for equipment shall be as follows:

Equipment Maximum Voltage Rating	Minimum Test Resistance
1,000-Volts or less	2 Megohms

G. Provide certification of torque values for feeder and service entrance conductors per equipment manufacturer's recommendation.

3.4 CONDUCTOR SIZES, REFERENCED ON PLANS

A. Copper, type THW or RHW unless noted.

B. Use no mechanical means for pulling No. 8 AWG conductors and smaller. Powdered soap stone or approved spray cream shall be the only lubricant used.

3.5 PULLING

A. Use no mechanical means for pulling No. 8 AWG conductors and smaller. Powdered soap stone or approved spray cream shall be the only lubricant used.

3.6 STRIPPING INSULATION

A. Do not ring the cable, always pare or pencil.

3.7 TAPING

A. If used shall be half lapped synthetic tape.

3.8 CONDUCTORS IN PANELS AND SWITCHBOARDS

A. Conductors in panels, switchboards, and terminal cabinets shall be neatly grouped and formed in a manner to "Fan" into terminals with regular spacing.

3.9 CABLE SUPPORTS

A. Provide conductor support devices as required by code in vertical cable runs.

3.10 RACEWAY SIZES REFERENCED ON DRAWINGS

A. Raceways are sized for copper, type THW, unless otherwise noted. Size all Raceways per code unless specifically noted to be larger on the drawings.

END OF SECTION 260519

SECTION 260526 - GROUNDING AND BONDING

PART 1 - GENERAL

1.1 WORK INCLUDED

A. A grounding system shall be provided for neutral ground and equipment ground as required by code.

1.2 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

PART 2 - PRODUCTS

2.1 GROUNDING CONDUCTORS

A. Copper, code size, with physical protection where subject to damage. Bare or green insulated.

PART 3 - EXECUTION

3.1 GENERAL

A. Provide all grounding for electrical systems and equipment as required by codes and as specified herein.

3.2 SIZE OF GROUND WIRE

A. As required by code. Where ground wire is exposed to physical damage or is used outside of building, protect with conduit.

3.3 GROUND CONNECTION OF WATER PIPING

A. Metal internal piping shall be grounded, as part of this Contract. This includes jumpers for dielectric fittings.

3.4 GROUND CONNECTION OF BUILDING STEEL

A. Structural metal shall be grounded, as part of this Contract.

3.5 CONNECTION TO THE GROUND BUS

A. Provide connections in accordance with the codes; including but not limited to raceway systems, switchboard/panelboard frames, service neutral, separately derived systems, electrically operated equipment and devices. No device or equipment shall be connected for electrical service which has a neutral conductor connected to a grounding conductor or to the frame within the device or equipment.

3.6 METHOD OF CONNECTION

A. Make all ground connections and ground cable splices by thermal welding. Grounding lugs, where provided as standard Manufacturer's items on equipment furnished, may be used.

3.7 FLEXIBLE RACEWAY

A. Shall not be used for grounding. Install separate ground conductor in all flexible raceway.

3.8 PVC RACEWAY

A. Install separate ground conductor in all PVC raceway as required per code.

3.9 DROP CORDS

A. Shall have a grounding wire and be connected with a grounding type plug and receptacle.

END OF SECTION 260526

SECTION 260532 - OUTLET AND PULL BOXES

PART 1 - GENERAL

1.1 WORK INCLUDED

A. Provide outlet and pull boxes to enclose devices, permit the pulling of conductors and for wire splices and branches.

1.2 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

PART 2 - PRODUCTS

2.1 INTERIOR WIRING

A. General: Outlet and pull boxes shall be pressed drawn steel, zinc coated with plaster ring where applicable. Welded boxes not allowed. Four-inch size minimum. Large pull boxes shall be fabricated sheet steel, zinc coated or baked enamel finish, with return flange and screw retained cover.

B. Surface Metal Raceway: Boxes of same Manufacture and to match Raceway. Boxes to accommodate standard devices and device plate.

C. Concrete and Masonry: Boxes for casting in concrete or mounting in masonry walls shall be the type specifically designed for that purpose.

D. Install pull boxes so as to be accessible after completion of building construction.

E. Ceiling outlet boxes shall be galvanized octagonal 4 inch, 1-1/2 inch deep (without fixture stud), 2-1/8 inches deep (with fixture stud).

2.2 EXTERIOR WIRING

A. Above Grade: Outlet and junction boxes shall be cast or malleable iron or shall be cast of corrosion resistant alloy compatible with Raceway to which it is connected. Pull boxes shall be fabricated of heavy gauge steel and hot dipped galvanized. All boxes shall have gasketed covers.

B. Below Grade: Where exposed to earth, boxes (handholes) shall be constructed of precast concrete with size, configuration, cover, grates and reinforcing as required by the particular installation. Manufacturer: Similar to Utility Vault 3030LA with base or Fogtite J11 Type 2 with base. Lid shall be H-20 rated where installed in traffic areas. Where not exposed to earth shall comply with Paragraph 2.02A above.

C. Exterior outlet boxes shall be weather resistant and rain tight, with appropriate covers, gaskets and screws.

PART 3 - EXECUTION

3.1 ANCHORING

A. All boxes shall be firmly anchored directly or with concealed bracing to building studs or joints. Boxes must be so attached so that they will not "Rock" or "Shift" when devices are operated.

3.2 FLUSH MOUNTING

A. Except for surface mounted boxes or boxes above accessible ceilings, all boxes shall have front edge (box or plaster ring) even with the finished surface of the wall or ceiling.

3.3 ELECTRICAL OUTLETS

A. General: Coordinate the work of this section with the work of other sections and trades. Study all Drawings that form a part of this Contract and confer with various trades involved to eliminate conflicts between the work of this section and the work of other trades. Check and verify outlet locations indicated on Architectural Drawings, door swings, installation details, layouts of suspended ceilings and locations of all plumbing, heating and ventilating equipment.

B. Centered on Built-In Work: In the case of doors, cabinets, recessed or similar features, or where outlets are centered between such features, such as between a door jamb and a cabinet, make these outlet locations exact. Relocate any outlets which are located off center.

C. Vertical and Horizontal Relationships: Where more than one outlet is shown or specified to be at the same elevation or one above the other, align them exactly on centerlines horizontally or vertically. Relocate as directed all such outlets (including lighting, receptacle, power signal and thermostat outlets) which are not so installed, at no additional cost to Owner.

D. Device Outlet Height: Measure from the finished floor.

*Switches	4 Feet, Set Vertically, to Top of Box
*Receptacles,	18 Inches, Set Vertically to Centerline
Telecommunications	
Other	As Noted or as Directed by Architect

**Heights may vary. See Drawings for additional information*

E. Ceiling Location: For acoustical material locate outlet either at the corner joint or in the center of a panel, whichever is closer to the normal spacing. Locate all outlets in the same room in the same panel location.

F. Installed In Sound Walls: Boxes installed in sound walls shall not be installed back to back. All boxes shall be separated by one stud space and shall be interconnected with flex conduit with a 90° loop. Where stud space separation is not possible, utilize sound attenuating mastic around each box. 3M Fire Barrier Moldable Putty Pads MPP+ (2.54 mm minimum) or similar.

3.4 ELECTRICAL WORK IN COUNTERBACKS, MILLWORK AND CASEWORK

A. Provide as shown and/or specified. Provide templates, where required, to other trades for drilling and cutting to insure accurate location of electrical fixtures (outlets and devices) as verified with the Architect. Provide all wiring, devices, plates and connections required by said fixture.

3.5 CONNECTION TO EQUIPMENT

A. For equipment furnished under this or other Divisions of the Specifications, or by others. Provide outlet boxes of sizes and at locations necessary to serve such equipment. An outlet box is required if the equipment has pigtail wires for external connection, does not have space to accommodate circuit wiring used. Study equipment details to assure proper coordination.

3.6 BLANK COVERS

A. Provide blank covers or plates over all boxes not covered by equipment.

3.7 JUNCTION OR PULL BOXES

A. Pull and junction boxes shall be installed as shown, and to facilitate pulling of wire and to limit the number of bends within code requirements. Boxes shall be permanently accessible and shall be placed only at locations approved by the Architect.

B. In suspended ceiling spaces, boxes shall be supported from the structure independently from ceiling suspension system.

C. The Drawings do not necessarily show every pull or Junction Box required. The Contractor is permitted to provide boxes deemed necessary by him for his work when installed in accordance with these Specifications.

3.8 BOXES CONTAINING MULTIPLE DEVICES

A. Boxes containing emergency and normal devices are permitted only with steel barriers Manufactured especially for the purpose of dividing the box into two completely separate compartments.

B. Device Boxes Containing Multiple Devices and Wiring Rated Over 150 Volts to Ground and Over 300 Volts Between Conductors are permitted only with steel barrier manufactured especially for the purpose of dividing the box into separate compartments for each device having exposed live parts.

3.9 BOXES IN EARTH

A. Provide for all wire splices and as required to pull conductors. Boxes (handholes) shall be set in place on a 3" sand bed. Coverplates shall be flush to, and match the slope of, the final surface grade.

3.10 NAMEPLATES

A. For all line voltage junction boxes, provide engraved nameplate indicating circuit numbering of all wiring in junction box.

END OF SECTION 260532

SECTION 260533 - RACEWAY

PART 1 - GENERAL

1.1 WORK INCLUDED

A. Provide Raceway System complete.

1.2 RELATED DOCUMENTS

A. Section 26 00 00 – General Electrical Conditions

PART 2 - PRODUCTS

2.1 GALVANIZED RIGID STEEL CONDUIT (GRS)

A. General: Hot dipped galvanized.

B. Fittings: Galvanized malleable iron or noncorrosive alloy compatible with galvanized conduit. Erickson couplings, watertight split couplings (O.Z. type or equivalent) permitted. Running thread or set screw type fittings not approved.

2.2 INTERMEDIATE METAL CONDUIT (IMC)

A. General: Hot Dipped galvanized.

B. Fittings: Galvanized malleable iron or noncorrosive alloy compatible with galvanized conduit. Erickson couplings, watertight split couplings (O.Z. type or equivalent) permitted. Running thread or set screw type fittings not approved.

2.3 ELECTRICAL METALLIC TUBING (EMT)

A. General: Hot dipped galvanized.

B. Fittings: Raintight; steel or malleable iron type using a split corrugated compression ring and tightening nut or stainless steel locking disc. Steel set screw fittings are acceptable for dry locations. Indenter, drive-on and pressure cast or die cast type set screw are not acceptable.

2.4 FLEXIBLE METAL CONDUIT (FMC, LFMC)

A. Dry Locations:
   1. General: Galvanized flexible steel for dry locations only.
   2. Fittings: Malleable iron or steel, Thomas and Betts "squeeze" type or equal.

B. Damp and Wet Locations:
   1. Liquid Tight: Polyvinyl chloride (PVC) weatherproof cover over flexible steel conduit.
   2. Fittings: Thomas and Betts "liquid tight" or equal.

2.5 SURFACE METAL RACEWAY

A. Formed steel or aluminum type. Standard factory finish. Where color choice is available, consult Architect/Engineer for selection prior to ordering.

2.6 RIGID NON-METALLIC CONDUIT (PVC)

A. Schedule 40 rigid polyvinyl chloride type unless otherwise noted.

2.7 RIGID ALUMINUM CONDUIT

A. Permitted only in specified locations.

B. Fittings copper free cast aluminum.

PART 3 - EXECUTION

3.1 GENERAL

A. Install Raceway concealed in construction unless noted otherwise on the Drawings or specifically approved in writing by the Architect/Engineer.

B. Cut Raceway ends square, ream and extend maximum distance into all couplings and connectors.

C. Provide and install manufactured end caps on all Raceway ends during construction to prevent the entrance of water or dirt. Tape, as a cover, not permitted.

D. Swab out all Raceways before pulling wires.

E. All elbows for GRS and PVC Raceway shall be factory radius bends. For all other Raceway, use factory radius bends of 1-1/4" and larger diameter.

F. Raceway shall not penetrate sheet metal ducts unless permission is granted by Architect/Engineer. All sleeves shall be provided for Raceway installation.

G. Provide 2 - 3/4" C.O. stub into accessible ceiling space from all recessed panelboards or systems terminal boxes.

3.2 GALVANIZED RIGID STEEL CONDUIT

A. All Connections shall be watertight. Install for all Raceways in concrete or where subject to damage.

3.3 INTERMEDIATE METAL CONDUIT

A. Intermediate metal conduit is permitted as a substitute for galvanized rigid steel conduit except where GRS is required by code.

3.4 ELECTRICAL METALLIC TUBING

A. Install for wiring in masonry, frame construction, furred ceilings and above suspended ceilings. May be used for exposed work in unfinished areas where not subject to damage. Where construction involves masonry work, surface cut masonry units wherever such masonry units are to remain unplastered or uncovered in complete construction.

3.5 RIGID ALUMINUM CONDUIT

A. May be used in lieu of galvanized rigid steel conduit where Raceway is run above grade or inside of buildings; rigid aluminum conduit not permitted where Raceways are encased in or attached to concrete or are below grade.

3.6 RACEWAYS UNDERGROUND

A. Galvanized rigid steel conduit - painted with two coats of bitumastic paint - or galvanized rigid steel conduit with 15 mil. polyvinyl chloride (PVC) jacket (repair abrasions with PVC base paint or PVC)

B. PVC Raceways may be used for underground runs when permitted by code. Field bends, when necessary, shall be formed only with factory recommended heater. Penetrations through floor and walls shall be galvanized rigid steel conduit. PVC, if used, shall be increased in size from that shown to include code required ground wire. Bends in excess of 10 degrees shall be GRS.

C. Arrange and slope Raceways entering building to drain away from building.

D. Ground wires shall be provided in all PVC Raceway.

3.7 INSERTS, SHIELDS AND SLEEVES

A. Furnish and set in place, in advance of pouring slabs and walls, all inserts and sleeves needed to execute Division 26 equipment installation.

B. Where supports in slabs are required after wall has been poured, use a drilled-in threaded insert, installed as recommended by Manufacturer.

C. Sleeves shall be provided for all wall penetrations.

3.8 RACEWAYS THAT STUB UP THROUGH FLOOR

A. Install at such depth that the exposed Raceway is vertical and no curved section of the elbow is visible.

B. PVC Raceway shall not be stubbed through floors.

3.9 SEALING OF RACEWAY PENETRATIONS

A. Exterior Wall Surfaces Above Grade: Seal around all penetrations with caulking approved by Engineer. For concrete construction above ground level, cast Raceway in wall or core drill wall and hard pack with a mixture of equal parts of sand and cement.

B. Exterior Surfaces Below Grade: Cast Raceway into wall (or floor) or use manufactured seal assembly (such as O.Z. type "FSK") cast in place.

C. Roofs: Provide mopped, lead, roof jack where Raceway penetrates roof membrane.

D. Fire Rated Floors, Walls, Ceiling/Roofs: Concrete or masonry, seal around Raceway penetration with Dow Corning 3-6548 silicone RTV foam or approved equal. Plaster or gypsum wallboard, seal around Raceway penetration with plaster, fire tape per local Fire Marshal's requirements.

3.10 SEALING OF RACEWAYS

A. Seal interior of all Raceways which pass through buildings roofs, floors or through outside walls of the building, above or below grade. Seal on the end inside the building using duct sealing mastic, non-hardening compound type, specially designed for such service to maintain the integrity of the seal of the wall, floor or roof. Pack around the wires in the Raceways.

3.11 HANGARS FOR RACEWAYS

A. In suspended ceiling spaces Contractor may, at his option, attach 1/2" or 3/4" EMT Raceways to the ceiling suspension system where such system is structurally suitable on independent wire secured at both ends; in which case, provide clips manufactured for the purpose.

B. When more than two Raceways will use the same routing, group together on a patented channel support system (such as Unistrut).

3.12 SURFACE METAL RACEWAY

A. Install parallel to building surface (i.e., wall, ceiling, floor). Fasten to surface as recommended by Manufacturer. Mount so Raceway is in the least obvious location. Shall be used in lieu of conduit in finished areas.

3.13 FLEXIBLE CONDUIT

A. Flexible conduit shall be used only for connection to motors and equipment subject to vibration with 90 degrees loop minimum to allow for isolation and for lay-in fluorescent fixtures above T-Bar ceilings. For fixture installations, one end of flex must terminate in rough-in junction box. Flex conduit shall not be installed over 6' long or used to connect from fixture to fixture. Use liquid tight for pumps, equipment which is regularly washed down, and equipment in damp locations. Provide ground wire.

3.14 PULL CORDS

A. Nylon type shall be included in all installed empty Raceway.

END OF SECTION 260533

SECTION 260534 - METAL CLAD CABLE (TYPE MC) AND FITTINGS

PART 1 - GENERAL

1.1 WORK INCLUDED

A. Provide Metal Clad (Type MC) Cable for power, control and lighting systems.

B. Provide wiring connections and terminations.

1.2 RELATED DOCUMENTS

A. Section 26 00 00 – General Electrical Conditions

1.3 REGULATORY REQUIREMENTS

A. UL 1569. Products shall be tested, approved and labeled/listed by Underwriters Laboratories, Inc.

1.4 USES PERMITTED

A. MC Cable is permitted to be used for 20amp lighting and power circuits where routing is above grade, concealed and the installation meets the requirements of NEC 330.

B. MC Cable shall NOT be used for homerun circuits from the fixture, receptacle, or equipment to the panelboard. Hard conduit must be used from the panelboard to the nearest accessible ceiling space to the panelboard.

C. MC Cable shall not be used for HVAC equipment.

PART 2 - PRODUCTS

2.1 CABLE ASSEMBLY

A. Metal clad cable assemblies shall consist of 2, 3 or 4 current carrying conductors and an equipment ground conductor.

B. Conductors: Solid Copper conductor, No. 12 AWG minimum or No. 10 AWG maximum. Installation methods shall be as specified under Part 3 - Execution.

C. Insulation: Conductor insulation shall be rated 600 volt, Type THHN, 90°C dry.

D. Fillers: Fillers shall be non-hygroscopic and non-wicking.

E. Binder: Core binder shall be corrugated polyester.

F. Sheath: The metal sheath shall be galvanized steel or aluminum. The metal sheath shall be extruded onto the cable or applied longitudinally, then wrapped and welded. The sheath shall then be corrugated for greater flexibility.

G. Jacketing: When PVC jacketing is required, the jacket shall be flame-retardant PVC with a temperature range of -40°C to 90°C.

H. Equipment Grounding Conductor: The equipment ground wire shall be of the same construction as specified in 2.02.A and 2.02.B and be at a minimum the same size as the current carrying conductors. The insulation color shall be green.

2.2 FITTINGS

A. Fittings shall be UL listed and identified for such use with metal clad continuous corrugated sheath cable, with or without PVC jacketing, as is appropriate for the installation.

B. Connectors shall be of steel or malleable iron and shall be a squeeze type clamp connector with a locknut for non-jacketed metal clad cable. Compression gland type connectors shall be used for jacketed metal clad cable.

PART 3 - EXECUTION

3.1 INSTALLATION – POWER AND LIGHTING SYSTEMS WIRING

A. All wiring shall be installed in compliance with the latest version of the National Electrical Code and all other applicable codes and standards as indicated elsewhere in these specifications.

B. Use of metal clad cable shall be permitted only for lighting, equipment and receptacle branch circuits. Metal clad cable shall not be permitted in locations designated to be hazardous Class I, II or III.

C. Metal clad cable shall be permitted only for motor circuits where the motor being served is less than ½ HP and rated for 120V, single phase. Metal clad cable is not permitted for HVAC equipment and controls.

D. Metal clad cable shall only be installed concealed within walls and above ceiling interstitial spaces. Where there is no ceiling interstitial space, metal clad cable may not be used.

E. Bends in corrugated sheath metal clad cable shall be made so that the cable will not be damaged. The radius of the curve of the inner edge of any bend shall not be less than seven (7) times the diameter of the metallic sheath.

F. Metal clad cable is not permitted to connect branch circuits to fume hoods, gas storage cabinets, or chemical storage cabinets.

G. No metal clad cable shall be installed in ventilation ducts or plenums.

H. Conductors in Enclosures: Provide neat and workmanlike installation with conductors tied with T&B Ty-Rap, Virginia Plastics, or equal, nylon wire ties in terminal cabinets, gutters and similar locations.

3.2 FITTINGS

A. Fittings used for connecting metal clad cable to boxes, light fixtures or other equipment shall be UL listed and identified for such use.

B. Cable preparation for installation of fittings shall follow manufacturer's instructions. The manufacturer's specialized tools shall be used for preparing cable ends for installation of fittings.

C. The cable end shall be cut square to ensure flush seating of the cable into the fitting. Fitting securement screws shall be properly torqued. Cable ends shall be fitted with insulating bushings intended for the type of metal clad cable being installed.

D. For jacketed metal clad cable, the outer jacket shall be removed to the length specified by the fitting manufacturer's instructions. Remove oils or solvent by-products from the outer jacket of the cable. The cable end shall be cut square to ensure flush seating of the cable into the fitting. The fitting gland nut shall be properly torqued to the manufacturer's specifications.

3.3 ARRANGEMENT AND SUPPORT

A. Metal clad cables shall be run parallel with walls or structural elements. Vertical runs shall be plumb; horizontal runs level and parallel with structure, as appropriate. Groups shall be racked together neatly with both straight runs and bends parallel and uniformly spaced.

B. Metal clad cables shall be securely fastened in place at intervals of not more than six feet, with suitable clamps or fasteners of approved type, and all vertical conduits shall be properly supported to present a mechanically rigid and secure installation.

C. Metal clad cable installed parallel to framing members, such as studs, joist, or rafters, shall be supported so that the nearest outside surface of the cable is not less than 1-1/4 inches from the nearest edge of the framing member. Where this distance cannot be maintained, the cable shall be protected by a steel plate, sleeve, or equivalent that is at least 1/16-inch thick.

D. Maintain at least 6-inch clearance between metal clad cables and other piping systems. Maintain 12-inch clearance between metal clad cables and heat sources such as flues, steam pipes, and heating appliances.

E. No metal clad cable shall be fastened to other conduits or pipes or installed so as to prevent the ready removal of other pipes or ducts for repairs.

F. Individual metal clad cables hung from roof structure or structural ceiling shall be supported by split-ring hangers and wrought-iron hanger rods. Where three (3) or more metal clad cables are suspended from the ceiling in parallel runs, use steel channels, Kindorf, Unistrut or equal, hung from 1/2-inch rods to support the conduits. The conduit on these channels shall be held in place with metal clad cable clamps designed for the particular channel that is used.

G. Secure metal clad cable support racks to concrete walls and ceilings by means of cast-in-place anchors; die-cast, rustproof alloy expansion shields; or cast flush anchors. Wooden plugs, plastic inserts, or gunpowder driven inserts shall not be used as a base to secure conduit supports.

H. Metal clad cable shall be supported immediately on each side of a bend and not more that one (1) foot from an enclosure where a run of metal clad cable ends.

I. Use of cable tray:

1. The sum of the cross-sectional areas of all cables shall not exceed the maximum allowable cable fill area allowed by NEC Tables 392.9, 392.9(E) and 392.9(F).

2. Cables shall be installed in a single layer with a maintained spacing of not less than one cable diameter between cables.

3. Ampacity of cables installed in cable tray shall meet the requirements of NEC 392.11.

3.4 INSPECTION AND TESTS

A. General: The electrical installation shall be inspected and tested to ensure safety to building occupants and operating personnel and conformity to Code

B. Measure and record insulation resistance of all power and control wiring including insulation resistance of all equipment:

1. The insulation resistance of each circuit phase-to-phase and phase-to-ground shall be measured. For circuits rated less than 600 volts, the resistance shall not be less than 2 megohms.

2. Systems rated above 240 volts shall be tested with a 1000-volt Megohmeter. Circuits rated 240 volts and below shall be tested with a 500-volt Megohmeter. The D.C. potential shall be applied for thirty (30) seconds.

C. The contractor shall record test readings and submit certified test to the Engineer for review and acceptance approval before energizing respective circuits.

END OF SECTION 260534

SECTION 262416 - PANELBOARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

1.2 WORK INCLUDED

A. Provide all panelboard equipment, complete; dead front type.

PART 2 - PRODUCTS

2.1 PANELBOARD TYPE

A. Panelboards shall be rated at proper voltage and current for intended use with busbars of copper or aluminum. Panels shall be 3-phase, 4-wire, 100% neutral, unless noted otherwise. Where aluminum is utilized, all lugs shall be of an approved compression type. Provide multiple lugs where conductors in parallel or "feed through" are shown on the Drawings.

B. Conductor Connectors shall be bolted to busbars using Grade 5 bolts and Belleville washers. Feeder conductor connectors shall be rated for 75 Degree C. wire when 75 Degree C. wire is indicated. Where aluminum conductors are utilized for feeders or branch circuits the connectors shall conform to Section 260519.

C. Panelboards shall have a separate ground bus bonded to the panelboard frame.

D. Where 120-Volt, 15- or 20-Amp breakers are intended for switching loads they shall be of type rated for switching duty labeled "SWD."

2.2 ACCEPTABLE MANUFACTURERS

A. General Electric

B. Square-D

C. Seimens

D. Cutler-Hammer

2.3 CIRCUIT BREAKERS

A. The following interrupting capacity, 10,000 AIC Symmetrical shall be considered minimum. Other ratings shall be as specified on panel schedules shown on the Drawings. Series rating of breakers is not allowed.

B. Mount breakers in all panelboards so that breaker handles operate in a horizontal plane. Bolt in type only. Provide common trip on all multiple pole breakers.

C. Where noted, provide spare breakers, complete for future connection of wiring circuits. Where "Space" is indicated for breakers, provide all bussing and breaker mounting hardware in the panelboard, provide steel knockouts in dead front metal closure of unused part of panel. If any steel knockouts are removed, provide breakers in such spaces or approved coverplates. Open spaces are not permitted.

D. For multi-wire branch circuits, provide approved breaker handle ties where required by NEC 210.4.

2.4 CABINET FOR EACH PANELBOARD

A. Flush or surface, as indicated; tight closing doors without play, when latched. Where two cabinets are located adjacent to each other in finished areas, provide matching trim of the same height. Where a remote controlled switch or contactor is mounted in any panelboard, mount on same frame as panelboard interior with screw retained access door in dead front shield; common door over circuit breakers and remote controlled device. Where flush mounted, provide (2) 3/4" conduits to accessible ceiling space for future expansion.

B. All conduits for future expansion shall stub into a junction box, where located above grade, and shall be sealed in the panel.

C. Provide cabinets of sufficient dimensions to allow for future expansion and addition of circuit breakers within the panelboards as indicated on panel schedules.

D. Provide cabinet front with full-height hinged door. One door over the interior and an additional hinged dead front cover over interior and wireway (door-in-door). Full-height front cover hinged to box with concealed trim clamps. Provide flush door locks.

E. Provide lock for each cabinet door. All Electrical Distribution Equipment Locks shall be keyed identically. Key system shall match existing. Supply Owner with minimum six keys.

F. Fasten panelboard front with machine screws with oval counter-sunk heads, finish hardware quality, with escutcheons or approved trim clamps. Clamps accessible only when dead front door is open are acceptable. Surface mounted panelboards with fronts greater than 48 inches vertical dimension shall be hinged at right side in addition to hinged door over dead front.

G. Finish: Provide factory prime coat for cabinets to be located in finished areas. Where cabinets are located in unfinished areas, standard lacquer or enamel finish, gray or blue-gray color, shall be substituted for factory prime coat.

2.5 SYSTEM OF NUMBERING AND BUS ARRANGEMENT

A. Shall be as shown on the Panel Schedules on the Drawings.

2.6 PANELBOARD NAMEPLATE

A. Provide engraved and filled (or color layer - engraved through outer layer) plastic nameplate with ½-inch high characters (for panel name); attached with screws to each NEMA 1 panelboard front. White on black, include voltage, phases, wires and minimum A.I.C. Rating in 3/8-inch characters.

B. Nameplate color shall be:

Emergency System:	White letters on red
Normal System:	White letters on black

PART 3 - EXECUTION

3.1 MOUNTING

A. Secure in place with top of cabinet at 6'-0", unless otherwise noted. Top of cabinet and trim shall be level. Firmly anchor cabinets directly or with concealed bracing to Building Structure. When panels are not located in or directly on a wall, provide a support frame of formed steel channel which is anchored to the floor and Ceiling Structure. Interiors shall not be installed until Structure is totally enclosed. Where panels are mounted adjacent to each other, the top edges shall be at the same height.

3.2 CIRCUIT INDEX

A. For each branch circuit panelboard provide a typewritten index listing each circuit in the panelboard by number with its proper load designation. Mount with a transparent protective cover inside cabinet door. Listing shall match circuit breaker arrangements, typically with odd numbers on the left and even numbers on the right. Room numbers used shall be final room numbers used in the building as verified with the Owner, and not room number assigned on Plans.

3.3 CABINET PAINTING

A. Cabinets furnished as prime painting shall be field painted to match color of adjacent wall. (See Division - Painting).

3.4 SPACE

A. Verify space available with equipment sizes and Code Required Working Clearances prior to Submittal of Shop Drawings.

3.5 GROUNDING

A. Provide separate ground busbar for all panels supplying isolated ground circuits.

3.6 FEED THROUGH AND DOUBLE LUGS

A. Provide feed through or double lugs with amperage equal to the incoming feeder amperage unless shown as larger.

END OF SECTION 262416

SECTION 262419 - MOTOR CONTROLLERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

1.2 WORK INCLUDED

A. Work under this section includes all requirements for motor controls to be furnished under the electrical portion of the work on all electrical motor driven equipment. Individually mounted starters shall be provided by Division 26 Contractor. Motor controls shall conform to NEMA Standards for each specific purpose.

B. The Division 26 Contractor shall furnish all motor controllers not included with equipment furnished under other divisions of these specifications or by Owner. The Division 26 Contractor shall install all motor controllers including all controllers not factory assembled into equipment furnished under other divisions of these specifications or by Owner.

1.3 MOTOR VOLTAGE INFORMATION

A. Voltages available are 480 Volt, 3-phase or 208 Volt, 3-Phase, and 115 Volt Single-Phase.

B. Circuits are designed (in general) for motors as follows:
   1. Smaller than 1/2 H.P. - 115 Volts, Single Phase 1/2 H.P. and larger - 460 or 200 Volts, 3 Phase.

C. Verify motor sizes and voltages provided under other divisions and notify General Contractor immediately if any discrepancies are noted.

1.4 REGULATORY REQUIREMENTS

A. Provide motor protection switches of the appropriate NEMA size. For units not using NEMA rating, use equivalent NEMA size.

PART 2 - PRODUCTS

2.1 MOTOR STARTERS

A. Magnetic Motor Starters: Unless noted otherwise, shall be full voltage non-reversing with three overloads sized to suit nameplate amperes of motor served, motor "On" and "Off" pilot lights, "Hands-Off-Auto" switch, and auxiliary contacts for interlocking.

B. Combination Motor Starter/Disconnect: Shall be fused switch type with all features of Paragraph A above. In addition, provide disconnect switch auxiliary contacts for disconnection of externally powered control circuits where applicable. Fuses shall be sized in accordance with motor manufacturer's requirements.

C. Manual Starters: Shall be toggle switch or push-button type, lockable in the "Off" position, with overload relays, pilot light and enclosure pursuant to Paragraph D below. Manual starters shall only be used where specifically shown or called out on the drawings and only for single phase, fractional horsepower motors.

D. Enclosures: All motor controllers shall be contained in an enclosure suitable for the environment in which the controller is mounted, and shall be weatherproof when exposed to weather.

E. Overload Devices: Shall be melting alloy or bimetallic type. One overload shall be provided for each phase. Provisions shall be made for resetting the overload devices from outside the starter enclosure. Provide ambient compensated overload devices only when the motor is at a constant temperature and the controller is subject to a separate, varying temperature. Automatic reset overload devices are not permitted.

2.2 ACCEPTABLE MANUFACTURERS

A. Square D

B. Allen Bradley

C. General Electric

D. Cutler-Hammer

E. Siemens

2.3 NAMEPLATES

A. Pursuant to Section 260000, Paragraph 2.05, provide nameplates permanently attach (with screws on NEMA 1 enclosures) on each controller, nameplates with the following information: Load served, voltage, phase, short circuit rating, panel/circuit number and where applicable fuse size and type.

2.4 FAN SHUTDOWN RELAYS

A. Contractor shall provide relay(s) with sufficient contacts to shutdown all fans over 2000 cfm upon receipt of Fire Alarm. See Section 283100. Coordinate coil voltage with Fire Alarm System Supplier.

PART 3 - EXECUTION

3.1 FINISHED AREAS

A. In finished areas, mount motor protection switches flush and install suitable coverplates.

3.2 HEATERS

A. Install heaters co-related with full-load current of motors provided.

3.3 OVERLOADS

A. Set overload devices to suit motors provided.

3.4 SUPPORTS

A. Securely mount to equipment, wall or acceptable mounting frame.

3.5 FAN SHUTDOWN WIRING

A. Provide wiring interlock connections for all (over 2000 cfm) fan starter control circuits via a relay to shutdown fans upon receipt of Fire Alarm.

3.6 CONNECTION TO MECHANICAL EQUIPMENT ON ROOFS

A. The Contractor shall coordinate all roofing penetrations with the general contractor and roofing contractor to assure that the roofing warranty is maintained.

B. Attachment of conduits to the roof to serve mechanical equipment and devices shall comply with Section 260533.

3.7 MECHANICAL EQUIPMENT NAMEPLATE RATINGS

A. The Division 260000 Contractor shall verify that the nameplate ratings of the mechanical equipment, when they arrive on site, are consistent with the ampacity called out on the drawings. The Contractor shall bring any discrepancies to the Engineers attention prior to installation of conduit and wiring.

END OF SECTION 262419

SECTION 262726 - SWITCHES AND RECEPTACLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

1.2 WORK INCLUDED

A. Provide all wiring devices and plates.

B. No push-in, friction, spring type terminals allowed.

C. All devices color shall be white, unless otherwise noted.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

A. Hubbell

B. Pass & Seymour

C. Leviton

D. Cooper

2.2 SWITCHES

A. "Industrial Specification Grade", quiet type, rated 277 volt, 20 amp, unless noted, with plastic handle. Single pole, double pole, 3-way, or locking type as required. Meets Fed. Spec. WS-896 Provide matching styles and colors in other devices as required for the conditions of installation. Hubbell CS1221, Cooper CSB120, Leviton 1221, and P&S 20AC1

B. Interchangeable type shall be rated same as above.

C. Momentary Contact Line Voltage Switches: Single pole, double throw, 3-wire, normally open. Rating same as above.

D. Fluorescent Dimmer: Fluorescent dimmer switch shall be rated at 16 amps, 120V or 277V, 60 hertz. Dimmer switch shall have a vertical slide with positive “off” button. Suitable for single-pole and 3-way. Dimmer shall have a radio/TV interference filter. Dimmer shall be matched with electronic dimming ballast. See Specification Section 265000. Leviton ‘Renoir II’ series.

E. LED Dimmer: LED dimmer switch shall be rated at 16 amps), 120V or 277V, 60 hertz. Dimmer switch shall have LED vertical slide with positive “off” button. Suitable for single-pole and 3-way. Dimmer shall have a radio/TV interference filter. Dimmer shall be matched with dimming driver. See Specification Section 265000. Leviton ‘Renoir II’ series.

F. Key Operated: Hubbell HBL1221L (or equal) with 1209 Key. Provide 24 spare Keys.

G. Timer Switch: Provide electronic light timer switch where indicated on drawings. The timer switch shall be connected to the room lighting and fan. The timer switch shall be programmable for time-out from 5 minutes to 2 hours. Set timer for standard 20 minutes time-out period, time scrolls up, flash off, beeper on. Manufacturer: Watt Stopper – Inteli-switch Digital Time Switch.

H. Motor rated switches: Switches serving as motor disconnecting means shall be horsepower rated with overload relays and meet requirements as stated above. See manual starters in Section 262419, ‘Motor Controllers’.

I. Device plates shall be Hubbell and Cooper Type 302 stainless steel.

2.3 RECEPTACLES

A. "Industrial Specification Grade", Duplex NEMA 5-20R configuration (20-Amp, 120-Volt) unless shown otherwise. Must have “rivetless ground” contact manufactured as an integral component of the external ground screw terminal. Meets Fed Spec. WC-596 Hubbell HBL5362, Cooper 5362, P&S 5362A, and Leviton 5362.

B. Ground-Fault Circuit-Interrupter Duplex Receptacles: NEMA 5-20R. Hubbell GF20ILA, and Cooper VGF20, for 20 Amp, 125-Volt AC. Provide GFI receptacles where required by code.

C. Weather Resistant (WR) / Ground Fault Circuit-Interrupter (GFCI) Outdoor Duplex Receptacles: NEMA 5-20R. Hubbell GFTR201 or equal, for 20 Amp, 125-Volt AC.

D. Special Purpose Receptacles: For special purpose receptacles, see drawings for voltage, amperage, and phase. Provide with matching plug delivered to the Owner.

2.4 OCCUPANCY SENSORS

A. Provide self-adjusting occupancy sensor light switching devices for control of lighting in all rooms and offices shown on drawings. Sensors shall be ceiling or wall mounted to provide adequate coverage. Occupancy sensors shall be “Leviton”, Model OSC20-M0W for ceiling mounting, OSW12-M0W for wall mounting, complete with OSP20-RD0 power pack and associated mounting hardware. Provide “Leviton” ODSOD-ID wall switch sensors where shown. Sensors shall be wired to maintain switching and circuits shown on drawings.

2.5 DEVICE PLATES

A. Interior: Plates for receptacles other than NEMA 5-20R shall have ampere rating, voltage and phase engraved in the plate. Plates for recessed boxes shall be Hubbell and Cooper Type 302 stainless steel. Attachment screws shall match finish of plate. Plates for surface mounted boxes shall be of pressed stainless steel with size to fit exactly the box used.

B. Exterior: Intermatic # WP1010MC, for vertical mount and # WP1010HMC for horizontal mount, or equivalent for receptacles. Metal cover shall be raintight while-in-use.

2.6 MULTIOUTLET ASSEMBLY (WHEN SHOWN)

A. Provide assemblies complete, including necessary fittings and hardware with circuits as indicated on Plans and outlet spacing as indicated. All assemblies shall contain ground wire. Wiremold or equal.

PART 3 - EXECUTION

3.1 MOUNTING

A. Rigidly fasten each device to the outlet box at proper position with the wall to bring receptacle flush with plate or switch handle the proper distance through the plate.

3.2 ORIENTATION

A. Set Switches vertical with handle operating vertically, up position "ON".

B. Set Receptacles vertical with ground slot down.

3.3 DEVICE PLATES

A. Shall be stainless steel for each new wiring device and for each telephone and signal equipment outlet, except where equipment mounted thereon covers the outlet box completely.

B. Provide new covers on existing outlet boxes being reused.

3.4 DIMMER SWITCHES

A. Provide a separate neutral for each phase.

B. Fluorescent dimmer switches require a 4 square backbox per switch.

3.5 RECEPTACLE GROUNDING

A. Provide bare bonding wire between receptacle grounding terminal and box. Plaster ear screws connecting frame to the box will not be acceptable for grounding.

B. Provide green insulated grounding conductor in all branch circuits supplying isolated ground and ground-fault circuit-interrupter type receptacles.

3.6 AMERICANS WITH DISABILITY ACCESS

A. Comply with all requirements of Washington State Americans with Disability and NEC 2014 codes.

END OF SECTION 262726

SECTION 262813 - FUSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

1.2 WORK INCLUDED

A. Provide all fuses as required. Provide three (3) spare of each size and type required. Fuses shall not be installed until equipment is ready to be energized. This measure prevents fuse damage during shipment of the equipment from the manufacturer to the jobsite or from water that may contact the fuse before the equipment is installed. Final tests and inspections shall be made prior to energization of the equipment. This shall include a thorough cleaning, tightening, and review of all electrical connections and inspection of all grounding conductors. All fuses shall be furnished by the Electrical Contractor. All fuses shall be of the same manufacturer.

PART 2 - PRODUCTS

2.1 MAINS, FEEDERS, AND BRANCH CIRCUITS

A. Circuits 0 to 600 amperes shall be protected by current limiting BUSSMANN LOW-PEAK Dual-Element Fuses LPN-RK (250 volts) or LPS-RK (600 volts). All dual-element fuses shall have separate overload and short-circuit elements. Fuse shall incorporate a spring activated thermal overload element having a 284°F. melting point alloy and shall be independent of the short-circuit clearing chamber. The fuse must hold 500% of rated current for a minimum of 10 seconds and be listed by Underwriters Laboratories, Inc., with an interrupting rating of 200,000 amperes r.m.s. symmetrical. The fuses shall be UL Class RK1 to maintain the Engineered protection of the system components.

B. Motor Circuits: All individual motor circuits with full load amperes ratings (FLA) of 480 amperes or less shall be protected by BUSSMANN LOW-PEAK Dual-Element Fuses LPN-RK (250 volts) or LPS-RK (600 volts). Larger H.P. motors shall be protected by BUSSMANN Type KRP-C Low-Peak Time-Delay Fuses of the ratings shown on the drawings. All other motors, (such as 1.0 service factor motors) shall be protected by BUSSMANN LOW-PEAK Dual-Element Fuses LPN-RK (250 volts) or LPS-RK (600 volts) installed in ratings of approximately 115% of the motor full load current except as noted above. The fuses shall be UL Class RK1 Dual Element Time Delay or Class L.

2.2 SPARE FUSES

A. Spare fuses shall be provided with a minimum of three of each ampere rating. See Section 265000 for quantities of spare fusing required for ballasted light fixtures.

2.3 ACCEPTABLE MANUFACTURERS

A. Bussman

B. Little Fuse

PART 3 - EXECUTION

3.1 FUSES

A. Install in all fusible devices provided under this Contract.

END OF SECTION

SECTION 262816 - DISCONNECTS AND FUSED SWITCHES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

1.2 WORK INCLUDED

A. Provided all disconnects, fused and unfused, required by code for equipment furnished under this and other divisions of these specifications and as shown on the drawings.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

A. General Electric

B. Square-D

C. Siemens

D. Cutler-Hammer

2.2 DISCONNECTS

A. Switch shall be heavy-duty type, shall be quick-break and shall be horsepower rated. Switch shall have blades as required to open all ungrounded conductors and shall be single throw unless noted.

B. Enclosure shall have interlocking cover to prevent opening door when switch is closed. Door interlock shall include a defeating scheme, shall be padlockable in the "Off" position.

C. Enclosure shall be suitable for environment in which mounted. All exterior enclosures shall have a minimum raintight rating.

2.3 FUSED SWITCHES (OR FUSED DISCONNECTS)

A. Shall be as above with addition of fuse space and clips to accept only fuses as noted in Section 262813.

B. Fuses shall be sized in accordance with manufacturer's requirements of protected equipment.

2.4 NAMEPLATES

A. Provide nameplates on all enclosures and include the following information: Load served, voltage, phase, panel and circuit number. Construct and attach in accordance with Section 260000, Paragraph 2.05.

PART 3 - EXECUTION

3.1 SUPPORTS

A. Secure solidly to wall or approved mounting frame. Disconnects supported only by Raceway are not acceptable.

3.2 SPLICES

A. Wiring space within enclosure shall not be used as a junction box.

3.3 INSTALLATION

A. All material installation shall be in accordance with manufacturers' recommendations and the provisions of applicable codes.

B. Fuses shall not be installed until equipment is ready to be energized.

END OF SECTION 262816

SECTION 265000 - LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Section 260000 – General Electrical Conditions

1.2 WORK INCLUDED

A. Provide the lighting system complete and operational.

B. Recessed fixtures installed in fire-resistive ceiling construction shall have the same fire rating as the ceiling or shall be provided with fireproofing boxes having materials of the same fire rating as the ceiling.

1.3 FIXTURE SCHEDULE MANUFACTURER'S SERIES NUMBERS

A. Are a design series reference and do not necessarily represent the number, size, wattage or the type of lamp, ballast or special requirements as specified hereinafter.

1.4 SUBMITTALS

A. Shall be neatly and clearly marked to indicate the fixtures, lamps and ballasts fully comply with contract documents. When substitute fixtures are submitted (if permitted) the data shall clearly cross reference (written or highlighted) that the substitute fixture complies with every detail of the specified fixture. Fixtures not fully complying with contract documents are not permitted.

PART 2 - PRODUCTS

2.1 METAL PARTS

A. Interior Fixtures: Steel or aluminum with 300°F, baked enamel finish, brushed aluminum with baked acrylic clear lacquer finish, or stainless steel with a brushed finish, manufacturer's standard color unless specified otherwise.

B. Exterior Fixtures: Corrosion resisting metal, a (non-ferrous, stainless steel or special finish) and in all cases suitable for outdoor service without tarnishing or other damage due to exposure; manufacturer's standard colors unless specified otherwise; cadmium plate all metal parts concealed by canopies, including screws, plates and brackets. All exposed fasteners shall be tamperproof.

C. Recessed Type: Incandescent fixtures shall have housing containing an integral thermal device pursuant to NEC 410.115(C).

2.2 LIGHT TRANSMITTING COMPONENTS

A. Virgin acrylic or polycarbonate plastic (0.125-inch thick overall minimum), UV stabilized or glass. Shall be contained in a captive metal frame that remains attached to the fixture when door is in open position.

2.3 SPECIAL PARTS

A. Adapters, Plates, Brackets and Anchors: Provide where required by construction features of the building to suitably mount lighting fixture. All such appurtenances and mounting methods shall be approved by the Architect/Engineer prior to fabrication and installation.

B. Low Voltage Transformers: Provide and install where required to power individual or linear runs of low voltage light fixtures.

2.4 LAMPS

A. General Electric, Sylvania, or Philips. All lamps supplied shall be by the same manufacturer.

B. Provide for each fixture in the exact number and type for which the fixture is designed or as noted.

C. Fluorescent Type:
1. Bi-pin, T-8 rapid start; color temperature of 3500 K; CRI 82; average life of 36,000 hours per 3 hour start.
2. Bi-pin, T-5 high output; color temperature of 3500 K; CRI 82; average life of 30,000 hours per 3 hour start.

D. Compact Fluorescent Type:
1. Twin tube, double twin tube, triple tube; 4-pin, amalgam, color temperature of 3500 K; CRI 82; average life of 20,000 hours. (Sylvania – Dulux).
2. Biax; 4-pin, color temperature of 3500 K; CRI 82; high lumen output. (Sylvania – Dulux); average life of 20,000 hours.

E. Solid-State Lighting: Fixtures shall have a lumen maintenance life expectancy (L70) of > 50,000 hours, a CRI of > 82, and a CCT of 3500K. Each solid-state fixture model shall be tested in accordance with IES LM-79.

2.5 BALLASTS - FLUORESCENT (Electronic)

A. Tested and approved for lamp type employed and approved by Lighting Design Lab specification committee.

B. Acceptance Manufacturers:
1. Advance
2. Magnetek
3. Motorola
4. Osram/Sylvania

C. UL and CBM labels.

D. Low temperature and/or outdoor application. Provide ballasts suitable for low temperature where outdoors or space ambient is expected to be below 50°F.

E. Electronic ballasts shall be high power factor, greater than 95% and total harmonic distortion (THD) less than 20%. Provide for operation with T-8, T-5 and CFL lamps. "A" sound rating. Neutral wire to be used in lighting circuit associated with electronic ballasts shall be #10 AWG CU.

F. All ballasts shall be provided with a UL listed factory pre-installed ballast disconnect.

G. Ballasts for T5 fluorescent lamps:
1. Sylvania “Quicktronic” or equivalent programmed rapid start.
2. Ballast factor of 98% or greater.
3. “A" sound rating.
4. Electronic pre-heat starting.
5. The ballast shall operate at 40 - 60 Khz without visible flicker.
6. Five Year Warranty.

H. Ballasts for T8 fluorescent lamps:
1. Advance "Centium" Series or Equivalent programmed rapid start.
2. Ballast factor of 98% or greater.
3. “A" sound rating for 265 MA. (T8 lamps).
4. The ballast shall operate at a frequency below 30 Khz or above 40 Khz without visible flicker.
5. Shall be designed for use with occupancy sensors by providing up to 30,000 lamp starts. The ballast shall heat the lamp cathodes to 650 degree C with no glow current before applying arc voltage to the lamp.
6. Electronic ballast harmonic distortion and current shall be less than 10% THD.
7. Where fluorescent light fixtures are to be located outside, the ballast shall be capable of 0 degree F. lamp ignition.
8. Five Year Warranty.

I. Ballasts for 5 to 30 Watt Compact Fluorescent Lamps:
1. Motorola "Gold" Edition rapid start or Equivalent.
2. Electronic, 4-pin.
3. Ballast factor of 98% or greater.
4. “A" sound rating.
5. The ballast shall operate at a frequency below 30 Khz or above 40 Khz without visible flicker (high frequency operation).
6. Electronic ballast harmonic distortion and current shall be less than 10% THD.
7. Minimum starting temperature –5 degree F/-20 degree C.
8. Five Year Warranty.

J. Emergency Battery Backup: Provide as indicated. Each fluorescent fixture unit shall consist of an automatic power failure device, test switch operable from outside of the fixture, pilot light visible from outside the fixture, automatic code-compliance testing, and fully automatic solid-state charger in a self-contained power pack. Battery shall be electrolyte type with power to supply two T-8 lamps at 1100 lumens each, two compact fluorescent lamps at 300 to 750 lumens each, or one T-5HO lamp at 1100 lumens for a period of 90 minutes. Emergency unit shall operate unattended and require no maintenance for a period of 5 years.
1. Emergency unit for T-8 lamps shall be Bodine B50 ST. or Lithonia PS1400QD/SD Emergency unit for compact fluorescent lamps shall be Bodine B94 or Lithonia PSDL3/SD. Notify the Engineer In cases where the Bodine units are too large to fit in the light fixtures. In such cases an ESI equivalent unit will be acceptable.

K. Generator Transfer Device: Transfer device shall be installed integral to each light fixture and shall automatically transfer power from the normal power source to the emergency circuit upon loss of normal power. Bodine #GTD.
1. Where the transfer device can not be mounted in the light fixture and the transfer device is indicated to control more than (1) light fixture on the same switch leg, provide Bodine #GTD20A.

a. The device shall be capable of bypassing the local switching means when normal utility power has been lost. The device shall consist of a test switch, a normal power indicator light and an alternate power indicator light. The unit shall be contained within its own enclosure, suitable for mounting on the wall and above accessible ceilings. The device shall be able to accommodate up to 20 amps of lighting load.

2.6 HANGING FOR PENDANT FIXTURES

A. Rigid type, with not less than 5 thread engagement at each end, consisting of iron pipe, with brass or aluminum tubing casing, or painted tubing not less than 0.040 inches thick.

B. Aircraft cable, stainless steel, sized appropriately by manufacturer for weight and seismic zone.

C. Provide a canopy for each fixture hanger except where fixture conceals the outlet box directly without a canopy.

D. Provide a safety chain for all glass pendant fixtures and for all fixtures mounted in gymnasiums.

2.7 OUTDOOR LIGHTING STANDARDS

A. Provide watertight insulating fuse in the base of lighting standards to individually protect each lighting fixture; buss Style "HEB" or approved, waterproof fuseholder with Buss fuse of appropriate capacity and voltage. Provide fuse for each hot circuit wire; do not fuse neutral.

B. Provide concrete preformed round poles with base plate for bolting to concrete foundation. Natural exposed aggregate finish. Height as noted on drawings.

C. Provide concrete foundations as shown on drawings. Field verify locations with Architect prior to installation of bases.

2.8 Outdoor ground mounted lighting fixtures

A. Provide concrete foundations for mounting of ground mounted lighting fixtures. Foundation shall be a minimum of 6” deeper than the light fixture and a minimum of 6” all around the base of the fixture. Provide #4 rebar with 3” minimum ring ties at 8” on center. The #4 rebar shall be vertically spaced approximately 6” apart. Field verify locations with Architect prior to installation of bases.

2.9 EXIT SIGNS

A. Fronts: Cutout stencils made of minimum #20 gauge sheet steel or sheet aluminum with red glass or plastic back of the cutout. Mount fronts either on concealed hinges or pull-out type with chain catch. Removable cutout arrows shall indicate direction of travel.

PART 3 - EXECUTION

3.1 LIGHTING FIXTURES - GENERAL

A. Size and mounting height from finished floor to bottom of fixture as indicated on the drawings. Verify mounting provisions prior to the ordering of fixtures. Fixtures shall be UL listed for the location, and application in which they are installed.

B. Ceiling fixtures shall be coordinated with and suitable for installation in, on or from the ceiling as shown. Installation and support of fixtures shall be in accordance with NFPA 70 and manufacturer's recommendations.

C. Recessed fixtures installed in seismic areas shall be installed utilizing specially designed seismic clips.

D. Suspended fixtures installed in seismic areas shall have 45° swivel hangers and shall be located with no obstructions within the 45° range in all directions. The stem, canopy and fixture shall be capable of 45° swing.

3.2 DIFFUSERS AND ENCLOSURES

A. Install lighting fixture diffusers only after construction work, painting and clean up are completed. Prior to final acceptance, remove all lamps, reflectors and diffusers, wash, rinse and reinstall.

3.3 ADJUSTMENT OF FIXTURES

A. Make all final spotlight and adjustable light settings under the direction of the Architect/Engineer during a scheduled period of time prior to the completion of the project. Include costs for all equipment and personnel expenses required for adjustment.

B. For fixtures with indirect lighting, notify Engineer prior to installation of any circumstance where the fixture lamp source will be within 12" of ceiling.

3.4 SUPPORT OF FLUORESCENT AND LED FIXTURES

A. Recessed Troffer Type: For fixtures supported by the ceiling suspension system, provide integral tabs, which rotate into position after fixture is lifted into the ceiling cavity. Provide two safety chains secured to structural members above suspended ceiling. Circuit connection shall be through use of 60-inch flexible conduit from a rigidly supported junction box. For plaster or GWB ceilings, provide a plaster frame compatible with light fixture.

B. Recessed Downlight Type: Mount in frames suitable for the ceiling, with the recessed portion of the fixture securely supported from the ceiling framing. For fixtures supported by a ceiling suspension system, provide two safety chains secured to structural members above suspended ceiling.

C. Surface and Pendant Mounted Type:

D. Where mounted on accessible ceilings, hang from structural members by means of hanger rods through ceiling or as approved.

E. Where ceiling is of insufficient strength to support weight of lighting fixture, provide additional framing to support as required. Fixtures shall be supported from structure with seismic bracing independent of ceiling.

F. For Pendant Mount Type: Provide a unistrut channel for mounting fixtures entire fixture length unless light fixture is designed specifically for supporting itself. Provide 3/8-inch thread rod secured to structural members for support of unistrut channel.

G. Continuous Runs of Fixtures: Straight when sighting from end to end, regardless of irregularities in the ceiling. Where fixtures are so installed, omit ornamental ends between sections.

3.5 LOCATION

A. Mount to the dimensions shown on the drawings. Mount at quarter points where no dimensions appear. Architect shall specify mounting locations where no dimensions appear and quarter point mounting is impractical or not indicated on the drawings.

B. Refer to details, mechanical drawings, and coordinate with mechanical Contractor for equipment and ductwork mounted in ceilings to prevent conflict with light fixtures prior to installation. If conflicts cannot be resolved with the Mechanical Contractor, notify Architect/Engineer.

3.6 SPARE FIXTURES

A. Self-Luminous Exit Sign: Provide (2) two Self-Luminous Exit Signs Lithonia # DSW1X Green or Red to match EX-1. Install at locations as directed by Architect.

3.7 CONCRETE FOUNDATIONS

A. Install at locations shown taking care to provide soil compaction same as required under paving to avoid settling and tilting of pole. Provide for all steel, concrete or aluminum poles shown. Concrete foundations shall have a minimum raceway sweeps of 90 degrees and anchor bolts shall be accurately set in foundations using a template supplied by the pole manufacturer. For concrete work and grouting, see Division 3 of the specifications. When concrete work has cured, base plates shall be leveled and grouted in place. Pole anchor bases shall then be set on base plates, leveled plumb on foundations, and secured with holding nuts.

3.8 FIXTURE TENTING

A. Contractor shall coordinate ceiling types with architectural drawings and specifications and provide equivalent fire rated enclosures above all light fixtures which penetrate rated ceilings.

END OF SECTION 265000

SECTION 283176 - FIRE ALARM SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including Divisions 0, 1, 26, 27, and 28 Specification Sections, apply to work of this section.

B. Phasing and Schedule: Phasing and Schedule are critical for successful completion of this project on an occupied school site and it is anticipated overtime, double-shifting, or special work schedules and coordination of phased work will be required. Refer to the Phasing Plans and specifications for additional information.

1.2 WORK INCLUDED

A. It is the intention of this division of the specifications and the accompanying drawings to describe and provide for the furnishing, installing, testing and placing in satisfactory and successful operation all equipment, materials, devices and necessary appurtenances to provide a complete electrical & fire alarm system, together with such other miscellaneous installations and equipment hereinafter specified and/or shown in the plans. The work shall include all materials, appliances and apparatus not specifically mentioned herein or noted on the plans, but which are necessary to make a complete working installation of all electrical systems shown on the plans or described herein. The drawings and specifications are complementary and what is called for in either is binding as if called for in both.

B. By submitting a bid, the Contractor is acknowledging that he has made a thorough examination of the Contract Documents, existing site and building conditions, and has determined that these documents do sufficiently describe the scope of construction work required under this Contract.

1.3 STANDARDS AND REGULATIONS

A. The work shall comply with the latest edition of the applicable Standards and Codes of the following:

ASTM	American Society for Testing and Materials
NBFU	National Board of Fire Underwriters
NEC	National Electrical Code
---	State Electrical Code
NESC	National Electrical Safety Code
NEMA	National Electrical Manufacturers Association
NFPA	National Fire Protection Association
U.L.	Underwriters Laboratories Inc.
IPCEA	Insulated Power Cable Engineers Associated
CBM	Certified Ballasts Manufacturers
---	Federal, State and Local Building Codes
ETL	Electrical Testing Laboratories

B. If any conflict occurs between Code Rules and this specification, the codes are to govern. Nothing in these drawings and specifications shall be construed to permit work not conforming to governing codes. Also, this shall not be construed as relieving the Contractor from complying with any requirements of the plans and specifications which may be in excess of, but not in conflict with, requirements of the Governing Codes.

1.4 PERMITS & FEES

A. The Contractor shall obtain and pay for all licenses, permits and inspections required by laws, ordinances and rules governing work specified herein. The Contractor shall arrange for inspection of work by the inspectors and shall give the inspectors all necessary assistance in their work of inspection.

B. The Contractor shall consult with and follow the requirements of the local fire marshal serving the area and shall coordinate his work with them.

C. All permits and fees for plan review, inspections, testing, etc. shall be included in the bid proposal.

1.5 DEFINITIONS

A. When "Provide" is used, it shall be interpreted as "furnishing and installing complete in operating condition".

B. When "Drawings" is used, it shall be interpreted as "all Contract Drawings for all Disciplines".

C. When "Contractors" is used, it shall be interpreted as the Fire Alarm Contractor.

1.6 INTENT OF DRAWINGS

A. The fire alarm drawings are intended to serve as working drawings for general layout. The equipment layout is diagrammatic and unless specifically dimensioned or detailed, does not indicate all fittings, hardware or appurtenances required for a complete operating installation.

B. Wiring diagrams are not intended to indicate the exact course of raceways or exact location of device. Raceway and device locations are approximately correct and are subject to revision as may be necessary or desirable at the time of installation. Precise location in every case shall be subject to the Engineer's approval.

1.7 EXISTING CONDITIONS

A. Examine the structure, building, and conditions under which Divisions 28 work is to be installed for conditions detrimental to proper and timely completion of the work. Do not proceed with work until deficiencies encountered in installation have been corrected. Report any delay or difficulties encountered in installation of Divisions 26 and 28 work which might be unsuitable to connect with work. Failure to report conditions shall constitute acceptance of other work as being fit and proper for the installation of Divisions 28 work.

B. Maintain continuity of existing circuits of equipment to remain. Existing circuits of equipment shall remain energized. Circuits which are to remain but were disturbed during demolition shall have circuits, wiring, and power restored back to original condition.

1.8 DEMOLITION

A. Fire alarm system (free standing or surface mounted), raceway (exposed), and conductors, no longer in service as a result of this Contract, shall be removed. Unused raceways or sleeves shall be cut flush at ceiling, floor, or wall, and filled with grout.

1.9 PROTECTION

A. The Contractor shall store and guard all equipment before installation and shall protect same, and replace any equipment that has been damaged prior to final acceptance.

1.10 HOUSEKEEPING

A. All electrical materials shall be kept stored in an orderly fashion protected from heat, cold, and the weather.

B. All marred surfaces shall be refinished and painted after installation.

C. All debris shall be removed from premises during work, as directed, and at completion of job.

1.11 AS-BUILT DRAWINGS

A. The Contractor shall maintain, in addition to any reference drawings, an as-built set of prints, on which all deviations from the original design shall be drafted in a neat, legible manner with red colored pencil. This red lined set shall identify all drawing revisions including addenda items, change orders, and Contractor revisions.

B. The Contractor shall update all references to specific products to indicate products actually installed on project.

C. Upon completion of the Division 28 Work, the Contractor shall deliver the red lined drawings and one set of neatly drafted as-built drawings on electronic media in AutoCAD R-2012 format to the Engineer for transmittal through the Engineer to the Owner.

1.12 WARRANTY

A. Provide a written warranty that the Division 28 work is free from mechanical and electrical defects. Contractor shall replace and repair, to the satisfaction of the Engineer, any parts of the installation which may fail within a period of 12 months after the certificate of final acceptance, provided that such failure is due to defects in material or workmanship, or failure to follow the specifications and drawings.

1.13 INSTRUCTIONS AND MANUALS

A. Manuals shall contain shop drawings, wiring diagrams, operating and maintenance instructions, replacement parts lists, and equipment nameplate data for all equipment and systems installed under the project. Signal equipment submittals shall contain step-by-step circuit description information designed to acquaint maintenance personnel with equipment operation in each mode of operation. Manuals shall contain original brochures supplied by manufacturers. Xerox copies of originals will not be accepted.

B. Each type of device provided shall be identified in the O & M Manual using the same identification as shown on the drawings and specifications. The information included must be the exact equipment installed not the complete "line" of the Manufacturer. Where sheets show the equipment installed and other equipment, the installed equipment shall be neatly and clearly identified on such sheets. Parts lists shall give full ordering information assigned by the original parts manufacturer. Relabeled and/or renumbered parts information as reassigned by equipment supplier is not acceptable. The following information shall be provided for each device:
   1. Manufacturer's name, address, and phone number.
   2. Local supplier's name, address, and phone number.
   3. Complete parts lists including quantities and manufacturer's part numbers.
   4. Installation instructions.
   5. Recommended maintenance items including maintenance procedure and recommended interval of maintenance listed in hours of operation, calendar unity, or other similar time unit.

C. The O & M Manual shall be assembled in a loose leaf, 3-ring, hard cover binder. The information contained in the manuals shall be grouped in an orderly arrangement by specification index. The manuals shall have a typewritten index and divider sheets between categories with identifying tabs. The covers shall be imprinted with the name of the job, Owner, Electrical Engineer, Division 28 Contractor, and year of completion. The back edge shall be imprinted with the name of the job, Owner, and year of completion.

D. Wiring Diagrams for each system shall be complete for the specific system installed under the Contract. "Typical" Line Diagrams will not be acceptable unless properly marked to indicate the exact field installation.

1.14 WORK NOT INCLUDED

A. Work to be included under this Contract shall be defined on drawings and in these specifications. Any details beyond these limits are meant only to give installation clarity to that portion which is a part of this Contract.

1.15 INSTRUCTION PERIODS

A. Upon completion of the work and after all tests and final inspection of the work by the authority(s) having jurisdiction, the Contractor shall demonstrate and instruct the Owner's designated operation and maintenance personnel in the operation and maintenance of the fire alarm system. The Contractor shall arrange scheduled instruction periods with the Owner. The Contractor's representatives shall be superintendents or foremen knowledgeable in the fire alarm system and suppliers representatives when so specified.

B. Scheduled Instruction periods shall be:
   1. Fire Alarm System ½ day

C. Costs for time involved by Contractor shall be included in the bid.

1.16 COMPLETION OF WORK

A. Upon completion of the Division 28 work, the Contractor shall deliver to the Engineer a completion letter stating that he has fulfilled all the requirements of his Contract for Division 28 work as set forth in the drawings and specifications and that all items in pre-final inspection lists submitted by the Engineer have been satisfactorily completed.

B. Arrange for and obtain all required inspections and certificates pertaining to the Division 28 work and deliver the certificates to the Engineer.

1.17 SUBMITTALS AND SHOP DRAWINGS

A. General:
1. The Fire Alarm System contractor shall simultaneously submit shop drawings, voltage drop calculations, back-up battery calculations, and manufacturers data sheets to the local Authority Having Jurisdiction and Architect/ Engineer for a review and shall be approved by the Architect/ Engineer prior to the purchase, fabrication, or installation of any system components.
2. Within 10 working days after the date of the letter rejecting any items of equipment, or materials as not in accordance with the specifications, Contractor shall submit a new list of items he proposes to furnish and install in place of those items rejected. If the Contractor fails to submit this new list within the above specified time, or if any items on this second list are rejected as not being in accordance with these specifications, the Engineer may select the items which the Contractor shall furnish and install without change in Contract price or time of completion.
3. The acceptance of a manufacturer's name or product by the Engineer does not relieve the Contractor of the responsibility for providing materials and equipment which comply in all details with the requirements of the Contract Documents. The Contractor shall be solely responsible for submitting materials at such a time to allow a minimum of two weeks for Engineer's review.
4. The Contractor is responsible for assuring that the conduit size and wire quantity, size, and type is suitable for the equipment supplied. The Contractor shall review the proper installation of each type of device with the manufacturer's representative.
5. Contractor shall submit floor plan shop drawings and complete equipment submittals (3) copies to each Fire Code Enforcing Authority as required, for approval, and pay all required review fees.

1.18 SHOP DRAWINGS

A. Prepare detailed working drawings that are not larger than the contract documents for the system layout in accordance with N.F.P.A. #72.

B. All items contained in Section 7.4 "Shop Drawings" of the latest edition of N.F.P.A. #72 adopted by the Authority Having Jurisdiction shall be included on the Fire alarm System Shop Drawings including, but not limited to the following:
1. Sheet Index.
2. Fire alarm System Component Legend.
3. Cabling Legend.
4. Alpha-numeric labeled cables based upon the "Cabling Legend" for each cable type and cable run.
5. Electrical Legend listing the electrical devices to be utilized as part of the Fire alarm System installation.
6. Site Plan.
7. Floor Plans indicating all Fire alarm System devices.
8. End-Of-Line Resistor(s) where applicable.
9. Device Address shown adjacent to each device.
10. One-Line Riser Diagram with all field devices and their respective room names, room numbers and device address.
11. "Sequence of Operations" matrix indicating all system Inputs and Outputs.
12. Mounting details and mounting heights

C. Provide "Shop Drawings" that are usable for trouble-shooting purposes showing equipment/device locations, conduit routing, junction boxes, connection cabling for the entire Fire alarm System layout, and riser diagrams.

D. Shop Drawings shall be clear and legible with a minimum text height of 1/8” for all text.

E. A graphical scale shall be provided for each floor plan or detail on the shop drawings in accordance with N.F.P.A. #72.

F. Projects that require more than one sheet to show the entire Fire alarm System shall require a key plan.

G. The key plan shall identify the location of the Fire alarm System that is contained on that sheet and shall contain a reference north arrow.

H. All sheets that contain a break in the building background shall contain a "Match Line" designation to indicate where the building and Fire alarm System continue, even if on the same sheet.

I. The shop drawings shall include a letter signed by either a designer or a registered professional engineer, currently employed by the system sub-contractor, responsible for the design depicted in the submittals and shop drawings. The letter shall state that the shop drawings conform to NFPA, NEC, and local codes as adopted by the local authority having jurisdiction or shall list items of non-conformance.

1.19 SUBMITTALS

A. Provide copies as specified by Division 1 and at a minimum provide six (6) sets of "Shop Drawings", Back-up Battery Calculations, Voltage Drop Calculations, Sound Calculations, Graphic Map(s), and Manufacturer’s Data Sheets to the Architect/Engineer for approval prior to the purchase, fabrication, or installation of any system component. Failure to receive the Architect/Engineer approval that results in reordering of material, removal of installed system components, and the re-installation of the Fire alarm System shall not be charged as additional cost to the Owner or General Contractor.

B. Equipment Submittals for the Fire alarm System shall be presented to the Architect / Engineer for review and approval within 30 calendar days from the date of the Contract signing by the General Contractor.

C. "Shop Drawings", Back-up Battery Calculations, Voltage Drop Calculations, Sound Calculations, and the Graphic Map(s) for the Fire alarm System shall be presented to the Architect / Engineer for review and approval within 60 calendar days from the date of the Contract signing by the General Contractor.

D. Graphic Maps shall be presented for review and approval within 60 calendar days from the date of the Contract signing by the General Contractor.

E. Equipment submittals shall be broken up by "Tabbed Dividers" that shall include, at a minimum, the following:
1. Fire alarm System Control Panel.
2. Fire Alarm Remote Annunciator Panels.
3. Power Supplies.
4. Initiating Devices.
5. Notification Appliances.
6. Graphic Maps.

7. Modules.
8. Miscellaneous Equipment.

F. Equipment submittals shall include, at a minimum, the following:
1. Fire alarm System Control Panel.
2. Fire alarm System Control Panel Enclosures.
3. Fire alarm System Terminal Cabinets
4. Fire Alarm Remote Annunciator Panels.
5. Main Fire alarm System Control Panel Power Supplies.
6. Remote Audible / Visual Power Supplies.
7. Fire alarm System Digital Audio Amplifiers.
8. Back-Up Batteries.
9. Internal Battery Chargers.
10. External Battery Chargers.
11. Initiation Devices:
    a. Manual Pull Stations.
    b. Heat Detectors.
    c. Smoke Detectors.
    d. Carbon Monoxide Only Detectors.
    e. Combination Smoke / Carbon Monoxide Detectors.
    f. Multi-Criteria Detectors.
12. Notification Appliances:
    a. Strobe-Only Appliances.
    b. Combination Horn / Strobe Appliances.
    c. Low-Frequency Sounders
13. Damage Stoppers (Wire Guards).
14. Graphic Maps.
15. Monitor Modules.
16. Relay Modules.
17. Isolation Modules.
18. Transient Voltage Surge Protection.
19. Wiremold Surface Raceway.
20. Wet Rated Cables.

G. Shop drawing submittals shall include the following information:
1. Floor plans identifying all Fire alarm System components and devices.
2. Cabling / conduit routing and sizing.
3. Fire alarm System zoning.
4. Point to point cabling diagrams.
5. One-line risers.
6. Back-up Battery Calculations.
7. Voltage Drop Calculations.
8. Graphic Map Details / Artwork

H. Equipment Submittals, Back-Up Battery Calculations, Voltage Drop Calculations, Sound Calculations, and full sized color bond Graphics Maps for the Fire alarm System shall be contained within a single 3-ring hard cover binder having a typewritten index and divider sheets between categories with identifying tabs.

I. Equipment Submittals shall contain original brochures supplied by manufacturers (Xerox copies of originals will only be accepted if they are clear and legible). Each type of device provided shall be identified in the Equipment Submittals using the same identification as shown on the drawings and specifications. The information included must be the exact equipment to be installed, not the complete "line" of the manufacturer. Where sheets show the equipment installed and other equipment, the installed equipment shall be neatly and clearly identified on such sheets.

J. If the submittals are being delivered electronically, the Fire alarm System Contractor shall provide the following:
   1. Submittal Drawings:
      a. The Submittal Drawings shall be a single PDF that is formatted to actual size (not 11x17) and collated in numerical order as designated in the title block of each drawing.
   2. Equipment Submittals:
      a. The Equipment Submittal shall be a single PDF.
      b. The Equipment Submittal PDF shall contain all equipment, devices, and components that are collated for printing on 8½"x11" sized paper.
      c. The Equipment Submittal PDF shall be a searchable document.
      d. The Equipment Submittal PDF shall be formatted for duplex printing with blank sheet inserted where necessary.
      e. The Equipment Submittal PDF shall contain a "Table of Contents" that indicates all pieces of equipment, devices, and components contained within each "Tabbed Divider."
      f. The Equipment Submittal PDF shall be bookmarked by "Tabbed Divider" and for each piece of equipment, device, and component.
   3. Back-Up Battery Calculations and Voltage Drop Calculations that are submitted as part of the Equipment Submittal PDF shall be formatted to the following:
      a. Calculations shall be included at the end of the Equipment Submittal PDF under a separate "Tabbed Divider" for both Back-Up Battery Calculations and the Voltage Drop Calculations.
      b. The Equipment Submittal "Table of Contents" shall also indicate all calculations being provided for both the Back-Up Battery and the Voltage Drop Calculations
   4. Back-Up Battery Calculations and Voltage Drop Calculations that are submitted as a separate PDF from the Equipment Submittal PDF:
      a. The single Back-Up Battery Calculations and Voltage Drop Calculations submittal PDF shall contain all calculations that are collated for printing on 8½"x11" sized paper.
      b. The Back-Up Battery Calculations and Voltage Drop Calculations submittal PDF shall be a searchable document.
      c. The Back-Up Battery Calculations and Voltage Drop Calculations submittal PDF shall be formatted for duplex printing with blank sheet inserted where necessary.
      d. The Back-Up Battery Calculations and Voltage Drop Calculations submittal PDF shall contain a "Tabbed Divider" to separate the Back-Up Battery Calculations from the Voltage Drop Calculations.
      e. The Back-Up Battery Calculations and Voltage Drop Calculations submittal PDF shall contain a "Table of Contents" that indicates all calculations contained within each "Tabbed Divider."
      f. The Back-Up Battery Calculations and Voltage Drop Calculations submittal PDF shall be bookmarked by "Tabbed Divider" and for each Back-Up Battery Calculation or Voltage Drop Calculation.
   5. Graphic Maps:
      a. Graphics Maps shall be submitted in a PDF that is full sized to allow printing of actual sized proposed Graphics Maps.

K. Review of Fire alarm System submittal by the Engineer or Architect does not relieve the Contractor of responsibility for compliance with the intent of all contract documents and / or code.

L. Any material found to be installed without prior approval will be required to be removed and replaced with only specified approved material at Contractor's cost.

M. The contract documents shall not be used as the Fire alarm System Contractor's Shop Drawings.

N. The Fire alarm System Shop Drawings shall be system specific with only Fire alarm System equipment and connections to other equipment that will be interfaced to the Fire alarm System being shown.

O. All re-submittals shall have the areas of revision clearly marked with revision clouds. Re-submittals without revision clouds shall be rejected.

1.20 SCHEDULE OF VALUES

A. See Section 260000 for requirements.

1.21 COMPETITIVE PRODUCTS

A. Any reference in the specifications to any article, device, product, material, fixture, form or type of construction by name, make or catalog number shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition. The Contractor, in such cases, may at his option use any article, device, product, material, fixture, form or type of construction which in the judgment of the Engineer, expressed in writing, is equal to that specified. However, any manufacturer not listed as an accepted bidder for a specific item must be submitted for acceptance in writing and with descriptive data verifying equal quality and performance at least ten (10) working days prior to the bid date for approval.

1.22 MANUFACTURER/EQUIPMENT PRIOR APPROVALS

A. Any manufacturer/equipment not listed as an approved substitute for a specified item must be submitted for acceptance in accordance with the front end specifications, in writing, with detailed information to include:
1. Manufacturer's Catalog Data
2. Complete Physical and Technical Data
3. Wiring Diagrams
4. Detailed reference (written or highlighted) noting compliance with the appropriate Specification Section and all applicable Specification item numbers within that Section
5. Complete type written index cross referencing all proposed substitutes and specified items
6. Detailed reference to specified items (written or highlighted) noting equal quality and performance of proposed substitute equipment
7. Other descriptive data, as required by the Engineer

B. The acceptance of a manufacturer’s name or product by the Engineer does not relieve the Contractor of the responsibility for providing materials and equipment which comply in all details with the requirements of the Contract Documents.

C. Only materials which are specified or approved as acceptable shall be used.

D. Substitutions of the specified equipment and/or supplier will be considered providing that sufficient documentation is provided to the Engineer which certifies that the equipment and/or supplier qualification meets the requirements of this specification. Any request for substitutions shall be submitted by the Contractor in writing so as to be received by the Architect not later than ten (10) days prior to the date set for the bid opening. Approval by the Engineer will be issued by addendum prior to the bid date.

E. Suppliers interested in furnishing substitute systems shall furnish to the Engineer a Riser Diagram showing size, number, type and arrangement for all interconnecting wiring with the request, for prior approval to bid. This Riser shall also be furnished to each interested bidding contractor during the bidding period.

1.23 MATERIALS

A. All materials must be of the quality herein specified. All materials shall be new, of the best quality and free from defects. They shall be designed to ensure satisfactory operation and operational life in the environmental conditions which will prevail where they are being installed.

B. Each type of material shall be of the same make and quality. The materials furnished shall be standard products of the manufacturers regularly engaged in the production of such equipment and shall be the manufacturer's latest standard design.

C. All materials shall be U.L. or E.T.L. listed for the purpose for which they are used.

D. Equipment in compliance with U.L. standards but not bearing their label is not acceptable. If the manufacturer cannot arrange for labeling of an assembled unit at the factory the unit shall be field evaluated per the Washington State Administrative Code (WAC) and the inspector’s requirements.

1.24 COMPLETE SYSTEM

A. The firm alarm system shall be complete and operational in every detail. Mention of certain materials in these specifications shall not be construed as releasing the Contractor from furnishing such additional materials and performing all labor required to provide a complete and operable system.

1.25 CUTTING AND PATCHING:

A. Obtain permission from the Owner’s Representative prior to cutting. Locate cuttings so they will not weaken structural components. Cut carefully and only the minimum amount necessary. Cut concrete with diamond core drills except where space limitations prevent the use of such drills.

B. All construction materials damaged or cut into during the installation of this work must be repaired or replaced with materials of like kind and quality as original materials by skilled labor experienced in that particular building trade.

C. In locations where recessed panels have been removed and not reinstalled, the prime contractor shall patch wall and finish to match adjacent surfaces.

1.26 REQUESTS FOR INFORMATION (RFI)

A. It is our intent to provide a timely response for RFIs regarding Division 28 Work. To further expedite this process, where a suggestion can be determined or derived at by the initiator of the RFI, it is required this suggestion be supplied with the submitted RFI. If no suggestion is given where one is possible, the RFI will be returned as incomplete. All Electrical RFIs shall be written on the form provided by the Engineer.

1.27 CLEANING AND PAINTING

A. All equipment, whether exposed to the weather or stored indoors shall be covered to protect it from water, dust and dirt.

B. After installing, all metal finishes shall be cleaned and polished, cleaned of all dirt, rust, cement, plaster, grease and paint.

C. In locations where recessed panels have been removed and not reinstalled, the prime contractor shall patch wall and finish to match adjacent surfaces.

1.28 EQUIPMENT IDENTIFICATION

A. Provide identifying engraved bakelite nameplate on all equipment, including pull boxes, to clearly indicate its use, area served, circuit identification, voltage, and any other useful data.

1.29 DEVIATION

A. Deviation from the shop drawings in construction or installation of equipment shall not be made unless Shop Drawings showing proposed deviations are submitted to and approved by the Engineer.

1.30 WIRING METHODS

A. All fire alarm wiring, where exposed, concealed in walls or above inaccessible ceilings, shall be in Raceway with Junction Boxes and Fittings.

B. It is permissible to install fire alarm low voltage cables open in D rings above accessible ceilings.

C. Where exposed in finished areas, the Contractor shall utilize Wiremold Series 700 metal raceway with all backboxes, fittings and accessories.

D. Provide access panels as needed for pull boxes and equipment located above ceiling or behind walls.

1.31 PENETRATIONS OF FIRE RATED ELEMENTS

A. Must be made such as to retain that rating. See Section 283176, 4.04.

1.32 HANGERS AND SUPPORTS

A. Provide hangers, brackets, and suspension rods and supplementary steel to support equipment.

B. Hangers provided under other divisions shall not be used for support of Division 28 equipment unless permitted by Engineer.

1.33 WORKMANSHIP AND OBSERVATION

A. Workmanship shall be of the best quality and none but competent workers shall be employed under the supervision of a competent foreman. All completed work shall represent a neat and workmanship like appearance.

B. All work and materials shall be subject to observation at any and all times by representatives of the Engineer.

1.34 MISCELLANEOUS

A. Provide complete seismic anchorage and bracing for the lateral and vertical support of conduit and electrical equipment, as required by the International Building Code.

B. Conduits that cross seismic separations shall be installed with flexible connection suitable to accommodate conditions. Secure raceways on each side of a separation and provide a minimum of 36” length of flexible conduit to span separation.

1.35 GROUNDING

A. A grounding system shall be maintained as required by code.

PART 2 - GENERAL FIRE ALARM SYSTEM REQUIREMENTS

2.1 GENERAL

A. The Fire alarms System design for this project is based upon a Notifier Fire Alarm System and accompanying components. Substitutions shall not be allowed.

B. Provide all material, labor, equipment, design, and services necessary to perform the installation of a complete intelligent (analog) reporting, microprocessor-controlled, and addressable (digital) Fire Alarm System, in accordance with the required and advisory provisions of the latest edition of N.F.P.A. #72 accepted by the Authority Having Jurisdiction, and project specifications, except as modified herein.

C. The Fire Alarm System contractor shall simultaneously submit shop drawings, voltage drop calculations, back-up battery calculations, and manufacturers data sheets to the local Authority Having Jurisdiction and Architect/ Engineer for a review and shall be approved by the Architect/ Engineer prior to the purchase, fabrication, or installation of any system components as detailed in paragraph 1.06 of Specification Section 283176.

D. Conform to the General Conditions, Supplementary Conditions, and Division 1.

E. The system shall include, but not be limited to: control unit, peripherals, power supplies, alarm initiating and indicating devices, conduit, wire, fittings, and accessories required in providing a complete operating system.

F. All units shall be located in accordance with the plans.

G. The system shall be of modular design to facilitate both expansion and service and shall be microprocessor based.

H. The system shall operate as a low voltage, non-coded, class “B” Fire Alarm System.

I. The system shall be capable of supporting the design as shown in the contract documents and have 25% spare capacity for future expansion.

J. The work covered by this section of the specifications shall be coordinated with the related work as specified elsewhere under the project specifications.

2.2 DESCRIPTION

A. The fire alarm system shall comply with requirements of NFPA Standard 72 for Protected Premises Signaling Systems except as modified and supplemented by this specification. The system shall be electrically supervised and monitor the integrity of all conductors.

B. The system shall be an active/interrogative type system where each addressable device is repetitively scanned, causing a signal to be transmitted to the main Fire alarm System control panel (FACP) indicating that the device and its associated circuit wiring is functional. Loss of this signal at the main FACP shall result in a trouble indication as specified hereinafter for the particular input.

C. The fire alarm system shall be manufactured by an ISO 9001 certified company and meet the requirements of BS EN9001: ANSI/ASQC Q9001-1994.

D. The system and its components shall be Underwriters Laboratories, Inc. listed under the appropriate UL testing standard as listed herein for fire alarm applications and the installation shall be in compliance with the UL listing.

E. The installing company shall employ technicians on site to guide the final check-out and to ensure the systems integrity.

F. The Fire alarm System shall be currently listed and approved by Underwriter's Laboratories Incorporated with a Local, Auxiliary, Remote Station, and Proprietary Protective Signaling Services "UUJS" Certificate of Compliance.

2.3 SYSTEM/DEVICE INTERFACE CONNECTIONS

A. The following system/device interfaces shall be connected to the Fire alarm System for auxiliary functions initiated by the Fire alarm System Control Panel and includes, but is not limited to:
1. Fire Protection Sprinkler System

2.4 SCOPE

A. A new, intelligent reporting, microprocessor controlled fire detection system shall be installed in accordance with the specifications and drawings.

B. The new Fire alarm System Control Panel shall be installed at the location shown on the Contract Documents.

C. The system shall be designed such that each signaling line circuit (SLC) is limited to only 80% of its total capacity at initial installation.

D. Basic Performance:
1. Alarm, trouble and supervisory signals from all intelligent reporting devices shall be encoded on NFPA Style 4 (Class B) Signaling Line Circuits (SLC).
2. Initiation Device Circuits (IDC) shall be wired Class B (NFPA Style A) as part of an addressable device connected by the SLC Circuit.
3. Notification Appliance Circuits (NAC) shall be wired Class B (NFPA Style Y) as part of an addressable device connected by the SLC Circuit.
4. Alarm signals arriving at the FACP shall not be lost following a primary power failure (or outage) until the alarm signal is processed and recorded.
5. Notification Appliance Circuits (NAC) circuits shall be arranged such that there is a minimum of one speaker circuit per floor of the building or smoke zone whichever is greater.

6. Notification Appliance Circuits (NAC) and control equipment shall be arranged such that loss of any one (1) circuit will not cause the loss of any other NAC circuit in the system.

2.5 QUALITY ASSURANCE

A. Each and all items of the Fire Alarm System shall be listed as a product of the SINGLE fire alarm system manufacturer under the appropriate category by Underwriters' Laboratories, Inc. (UL), and shall bear the UL label. All control equipment shall be listed under UL category UOJZ as a single control unit. Partial or pending listings shall not be acceptable.

B. In addition to the UL-UOJZ requirement mentioned above, the system controls shall be UL listed for Power Limited Applications per NEC Article 760. All circuits must be marked in accordance with NEC Article 760-23.

C. All fire alarm equipment shall be of a single supplier and installed by an authorized factory distributor, to ensure proper component application, system uniformity, and the availability of prompt, emergency service by factory trained technicians.

D. The Fire Alarm System shall be currently listed and approved by Underwriters Laboratories, Inc. Certificate Service for Protective Signaling Services--Local, Auxiliary, Remote Station and Proprietary Signal System Listing Program. Proof of this listing shall be included with all prior approval requests. At the request of the Engineer, an UL certificate specific to this installation shall be furnished by the Fire Alarm System Sub-Contractor. The U.L. certificate shall be issued only by Fire Alarm System Sub-Contractor. Certificates issued by any company not directly associated with the installation of this project will be rejected.

E. The equipment and installation shall comply with the current applicable provisions of the following standards:
1. National Electric Code
2. National Fire Protection Standards:
   a. NFPA 71 Central Station Signaling Systems-Protected Premises Unit.
   b. NFPA 72 National Fire Alarm Code
   c. NFPA 70 National Electric Code
3. ADA Americans with Disabilities Act
4. ANSI A117 Washington Barrier Free Regulations

F. All requirements of the Local Authority Having Jurisdiction.

G. The system and all components shall be listed by Underwriters Laboratories, Inc. for use in fire protective signaling systems under the following standards as applicable:

UL 38	Manually Actuated Signaling Boxes
UL 50	Cabinets and Boxes
UL 228	Door Closer-Holders for Fire Protective Signaling Systems.
UL 268	Smoke Detectors for Fire Protective Signaling Systems
UL 268A	Smoke Detectors for Duct Applications
UL 346	Waterflow Indicators for Fire Protective Signaling Systems.
UL 464	Audible Signaling Appliances
UL 521	Heat Detectors for Fire Protection
UL 864	Control Units for Fire Protective Signaling System
UL 1481	Power Supplies for Fire Protective Signaling Systems
UL 1971	Visual Notification Appliances

2.6 SERVICE

A. The equipment manufacturer representative shall have a local office staffed with trained, full-time employees who are capable of performing testing, inspection, repair maintenance services, and inventory parts for the life of the fire alarm system.

B. This organization must have a minimum of five (5) years of experience servicing fire alarm systems and shall respond to service calls within 48 hours during or after the warranty period.

C. Prior to completion of installation, the manufacturer's representative shall provide a preventative maintenance agreement, which shall at the Owners option, become effective at the end of the 12 month warranty period.

D. Upon completion of the project, the system subcontractor shall provide to the owner, an agreement for the purpose of providing off-site monitoring services.

2.7 GENERAL OPERATION

A. Upon actuation of any initiating device (manual stations, automatic detectors, etc.) all alarm notifying units (horns, visual alarm lamps, etc.) shall operate continuously until such time as the manual station or automatic detector is restored to normal and the fire alarm control unit 'silenced'. Alarm signals shall be annunciated by point and zone at the control panel.

B. As per plans, the following additional functions shall be performed in the event of an alarm:
1. Alarms shall be annunciated at a remote annunciator.
2. Alarms shall trip the municipal system, and/or remote central station system.
3. Strobe units shall be controlled independently from audible units. Upon system silence, strobe units will continue to flash until system reset is provided.

C. Alarm circuits shall remain energized and the zone annunciation LED will continue to flash until the acknowledge switch is operated at which time the audible signaling devices will be de-energized. Should an alarm be initiated in a subsequent zone after an alarm has been acknowledged, the alarm signals shall be re-energized. The control panel shall be restored to normal by operation of a reset switch after the initiating device has been restored to normal.

2.8 FIELD PROGRAMMING

A. The system shall be programmable, configurable, and expandable in the field without the need for special tools or electronic equipment and shall not require field replacement of electronic integrated circuits. All programming shall be accomplished through the standard common control panel keyboard or through the use of the CRT-2 keyboard. All field defined programs shall be stored in non-volatile memory.

B. The programming function shall be enabled with a special 5-digit password that may be defined specifically for the system when it is installed.

C. This password may be changed to a new value at any time by system's Sub-Contractor. In the event that the system's sub-contractor may define a password and then lose or forget it, the system shall be designed so that the valid password may be determined by special procedures available through the system manufacturer.

D. The system shall provide means for automatic programming of its operation to conform with certain N.F.P.A. Standards through internal software. The following N.F.P.A. operations are to be available through this means:
1. NFPA 72: National Fire Alarm Code

PART 3 - PRODUCTS

3.1 GENERAL

A. All equipment and components shall be new, and the manufacturer's current model. The materials, appliances, equipment and devices shall be tested and listed by a nationally recognized approvals agency for use as part of a protected premises protective signaling (fire alarm) system. The authorized representative of the manufacturer of the major equipment, such as control panels, shall be responsible for the satisfactory installation of the complete system.

B. All equipment and components shall be installed in strict compliance with each manufacturer's recommendations. Consult the manufacturer's installation manuals for all wiring diagrams, schematics, physical equipment sizes, etc. before beginning system installation.

C. All equipment shall be attached to walls and ceiling/floor assemblies and shall be held firmly in place (e.g., detectors shall not be supported solely by suspended ceilings). Fasteners and supports shall be adequate to support the required load.

3.2 FIRE ALARM SYSTEM CONTROL PANEL

A. The Fire alarm System Control Panel
   1. The Fire alarm System Control Panel shall meet the modular listing requirements of the ninth edition of UL Standard 864 "Standard for Control Units and Accessories for Fire Alarm Systems" for ease of installation, maintenance, and future expansion.
   2. Each subassembly of the Fire alarm System Control Panel shall include the appropriate UL modular label. This includes all printed circuit board assemblies, power supplies, and enclosure parts.
   3. The system shall provide means for all Signaling Line Circuit (SLC) devices on any Signaling Line Circuit (SLC) loop to be auto programmed into the system by specific address.
   4. The system shall recognize specific device type ID's and associate that ID with the corresponding address of the device.
   5. The Fire alarm System Control Panel shall support the following items:
   6. Up to (8) Fire Alarm Remote Annunciator Panels.
   7. Provide new Circuit Labels and Directory cards for panels modified and / or added.
   8. The Fire alarm System Control Panel shall have a 6 amp power supply and be capable of expansion to a maximum of 54 total amps via bus connected expander modules that supervise low battery, loss off AC, and loss of communication.
   9. The Fire alarm System Control Panel shall include "Form C" alarm, trouble, supervisory, and security relays rated at a minimum of 2.0 amps @ 30 Volts D.C.
   10. All programming or editing of the existing program in the system shall be achieved without special equipment and without interrupting the alarm monitoring functions of the Fire alarm System Control Panel.
   11. The Fire alarm System Control Panel shall allow for loading and editing special instructions and operating sequences as required in addition to being capable of onsite programming to accommodate and facilitate expansion, building parameter changes or changes as required by local codes.
   12. Visually and audibly annunciate any "Alarm", "Trouble", or "Supervisory" condition at the operator's terminals, Fire alarm System Control Panel, and at the Fire alarm System Remote Annunciator Panels.
   13. Built-in universal communicator.
   14. The Fire alarm System Control Panel shall provide the following features:
      a. Supervision of all initiating signaling and notification circuits throughout the facility by way of connection to addressable control, monitor, and relay modules.
      b. Detect the activation of any initiating device and the location of the alarm condition.

c. Operate all notification appliances and auxiliary devices as programmed.
d. PAS pre-signal, meeting N.F.P.A. #72 requirements.
e. Rapid manual station reporting (under 3 seconds).
f. Shall meet N.F.P.A. #72 requirements for activation of notification circuits within 10 seconds of initiating device activation.
g. Coding panel node notification circuits in March Time (120 PPM), Temporal (N.F.P.A. #72), and California Code
h. Periodic detector test (conducted automatically by the software).
i. Shall support Two-Stage operation, Canadian Dual Stage (3 minutes) and Canadian Dual Stage (5 minutes).
   1) Two-stage operation shall allow 20 Pulses per Minute (PPM) on alarm and 120 Pulses per Minute (PPM) after 5 minutes or when a second device activates.
   2) Canadian Dual stage operation is the same as Two-Stage except will only switch to second stage by activation of Drill Switch 3 or 5 minute timer.
j. Self-optimizing pre-alarm for advanced fire warning, which allows each detector to learn its particular environment and set its pre-alarm level to just above normal peaks.
k. Cross zoning with the capability of counting: two detectors in alarm, two software zones in alarm, or one smoke detector and one heat detector.
l. Coding option that will synchronize specific strobe lights designed to accept a specific "Sync Pulse".
m. Control-by-time for non-fire operations (with holiday schedules).
n. Day/night automatic adjustment of detector sensitivity.
o. Device "Blink Control" to turn off detector / module Light Emitting Diodes (LEDs) for special areas such as sleeping areas.

15. Permitted zone types that allow Input/Output linking shall be:
    a. General: Up to 1,000 zones.
    b. Releasing Up to 10 zones.
    c. Special: Up to 10 zones.
    d. Logic: Up to 1,000 zones.
    e. Trouble: Up to 1,000 zones.
16. Install Synchronization modules and/or equipment as recommended by the manufacturer to meet all code requirements that are powered from a Notification Appliance Circuit (NAC) output for the following appliances:
    a. Visual Notification Appliances (strobes)
    b. Audible Notification Appliances (horns or speakers)
    c. Multiple Low Frequency Sounder Appliances and/or standard Sounder Appliances installed within a single dwelling unit.
17. The Signaling Line Circuit (SLC) interface board shall be able to drive a "Class B" twisted unshielded circuit up to 12,500 feet in length.
18. The Fire alarm Control Panel shall be capable of communicating on a Local Area Network (LAN), a firmware package that utilizes a peer-to-peer, and an inherently regenerative communication format and protocol.

B. Central Processing Unit (CPU):
1. The Fire alarm System Control Panel shall contain a microprocessor based Central Processing Unit (CPU) that shall communicate with, monitor, and control all external interfaces and annunciate A "Trouble" condition for a loss in communications for the following at a minimum:
   a. Intelligent Addressable Smoke Detectors.
   b. Intelligent Addressable Thermal (Heat) Detectors.
   c. Addressable Modules.
   d. Control Circuits.
   e. Notification Appliance Circuits.
   f. Transponders.

g. Annunciators.
h. Other System Controlled Devices.
i. Peripheral Equipment.

2. It shall include an EPROM for system program storage, flash memory for building-specific program storage, and a "watch dog" timer circuit to detect and report microprocessor failure.
3. Upon a loss of response from a device, the Central Processing Unit shall:
   a. Sound an audible trouble
   b. Illuminate a Light Emitting Diode (LED) indicating loss of communications.
   c. Indicate which device or devices are not responding
   d. Print the information in the history buffer.
4. The Central Processing Unit shall contain and execute all control-by-event programs for specific action to be taken if an "Alarm" condition is detected by the system that shall be held in non-volatile programmable memory and shall not be lost with system primary and secondary power failure.
5. A special program check function shall be provided to detect common operator errors.
6. An auto-program (self-learn) function shall be provided to quickly install initial functions and make the system operational.
7. For flexibility and to ensure program validity, an optional Windows(TM) based program utility shall be available that is capable of the following:
   a. Have the ability to off-line program the system with batch upload/download.
   b. Have the ability to upgrade the manufacturers (FLASH) system code changes.
   c. Have a verification utility, which scans the program files, identifying possible errors.
   d. Have the ability to compare old program files to new ones, identifying differences in the two files to allow complete testing of any system operating changes.
8. The Central Processing Unit shall provide a real-time clock for time annotation of system displays, events, and history files that shall not be lost if system primary and secondary power supplies fail.
9. The Central Processing Unit’s real time clock may also be used to control non-fire functions at programmed time-of-day, day-of-week, and day-of-year.
10. The Central Processing Unit shall be capable of being programmed, configured, and expanded on site without requiring the use of any external programming equipment.
11. The system programming shall be "Backed Up" via an upload/download program and stored on compatible removable media.
12. The Central Processing Unit and associated equipment shall be protected from voltage surges or line transients.
13. Data transmissions between the Central Processing Unit and each peripheral device shall be continuously scanned for proper operation, reliable, and error free. The transmission scheme used shall employ dual transmission or other equivalent error checking techniques.
14. The Central Processing Unit shall provide double pole relays for the following items:
   a. Fire Alarm
   b. System Trouble
   c. Supervisory
   d. Security
15. The Central Processing Unit shall provide one high-speed serial connection for support of network communication modules.
16. In the event of Central Processing Unit failure, all Signaling Line Circuits (SLC's) loop modules shall fallback to degrade mode.
   a. Degrade mode shall treat the corresponding Signaling Line Circuits (SLC's) loop control modules and associated detection devices as conventional two-wire operation.
   b. Activation of any initiating device in this mode shall automatically activate associated Notification Appliance Circuits.

C. System Display Interface Assembly:
   1. The Fire alarm System Control Panel shall include a full featured System Display Interface Assembly that shall include the following:
      a. A backlit 80-character Liquid Crystal Display (LCD)
      b. Individual, color coded system status LEDs
      c. A full PC style QWERTY alphanumeric keypad for the field programming and control of the fire alarm system.
      d. Display custom alphanumeric labels for all intelligent devices, Addressable Modules, software zones, etc.
      e. Label information shall be stored in programmable nonvolatile memory (NVRAM).
      f. May be used to program all system operational parameters.
      g. Display battery charging current and voltage.
   2. It shall also provide 10 Light Emitting Diodes (LEDs), which will indicate the status of the following system parameters:
      a. AC Power: Green Led
      b. System Alarm: Red Led
      c. System Trouble: Yellow Led
      d. Signal Silence: Yellow Led
      e. Pre Alarm: Yellow Led
      f. Point Disabled: Yellow Led
      g. Cpu Failure : Yellow Led
      h. Security: Yellow Led
      i. Supervisory: Yellow Led
      j. Other Event: Yellow Light Emitting Diode (Led)
   3. Two different password levels will be accessible through the System Display Interface Assembly to prevent unauthorized system control or programming.
      a. Level 1 (User): Shall be used for status level changes such as point/zone disable or manual on/off commands (Building Manager).
      b. Level 2 (Master): Shall be used for actual change of the life safety program (installer) and allow access to password change screens.
      c. These passwords shall be five (5) digits at a minimum. Upon entry of an invalid password for the third time within a one minute time period an encrypted number shall be displayed. This number can be used as a reference for determining a forgotten password.
   4. The System Display shall include the following operator control switches:
      a. Signal Silence
      b. Lamp Test
      c. Reset
      d. Alarm Active (Drill Switch)
      e. Acknowledge
   5. Depression of the Scroll Display key shall display the next event in the selected queue allowing the operator to view events by type including:
      a. Ac Power
      b. Fire Alarm
      c. Pre-Alarm Warning
      d. Security Alarm
      e. Supervisory Signal
      f. Trouble
      g. Disabled Points
      h. Alarm Silenced
      i. Controls Active
      j. Pre-Discharge
      k. Discharge
      l. Abort
   6. A "PRINT SCREEN" button shall be provided for printing the event currently displayed on the 640-character Liquid Crystal Display (LCD).

D. System Reports:
   1. The Fire alarm System shall provide means to obtain a variety of reports listing all:
      a. Events
      b. "Alarm" Conditions
      c. "Trouble" Conditions
      d. "Supervisory" Conditions
      e. Security History
   2. Additional reports shall be available for the following:
      a. Last Walk Test performed
      b. Detector maintenance report containing the status of each installed addressable detector
      c. All Network Parameters
      d. All panel settings including broad cast time
      e. Event Ordering
      f. Block Acknowledge
      g. Panel timer values for Auto Silence
      h. Silence Inhibit
      i. AC Fail Delay time
      j. Supervision settings for power supply
      k. Supervision settings for printers
      l. All programmed logic equations
      m. All custom action messages
      n. All non-fire and output activations (if pre-programmed for logging) all active points filtered by alarms only
      o. Troubles Only
      p. Supervisory Alarms
      q. Pre-Alarms
      r. Disabled Points
      s. Activated Points
      t. All installed points filtered by Signaling Line Circuits (SLC) points
      u. Logic Zones
      v. Annunciators
      w. Releasing Zones
      x. Special Zones
      y. Trouble Zones

3.3 SYSTEM DISPLAY

A. The system display shall provide all the controls and indicators used by the system operator and may also be used to program all system operational parameters.

B. The display assembly shall contain, and display as required, custom alphanumeric labels for all intelligent detectors, addressable modules, and software zones.

C. The system display shall provide a 640-character backlit alphanumeric Liquid Crystal Display (LCD). It shall also provide ten Light-Emitting-Diodes (LEDs) that indicate the status of the following system parameters: AC POWER, FIRE ALARM, PREALARM, SECURITY, SUPERVISORY, SYSTEM TROUBLE, OTHER EVENT, SIGNALS SILENCED, POINT DISABLED, and CPU FAILURE.

D. The system display shall provide a QWERTY style keypad with control capability to command all system functions, entry of any alphabetic or numeric information, and field programming. Two different password levels with up to ten (one Master and nine User) passwords shall be accessible through the display interface assembly to prevent unauthorized system control or programming.

E. The system display shall include the following operator control switches: ACKNOWLEDGE, SIGNAL SILENCE, RESET, DRILL, and LAMP TEST. Additionally, the display interface shall allow scrolling of events by event type including, FIRE ALARM, SECURITY, SUPERVISORY, TROUBLE, and OTHER EVENTS. A PRINT SCREEN button shall be provided for printing the event currently displayed on the 640-character LCD.

3.4 LOOP (SIGNALING LINE CIRCUIT) CONTROL MODULE

A. The Loop Control Module shall monitor and control a minimum of 318 intelligent addressable devices. This includes 159 intelligent detectors (Ionization, Photoelectric, or Thermal) and 159 monitor or control modules.

B. The Loop Control Module shall contain its own microprocessor and shall be capable of operating in a local/degrade mode (any addressable device input shall be capable of activating any or all addressable device outputs) in the unlikely event of a failure in the main CPU.

C. The Loop Control Module shall provide power and communicate with all intelligent addressable detectors and modules on a single pair of wires. This SLC Loop shall be capable of operating as a NFPA Style 6 (Class B) circuit.

D. The SLC interface board shall be able to drive an NFPA Style 6 twisted unshielded circuit up to 12,500 feet in length. The SLC Interface shall also be capable of driving an NFPA Style 6, no twist, no shield circuit for limited distances determined by the manufacturer. In addition, SLC wiring shall meet the listing requirements for it to exit the building or structure. "T"-tapping shall be allowed in either case.

E. The SLC interface board shall receive analog or digital information from all intelligent detectors and shall process this information to determine whether normal, alarm, or trouble conditions exist for that particular device. Each SLC Loop shall be isolated and equipped to annunciate an Earth Fault condition. The SLC interface board software shall include software to automatically maintain the detector's desired sensitivity level by adjusting for the effects of environmental factors, including the accumulation of dust in each detector. The analog information may also be used for automatic detector testing and the automatic determination of detector maintenance requirements.

3.5 FIRE ALARM SYSTEM CONTROL PANEL ENCLOSURES

A. The Fire alarm System Control Panel Enclosure shall be listed to UL #50 "Enclosures for Electrical Equipment, Non-Environmental Considerations", N.F.P.A. #72, and shall be approved for fire protection service.

B. The control panel enclosure shall be suitable for surface or semi-flush mounting.

C. The control panel enclosure shall be corrosion protected, given a rust-resistant prime coat, and manufacturer's standard finish.

D. The back box and door shall be constructed of 0.060" steel with provisions for electrical conduit connections into the sides and top.

E. The door shall provide a key lock and include a transparent opening for viewing all indicators.

F. For convenience, the door shall have the ability to be hinged on either the right or left-hand side.

G. The control panel enclosure shall be modular in structure for ease of installation, maintenance, and future expansion.

3.6 POWER SUPPLY

A. The Addressable Main Power Supply shall operate on 120/240 VAC, 50/60 Hz, and shall provide all necessary power for the FACP.

B. The Addressable Main Power Supply shall provide the required power to the CPU using a switching 24 VDC regulator and shall incorporate a battery charger for 24 hours of standby power using dual-rate charging techniques for fast battery recharge.

C. The Addressable Main Power Supply shall provide a battery charger for 24 hours of standby using dual-rate charging techniques for fast battery recharge. The supply shall be capable of charging batteries ranging in capacity from 7-200 amp-hours within a 48-hour period.

D. The Addressable Main Power Supply shall provide a very low frequency sweep earth detect circuit, capable of detecting earth faults.

E. The Addressable Main Power Supply shall be power-limited per UL864 requirements.

3.7 TERMINAL BOXES, JUNCTION BOXES AND CABINETS

A. All boxes and cabinets shall be UL listed for their intended purpose.

B. Provide outlet and pull boxes to enclose devices, permit the pulling of conductors and for wire splices and branches.

C. Surface Metal Raceway: Boxes of same Manufacture and to match Raceway. Boxes to accommodate standard devices and device plate.

D. Install pull boxes so as to be accessible after completion of work.

E. All boxes shall be firmly anchored directly or with concealed bracing to building studs or joints. Boxes must be so attached so that they will not "Rock" or "Shift" when devices are operated.

F. Except for surface mounted boxes or boxes above accessible ceilings, all boxes shall have front edge (box or plaster ring) even with the finished surface of the wall or ceiling.

G. Provide blank covers or plates over all boxes not covered by equipment.

H. Pull and junction boxes shall be installed as shown, and to facilitate pulling of wire and to limit the number of bends within code requirements. Boxes shall be permanently accessible and shall be placed only at locations approved by the Engineer.

I. In suspended ceiling spaces, boxes shall be supported from the structure independently from ceiling suspension system.

J. The Drawings do not necessarily show every pull or Junction Box required. The Installing Vendor is permitted to provide boxes deemed necessary by him for his work when installed in accordance with these Specifications.

3.8 BATTERIES AND EXTERNAL CHARGER

A. Battery:
1. Shall be 12 volt, Gell-Cell or AGM (Absorbed Glass Mat) type.

2. Battery shall have sufficient capacity to power the fire alarm system for not less than 24 hours plus 15 minutes of alarm upon a normal AC power failure.
3. The batteries are to be completely maintenance free. No liquids are required. Fluid level checks refilling, spills and leakage shall not be required.

B. External Battery Charger:
1. Shall be completely automatic, with constant potential charger maintaining the battery fully charged under all service conditions. Charger shall operate from a 120/240-volt 50/60 hertz source.
2. Shall be rated for fully charging a completely discharged battery within 48 hours while simultaneously supplying any loads connected to the battery.
3. Shall have protection to prevent discharge through the charger.
4. Shall have protection for overloads and short circuits on both AC and DC sides.

3.9 FIRE ALARM REMOTE ANNUNCIATOR PANEL (FARAP)

A. For the purpose of providing a remote system status display, a Fire Alarm Remote Annunciator Panel shall be provided in locations as indicated on the contract documents.

B. The alphanumeric display annunciator shall be a supervised, remotely located back-lit LCD display containing a minimum of eighty (80) characters for alarm annunciation in clear English text.

C. The display shall be UL listed for fire alarm application with an On-line/Power LED.

D. The LCD annunciator shall display all alarm and trouble conditions in the system.

E. An audible indication of alarm shall be integral to the alphanumeric display.

F. The display shall be UL listed for fire alarm application.

G. It shall be possible to connect up to a minimum of 32 terminal mode LCD annunciators and be capable of wiring distances up to 6,000 feet from the Fire alarms Control Panel.

H. The system shall allow a minimum of 32 terminal mode LCD annunciators.

I. Up to 10 LCD annunciators shall be capable of the following system functions which shall be protected from unauthorized use by a key switch or password:
1. Acknowledge.
2. Signal Silence.
3. System Reset.

J. The LED annunciator shall offer an interface to a graphic style annunciator.

K. Provide fire alarm remote annunciator panel with an integral Piezo sounder with an Alarm/Trouble switch for audible indication of alarm and trouble conditions.

L. Provide flush or surface mounted, in location as indicated on the contract documents.

M. The Fire Alarm Remote Annunciator Panel shall be programmed to clearly indicate the exact same information that is displayed at the Fire alarms Control Panel on the LCD annunciator screen.

3.10 FIELD DEVICES

A. Intelligent and Addressable Photoelectric Smoke Detectors:
1. The intelligent photoelectric detectors shall be intelligent and addressable, and shall connect with two wires to one of the fire alarm control panel signaling line circuit loops.
2. The detectors shall use the photoelectric principle to measure smoke density and shall, on command from the control panel, send data to the panel representing the analog level of smoke density.
3. The detectors shall be ceiling mount and shall include a twist-lock base.
4. The detectors shall provide a test means whereby they will simulate an alarm condition and report that condition to the control panel. Such a test may be initiated at the detector itself, by activating a magnetic switch, or may be activated remotely on command from the control panel.
5. The detectors shall provide address-setting means on the detector head using rotary decimal switches. The detectors shall also store an internal identifying code, which the control panel shall use to identify the type of detector.
6. The detectors shall provide dual alarm and power LEDs. Both LEDs shall flash under normal conditions, indicating that the detector is operational and in regular communication with the control panel. Both LEDs may be placed into steady illumination by the control panel, indicating that an alarm condition has been detected. If required, the flashing mode operation of detector LEDs shall be controlled through the system field program. An output connection shall also be provided in the base to connect an external remote alarm LED.
7. The detector sensitivity shall be set through the fire alarm control panel, and shall be adjustable in the field through the field programming of the system.
8. Addressable smoke detectors shall provide dual (2) status LEDs. Both LEDs shall flash under normal conditions, indicating that the detector is operational and in regular communication with the control panel, and both LEDs shall be placed into steady illumination by the control panel, indicating that an alarm condition has been detected. If required, the flashing mode operation of the detector LEDs can be programmed off via the fire control panel program.
9. The fire alarm control panel shall permit detector sensitivity adjustment through field programming of the system. Sensitivity can be automatically adjusted by the panel on a time-of-day basis.
10. Using software in the FACP, detectors shall automatically compensate for dust accumulation and other slow environmental changes that may affect their performance. The detectors shall be listed by UL as meeting the calibrated sensitivity test requirements of NFPA Standard 72, Chapter 7.
11. The detectors shall be ceiling-mount and shall include a separate twist-lock base which includes a tamper proof feature.

B. Conventional Heat Detectors: Rate of rise and fixed temperature detectors shall be rated at 135 degrees F for areas of ambient temperatures of 100 degrees F or less.
1. Detectors shall have a smooth ceiling rating of 2500 square feet and shall be installed in accordance with NFPA 72E
2. Fixed temperature detectors rated at 194 degrees F shall be provided as indicated on the drawings or in areas subject to high ambient temperatures in excess of 100 degrees F. Smooth ceiling rating: 625 sq. ft.

C. Carbon Monoxide Detectors:
1. Carbon Monoxide Detectors can be mounted on the wall or ceiling.
2. Carbon Monoxide Detectors shall be flush mounted when located in finished areas.
3. Wall mounted Carbon Monoxide Detectors installed in indoor locations shall be at 80" above the finished floor or 6" below the ceiling, whichever is lower.
4. Carbon Monoxide Detectors shall be placed in the following locations:
   a. On every floor of a Dwelling Unit.

b. Within 10 feet of all Dwelling Unit sleeping areas.
c. In any room that contains a fuel-burning appliance.

D. Combination Smoke / Carbon Monoxide Detectors:
1. Combination Smoke / Carbon Monoxide Detectors can be mounted on the wall or ceiling.
2. Carbon Monoxide Detectors shall be flush mounted when located in finished areas.
3. Wall mounted Carbon Monoxide Detectors installed in indoor locations shall be at 80" above the finished floor or 6" below the ceiling, whichever is lower.
4. Carbon Monoxide Detectors shall be placed in the following locations:
a. On every floor of a Dwelling Unit.
b. Within 10 feet of all Dwelling Unit sleeping areas.
c. In any room that contains a fuel-burning appliance.

E. Monitor Modules: Addressable monitor modules shall be provided to connect one supervised IDC zone of conventional alarm indicating devices (any N.O. dry contact devices, including 4-wire smoke detector(s)), to one of the fire alarm control panel signaling line circuit (SLC) loops.
1. The monitor module shall mount in a 4-inch square, 2-1/8" deep electrical box, to a surface mounted back box, or directly into the fire alarm control panel.
2. The IDC zone may be wired for Style D or Style B operation. The monitor module shall provide address-setting means using rotary decimal switches and shall also store an internal identifying code, which the fire alarm control panel shall use to identify the type of device. An LED shall be provided which shall flash under normal conditions, indicating that the monitor module is operational and in regular communication with the control panel.
3. For difficult to reach areas, the monitor module shall be available in a miniature package and shall be no larger than 2-3/4 inch (70 mm) x 1-1/4 inch (31.7 mm) x 1/2 inch (12.7 mm). This version need not include Style D or an LED.
4. For multiple dry contact monitoring a module shall be available that provides 10 Style B or 5 Style D input circuits.

F. Control Module:
1. The control module shall be used to connect a conventional indicating appliance circuit of 24 VDC compatible polarized audio-visual indicating appliances to one of the NAC loops.
2. The control module shall mount in a standard 4-inch square, 2-1/8" deep electrical box.
3. The control module may also be wired as a dry contact (form C) relay.
4. Power for the relay coil shall be provided by the NAC loop to reduce wiring connection requirements.
5. The control module NAC may be wired for Style Z or Style Y (Class A/B) with a current rating of 2 Amps for Style Z and 3 Amps for Style Y. For speaker applications the module is rated for 50 watts at 25 or 70.7.
6. Audio/visual power shall be provided by a separate supervised power circuit from the main fire alarm control panel or from a supervised UL listed remote power supply.
7. The control module shall be suitable for pilot duty applications and rated for a minimum of 0.6 amps at 30 VDC.
8. For multiple circuit control a module shall be available that provides 6 Style B or 3 Style D control circuits.

G. Isolator Module:
1. The isolator module shall be used to isolate wire-to-wire short circuit on an SLC loop in order to limit the number of other modules or detectors that are incapacitated by the short circuit fault.
2. If a wire-to-wire short occurs, the isolator shall automatically open circuit the SLC loop.
3. When the short is corrected, the isolators shall automatically reconnect the isolated section of the SLC loop.

4. Provide isolation modules at logical junctions corresponding to architectural wings or sections of the building or campus.
5. At minimum, an isolation module shall be provided for every 50 SLC sloop devices. Should multiple, remote power supplies be required, a minimum of one isolation module shall be provided for devices served by each remote power supply.

H. Addressable Relay Module:
1. Addressable Relay Modules shall be available for HVAC control and other building functions. The module shall provide two form C relays rated at up to 3 Amps resistive and up to 2.0 Amps inductive. The relay coil shall be magnetically latched to reduce wiring connection requirements, and to insure that 100% of all auxiliary devices energize at the same time on the same pair of wires.
2. For multiple relay control a module shall be available that provides 6 programmable Form-C relays.

I. Addressable Manual Stations:
1. Addressable manual stations shall be provided to connect one addressable, supervised manual station to one of the fire alarm control panel signaling line circuit (SLC) loops.
2. The manual station shall, on command from the control panel, send data to the panel representing the state of the manual switch.
3. Manual fire alarm stations shall be double action type with a key operated test-reset lock, and shall be designated so that after actual emergency operation, they cannot be restored to normal use except by the use of a key.
4. All operated stations shall have a positive, visual indication of operation that cannot be reset without the use of a key. The word FIRE shall appear on the front of the stations in raised letters.
5. Stations shall be suitable for surface mounting on matching back box, or semi-flush mounting on a standard single gang box. The manual stations shall provide address-setting means using rotary decimal switches and shall also store an internal identifying code, which the control panel shall use to identify the type of device.
6. An LED shall be provided which shall flash under normal conditions, indicating that the manual station is operational and in regular communication with the control panel. The LED may be placed into steady illumination by the control panel, indicating that an alarm condition has been detected. The station shall provide a key reset. The key shall be the same as used for the fire control panel.
7. All addressable manual fire alarm stations shall be surface-mounted to a back box. This back box will be color coordinated with the front panel of the manual fire alarm station, and shall not allow any corner of the manual fire alarm station to protrude.
8. A mounting plate will be provided to allow the installation of an isolator/control/monitor module directly in the fire alarm control panel back box.

3.11 SOUNDER BASE ONLY APPLIANCES

A. Sounder Base Only Appliances shall be listed to UL #268 "Smoke Detectors for Fire Alarm Systems", UL #464 "Standard for Audible Signal Appliances", and be compatible with the fire alarm System Control Panel.

B. Sounder Base Only Appliances shall be provided in residential dwelling unit applications only.

C. The fire alarm System Control Panel shall be able to:
1. Distinguish the Sounder Base Only Appliance as a unique device type on the Signaling Line Circuit (SLC) loop or on a Notification Appliance Circuit (NAC).
2. When connected to a Notification Appliance Circuit (NAC), power is supervised via the Notification Appliance Circuit (NAC) circuit supervision while in standby mode (EOL resistor required for Class B operation).

3. Can command an individual sounder base or a group of sounders in a suite or other multi-room configuration to activate.
4. Capable of allowing selection of volume, tone, and group.

D. Sounder Base Only Appliances shall be capable of producing:
1. Two distinct volume levels:
a. 75 dBA at 10'-0".
b. 85 dBA at 10'-0".
2. A variety of tone patterns required by N.F.P.A. #72 for commercial and residential applications:
a. Continuous.
b. ANSI Temporal 3 (Smoke Alarm).
c. ANSI Temporal 4 (CO Alarm).
d. March Time.

E. Sounder Base Only Appliances shall include a tamper-resist feature that prevents its removal from the base without the use of a tool.

F. Sounder Base Only Appliances shall have a mechanical locking feature that prevents removal of attached sensor head.

G. Sounder Base Only Appliances shall have the following features:
1. Capability of interconnection to other sounder bases to allow activation of all sounder bases within specific dwelling units.
2. Capability of being synchronized in accordance with N.F.P.A. #72.
3. Be silenceable from the fire alarm System Control Panel.

H. Sounder Base Only Appliances shall be installed in pre-wired mounting plate that fits various junction box sizes.

3.12 LOW FREQUENCY SOUNDER ONLY APPLIANCES

A. Low Frequency Sounder Only Appliances shall be listed to UL #464 "Standard for Audible Signal Appliances", UL #1971 “Standard for Signaling Devices for the Hearing Impaired", N.F.P.A. #72, shall be approved for fire protective service, and be compatible with the fire alarm System Control Panel.

B. Low Frequency Sounder Only Appliances shall be Intelligent, Analog, and Addressable that shall connect to the fire alarm System Control Panel's Notification Appliance Circuits (NAC) or Signaling Line Circuits (SLC).

C. Low Frequency Sounder Only Appliances shall have the following characteristics:
1. Shall be 24 Volts D.C.
2. Be installed on the ceiling or on the wall.
3. Shall be red or white finished.
4. Tamper resistant construction.
5. Frequency range of 520 Hz ±10% square wave tone.
6. Permanent marking on the housing that reads "Low Frequency Sounder".
7. Shall have three (3) audibility options and an option to switch between a temporal three-pattern and a non-temporal (continuous) pattern.
8. Shall produce a nominal sound output of 76 dBA at 10'-0"
9. Shall produce a maximum sound output of 80 dBA at 10'-0".
10. Shall be plug-in type.
11. Shall terminate at a universal mounting plate.

D. Low Frequency Sounder Only Appliances installed in interior climate controlled spaces shall have an operating temperature between 32°F and 120°F.

E. If the Low Frequency Sounder Only Appliances are not UL 9th edition listed with the corresponding panel or power supply being used, then refer to the compatibility listing of the panel to determine maximum devices on a circuit.

3.13 STROBE ONLY APPLIANCES

A. Strobe Only Appliances shall be listed to UL #1638 "Standard for Visual Signaling Appliances - Private Mode Emergency and General Utility Signaling" shall be approved for fire protective service, and be compatible with the fire alarm System Control Panel.

B. Strobe Only Appliances shall be Intelligent, Analog, and Addressable that shall connect to the fire alarm System Control Panel's Notification Appliance Circuits (NAC) or Signaling Line Circuits (SLC).

C. Strobe Only Appliances shall have the following characteristics:
1. Shall be 24 Volts D.C.
2. Be installed on the ceiling or on the wall.
3. Shall be red or white finished.
4. Tamper resistant construction.
5. Shall flash at a rate of one flash per second at 1Hz over the strobes entire operating voltage.
6. Shall be xenon / zenon flash tube type.
7. Associated lens/reflector system shall be rated at a minimum of 15 candela and meet or exceed the requirements of the Americans with Disabilities Act (ADA).
8. Shall have field selectable candela settings.
9. Shall be plug-in type.
10. Shall terminate at a universal mounting plate.
11. Shall be backward compatible.

D. Strobe Only Appliances installed in interior climate controlled spaces shall have an operating temperature between 32°F and 120°F.

E. Weatherproof Strobe Only Appliances installed outdoors or in spaces of high humidity shall have the following characteristics:
1. Shall be listed for outdoor use by UL.
2. Shall have an operating temperature between -40°F and 151°F.
3. Shall be provided with an outdoor/weatherproof back box with:
   a. Conduit entries of ½" and ¾".
   b. Weatherproof sealant per the manufacturer's recommendations to prevent moisture from entering the structure.

F. If the Strobe Only Appliances are not UL 9th edition listed with the corresponding panel or power supply being used, then refer to the compatibility listing of the panel to determine maximum devices on a circuit.

G. Provide wire guards for Strobe Only Appliances installed in Gymnasiums, Multi-Purpose Rooms, Play Areas, Play Sheds, or in areas subject to mechanical damage.

3.14 COMBINATION HORN / STROBE APPLIANCES

A. Combination Horn / Strobe Appliances shall be listed to UL #464 "Standard for Audible Signal Appliances", UL #1638 "Standard for Visual Signaling Appliances - Private Mode Emergency and General Utility Signaling", UL #1971 “Standard for Signaling Devices for the Hearing Impaired", shall be approved for fire protective service, and be compatible with the fire alarm System Control Panel.

B. Combination Horn / Strobe Appliances shall be Intelligent, Analog, and Addressable that shall connect to the fire alarm System Control Panel's Notification Appliance Circuits (NAC) or Signaling Line Circuits (SLC).

C. The Horn Appliance shall be powered independently of the Strobe Appliance on a coded or non-coded power supply.

D. Combination Horn / Strobe Appliances shall have the following characteristics:
1. Shall be 24 Volts D.C.
2. Be installed on the ceiling or on the wall.
3. Shall be red or white finished.
4. Tamper resistant construction.
5. Shall have three (3) audibility options and an option to switch between a temporal three-pattern and a non-temporal (continuous) pattern.
6. Shall produce a nominal sound output of 82 dBA at 10'-0"
7. Shall produce a maximum sound output of 90 dBA at 10'-0".
8. Shall flash at a rate of one flash per second at 1Hz over the strobes entire operating voltage.
9. Shall be xenon / zenon flash tube type.
10. Associated lens/reflector system shall be rated at a minimum of 15 candela and meet or exceed the requirements of the Americans with Disabilities Act (ADA).
11. Shall have field selectable candela settings.
12. Shall be plug-in type.
13. Shall terminate at a universal mounting plate.
14. Shall be backward compatible.

E. Combination Horn / Strobe Appliances installed in interior climate controlled spaces shall have an operating temperature between 32°F and 120°F.

F. Weatherproof Combination Horn / Strobe Appliances installed outdoors or in spaces of high humidity shall have the following characteristics:
1. Shall be listed for outdoor use by UL.
2. Shall have an operating temperature between -40°F and 151°F.
3. Shall be provided with an outdoor/weatherproof back box with:
   a. Conduit entries of ½" and ¾".
   b. Weatherproof sealant per the manufacturer’s recommendations to prevent moisture from entering the structure.

G. If the Combination Horn / Strobe Appliances are not UL 9th edition listed with the corresponding panel or power supply being used, then refer to the compatibility listing of the panel to determine maximum devices on a circuit.

H. Provide wire guards for Combination Horn / Strobe Appliances installed in Gymnasiums, Multi-Purpose Rooms, Play Areas, Play Sheds, or in areas subject to mechanical damage.

3.15 COMBINATION LOW FREQUENCY SOUNDER / STROBE APPLIANCES

A. Combination Low Frequency Sounder / Strobe Appliances shall be listed to UL #464 "Standard for Audible Signal Appliances", UL #1971 “Standard for Signaling Devices for the Hearing Impaired", N.F.P.A. #72, shall be approved for fire protective service, and be compatible with the fire alarm System Control Panel.

B. Combination Low Frequency Sounder / Strobe Appliances shall be Intelligent, Analog, and Addressable that shall connect to the fire alarm System Control Panel's Notification Appliance Circuits (NAC) or Signaling Line Circuits (SLC).

C. Combination Low Frequency Sounder / Strobe Appliances shall be wired as a primary signaling notification appliance and comply with the Americans with Disabilities Act requirements for visible signaling appliances.

D. Combination Low Frequency Sounder / Strobe Appliances shall have the following characteristics:
1. Shall be 24 Volts D.C.
2. Be installed on the ceiling or on the wall.
3. Shall be red or white finished.
4. Tamper resistant construction.
5. Frequency range of 520 Hz ±10% square wave tone.
6. Permanent marking on the housing that reads "Low Frequency Sounder".
7. Shall have three (3) audibility options and an option to switch between a temporal three-pattern and a non-temporal (continuous) pattern.
8. Shall produce a nominal sound output of 76 dBA at 10'-0"
9. Shall produce a maximum sound output of 80 dBA at 10'-0".
10. Shall flash at a rate of one flash per second at 1Hz over the strobes entire operating voltage.
11. Shall be xenon / zenon flash tube type.
12. Associated lens/reflector system shall be rated at a minimum of 15 candela and meet or exceed the requirements of the Americans with Disabilities Act (ADA).
13. Shall have field selectable candela settings.
14. Shall be plug-in type.
15. Shall terminate at a universal mounting plate.

E. Combination Low Frequency Sounder / Strobe Appliances installed in interior climate controlled spaces shall have an operating temperature between 32°F and 120°F.

F. If the Combination Low Frequency Sounder / Strobe Appliances are not UL 9th edition listed with the corresponding panel or power supply being used, then refer to the compatibility listing of the panel to determine maximum devices on a circuit.

3.16 TRANSIENT AND SURGE PROTECTION

A. If not provided as an integral part of the system power supply, an external, 120 VAC transient and surge shall be provided for protection of all components of the system.

B. Protector shall be UL listed under sections 1449, 1283 and 497A, have a minimum energy handling of 70 Joules on line to line, line to neutral and line to ground spikes.

C. Response time shall be 5 nanoseconds or less and shall begin at 140 VAC.

D. Provide (1) dedicated TVSS at each 120 Volts A.C. hard wired connection point.

3.17 WIREMOLD SURFACE RACEWAY

A. Wiremold Surface Raceway shall be meet the requirements of Underwriters Laboratories Inc. and conform to U.S. Federal Specification W-C-582.

B. Wiremold Surface Raceway shall be in accordance with N.F.P.A. #70, local requirements, and state requirements.

C. Wiremold Surface Raceway shall be constructed of steel with a minimum thickness of 0.040".

D. Wiremold Surface Raceway shall have the following features:
1. Rugged steel raceway.
2. Low-profile and unobtrusive appearance.
3. Base and cover are preassembled as a one-piece unit.
4. Surface mounting.
5. Full line of fittings.
6. Fittings have removable covers.
7. UL #5 "Standard for Surface Metal Raceways and Fittings" and ADA compliant.

3.18 GRAPHIC MAPS

A. The Graphic display shall have the following physical characteristics:
1. The Indoor Graphic shall be a full color image with no less than the following areas (listed below) shown in different colors.
2. The Graphic shall be secured in a black anodized aluminum frame, have Tempered Glass to protect the graphic image, and be mounted with a concealed security hanging system.
3. The Graphics Map shall be installed directly adjacent to the Fire alarm System Remote Annunciator Panel and main Fire alarm System Control Panel.
4. The Graphics Map shall be a minimum of 11"x17" in size, but shall be based upon the actual building footprint. Provide 1/8” text minimum.
5. Suggested manufacturer is HR Kirkland.

B. The Graphic shall have the following features:
1. Provide a graphical representation of the main building floor plan, all other structures, and portable buildings. At a minimum, include the information:
   a. Building name(s) (and numbers where applicable).
   b. Room names and numbers.
   c. Doors.
2. Show the location of the FACP(s) (in Red).
3. Show the location(s) of the FARAP(s) (in Red).
4. Show a “You Are Here” (in Red) with an arrow pointing at the wall or area location of where Graphic Map is to be installed.
5. Show the connections and system(s) being monitored by the Fire alarm System. Include a System Legend at the top of the Graphic for EACH of the following systems:
   a. Fire Suppression System, consisting of:
      1) Post Indicator Valve.
      2) Water Flow Switch(s).
      3) Tamper Switch(s).
      4) Pressure Switch(s).
      5) Other systems that would typically interface to the Fire alarm System.
6. Show the “North” arrow on the drawing.
7. For multi-story buildings, the bottom of the graphic shall be the lowest level of the building, continuing to the top of the graphic with the highest level of the building.

8. Locate at the top of the Graphic, the image/logo and name of the Owner, approximately four-inches in height. This size of EACH image shall be consistent on EACH Graphic that is submitted.
   a. Coordinate with the Owner to obtain the graphic images and logos.
9. EACH of the following areas on the Graphic shall be separated by a pastel Color:
   a. Administrative Areas
   b. Sleeping Rooms
   c. Hallways
   d. Multipurpose Room(s)
   e. Kitchen
   f. Restrooms
   g. Truck Bays
10. The room numbering system depicted in all graphics and referenced in data bases generated by the Fire alarm System Contractor shall match that of the final signage and room identification system adopted by the Owner, unless specifically approved in writing otherwise, by the Architect and/or Engineer.
11. Interior Graphic Maps shall consist of the following:
   a. The full scale colored image shall be printed on the reverse side of a 10 mil polycarbonate Lexan.
   b. Standard background shall be white.
   c. The Lexan image shall mount to a rigid 1/8" substrate with removable adhesive mounts.
   d. The Graphic Map shall be secured to a black anodized aluminum frame.
   e. Provide Graphic Map with a concealed security hanging system to prevent unauthorized removal.

3.19 FIRE SPRINKLER SYSTEM CONNECTIONS

A. Provide addressable monitor modules for each fire sprinkler system device that is to be connected and monitored by the Fire alarms System consisting of the following items:
   1. Post Indicator Valve(s) (PIV)'s.
   2. Water Flow Switch(s).
   3. Tamper Switch(s).

B. Provide quantities as required by Code and by the Authority Having Jurisdiction.

C. The Fire alarm System Contractor shall provide a new electric bell. The bell shall be powered by a 24 Volts D.C. power source through the Fire alarm System Control Panel, allowing the electric bell to be on a back-up battery supply.

D. Fire protection sprinkler system tamper switches on the valve controlling the backflow preventer full forward flow test piping shall be connected to the Fire alarm System Control Panel.

PART 4 - EXECUTION

4.1 INSTALLATION

A. Installation shall be in accordance with the NEC, NFPA 72, local and state codes, as shown on the drawings, and as recommended by the major equipment manufacturer.

B. All conduit, junction boxes, conduit supports and hangers shall be concealed in finished areas and may be exposed in unfinished areas. Smoke detectors shall not be installed prior to the system programming and test period. If construction is ongoing during this period, measures shall be taken to protect smoke detectors from contamination and physical damage.

C. All fire detection and alarm system devices, control panels and remote annunciators shall be flush mounted when located in finished areas and may be surface mounted when located in unfinished areas.

D. Manual Pull Stations shall be suitable for surface mounting or semi-flush mounting as shown on the plans, and shall be installed not less than 42 inches, nor more than 48 inches above the finished floor.

4.2 WIRING

A. All wiring shall be contained in metal raceways. Wiring insulation shall be one of the types required by NEC 725-16 and shall be consistently color coded throughout the system.

B. Permanent wire markers shall be affixed to all conductors at terminations and splices. Numbering system shall be consistent with shop drawings.

C. All terminations shall be T & B "Sta-Kon" (or equivalent) self-insulated, flanged or forked tongue lugs where connected at screw type terminals. Wiring in main control cabinet shall be neatly arranged and bundled with wire ties (or equivalent).

D. Install wiring equipment in strict accordance with manufacturer's instructions. No wire other than the detector circuit shall be permitted in conduit feeding detectors unless approved.

E. Minimum wire size for 120 VAC wiring shall be #12 THHN.

F. Minimum wire size for initiating alarm circuit, i.e., pull stations, heat and smoke detectors, shall be minimum #16 twisted shielded pair FPL rated.

G. Minimum wire size for speaker and indicating circuits, i.e., horns, strobes, shall be minimum #16 shielded, twisted FPL rated cable. Indicating circuits shall be sized in accordance with manufacturer recommended voltage drop requirements, minimum size #14 AWG.

H. Provide separate raceway or shielded cable as required or recommended by system manufacturer to prevent the introduction of noise into the system.

I. All new Fire alarm System junction boxes shall be painted red and annotated “FA” on the cover in bold black print, having a minimum character font size of 2” tall X 1” wide.

J. Wiring shall be in accordance with local, state and national codes (e.g., NEC Article 760) and as recommended by the manufacturer of the fire alarm system. Number and size of conductors shall be as recommended by the fire alarm system manufacturer, but not less than 18 AWG (1.02 mm) for initiating device circuits, signaling line circuits, and notification appliance circuits.

K. All wire and cable shall be listed and/or approved by a recognized testing agency for use with a protective signaling system.

L. Wire and cable not installed in conduit shall have a fire resistance rating suitable for the installation as indicated in NFPA 70 (e.g., FPLR).

M. The system shall permit the use of IDC and NAC wiring in the same conduit with the multiplex communication loop.

N. All field wiring shall be completely supervised. In the event of a primary power failure, disconnected standby battery, removal of any internal modules, or any open circuits in the field wiring; a trouble signal will be activated until the system and its associated field wiring are restored to normal condition.

O. All analog voice speaker and analog telephone circuits shall use twisted/shielded pair to eliminate cross talk.

P. Connections to the communicator will be made by the Fire Alarm Vendor, in the presence of the Electrical Contractor, 1-week prior to the final acceptance test with the AHJ.

Q. All circuits shall be identified in accordance with table 3.02L with labels to include wire type, quantity and circuit number. Wire code shall match AHJ approved shop drawings wire code. Labels must be provided at the FACP and all junction boxes. Labels shall be produced using an electronic labeler.

Table 3.03 R

Example: C2HX3
C = Signal Circuit Wire
2 = Signal circuit number
H = Annunciator wire
X = Addressable initiating device circuit wire
3 = Addressable initiating device circuit number

4.3 CONDUIT

A. Conduit:
1. Conduit shall be in accordance with The National Electrical Code (NEC), local and state requirements.
2. All wiring in exposed areas shall be installed in conduit or raceway.
3. Conduit fill shall not exceed 40 percent of interior cross sectional area where three or more cables are contained within a single conduit.
4. Wiremold fill shall not exceed 40% of the interior cross sectional area.
5. It is permissible to install fire alarm low voltage cables open in D rings above accessible ceilings.
6. Cable must be separated from any open conductors of Power, or Class 1 circuits, and shall not be placed in any conduit, junction box or raceway containing these conductors, as per NEC Article 760.
7. Wiring for 24 volt control, alarm notification, and similar power-limited auxiliary functions may be run in the same conduit as initiating and signaling line circuits. All circuits shall be provided with transient suppression devices and the system shall be designed to permit simultaneous operation of all circuits without interference or loss of signals.
8. Conduit shall not enter the fire alarm control panel, or any other remotely mounted control panel equipment or backboxes, except where conduit entry is specified by the FACP manufacturer.
9. Conduit shall be 3/4 inch (19.1 mm) minimum.

4.4 PENETRATIONS

A. Fire Resistance Rated Penetrations:
1. Where Fire alarm System conduit penetrates a fire resistance rated wall or floor assembly, the Fire alarm System Contractor shall provide a fire rated penetration that maintains the integrity and fire resistance rating of the assembly being penetrated.

2. The fire resistance rated penetrations of walls or floor assemblies shall consist of one of the following:
    a. Cabling in Conduit: Fire alarm System cabling installed in conduit shall be provided with sealant between the conduit and the wall or floor penetration
    b. Exposed Cabling: Fire alarm System cabling installed exposed shall be provide with a section of conduit (sleeve) that extends past both faces of the penetration by a minimum distance of 6". Seal both ends of conduit (sleeve) with U.L listed approved material and sealant that maintains the fire resistance rating of the assembly being penetrated. Provide fire resistance rated sealant to both sides of assembly penetration between the conduit (sleeve) and the wall or floor assembly.
    c. Exposed Cabling: Fire alarm System cabling installed exposed shall be provide with a fire resistance rated grommet that maintains the fire resistance rating of the assembly being penetrated, such as those manufactured by Specified Technologies Incorporated (STI). The grommet shall slipover the cabling and snap together to form a round grommet that can slide into the penetration. A separate grommet shall be required for each side of the assembly.

B. Non-Fire Resistance Rated Penetrations:
1. The Non-fire resistance rated penetrations of walls or floor assemblies shall consist of one of the following:
    a. Cabling in Conduit: Fire alarm System cabling installed in conduit shall not require additional sealant between the conduit and the wall or floor penetration
    b. Exposed Cabling: Fire alarm System cabling installed exposed shall be provide with a section of conduit (sleeve) that extends past both faces of the penetration by a minimum distance of 6". Additional Sealant shall not be required.
    c. Exposed Cabling: Fire alarm System cabling installed exposed shall be provide with a Non-fire resistance rated grommet, such as those manufactured by Specified Technologies Incorporated (STI). The grommet shall slipover the cabling and snap together to form a round grommet that can slide into the penetration. A separate grommet shall be required for each side of the assembly.

C. Smoke Barrier/Partition Penetrations:
1. Where Fire alarm System conduit penetrates a smoke barrier/partition wall or floor assembly, the Fire alarm System Contractor shall provide a smoke barrier/partition penetration that prevents the passage of smoke through the assembly being penetrated.
2. Smoke barrier/partition penetrations of walls or floor assemblies shall consist of one of the following:
    a. Cabling in Conduit: Fire alarm System cabling installed in conduit shall be provided with sealant between the conduit and the wall or floor penetration
    b. Exposed Cabling: Fire alarm System cabling installed exposed shall be provide with a section of conduit (sleeve) that extends past both faces of the penetration by a minimum distance of 6". Seal both ends of conduit (sleeve) with U.L listed approved material and sealant that prevents the passage of smoke. Provide sealant between the conduit (sleeve) and the wall or floor assembly on both sides of assembly penetration.
    c. Exposed Cabling: Fire alarm System cabling installed exposed shall be provide with a Non-fire resistance rated grommet, such as those manufactured by Specified Technologies Incorporated (STI). The grommet shall slipover the cabling and snap together to form a round grommet that can slide into the penetration. A separate grommet shall be required for each side of the penetration.

D. All firestop systems shall be installed in accordance with the manufacturer’s recommendations and shall be completely installed and available for inspection by the local authorities prior to cabling system acceptance.

E. The Fire alarm System drawings do not specifically identify penetrations through walls, floors, platforms, and foundations.

F. The Fire alarm System Contractor shall review drawings to determine penetration locations.

G. All penetrations through walls, floors, platforms, and foundations are the responsibility of the Fire alarm System Contractor.

H. All penetrations shall have red ¾" wide bands within 1'-0" of each side of the wall/floor being penetrated.

4.5 ADDITIONAL FIELD DEVICES AND INSTALLATION LABOR

A. In order to minimize the schedule and cost impact of implementing minor changes during the course of construction, the following list of material and installation labor shall be included in this scope of work. The contractor shall include in his bid the listed materials, labor that is based on existing jobsite conditions and established construction standards, and all fees associated with documenting and executing these changes. The locations of additional field devices shall be as directed by the Engineer or Architect.

B. The material included but is not limited to for each school:

QTY	ITEM
4	Photo Electric Smoke Detector/Bases
2	Heat Detectors
1	Manual Pull Stations
4	Horn/Strobe Units
20	Device Boxes
20	4S J-boxes with blank covers
500 LF	½" EMT with 4-#14 THHN wire (includes couplers, straps, connectors, etc.)
20 Hrs.	Labor for Journeyman Electrician
1 Lot	Miscellaneous fees, tools, material, handling, O H & P

4.6 OPERATION AND MAINTENANCE MANUALS

A. Bind Operation & Maintenance Manual for the Fire alarm System in a single hard-backed binder. Spine of each binder shall have following typewritten lettering inserted:

OPERATION
AND
MAINTENANCE
MANUAL
FIRE ALARM SYSTEM

B. Operation and Maintenance Binders:
1. Binders shall be commercial quality, and shall have (3) D-style rings.
2. Binders shall have durable plastic covers with clear pockets on the cover and spine to hold labels.
3. Binders shall have a 1 inch minimum and 3 inch maximum ring size.
4. Binders shall not be filled more than 2/3 of its capacity to accommodate future revisions.
5. Where two or more binders are necessary to accommodate data, correlate data in each binder into related groupings according to the project manual table of contents. Cross-reference other binders where necessary to provide essential information for proper operations and maintenance of each piece of equipment.

C. Operation and Maintenance manuals shall contain the following:
   1. Cover: Identify each binder with a typed or printed title.
   2. Project Directory: Name, address, and phone number of Architect, General Contractor, and Electrical Subcontractors. Also include complete list of equipment installed with name, address, and phone number of each vendor.
   3. Table of Contents: List every item separated by a divider, using the same identification as on the divider tab.
   4. Dividers: Provide heavy paper dividers with printed tabs for each section. Immediately following the divider tab include a description of product.
   5. Typewritten Operation and Maintenance instructions.
   6. Complete replacement parts lists.
   7. Manufacturer's equipment submittal literature for all components used in the system.
   8. Typewritten "Sequence of Operations".
   9. Thorough testing procedures.
   10. Recommended testing frequency for each item.
   11. Acceptance Test Certificates.
   12. Copy of as-built drawings.
      a. Where oversized drawings are necessary, fold drawings to the same size as text pages and use as foldout.
      b. If drawings are too large to be used practically as a foldout, place the drawing neatly folded in the front or rear pocket of the binder. Insert a typewritten page indicating drawing title, description of contents and drawing location in the appropriate location in the manual.
   13. Warranties: Provide a copy of each warranty in the appropriate manual. Provide written data outlining the procedures to follow in the event of product failure.
   14. Electronic copy of the final system program software. (USB Drive / CD)

D. Submit copies as specified by Division 1, and at a minimum, provide **three (3) copies** of Operation & Maintenance Manual to Architect and Engineer to review prior to scheduling the training session.

E. Operation and Maintenance manuals shall contain original color printed brochures supplied by manufacturers (Xerox black and white copies of originals will not be accepted).

F. The information included must be the exact equipment installed not the complete "line" of the manufacturer. Where sheets show the equipment installed and other equipment, the installed equipment shall be neatly and clearly identified on such sheets.

4.7 AUTOMATIC DETECTORS

A. Locate detectors not less than two (2) feet from a supply or exhaust ventilation grille.

4.8 DEVICE LOCATIONS

A. Device locations may be changed within 15 feet without extra charge, if so desired by the Engineer, before installation.

4.9 AS-BUILT DOCUMENTATION

A. Three sets of as-built drawings shall be provided by the Electrical Contractor to the Architect which clearly indicates:
   1. Actual routing of all raceways.
   2. Actual cable type, numbers, and routing.

3. Actual system wiring diagrams, connection diagrams, and interface of all components in the system.
4. Actual room number and programming addressed assigned for all components in the system.

B. The Contractor shall include in the maintenance manuals the following as a minimum:
1. Reduced copy (11”x17”) of record drawings.
2. Cuts on all equipment and components.
3. Complete wiring diagram of system including internal workings of main panel and annunciators.
4. Acceptance test certification.

C. Following the completion of final system programming, the systems contractor shall provide to the Engineer, a hard copy printout of the final system program software or "point status report". A hard copy of the "system report" which documents the status of all active devices in the system shall also be provided.

D. Note: The room numbering system depicted in all graphics and referenced in data bases generated by the system contractor shall match that of the final signage and room identification system adopted by the Owner, unless specifically approved in writing otherwise, by the Engineer.

4.10 MOUNTING HEIGHTS AND LOCATIONS

A. Fire Alarm Control Panel (FACP):
1. The Fire alarm Control Panel shall be installed in the location indicated on the contract documents.
2. The Fire alarms Control Panel shall be flush mounted when located in finished areas and may be surface mounted when located in unfinished areas.
3. The top of the Fire alarms Control Panel shall be located 60" above the finished floor, unless noted otherwise and shall be installed level.

B. Fire Alarm Remote Annunciator Panel (FARAP):
1. The Fire Alarm Remote Annunciator Panel(s) shall be flush mounted when located in finished areas and may be surface mounted when located in unfinished areas.
2. The top of the Fire Alarm Remote Annunciator Panel(s) (FARAP) shall be located 48" above the finished floor, unless noted otherwise and shall be installed level.
3. The Fire Alarm Remote Annunciator Panel (FARAP) shall be located where indicated on the Contract Documents.

C. Graphics Maps:
1. Provide a graphical representation of the floor plan(s) for all structures directly adjacent to the Fire alarms Control Panel (FACP) on the opposite side of the enclosure hinge.
2. Provide a graphical representation of the floor plan(s) for all structures directly adjacent to the Fire Alarm Remote Annunciator Panel (FARAP) on the opposite side of the enclosure hinge.
3. Leave 4" to 6" of wall space between the Graphic Map and the Fire alarms Control Panel (FACP).
4. Leave 4" to 6" of wall space between the Graphic Map and the Fire Alarm Remote Annunciator Panel (FARAP).
5. The top of the Graphic Map shall be located 60" above the finished floor, unless noted otherwise.
6. The top of the Graphic Map shall be level.

7. Prior to mounting, insure the appropriate "You Are Here" location on the Graphic is installed in the correct location, in reference to the room or area of the building that it is being mounted at.
8. Use the Manufacturer provided mounting hardware and install per Manufacturer's recommendations.

D. Initiating Devices:
1. See "Fire Alarm Legend" on the Contract Documents.

E. Notification:
1. See "Fire Alarm Legend" on the Contract Documents.

4.11 WARRANTY

A. All components, parts, and assemblies supplied by the manufacturer shall be guaranteed against defects in materials and workmanship for a period on 12 months. Warranty service shall be provided by a trained specialist of the equipment manufacturer. The specialist shall be based in a fully staffed office located within a reasonable distance from the job site. Contractor shall replace or repair defects in material or workmanship for a period of 12 months after the certification of final acceptance.

4.12 FORMAL TESTS AND INSPECTIONS

A. Do not submit a request for formal test and inspection until the preliminary test (including audibility and intelligibility testing results) are completed and corrections are made and approved.

B. Submit a written request to local fire protection authority for formal inspection at least 14 days before the inspection date.

C. An experienced technician regularly employed by the system installer shall be present during the inspection.

D. At this inspection, repeat any or all of the required tests as directed.

E. Correct defects in work provided by the Contractor and perform additional system tests until the system complies with current code and the contract requirements.

F. Furnish appliances, equipment, electricity, instruments, connecting devices and personnel for the tests.

G. Furnish Architect with three (3) copies of test certificates required by testing agencies.

4.13 FIRE ALARM SYSTEM TESTING

A. Upon completion on the system installation, the Fire alarm System Contractor shall conduct a system test for the Owner, Architect, Engineer, and Authority Having Jurisdiction (for those who wish to attend) to verify operation of the system.

B. This system test shall be conducted by a factory trained technician.

C. The Fire alarm System Contractor shall provide a minimum of (2), two-way communication devices for the system test.

D. The Fire alarm System Contractor shall completely fill out all applicable documents contained Section 7.8 "Forms" in the 2013 Edition of N.F.P.A. #72.

E. If the Fire alarm System Contractor fails the Authority Having Jurisdiction system test and inspection, the following shall occur:
1. The Fire alarm System Contractor shall make all of the necessary corrections as required, to pass the Authority Having Jurisdiction testing and inspection.
2. Notify the Authority Having Jurisdiction and schedule another test.
3. Pay all associated fees for additional site visits made by the Authority Having Jurisdiction.
4. Continue making corrections until the Fire alarm System has been accepted by the Authority Having Jurisdiction.

F. After acceptance of the system testing, the Fire alarm System Contractor shall submit a copy of approved test certificates with Authority Having Jurisdiction signature

4.14 TESTING REQUIREMENTS

A. Fire alarm Control Panel testing shall include, but is not limited to the following:
1. Verify Control Panel LED's.
2. Verify Control Panel Display.
3. Verify Control Panel Piezo-electric audible device operates.
4. Verify "Alarm" Condition at the Control Panel.
5. Verify "Trouble" Condition at the Control Panel.
6. Verify "Supervisory" Condition at the Control Panel.
7. Verify "Alarm Silence" Switch at the Control Panel.
8. Verify "Queue Switch" at the Control Panel.
9. Verify "Reset Switch" at the Control Panel.
10. Verify AC Power Failure at the Control Panel.
11. Verify Battery Trouble at the Control Panel.
12. Verify Battery Charger Output at the Control Panel.
13. Verify Battery Back-up "Draw Down" Test at the Control Panel.
14. Verify Ground Fault Condition at the Control Panel.
15. Verify Open Circuit condition at the Control Panel.
16. Verify Short Circuit condition at the Control Panel.
17. Verify Addresses match the address and location of all field devices at the Control Panel.
18. Verify Remote Annunciator Panel LED's.
19. Verify Remote Annunciator Panel Display.
20. Verify Remote Annunciator Panel Piezo-electric audible device operates.
21. Verify "Alarm" Condition at the Remote Annunciator Panel.
22. Verify "Trouble" Condition at the Remote Annunciator Panel.
23. Verify "Supervisory" Condition at the Remote Annunciator Panel.
24. Verify "Alarm Silence" Switch at the Remote Annunciator Panel.
25. Verify "Queue Switch" at the Remote Annunciator Panel.
26. Verify Remote Annunciator Panel display matches the display at the Fire alarm System Control Panel.

B. Fire alarm System Power Supply testing shall include, but is not limited to the following:
1. Verify AC Power Failure at the Power Supply.
2. Verify Battery Trouble at the Power Supply.
3. Verify Battery Charger Output at the Power Supply.
4. Verify Battery Back-up "Draw Down" Test at the Power Supply.
5. Verify Ground Fault at the Power Supply.
6. Verify Open Circuit at the Power Supply.
7. Verify Short Circuit at the Power Supply.

C. Fire alarm System Initiating Device testing shall include, but is not limited to the following:
   1. Verify activation of all Manual Pull Stations initiates an "Alarm" condition at the Fire alarm System Control Panel.
   2. Verify activation of all System Smoke Detectors initiate an "Alarm" condition at the Fire alarm System Control Panel.
   3. Verify activation of all System Heat Detectors initiates an "Alarm" condition at the Fire alarm System Control Panel.
   4. Verify activation of all Dwelling Unit Smoke Detectors initiate a "Supervisory" condition at the Fire alarm System Control Panel.
   5. Verify activation of all System Carbon Monoxide Detectors initiates an "Alarm" condition at the Fire alarm System Control Panel.
   6. Verify activation of all Dwelling Unit Carbon Monoxide Detectors initiates all Low Frequency Sounders within the Dwelling Unit only.

D. Fire alarm System Notification Appliance testing shall include, but is not limited to the following:
   1. Verify that all Strobes are operational and synchronized.
   2. Verify that all Horns are operational and synchronized.

E. Fire Protection System Connections testing shall include, but is not limited to the following:
   1. Verify opening of each normally closed sprinkler system control valve initiates a "Supervisory" condition at the Fire alarm System Control Panel.
   2. Verify closing of each normally open sprinkler system control valve initiates a "Supervisory" condition at the Fire alarm System Control Panel.
   3. Verify activation of all sprinkler system water flow switches initiate an "Alarm" condition at the Fire alarm System Control Panel.
   4. Verify sprinkler system electric bell actuation is less than 60 seconds from the time that each inspector’s test valve is opened.

F. Initiating Device Circuits (IDC), Signaling Line Circuit (SLC), and Notification Appliance Circuit (NAC) cable testing shall include, but is not limited to the following:
   1. Loop Resistance test.
   2. Verify Open Circuit condition on Negative Leg of all circuits.
   3. Verify Open Circuit condition on Positive Leg of all circuits.
   4. Verify Open Circuit Ground condition on Negative Leg of all circuits.
   5. Verify Open Circuit Ground condition on Positive Leg of all circuits.
   6. Verify Open Circuit Cable-to-Cable Short condition in all circuits.
   7. Verify Closed Circuit Ground Fault condition in all circuits.
   8. Verify Closed Circuit Cable-to-Cable Short condition in all circuits.
   9. Verify Closed Circuit Cable-to-Cable Short and Ground condition on Negative Leg of all circuits.
   10. Verify Closed Circuit Cable-to-Cable Short and Ground condition on Positive Leg of all circuits.
   11. Verify Circuit Voltage of each circuit at maximum system operation.
   12. Verify Current Draw of each circuit at maximum system operation.
   13. Verify Class "B" wiring in all circuits.

4.15 AUDIBILITY REQUIREMENTS

A. The fire alarms system contractor shall perform audibility testing in each space of the building prior to acceptance testing.

B. Decibel readings shall be taken at a point 10'-0" from the appliance at an elevation of 5'-0" above finished floor.

C. The sound level shall meet both of the following requirements:
   1. A minimum of 15 decibels (dBs) above the average ambient sound level.
   2. A minimum of 5 decibels (dBs) above the maximum sound level having a minimum duration of 60 seconds.

D. Decibel measurements shall be taken using the "A-weighted" measurements which are relatively flat from 600 Hz to 7,000 Hz, "B-weighted" (relatively flat from 300 Hz to 4,000 Hz) and "C-weighted" (relatively flat from 700 Hz to 4,000 Hz, measurements will not be acceptable.

4.16 INSTRUCTION AND TRAINING PERIOD

A. Upon completion of the work and after all tests and inspections by the authority(s) having jurisdiction, the Fire alarms system contractor shall "Hands On" demonstrate and train the Owner's designated operation and maintenance personnel in the operation and maintenance of the Fire alarms system.

B. The Fire alarms System Contractor shall submit Operations and Maintenance Manuals to the Owner and Engineer to review prior to scheduling the instruction session.

C. The Fire alarms System Contractor shall provide a typewritten "Sequence of Operations."
   1. The sequence shall be simplified steps to operate the basic functions of the Fire alarms System.
   2. The sequence shall be laminated and attached, in clear view, to either the FACP or the adjacent wall.

D. The Fire alarms System contractor shall arrange scheduled instruction periods with the Owner’s designated operation and maintenance personnel.

E. The Fire alarms Contractor shall provide for (1) editing session of the control panel programming at no cost to the Owner to address any changes required by the Owner.

F. Scheduled training periods shall be based upon complexity of the system installed, but in no case be less than 4 hours.

G. Upon request of the Owner, a Power Point presentation of the training period shall be made available by the Fire Alarm System Contractor at no additional cost to the Owner.

END OF SECTION 283176

SECTION 312300 – EXCAVATING, BACKFILLING, AND COMPACTING FOR UTILITIES AND STRUCTURES

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. Excavating, backfilling, and compacting for utilities, including pipe, structures, and appurtenances.

B. Control of water in trenches.

C. Foundation stabilization for pipe and utility structures.

D. Pipe bedding for pipe and utility structures.

1.2 RELATED REQUIREMENTS

A. Section 312500 – Erosion and Sedimentation Control

B. Section 331100 – Water Distribution

C. Section 334000 – Storm Drainage

1.3 REFERENCE STANDARDS

A. WSDOT Standard Specifications – Washington State Department of Transportation 2016 Standard Specifications for Road, Bridge, and Municipal Construction.

B. City of Federal Way, Public Works Department Development Standards, current edition.

C. Lakehaven Utility District Water System Design Standards and Material/Construction Specifications (2012).

D. ASTM D 6913 – Test Methods for Particle-Size Distribution (Gradation) of Soils Using Sieve Analysis.

E. ANSI/ASTM D1557 – Test Methods for Laboratory Compaction Characteristics of Soil using Modified Effort.

F. ASTM C94-86 – Ready-Mixed Concrete.

G. AASHTO T176 – Plastic Fines in Graded Aggregates and Soils by use of the Sand Equivalent Test.

H. ASTM D6938 – Test Methods for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth).

1.4 UTILITIES AND STRUCTURES DEFINITIONS

A. Unsuitable Material: Soil, organics, waste, or other material not complying with these specifications, not capable of supporting foundations, or not capable of compaction to specified density. Old fill soils and buried top soils are unsuitable.

B. Pothole: An exploratory excavation to uncover a buried utility and determine location, elevation, size, and type of material.

1.5 SUBMITTALS

A. General: Comply with Section 013000.

B. Samples: Submit minimum 50-pound sample for each material four business days prior to placing material.

C. Quality Assurance/Control Submittals:

1. Test Reports: Sieve analysis for each material.
2. Certification:

    a. WSDOT pit certification for each pit.
    b. Disposal site operator certification that disposal site complies with all local, state, and federal regulations.

1.6 QUALITY ASSURANCE

A. Qualifications.

1. Surveyor: Land surveyor licensed in state of Washington with experience on similar projects.
2. Construction Crew Foreman: Minimum six years' working experience and four years' experience as foreman performing similar work.

B. Regulatory Requirements:

1. All Work and material shall be in accordance with WSDOT Standard Specifications.
2. Comply with Lakehaven Utility District standards.

PART 2 - PRODUCTS

2.1 AGGREGATE MATERIALS

A. Bedding Material for Pipe: WSDOT Standard Specification Section 9-03.12(3), Gravel Backfill for Pipe Zone Bedding.

B. Foundation Material: WSDOT Standard Specifications Section 9-03.17, Class A.

C. Drain Rock for Subdrainge System: Gravel backfill for drains in accordance with WSDOT Standard Specification Section 9-03.12(4).

D. Structural Fill: Crushed, partially crushed, or naturally occurring granular material. Free from wood waste, organics, and other extraneous or unsuitable material, in accordance with WSDOT Standard Specifications Section 9-03.14(1), Gravel Borrow. Restrict fines content to no more than 5 percent passing Number 200 sieve. On-site material is not suitable for use as structural fill.

E. Trench Backfill: WSDOT Standard Specifications Section 9-03.9(3), Crushed Surfacing Top Course (CSTC).

2.2 UTILITIES AND STRUCTURES SOURCE QUALITY CONTROL

A. Tests and Inspection: Provide sieve analysis in accordance with ASTM D422 for each material type. Perform tests and analyses of aggregate material in accordance with WSDOT Standard Specifications. If tests indicate materials do not meet specified requirements, change material and retest.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Site Verification of Conditions: Verify as follows:

1. Verify survey benchmark and intended elevations for the Work are as indicated.
2. Verify erosion control is in place and operating properly.
3. Verify locations and elevations of existing pipes and structures at points of connection and at crossings prior to beginning Work. Pothole, expose pipes, determine invert elevations, verify with design, and inform Architect of deviations affecting design prior to mobilizing crews and beginning construction.
4. Verify location and elevation of proposed building plumbing stub out prior to beginning Work.

3.2 PREPARATION

A. Protection:

1. The majority of underground utilities will not be located through “Dial Dig.” Contractor shall provide work through utility locate company or perform Work. Call “Dial Dig” 1-800-424-5555, 48 hours (two working days) prior to beginning construction. Employ and pay for a locator service to locate and mark utilities in addition to the "DIAL DIG" service.
2. Protect and maintain existing utilities which are to remain.
3. Identify existing structural foundations near excavations. Verify excavation will not undermine footings or supports and cause damage to structures.
4. Protect plant life, lawns, trees, and other features remaining as a portion of final landscaping or preserved for erosion control.
5. Protect benchmarks, existing structures, rockeries, sidewalks, railings, paving, and curbs.
6. Protect existing structures scheduled to be demolished but occupied by the Owner.
7. Protect pavement or paved areas intended to remain from damage.
8. Use all means necessary to prevent the erosion of freshly graded areas during construction or until such a time that permanent drainage and erosion control measures are fully operational.

3.3 CONSTRUCTION

A. Grade and Alignment:

1. Identify and set required lines, levels, contours, and datum.
2. Stake alignment and grade and construct in locations shown on Drawings.
3. Comply with City of Federal Way requirements for water, sewer, and power.
4. Establish extent of excavation by area and elevation.
5. Adjust alignment and grade to accommodate conflicts and field conditions. Obtain Architect’s approval prior to adjustments.

B. Utilities And Structures, Shoring and Bracing of Excavation:

1. Provide sheeting, shoring, and bracing in accordance with state and local codes.
2. Do not use horizontal strutting below pipe barrel.
3. Do not use pipe as support for trench bracing.
4. Do not remove shoring below top of pipe.
5. Backfill immediately following removal of shoring and bracing.
6. Support adjacent structures, including utilities and pipe chases, which may be damaged by excavation Work.

C. General Excavation:

1. Perform excavation of every description and whatever substance encountered to depths, lines, and grades indicated.

2. Pile trench excavated material so surface water is prevented from flowing into excavation, and there is minimum inconvenience to Owner's access to the buildings. Provide free access to fire hydrants, water valves, meters and driveways and leave clearance to enable free flow of storm water in gutters, conduits, and natural water courses.
3. Remove and reconstruct utilities as required to perform Work.
4. Do not interfere with or excavate within pressure prism of foundations. Pressure prism is defined as a 1 horizontal to 1 vertical line projected from footing bottom.
5. Prevent movement of soil in areas supporting existing foundations, slabs, poles, underground utilities, trees, pipelines, or other structures.
6. Hand trim excavation and leave free of loose matter.
7. Correct unauthorized excavation at no cost to Owner.
8. Schedule Work to include backfilling trenches by the completion of each shift.

D. Trench Excavation:

1. Unless otherwise indicated, open cut excavations.
2. Exercise caution in operating heavy equipment over pipelines. Do not damage existing improvements.
3. Immediately repair leaks or breaks caused by construction operations at no cost to Owner and in a manner acceptable to Architect and utility owner.
4. Control side walls of excavation to minimize caving.
5. In the event the maximum allowable trench width is exceeded and depending on depth of trench, improve pipe bedding by utilizing concrete or other bedding materials as directed by Architect.
6. Excavate trench bottom to lines and grades shown with proper allowance for pipe thickness and pipe bedding. Do not permit material containing rocks or cobbles larger than 2 inches in maximum dimension within 6 inches of pipe. Remove material of this type from trench bottom and replace with foundation gravel.
7. Should excavation be carried below lines and grades as shown because of trenching operations, backfill such excavated space to proper elevation as directed by Artchitect, at no cost to Owner.

E. Control of Water:

1. Keep excavation free from water. Dewater as necessary.
2. Direct drainage away from excavation.
3. Grade top perimeter of excavation to prevent surface water from draining into excavation.
4. Direct runoff and water from dewatering into sedimentation filtration. Provide additional filtration necessary to prevent silt-laden water from leaving the site.

F. Pipe Bedding:

1. Place bedding on approved trench bottom before pipe is installed. Spread smoothly to support pipe uniformly. Do not use blocking to adjust pipe to grade. Dig holes for bells as required to ensure uniform support along pipe barrel.
2. Compact bedding as follows: Compact bedding to at least 95 percent maximum density as determined by ASTM D1557 under buildings, structures, and 6 feet

outside and within paved areas and sidewalks. Compact bedding in other areas to at least 90 percent maximum density as determined by ASTM D1557.

G. Backfilling and Compaction:

1. Backfill to grades, contours, levels, and elevations shown on Contract Drawings with structural fill or Trench Backfill. On-site material is not suitable for use as structural fill and Trench Backfill.
2. Backfill systematically, as early as possible, to allow maximum time for natural settlement. Do not backfill over porous, wet, frozen, or spongy subgrade surfaces.
3. Place and compact backfill materials in continuous layers not exceeding 8 inches in compacted thickness.
4. Employ a placement method that does not disturb or damage utilities in trenches.
5. Condition backfill within plus or minus 3 percent of its optimum moisture content so specified compaction can be attained readily. Material containing excessive moisture, beyond moisture content for specified density as determined by laboratory compaction tests, shall not be used for backfill.
6. Raise backfill around structures evenly.
7. Finish area to uniform contour to drain properly and grade entire surface to a neat appearing surface.
8. Remove excavated on-site soil material and surplus fill material from the site to an approved contractor-provided off-site waste site.

H. Compaction:

1. Under pavements, curbs, curbs and gutters, sidewalks, and other structural improvements: 95 percent, within 2 foot vertical of finish grade and 90 percent below this level in accordance with ASTM D1557. Compact pavement bases in accordance with Section 32 13 13.
2. Use hand-operated equipment within 6 feet of building walls.
3. Compact backfill material by towed or self-propelled mechanical compactors in uniform layers not exceeding 10 inches in loose depth.

I. Initial Backfill:

1. After pipe has been laid properly and inspected, place and compact initial backfill around pipe to a minimum depth of 8 inches over top of pipe. Place initial backfill in lifts of not more than 10 inches in compacted thickness. Bring lifts together on both sides of pipe and carefully work backfill under pipe haunches by means of a shovel, vibration, or procedures approved by Architect. Take necessary precautions to protect pipe from any damage or shifting.
2. Subsequent Backfill: Place and compact subsequent backfill material after initial backfill has been placed and approved by Architect.
3. Perform compaction within 2 feet of existing or new structures by hand-operated vibratory compactors. Compact within 6 feet of wall to 95 percent maximum density as determined by ASTM D 1557.
4. Reopen trenches where settlement occurs to depths necessary for compaction; refill and compact with surface restored to grade.
5. Water settling or water jetting will not be allowed.

3.4 RESTORATION

A. Restore disturbed pavement and improvements to remain in operation.

3.5 FIELD QUALITY CONTROL

A. Obtain required inspections, tests, approvals, and location recording prior to covering or enclosing Work.

B. Site Tests:

1. Comply with City of Federal Way requirements.
2. Comply with Lakehaven Utility District requirements.
3. Comply with Section 014000.
4. Compaction test performed by Owner.

C. Inspection:

1. Comply with Section 014000.
2. Comply with City of Federal Way and Lakehaven Utility District requirements.
3. After completion of trench and prior to placing pipe.
4. After completion of pipe and bedding, and prior to backfilling.

3.6 PROTECTION

A. Protect bottom of excavations and soil adjacent to and beneath foundations from freezing.

B. Protect excavated material and excavating foundation (subgrade) from damage due to excess moisture.

C. Take necessary precautions to protect soil from excess moisture by such means necessary, including: Construct ditches and swales to intercept surface water; cover stockpiled material; cover exposed trenches; do not expose more area than can be worked and protected; and dewater by pumping.

3.7 CLEANUP

A. Dispose of all excavated surplus or unsuitable material at a Contractor provided off-site location approved by the Owner.

B. Remove and dispose of abandoned pipe, broken pavement, and rubbish from Project site in accordance with laws, regulations, and ordinances of an approved off-site location provided by Contractor.

C. Dispose of waste, surplus, and unsuitable materials according to laws, regulations, and ordinances.

END OF SECTION 312300

SECTION 312500 – EROSION AND SEDIMENTATION CONTROL

PART 1 - GENERAL

1.1 Related documents

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to this section.

1.2 SUMMARY

A. Work in this section includes:

1. Silt control measures.
2. Measures to keep streets clean.
3. Polyethylene (PE) sheeting cover for exposed soil.
4. Maintaining, monitoring, and supplementing silt control and stormwater runoff control measures.
5. Dewatering.

B. Related sections include the following:

1. Section 312300 – Excavating, Backfilling, and Compacting for Utilities and Structures
2. Section 334000 – Storm Drainage

1.3 REFERENCES

A. Comply with applicable provisions of the following specifications and documents:

1. WSDOT Standard Specifications – Washington State Department of Transportation 2016 Standard Specifications for Road, Bridge, and Municipal Construction.
2. City of Federal Way Public Works Department Development Standards, current edition.

1.4 SUBMITTALS

A. Product Submittals: Submit under provisions of Section 013000.

B. Disposing of Silty Water Off Site (Contractor's option to treatment train): Prior to performing site clearing or stripping, submit letter identifying equipment available for transport. List subcontractor, if used. List method of disposal.

1.5 REGULATORY REQUIREMENTS

A. All Work and material shall be in accordance with WSDOT Standard Specifications.

B. Comply with City of Federal Way standards.

1.6 SEQUENCING AND SCHEDULING

A. Install erosion control measures in work areas prior to any clearing, grubbing, demolition, general site grading, or other construction in the area. Erosion control items shall be installed and removed at various times throughout the duration of the project.

1.7 MAINTENANCE

A. Maintain erosion control through the duration of the project.

B. Maintain erosion control after substantial completion in accordance with this section.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Filter Fabric Fence: WSDOT Standard Specifications Section 9-33, Table 6: Geotextile for temporary silt fence.

B. Compost sock (Silt Sock): WSDOT Standard Plan I-30.40-01.

C. Temporary Construction Fence:

1. Six-foot-high chain link fence, new or used, in good condition.
2. Woven galvanized steel wire mesh and steel post per ASTM A392-06 Standards.
3. Post shall be 2 feet deep in ground or secured by concrete blocks in paved areas.
4. Provide 20-foot-wide gate at construction entrance.

D. Orange Protective Fence: Minimum 3 feet tall, heavy plastic, with readily visible mesh, minimum mesh width 0.4 inches. Color: Safety orange.

E. Filter Bag Inserts: Commercially manufactured filter bags specifically manufactured for silt filtering and which will provide filtering performance required.

F. Polyethylene (PE) Sheeting: WSDOT Standard Specifications Section 9-14.5(3).

G. Quarry spalls: WSDOT Standard Specifications Section 9-13.6.

H. Storm Drain Pipe: Section 334000.

PART 3 - EXECUTION

3.1 PREPARATION

A. Locate existing utilities, avoid damage or disturbance. Call “Dial Dig 1-800-424-5555” 48 hours (two working days) before beginning construction. Employ and pay for a locator service to locate and mark utilities in addition to “DIAL DIG” service.

B. Survey limits of Work to install orange construction, chain link construction, and silt fences.

C. Protect plant life, lawns, and other features remaining as a portion of final landscaping or interim erosion control.

D. Protect benchmarks, horizontal control, existing structures, fences, paving, and curbs.

E. Perform clearing or other work required to installing erosion control.

F. Survey/layout sediment traps.

3.2 CONSTRUCTION

A. Filter Fabric Fence: Field adjust location to perimeter of clearing and stripping. Location shown on Drawings is schematic. Cast all trench excavation soils from fence installation to the Construction side of fence. Overlap filter fabric fence joints minimum 1 foot prior to backfilling trench.

B. Polyethylene Sheeting: Overlap joints minimum 28 inches. Overlap in direction of drainage and prevent water from draining onto material being protected. Secure in place to prevent movement and damage. Provide sandbags at 2.5 feet spacing and tie sand bags together with rope on slopes greater than 3:1. Minimize driving stakes through plastic.

C. Mulch: Mulch exposed soils not protected by other means. Provide continuous covering minimum depth 3 inches. Apply mulch with tackifier to prevent blowing.

D. Sediment Pond: Field adjust shape and location. Dewater, remove sediment, and back fill with structural fill after retirement.

3.3 ADJUSTMENTS AND REVISIONS

A. Adjust or move swales, berms, pipes, pumps, culverts, bales, and silt fences as necessary during construction.

3.4 PROTECTION AND MAINTENANCE

A. Protection:

1. Where possible, maintain natural vegetation for silt control.
2. Prevent silt-laden water from leaving site or from entering off-site storm sewer systems.
3. Stabilize slope, cut, or fill areas where Work is stopped for more than 30 days by mulching, polyethylene sheeting, or other method to prevent erosion and sediment transport.
4. Keep off-site parking areas, sidewalks and streets clean from construction activities. Keep paved surfaces clean using mechanical sweeping equipment, hand shovels, brooms, or other accepted methods suitable for removing dirt, rock, silt, and sand. No street washing will be allowed.

B. Supplementary Measures: Provide additional silt control and temporary erosion control measures required to protect soils and prevent silt-laden runoff from leaving project site.

C. Maintenance: Monitor and maintain silt control measures. Maintain temporary erosion control facilities until need for each facility is superseded by other stabilization methods or until Architect authorizes removal.

D. Inspect and repair temporary erosion control facilities. Inspect entire system to ensure proper operation a minimum of once each week, during and after storms, and prior to weekends and holidays.

END OF SECTION 312500

SECTION 321313 – ASPHALT PAVING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to this section.

1.2 SUMMARY

A. Work in this section includes:

1. Pavement removal.
2. Pavement patching.
3. Soil sterilization.
4. Aggregate base course.
5. Asphalt concrete paving.
6. Pavement marking.

B. Related sections include the following:

1. Section 312300 – Excavating, Backfilling, and Compacting for Utilities and Structures
2. Section 312500 – Erosion and Sedimentation Control
3. Section 321300 – Cement Concrete Pavement

1.3 REFERENCES

A. WSDOT Standard Specifications – Washington State Department of Transportation 2016 Standard Specifications for Road, Bridge, and Municipal Construction.

B. City of Federal Way, Public Works Department Development Standards, current edition.

C. ANSI/ASTM D 1557-91 – Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2,700 kN-m/m3).

D. ASTM D2922-91 – Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods - (Shallow Depth).

E. ASTM D3017-88 – Test Method for Moisture Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth).

F. ASTM D1556-90 – Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method.

G. ASTM D2950 – Density of Bituminous Concrete in Place by Nuclear Method.

H. MUTCD – Manual on Uniform Traffic Control Devices for Streets and Highways, current edition.

1.4 SUBMITTALS

A. Comply with Section 013000.

B. Product Data: Soil residual herbicide, including hazardous waste data sheet.

C. Quality Assurance/Control Submittals: Certificates – tack coat, asphalt concrete mix. Certificate stating material complies with specifications and documentation material is approved by WSDOT.

1.5 QUALITY ASSURANCE

A. Qualifications: Paving contractor and crew foreman shall have minimum three years' experience with paving projects of this type. Submit list of projects for three years' experience. Note date, owner, type, and size of overlay and location.

B. Pre-Installation Meeting:

1. Coordinate and attend meeting prior to paving and preparation.
2. Attendees to include paving contractor, Owner, and Architect.
3. Agenda to include sequencing of Work, schedule, and responsibilities.

1.6 ENVIRONMENTAL REQUIREMENTS

A. Comply with Section 5-04.3 of WSDOT Standard Specifications.

B. Minimum air temperature for placing asphalt paving 55 degrees F and rising.

C. Do not perform paving in rain.

1.7 SEQUENCING AND SCHEDULE

A. Maintain access to public roads and sidewalks during construction.

B. Complete Work no later than indicated on the bid proposal.

C. Schedule and coordinate Work to maintain access to occupied buildings nearby.

PART 2 - PRODUCTS

2.1 SOIL RESIDUAL HERBICIDE

A. WSDOT Standard Specifications Section 5-04.3(5)D.

B. Use only products approved by Owner.

2.2 ASPHALT CONCRETE PAVEMENT

A. Hot Mix Asphalt: HMA Cl. 1/2-inch PG 58-22 or HMA Cl. 1/2-inch PG 64-22 as specified in Section 5-04 and Section 9-03 of the WSDOT Standard Specifications. Meet requirements for Asphalt Concrete Pavement (ACP). Class B modified asphalt pavement will be considered as a substitution request.

2.3 CRUSHED SURFACING TOP COURSE (CSTC)

A. WSDOT Standard Specifications Section 9-03.9(3).

2.4 CRUSHED SURFACING BASE COURSE (CSBC)

A. WSDOT Standard Specifications Section 9-03.9(3).

2.5 TACK COAT

A. Cationic emulsified asphalt in accordance with WSDOT Standard Specifications Section 9-02.1(6).

2.6 PAINT

A. Non-reflectorized traffic line paint in accordance with WSDOT Standard Specifications Section 8-22.

B. Color:

1. Striping: White.
2. Fire lane marking: Yellow.
3. Disabled parking symbol: White on blue background, in accordance with MUTCD.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify compacted subgrade is dry and ready to support paving and imposed loads.

B. Verify base gradients and elevations are correct.

C. Verify subsurface Work is completed and no further excavation will be required within limits of Work.

D. Verify demolition Work within or adjacent to the Work is complete.

E. Verify heavy construction traffic is as complete as possible and traffic remaining will not damage or degrade the Work.

F. Verify fire department has been advised of restrictions to site access during Work.

G. Verify weather forecast during planned time of placement is within weather limitations.

H. Verify door locations and required clearances for swing out over walkways.

3.2 PREPARATION

A. Prepare and compact subgrade in accordance with WSDOT Standard Specifications Section 2-06.

B. Water and thoroughly mix subgrade until optimum moisture content is obtained when deficiency of moisture content exists. When excess moisture exists, rework and aerate subgrade until optimum moisture content is obtained.

C. Condition existing surface in accordance with WSDOT Standard Specifications Section 5-04.3(5).

D. Adjust top of structures, manhole covers, valve boxes, grates, cleanout covers to grade. Comply with WSDOT Standards for structures.

E. Areas receiving new paving section: Excavate, remove, and dispose of excess material. Fine grade to maintain drainage and prepare subgrade.

F. Apply herbicide to subgrade in new pavement and patching areas.

3.3 CONSTRUCTION

A. Removal and Disposal of Existing Asphalt Paving: Saw cut at limits of removal with neat, straight lines. Dispose of material removed and waste to offsite disposal area approved by Architect.

B. Base Courses:

1. Place in accordance with WSDOT Standard Specifications Section 4-04.3.
2. Spread aggregate over prepared substrate to a total compacted thickness as indicated on Drawings.
3. Place aggregate in maximum 6-inch layers and compact to 95 percent in accordance with ASTM D1557.
4. Level and contour surfaces to elevations and gradients indicated on Drawings.
5. Add small quantities of fine aggregate to coarse aggregate as appropriate to assist compaction.
6. Add water as necessary to assist compaction. If excess water is apparent, remove aggregate and aerate to reduce moisture content.
7. Use mechanical tamping equipment in areas inaccessible to compaction equipment.

C. Soil Sterilization:

1. Apply Soil Residual Herbicide in accordance with WSDOT Standard Specifications Section 5-04.3(5)D.
2. Protect surrounding area from effects of soil sterilization.
3. Do not allow toxic material to run off onto adjacent vegetation or to storm system.

D. Asphalt Concrete Pavement:

1. Construct asphalt concrete pavement in accordance with the requirements of WSDOT Standard Specifications Section 5-04.
2. Before pavement is constructed, trim pavement cuts so marginal lines will form with straight edges and vertical faces.
3. Prepare subgrade in accordance with the requirements of WSDOT Standard Specifications Section 2-06.
4. Hand tamp in areas not accessible to rolling equipment.
5. Ensure joints made during paving operations are straight, clean, vertical, and free of broken or loose material.
6. Seal all contact joints between asphalt pavement joints, curbs, walls, and drains with tack coat.
7. Back tamp exposed edges to 45 degrees.
8. Establish smooth grades with minor cuts or fills. Maintain proper drainage and correct low spots that do not currently drain.
9. Compact crushed surfacing top course to 95 percent in accordance with ASTM D 1557.
10. Adjust utility structures and castings to finished grade.

11. Place asphalt pavement in accordance with this section.

E. Pavement Marking

1. Preparation:

a. Verify paving and curbing is complete and surface is ready to receive striping.
b. Verify distance between curbs to ensure adequate width for the indicated number of stalls.
c. Verify weather forecast during planned time of placement is within weather limitations.
d. Clean and prepare surface for receiving paint in accordance with WSDOT Standard Specifications Section 8-22.3(2).
e. Layout lines and symbols to spacing and locations shown on Drawings.

2. Painting: WSDOT Standard Specifications Section 8-22.3(3).
3. Handicap parking striping:

a. State and federal requirements.
b. Locations as shown on Drawings.

3.4 TOLERANCES

A. Abutting existing surfaces to be matched: within 1/8 inch.

B. Pavement areas: Generally smooth, free of depressions exceeding 3/8 inch in 10 feet. Minor deviations may be allowed if approved by Architect.

3.5 PROTECTION

A. Do not allow vehicular traffic on newly paved areas until surface has cooled to atmospheric temperature.

B. Protect surrounding area from effects of soil sterilization. Do not allow toxic material to run off onto adjacent vegetation or to storm system.

3.6 FIELD QUALITY CONTROL

A. Site Tests: Following tests will be performed by Architect.

1. Subgrade density prior to paving, Reference Section 014000.
2. Asphalt and Base Course density.
3. Compact asphalt paving in accordance with 2016 WSDOT Standard Specifications, minimum 91 percent for Rice or 95 percent for Marshall test.
4. If tests indicate Work does not meet specified requirements, Contractor shall remove Work, replace, and retest.

B. Inspection: Owner will observe the Work at the following milestones.

1. After completion of subgrade and before placing base course.
2. After placing base course and before placing asphalt.
3. After placing asphalt base and before placing additional lift of asphalt.

3.7 CLEANING

A. Clean surfaces within five days of substantial completion.

B. Dispose of all surplus, unsuitable, or waste materials according to laws, regulations, and ordinances at an approved offsite waste site obtained by Contractor.

END OF SECTION

SECTION 331100 – WATER DISTRIBUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to this section.

1.2 SUMMARY

A. Work in this section includes:

1. Pipe, fittings, valves, hydrants, and appurtenances.
2. Connection to existing water main.
3. Fire Department Connection (FDC).
4. Water meter, meter vault.
5. Double Detector Check Valve and Vault.
6. Water services for fire sprinkler.

B. Related Sections include the following:

1. Section 312300 – Excavating, Backfilling, and Compacting for Utilities and Structures

1.3 REFERENCES

A. Lakehaven Utility District Water System Design Standards and Material/Construction Specifications (2012).

B. WSDOT Standard Specifications – Washington State Department of Transportation 2016 Standard Specifications for Road, Bridge, and Municipal Construction.

C. ASTM A252 – Welded and Seamless Steel Pipe Piles.

D. AWWA C104 – Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water.

E. AWWA C105 – Polyethylene Encasement for Ductile - Iron Pipe Systems.

F. AWWA C111 – Rubber-Gasket Joints for Ductile-Iron and Gray-Iron Pressure Pipe and Fittings.

G. AWWA C151 – Ductile Iron Pipe.

H. AWWA C153 – Ductile-Iron Compact Fittings.

I. AWWA C509 – Resilient-Seated Gate Valves for Water Supply Service.

J. AWWA C550 – Protective Epoxy Interior Coatings for Valves and Hydrants.

K. AWWA C651 – Disinfecting Water Mains.

L. NFPA 24 – Installation of Private Fire Service Mains and their Appurtenances.

1.4 QUALITY ASSURANCE

A. Qualifications:

1. Surveyor: Land surveyor licensed in state of Washington with experience surveying underground utilities.
2. Crew Foreman: Minimum six years' working experience and four years' experience as foreman performing similar work.
3. Contractor performing work for Fire Protection Sprinkler System:

    a. Licensed as a Level U or Level 3 Fire Protection Sprinkler System Contractor by the State of Washington.
    b. Have at least one person on site during construction and testing of all fire protection sprinkler system elements with a Level U or Level 3 Certificate of Competency issued by the Washington State Patrol Fire Marshal's Office.

B. Pre-Installation Meetings:

1. Schedule, coordinate, attend, and lead pre-installation meeting.
2. Schedule and attend meeting prior to beginning work

1.5 SUBMITTALS

A. Comply with Section 013000.

B. Contractor provided Lakehaven Utility water permits.

C. Product Data: All products in this section.

1. Catalog cuts, shop drawings, and specifications for Double Detector Check Valve Assembly.

D. Operation and maintenance data for gate valves.

E. Certification: Certification of accuracy for test gage.

F. Fire Protection Sprinkler System Contractor Certification:

1. Copy of Fire Protection Sprinkler System Contractor license.

2. Copy of Certificate of Competency for person designated to be on site during fire protection sprinkler system construction.

G. Closeout Submittals: Record Drawings:

1. Record actual locations of piping mains, valves, connections, and invert elevations.
2. Record location of utilities and structures encountered and not shown or not in agreement with Drawings.
3. Record changes in soil conditions not noted on Drawings.
4. Prepare record drawings in accordance with Section 017200 and Lakehaven Utility District Requirements

1.6 REGULATORY REQUIREMENTS

A. Comply with Lakehaven Utility District requirements.

B. Comply with NFPA requirements.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Handle pipe, fittings, and specials to ensure delivery to site and final installation in undamaged condition. Do not damage pipe coating and lining. Keep pipe clean. Load and unload pipe and fittings using hoists in a manner to avoid shock or damage. Do not drop, skid, or roll pipe against other pipe. Repair any part of damaged coating or lining. Separate rejected pipe immediately from undamaged pipe. Remove damaged pipe from site within 24 hours.

1.8 SEQUENCING AND SCHEDULING

A. Notify Owner's Representative 72 hours prior to making connections to existing mains.

B. Notify Owner of service shutdown. Provide notification at least 48 hours prior to discontinuation of service, including estimated duration of shutdown.

C. Advise Fire Marshall and Owner's Representative of proposed water shut off that will affect hydrants, fire sprinkler systems, alarm systems, and other services.

D. Maintain water systems in areas of site to be occupied and remain in operation by Owner during construction.

PART 2 - PRODUCTS

2.1 GENERAL

A. Lakehaven Utility District Water System Design Standards and Material/Construction Specifications (2012).

B. WSDOT Standard Specifications, 2014.

C. “Reduction of Lead in Drinking Water Act.”

2.2 PIPE AND FITTINGS

A. Ductile Iron Pipe: Centrifugal cast in 18-foot nominal lengths conforming to AWWA C151; cement-mortar lined conforming to AWWA C104; bituminous exterior coating conforming to AWWA C151; Standard Thickness Class 52.

B. Non-restrained Joints: Rubber gasket, push-on type or mechanical joint (MJ) conforming to AWWA C111.

C. Restrained Joints: Lakehaven Utility standards; Series 1100 HD MEGALUG Harness, Series 1100 MEGALUG. Use same joint restraint for push-on joints throughout project. Use same joint restraint for mechanical joints throughout project.

D. Pipe Fittings: Ductile iron short body, conform to AWWA C153, cement mortar lined in accordance with AWWA C104. Mechanical joint pressure rating 350 psi, flange joint pressure rating 250 psi.

E. Flanged Fittings: Conform to ANSI B16.1, Class 125 drilling pattern, gasket neoprene or chlorinated butyl.

2.3 TRANSITION, REDUCING, AND FLEXIBLE COUPLINGS

A. Conform to Lakehaven Utility District Construction Standards. Determine existing pipe size and order transition coupling with proper dimensions.

B. Rockwell or Romac constructed with gray iron sleeves and ductile or malleable iron followers; ductile iron or electrogalvanized steel bolts and nuts; manufacturer’s standard factory finish.

2.4 VALVES AND APPURTENANCES

A. General: Provide 2-inch square AWWA standard operating nut direct buried valves. Furnish an extended stem within 2 feet of finished grade and a 1/4-inch thick steel

plate welded to stem as rock stop for direct buried valves with operating nuts installed 5 feet or more below finished grade.

B. Gate Valves, 2 inches and larger to 12 inches.

1. Seat: Resilient, wedge-type conforming to AWWA C509.
2. Stem: Non-rising with o-ring stem seals.
3. Joints: Mechanical or flange as noted on Drawings. Restrain joints where indicated on Drawings.
4. Opening Direction: Counterclockwise.
5. Pressure Rating: Service at 200 psig working and 400 psig test pressure.
6. Internal Coating: Iron surfaces and valve body with epoxy to AWWA C550.
7. Portion of gate exposed to line velocity: Rubber encapsulated, field replaceable, and with dual seal on mating body seal.
8. Installation: In any position with rated seating in both directions.
9. Marking: AWWA C 515, include name of manufacturer, year of manufacture, maximum working pressure, and valve size.

C. Valve Boxes: Cast iron, two-piece slip-type standard design with a base corresponding to size of valve, coat-tar painted by manufacturer using its standard coating; cast the word “WATER” in the cover; Rich 910 series.

2.5 POST INDICATOR VALVE

A. AWWA Standards.

B. Fire Department requirements.

C. Provide tamper switch.

D. UL/FM approved.

E. Lockable handle, heavy Plexiglas window with valve position indicator reading open or closed.

2.6 TAPPING SLEEVE

A. Cast or ductile iron body, full circle split sleeve type. Mueller.

B. Lakehaven Utility District Standards.

2.7 POLYETHYLENE FILM

A. AWWA C105.

2.8 CONCRETE

A. Type III cement, minimum compressive strength of 3,000 psi. Design mix to achieve strength prior to pressure testing.

2.9 FIRE DEPARTMENT CONNECTION (FDC)

A. Lakehaven Utility District Standards.

B. Cast Brass body, for free standing mounting on riser pipe. UL/FM approved, with clapper valve.

C. Hose connection: As shown on the Drawings. Comply with fire marshal’s requirements.

D. Pipe Connection: 4-inch-diameter, threaded for IPS.

E. Provide brass plate for mounting on riser pipe marked “AUTO SPRKR & STAND PIPE” and marked with name of building served.

F. Locking Plug: Provide a locking plug for each hose connection. Knox Locking Plug #3043, by Knox Company, (800) 552-5669.

2.10 DOUBLE DETECTOR CHECK VALVE ASSEMBLY

A. Double Detector Check Valve Assembly: Comply with Lakehaven Utility District Standard Detail B-19d.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Verify surfaces are ready to receive Work.

B. Verify grades are at subgrade elevation.

C. Verify erosion control is installed and functioning.

D. Verify field measurements are as shown on Drawings.

E. Verify location, size, and type of existing utilities at point of connection and at points of crossing other utilities. Pothole, expose pipes, determine invert elevations, verify with design, and inform Owner's Representative of deviations affecting design prior to mobilizing crews and beginning construction.

F. Verify and coordinate location and elevation of plumbing stub out and adjust locations to match.

3.2 PREPARATION

A. Obtain Lakehaven Utility District water permits from Owner.

B. Coordinate with Lakehaven for water connection and DDCV installation.

C. Protect surrounding Work from damage or disfiguration. Protect adjacent pavement remaining in service from damage.

D. Protect existing utilities from damage and disturbance. Provide shoring to support existing utilities and their support prism or remove and replace utilities where shoring is not practical. Removing and replacing utilities to be performed in accordance with utility Owner’s standards.

E. Erect barriers and barricades to direct and protect adjacent traffic.

F. Maintain water service to existing buildings. Coordinate with Owner and Owner's Representative to determine time and duration of required water system shutdowns.

G. Field locate and mark existing utilities, whether shown or not, prior to construction, avoid damage or disturbance. Protect, maintain, and repair, where damaged. For aid in utility location call 1-800-424-5555, 48 hours (two working days) prior to beginning construction. Dial Dig will only locate gas. Provide and pay for additional marking as required

H. Field stake alignment and grade. Comply with Lakehaven Utility District requirements.

3.3 EXECUTION

A. Excavation and Backfill: Comply with Section 31 23 00. Provide extra width trench as necessary where deflecting pipe. Excavate to depths required to provide minimum cover as indicated on Drawings. Excavate deeper as required to accommodate changes in grade, vaults, connections, or to install pipe under existing pipelines or other utilities. Adjust pipe depth at connection to existing main. Adjust pipe profile to pass below conflicting utilities. Provide minimum 12 inch clearance. Depth Adjustments: 2 feet or less at no adjustment in cost.

B. Installation of Pipe and Fittings:

1. Inspect pipe for structural defects and defects in coating and lining before it is placed in trench. Clean pipe fittings and valves of dirt and foreign material as they are placed. Plug open ends of pipe and fittings with temporary water-tight plug whenever Work is stopped or when water in trench threatens to enter pipe. Keep groundwater from entering pipe at all times. Lay and maintain pipe to required lines with fittings and valves at required locations and valve stems

plumb. Lay pipe in accordance with manufacturer's instructions and to AWWA standards for type of pipe being installed. Construct pipelines to provide cover shown on Drawings. Slope need not be constant, but install pipelines so no high or low points exist in finished line except at locations of fire hydrants, blow offs, air/vacuum valves, or future pipe extensions.

2. Alignment of Pipe: At conflicts with other utilities, such as telephone and existing water mains, realign pipe subject to approval of Owner's Representative.
3. Cutting Pipe: Cut pipe smooth, even, and square. Remove chips and cuttings from interior of pipe. Bevel cut pipe ends to prevent damage to gaskets during installation.
4. Laying of Pipe on Curves: Long radius curves, either horizontal or vertical, may be laid with standard pipe by deflecting joints. If pipe is shown curved on Drawings and no special fittings are shown, assume curves can be made by deflecting joints with standard lengths of pipe. Do not exceed 50 percent of manufacturer's printed recommended deflection at each pipe joint when pipe is laid on a horizontal or vertical curve. Where field conditions require deflection or curves not anticipated by Drawings, Owner's Representative will determine methods to be used. Additional payment will not be made for laying pipe on curves nor for field changes involving standard lengths of pipe deflected at joints. When rubber gasketed pipe is laid on a curve, join pipe in a straight alignment and deflect to the curved alignment. Make trenches wider on curves for this purpose.

C. Installation of Valves and Valve Boxes: Upon delivery at job site, open valves to prevent collection of water in valve. Clean valve interior of foreign matter and inspect both in open and closed position prior to installation. Set valves and valve boxes plumb except where otherwise indicated on the Drawings, and place valve boxes over valve or valve operator so valve box does not transmit shock or stress to valve. Tamp backfill carefully around valve box to a distance of 3 feet on sides or to undisturbed face of trench if it is closer. Provide concrete tie down at valves indicated on Drawings.

D. Reaction Blocking (Thrust Blocking): Furnish and install cast-in-place concrete reaction blocking at plugs, caps, tees, bends deflecting more than 11 degrees and where indicated on Drawings. Cast concrete directly against undisturbed trench wall. Place PE sheeting between pipe and concrete. Form blocking should not obstruct access to pipe joints or fittings. Size thrust block per detail on Drawing. Increase thrust blocking size for existing soils conditions as directed by Owner's Representative.

E. Restrained Joints: Provide restrained joints at fire hydrant laterals and pipes, joints, and fittings. Restrained joints may be used at vertical bends in lieu of gravity thrust block. Install lengths of restrained pipe from each side of fittings at vertical bends as indicated on Drawings or as determined by Owner's Representative. Install in accordance with manufacturers' recommendations.

F. Connection to Existing Water Mains :

1. Expose existing pipe and verify diameter and proper material type and sizes prior to beginning Work.
2. Lakehaven Utility District and WSDOT requirements.

3. Connection to existing water mains shall be performed by Lakehaven Utility District.
4. Use prechlorinated pipe valves and fittings.
5. Do not connect new construction to existing water mains until the new system is pressure tested, disinfected, flushed, purity tested, and approved by the Architect.

G. Flexible Couplings:

1. Install in accordance with manufacturer's instructions.
2. Wrap buried flexible couplings with two layers of PE film extending a minimum of 3 feet each side of center of flexible coupling overlap joints in film minimum 6 inches.

H. Vertical Bends:

1. Fabricate vertical bends on water main 4 inches in diameter and larger with restrained joint ductile iron pipe.

I. Fire Department Connection:

1. Install plumb, wrap portion of steel pipe below ground or in contact with concrete with cold applied tape coating in accordance with AWWA C209, orient hose connection toward street.
2. Paint standpipe in accordance with County fire department requirements
3. Provide concrete pad for base per drawings.

J. Fire Hydrants: Mark all fire hydrants not in service by covering with burlap sack.

K. Double Detector Check Valve Assembly:

1. Lakehaven Utility District Standards.
2. Coordinate with Lakehaven for meter installation.

3.4 PRESSURE TESTS

A. Lakehaven Utility District requirements.

B. Notify Owner's Representative 48 hours prior to required inspection time.

C. Provide all test equipment and personnel to prepare for and perform test.

D. Test in accordance with Section 014000.

E. Pressure Tests: Backfill pipeline sufficiently to prevent movement of pipe under pressure. Place reaction blocking and allow concrete to cure and reach specified strength before testing. Repair damage due to failures at no cost to Owner.

F. Furnish pumps, test gages, plugs, saddles, corporation stops, miscellaneous hose, piping, and other equipment necessary to fill pipeline with water and complete

hydrostatic test. Furnish 4.5 inch minimum diameter test gage having 0 to 300 psi range with 1/4 of 1 percent accuracy accompanied with certifications of accuracy from a laboratory approved by Owner's Representative. Fill water main only through a backflow prevention device supplied by Contractor and approved by City of Federal Way.

G. Prior to testing, fill pipeline with water and allow to stand under pressure sufficient time to allow escape of air and, if applicable, allow pipe lining to absorb water.

H. Test pipelines and connecting piping in sections between temporary caps or valves by admitting water to the line gradually to full test pressure. Testing against closed valves will be permitted provided pressure differential across valve does not exceed rated working pressure of valve.

I. Hydrostatically test water mains and appurtenances 6 inches in diameter and larger at 200 psi. Apply test pressure at low end of section of water main being tested. Vent air in pipe prior to test.

J. Test by pressurizing main to required pressure, stop pump for 15 minutes, and then pressurize main to test pressure again. Observe section being tested to detect any visible leakage. Use clean container for holding water for pressurizing main being tested. Sterilize makeup water by adding chlorine to concentration of 50 mg/l. Accurately determine water quantity required to restore pressure by pumping through positive displacement water meter with a sweep unit hand registering 1 gallon per revolution. Use meter approved by City of Federal Way and WSDOT. Test acceptability will be determined as follows: Comply with City of Federal Way and WSDOT standards. There shall not be an appreciable or abrupt loss in pressure during 15-minute test period.

K. Limit sections to be tested normally to 1,600 feet. Owner's Representative may require the first section of pipe, not less than 1,000 feet in length, be tested in order to qualify crew and material. Do not continue pipe laying more than an additional 1,000 feet until first section has been tested successfully.

L. Perform hydrostatic tests on every complete section of water main between valves, or as directed by Owner's Representative. Each valve side shall withstand same test pressure as pipe, with no active pressure in pipe section beyond closed valves. Make tests with hydrant auxiliary gate valves open and pressure against hydrant valve. After test is completed, each gate valve will be acceptable if there is no immediate loss of pressure on gage when pressure is applied to valve being checked. Verify pressure differential across valve does not exceed rated test pressure of valve.

M. When hydrants are included with section of main pipe to be tested, conduct testing in two separate tests as follows:

1. Test No. 1 - Water main gate valves and hydrant auxiliary gate valves closed, with hydrant operating stem valves and hose ports wide open.
2. Test No. 2 - Water main gate valves and hydrant operating stem valves tightly closed but hydrant auxiliary gate valves and hose ports wide open.

N. Correct visible leakage detected regardless of allowable leakage specified above. Should tested section fail to meet pressure test successfully as specified, locate and repair defects and retest pipeline at no cost to Owner.

O. Prior to notifying Owner's Representative to witness pressure test, have equipment set up completely, ready for operation, and have tested successfully to ensure pipe is in satisfactory condition.

3.5 DISINFECTION OF WATER MAINS

A. Before being placed in service, chlorinate and obtain a satisfactory bacteriological report for new water mains and repaired portions of, or extensions to, existing mains.

B. Flush pipe (including private fire lines not receiving sterilization) prior to being disinfected to remove solids or contaminated material that may have become lodged in pipe. If no hydrant is installed at end of main, provide a tap large enough to develop a velocity of at least 2.6 fps in main. Provide taps required for temporary or permanent release of air and chlorination or flushing purposes. Where dry calcium hypochlorite is used for disinfection of pipe, perform flushing after disinfection. Dispose of treated water flushed from mains and neutralize wastewater for protection of aquatic life in receiving water before disposal into any natural drainage channel. Dispose disinfecting solution during test to Owner's Representative's and local authorities' satisfaction. If approved by sewer system owner and Owner's Representative, disposal may be made to any available sanitary sewer provided rate of disposal will not overload sewer.

C. Sterilization: Lakehaven Utility District Standards.

D. Preventing Reverse Flow: Do not make connections between existing distribution system and pipelines not disinfected and constructed under this Contract without a DSHS approved back flow preventer installed in connecting line.

E. Chlorinating Connections to Existing Water Mains: Follow chlorinating procedure as specified in AWWA C651. Swab closure fittings with a very strong chlorine solution (5 to 6 percent Cl).

3.6 FINAL FLUSHING AND TESTING OF MAINS

A. Following chlorination, flush treated water from newly laid pipe until replacement water throughout its length shows, upon test, absence of chlorine. In the event chlorine is normally used in supply source, then tests shall show a residual not in excess of that carried in system.

B. Dispose of chlorinated water in accordance with DOE and Department of Fish and Wildlife requirements. Neutralize water for protection of aquatic life in the receiving water before disposal into drainage system.

C. Locate a sample tap ahead of flushing hose for convenience and sanitary sampling.

D. Before placing lines into service, a satisfactory report shall be received from a certified test lab on samples collected from representative points in new system. Samples shall be collected and bacteriological tests obtained by the Contractor. Costs of water sample analysis shall be borne by Contractor as incidental Work to water main installations.

E. Should initial treatment result in an unsatisfactory bacteriological test, repeat original chlorination procedure until satisfactory results are obtained. Failure to obtain a satisfactory bacteriological test will be considered as failure to keep pipe clean during construction or to chlorinate the main as specified. Additional chlorination required to obtain satisfactory test result shall be completed at no additional cost to Owner.

END OF SECTION 331100

SECTION 334000 – STORM DRAINAGE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to this section.

1.2 SUMMARY

A. Work in this section includes:

1. Storm Drains
2. Roof Drains
3. Catch Basins and Clean Outs

B. Related sections include the following:

1. Section 312300 – Excavating, Backfilling, and Compacting for Utilities and Structures
2. Section 312500 – Erosion and Sedimentation Control

1.3 REFERENCES

A. WSDOT Standard Plans – Washington State Department of Transportation 2016. Standard Plans for Road, Bridge, and Municipal Construction.

B. WSDOT Standard Specifications – Washington State Department of Transportation 2016 Standard Specifications for Road, Bridge, and Municipal Construction.

C. City of Federal Way, Public Works Department Development Standards, current edition.

1.4 QUALITY ASSURANCE

A. Qualifications: Crew Foreman: Minimum six years' working experience and four years' experience as foreman performing similar work.

B. Regulatory requirements:

1. Comply with City of Federal Way Standards.
2. Comply with WSDOT Standards.

1.5 SUBMITTALS

A. Submit under provisions of Section 013000.

1. Pipe, fittings, catch basins, castings, and accessories.

B. Manufacturers' Installation Instructions: Indicate special procedures required to install products specified.

C. Record Documents: Submit under provisions of Section 017200. Record actual structure locations of pipe runs, connections, and invert elevations accurately. Identify and describe unexpected variations to subsoil conditions or discovery of uncharted utilities.

D. Samples :

1. Submit under provisions of Section 013000.
2. Submit minimum 50-pound sample for each material four business days prior to placing material.
3. Quality assurance/control submittals.
4. Test Reports: Sieve analysis for each material.

E. Closeout Submittals:

1. Accurately record actual locations of pipe runs, connections, and invert elevations.
2. Identify and describe unexpected variations to subsoil conditions or discovery of uncharted utilities.

1.6 SEQUENCING AND SCHEDULING

A. Maintain on-site storm drainage during construction.

B. Construct the erosion control facilities as shown in the Drawings.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Structural Fill: Section 31 23 00.

B. Bedding: Section 31 23 00.

C. Storm Drain Pipe: WSDOT Standard Specifications Section 9-05. Acceptable pipe materials:

1. Corrugated Polyethylene Storm Sewer Pipe: WSDOT Standard Specifications Section 9-05.20.
2. Reinforced Concrete Pipe: WSDOT Standard Specifications Section 9-05.7.
3. Ductile Iron Sewer Pipe: WSDOT Standard Specifications Section 9-05.13.

D. Catch Basins, Inlets, and Yard Drains:

1. Type 1 Catch Basins: WSDOT Standard Plan B-5.20-01.
2. Type 2 Catch Basins: WSDOT Standard Plan B-10.20-01.
3. Load Ratings: HS20, AASHTO Section 3.7.

E. Metal Castings: Load ratings: HS20. Locking type.

F. Grates in pedestrian access areas to comply with ADA requirements.

G. Cleanouts: WSDOT Standard Plan B-85.40-00.

H. Frame and Grate: WSDOT Standard Plan B-30.10-01, B-30.20-02, B-30.50-01, and B-30.80-00. Comply with ADA requirements at pedestrian areas.

I. Solid Ring and Cover: WSDOT Standard Plan B-30.70-03. Lettering “STORM.”

2.2 SOURCE QUALITY CONTROL

A. Tests and Inspections:

1. Tests and analyses of aggregate material will be performed in accordance with WSDOT Standard Specifications.
2. If tests indicate materials do not meet specified requirements, change material and retest.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Site Verification of Conditions: Verify as follows:

1. Verify survey benchmark and intended elevations for the Work are as indicated.
2. Verify excavation is ready to receive Work; and excavations, dimensions, and elevations are as indicated on Drawings.
3. Verify existing utilities have been marked.
4. Verify erosion control is in place and operating properly.
5. Verify inverts at points of connection. Pothole, expose pipes, determine invert elevations, verify with design, and inform Architect of deviations affecting design prior to mobilizing crews and beginning construction.
6. Verify vegetation to remain is protected and marked prominently.
7. Verify removal of abandoned utilities is complete.

3.2 PREPARATION

A. Protection:

1. Locate existing utilities, avoid damage or disturbance. For aid in utility location, call “Dial Dig 1-800-424-5555,” 48 hours (two working days) prior to beginning construction. Dial Dig will only locate Gas. Provide and pay for additional marking as required.
2. Protect and maintain existing utilities that are to remain.
3. Protect utilities to be abandoned until they have been abandoned.
4. Protect plant life, lawns, and other features remaining as a portion of final landscaping.
5. Protect benchmarks, existing structures, sidewalks, railings, paving, and curbs.
6. Use all means necessary to prevent the erosion of freshly graded areas during construction or until such time that permanent drainage and erosion control measures are fully operational.

B. Preparation:

1. Survey and stake limits. Slope stake toe and top of cuts and fills. Construct orange fence at construction limits.
2. Identify required lines, levels, contours, and datum. Should indicated figures conflict with actual conditions, notify Architect, and await direction before proceeding.
3. Verify elevations where matching existing grade. Notify Architect where grading to match existing creates adverse effects, such as blocking grading, abrupt change in grade, slopes steeper than allowed.

3.3 CONSTRUCTION

A. Excavation:

1. Section 312300.
2. Remove large stones or other hard matter which could damage piping or impede consistent backfilling or compaction.

B. Pipe:

1. Install in accordance with manufacturer’s recommended procedures, ASTM Standards, and WSDOT Standard Specifications.
2. Maintain line and grade per Drawings.
3. Join pipe in accordance with manufacturer’s recommended procedure and WSDOT Standard Specifications.
4. WSDOT Standard Specifications Section 7-04.3.

C. Catch Basins and Storm Drain Manholes:

1. WSDOT Standard Specifications Section 7-05.
2. Form bottom of excavation clean and smooth to correct elevation.
3. Place base sections on 12 inches minimum compacted thickness bedding. Smooth and level to ensure uniform contact and support. Where subgrade cannot be compacted due to excess moisture, provide lean concrete pad minimum 12 inches thick.
4. Extend bedding to the limits of the excavation.
5. Compact bedding 95 percent of the maximum density. Verify alignment and elevation of entering pipes.
6. Construct structures plumb and level.
7. Make completed manhole rigid, true to dimensions, and watertight.
8. Backfill evenly around structure to prevent displacement and unequal stresses.
9. Wet lift holes and fill with mortar inside and out.
10. Smooth and point structure joints inside and out. Ensure water tightness.
11. Remove loops flush with the inside wall surface after the manhole has been completed for precast manhole elements where steel loops have been provided in lieu of lift holes.
12. Remove sharp cutoff protrusions. If concrete spalling occurs as a result of the loop removal, restore the spalled area to a uniform smooth surface with cement mortar.

D. Backfilling: Section 312300.

E. Roof Drain Connection:

1. Verify location and elevation of roof drains at connection point.
2. Field adjust pipe route and elevation to connect with building roof drains and drain to storm drainage system.
3. Provide minimum 2-foot cover over pipe.
4. Maintain slope to drain. 2 percent slope preferred, 1 percent slope allowed where necessary to maintain minimum cover.
5. Make changes in pipe direction with 45-degree bend maximum. Minimum 2 feet straight section between bends.

F. Cleanouts:

1. Construct plumb and level.
2. Adjust top to finish grade. Verify top of cleanout elevation.

3.4 FIELD QUALITY CONTROL

A. Section 014000: Low pressure air test in accordance with City of Federal Way Standards.

B. Site Tests:

1. Perform compaction test

2. If tests indicate Work does not meet specified requirements, recompact and retest.

C. Inspection: Owner will observe the Work at the following milestones: After completion of pipe, manholes, cleanouts, bedding, and before backfilling.

3.5 CLEANING

A. Prior to final acceptance, flush out accumulated construction debris and remove other foreign matter from storm drains. Do not allow flushed material to enter downstream system.

3.6 PROTECTION

A. Protect completed work from damage.

B. Protect slopes from erosion.

END OF SECTION 334000