South King Fire and Rescue

Station 64 Facility Improvements

ADDENDUM #2

March 16, 2018

TO ALL BIDDERS:

The Bid Documents issued **February 23, 2018** for the project noted above are amended by this Addendum #2.

Receipt of this addendum shall be acknowledged by inserting its number in the space provided on the bid form.

DRAWINGS

ARCHITECTURAL

ITEM 1. A01.01 ASSEMBLY SCHEDULES:

a. Wall Assembly E01, REVISE note " 2" FIBERGLASS THERMAL SPACER SET IN GROUT BED, SPACING AND FASTENERS PER MFRREC" to read " 2" FIBERGLASS THERMAL SPACER SET IN GROUT BED, HORIZONTAL SPACING @ 24" OC, VERTICAL SPACING @ 48" OC MAX, FASTENERS PER MFRREC"

END OF ADDENDUM #2